

PROJECT MANUAL

Volume 1 of 2

New Construction for

Bank of America

Centerville

782 W. Parrish LN

Centerville, Utah, 84014

Prepared by

Gensler

2575 E. Camelback Rd.

Suite 175

Phoenix, AZ 85016

Tel. 602.523.4900

Project Number: 057.7202.950

TABLE OF CONTENTS

(Volume 2 Contents appear as gray for overall reference in this volume 1)

PROCUREMENT AND CONTRACTING REQUIREMENTS GROUP

DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMENTS

INTRODUCTORY INFORMATION

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	00 01 01	Project Title Page
	00 01 10	Table of Contents

CONTRACTING REQUIREMENTS – BY OWNER

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	00 60 04	Data Transfer Agreement
	00 60 05	Request for Interpretation
	00 60 06	Substitution Request
	00 60 07	Bulletin

SPECIFICATIONS GROUP

GENERAL REQUIREMENTS SUBGROUP

DIVISION 01 - GENERAL REQUIREMENTS

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	01 10 00	Summary
	01 17 00	Erosion and Sedimentation Control Plan
	01 25 00	Substitution Procedures
	01 26 00	Contract Modification Procedures
	01 26 13	Requests for Interpretation (RFI)
	01 29 00	Payment Procedures
	01 31 00	Project Management and Coordination
	01 32 00	Construction Progress Documentation
	01 33 00	Submittal Procedures
	01 40 00	Quality Requirements
	01 42 00	References
	01 50 00	Temporary Facilities and Controls
	01 60 00	Product Requirements
	01 73 00	Execution
	01 73 29	Cutting and Patching
	01 74 19	Construction Waste Management and Disposal
	01 77 00	Closeout Procedures
	01 78 23	Operation and Maintenance Data
	01 78 39	Project Record Documents
	01 79 00	Demonstration and Training
	01 81 13.13	Sustainable Design Requirements – LEED For New Construction and Major Renovations

01 81 13.16	Sustainable Design Requirements – LEED For Commercial Interiors
01 81 19	Indoor Air Quality (IAQ) Management
01 91 13	General Commissioning Requirements
01 91 14	Commissioning of the Building Envelope

FACILITY CONSTRUCTION SUBGROUP

DIVISION 02 – EXISTING CONDITIONS - (Not Used)

DIVISION 03 – CONCRETE

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	03 30 00	Cast-In-Place Concrete (Refer to Structural Drawings)
	03 54 16	Hydraulic Cement Underlayment

DIVISION 04 – MASONRY

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	04 73 00	Manufactured Masonry Veneer

DIVISION 05 – METALS

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	05 12 00	Structural Steel (Refer to Structural Drawings)
	05 21 00	Steel Joists Framing (Refer to Structural Drawings)
	05 31 00	Steel Decking (Refer to Structural Drawings)
	05 40 00	Cold-Formed Metal Framing (Refer to Structural Drawings)
	05 50 00	Metal Fabrications

DIVISION 06 – WOOD, PLASTICS, AND COMPOSITES

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	06 10 00	Rough Carpentry
	06 16 00	Sheathing
	06 40 23	Interior Architectural Woodwork
	06 64 00	Plastic Paneling

DIVISION 07 – THERMAL AND MOISTURE PROTECTION

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	07 13 26	Self-Adhering Sheet Waterproofing
	07 21 00	Thermal Insulation
	07 26 16	Underslab on Grade Vapor Retarder
	07 27 26	Fluid Applied Membrane Air Barrier
	07 42 13.13	Formed Metal Wall Panels
	07 42 13.16	Metal Plate Wall Panels
	07 42 13.23	Metal Composite Material Wall Panels.
	07 54 23	Thermoplastic Polyolefin (TPO) Roofing
	07 62 00	Sheet Metal Flashing and Trim
	07 71 00	Roof Specialties
	07 72 00	Roof Accessories
	07 92 00	Joint Sealants

DIVISION 08 – OPENINGS

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	08 11 13	Hollow Metal Doors and Frames
	08 14 16	Flush Wood Doors
	08 31 13	Access Doors and Frames
	08 41 13	Aluminum-Framed Entrances and Storefronts
	08 41 26	All-Glass Entrances and Storefronts
	08 71 00	Door Hardware
	08 80 00	Glazing
	08 87 00	Glazing Surface Films

DIVISION 09 – FINISHES

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	09 22 16	Non-Structural Metal Framing
	09 24 00	Cement Plastering
	09 29 00	Gypsum Board
	09 30 13	Ceramic Tiling
	09 51 10	Acoustical Ceilings
	09 65 13	Resilient Base and Accessories
	09 65 19	Resilient Tile Flooring
	09 68 16	Sheet Carpeting
	09 72 00	Wall Covering
	09 91 13	Exterior Painting
	09 91 23	Interior Painting
	09 96 20	Graffiti-Resistant Coating System

DIVISION 10 – SPECIALTIES

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	10 11 00	Visual Display Surfaces
	10 14 23	Panel Signage
	10 28 00	Toilet Accessories
	10 44 00	Fire-Protection Specialties
	10 75 16	Ground-Set Flagpoles

DIVISION 11 – EQUIPMENT

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	11 31 10	Pantry Appliances

DIVISION 12 – FURNISHINGS

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	12 24 13	Roller Window Shades
	12 36 61	Simulated Stone Countertops
	12 48 13	Entrance Floor Mats and Frames
	12 90 00	Building Accessories

DIVISION 13 - SPECIAL CONSTRUCTION – Not Used

DIVISION 14 – CONVEYING EQUIPMENT - (Not Used)

FACILITY SERVICES SUBGROUP

DIVISION 21 – FIRE SUPPRESSION – NOT USED

DIVISION 22 – PLUMBING

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
00-00-00	22 05 00	Common Work Results for Plumbing
	22 05 23	General-Duty Valves for Plumbing Piping
	22 05 29	Hangers and Supports for Plumbing Piping and Equipment
	22 05 53	Identification for Plumbing Piping and Equipment
	22 07 00	Plumbing Insulation
	22 08 00	Commissioning of Plumbing
	22 11 16	Domestic Water Piping
	22 11 19	Domestic Water Piping Specialties
	22 13 16	Sanitary Waste and Vent Piping
	22 13 19	Sanitary Waste Piping Specialties
	22 14 23	Storm Drainage Piping Specialties
	22 33 00	Electric Domestic Water Heaters
	22 40 00	Plumbing Fixtures
	22 47 00	Drinking Fountains and Water Coolers

DIVISION 23 – HEATING VENTILATING AND AIR CONDITIONING

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	23 05 00	Common Work Results for HVAC
	23 05 13	Common Motor Requirements for HVAC Equipment
	23 05 29	Hangers and Supports for HVAC Piping and Equipment
	23 05 53	Identification for HVAC Piping and Equipment
	23 05 93	Testing, Adjusting, and Balancing for HVAC
	23 07 00	HVAC Insulation
	23 07 13	Duct Insulation
	23 08 00	Commissioning of HVAC
	23 09 00	Instrumentation and Control for HVAC
	23 11 23	Facility Natural-Gas Piping
	23 31 13	Metal Ducts
	23 33 00	Air Duct Accessories
	23 34 23	HVAC Power Ventilators
	23 37 13	Diffusers, Registers, and Grilles
	23 37 23	HVAC Gravity Ventilators
	23 74 13	Packaged, Outdoor, Central-Station Air-Handling Units
	23 82 39	Unit Heaters

DIVISION 25 – INTEGRATED AUTOMATION – NOT USED

DIVISION 26 – ELECTRICAL

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	26 05 00	Common Work Results for Electrical
	26 05 19	Low-Voltage Electrical Power Conductors and Cables
	26 05 26	Grounding and Bonding for Electrical Systems
	26 05 29	Hangers and Supports for Electrical Systems
	26 05 33	Raceway and Boxes for Electrical Systems
	26 05 53	Identification for Electrical Systems

26 09 23	Lighting Control Devices
26 24 16	Panelboards
26 27 26	Wiring Devices
26 28 16	Enclosed Switches and Circuit Breakers
26 33 23	Central Battery Equipment
26 43 13	Transient-Voltage Suppression for Low-Voltage Electrical Power Circuits
26 50 00	Commissioning of Lighting Systems
26 51 00	Interior Lighting
26 56 00	Exterior Lighting

DIVISION 27 – COMMUNICATIONS – NOT USED

DIVISION 28 – ELECTRICAL SAFETY AND SECURITY

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	28 31 11	Digital, Addressable Fire-Alarm System

DIVISION 31 – EARTHWORK

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	31 31 16	Termite Control

DIVISION 32 – EXTERIOR IMPROVEMENTS

<i>Date</i>	<i>Section No.</i>	<i>Title</i>
	32 17 13	Parking Bumpers
	32 17 23	Pavement Markings

END OF TABLE OF CONTENTS

Data Transfer Agreement

Entity Requesting Data ("Transferee")	Transferee Contact Name
Project	Project Number
Client	Date
File 1DTA	This is page 1 of

Transferee has asked Gensler to provide electronic copies of, or access to, certain drawings, specifications, or other documents, CAD data files, and/or building information models (collectively, "Data") prepared by Gensler and/or its consultants (collectively "Gensler") for the Project. Gensler agrees to provide Transferee with the requested Data, under the terms of this Data Transfer Agreement ("Agreement").

1. The transfer of the Data is not and shall not be deemed a sale. The Data are instruments of service. Gensler shall be deemed the Data's author and shall retain all proprietary rights, including any copyrights, embodied therein.
2. Transferee may transfer the Data to its contractors, subcontractors, suppliers, and consultants (collectively "Others"), provided Transferee requires the Others to be bound by this Agreement as if they were the Transferee in this Agreement. Transferee and Others may use the Data only for purposes related to the Projects.
3. Transferee acknowledges that anomalies and errors may occur when the Data is transferred electronically or used in an incompatible computer environment. Transferee solely accepts the risks associated with, and the responsibility for, any damages to hardware, software, computer systems, or networks related to the Data's transfer or use. Gensler shall have no responsibility to provide software or training to allow Transferee to use the Data.
4. Gensler shall have no duty to modify or update the Data. Gensler may retain an archival copy of the Data, which shall be conclusive proof and govern in any dispute over the Data's form or content.
5. Transferee agrees to indemnify, defend and hold Gensler, its officers, directors, shareholders, employees, agents, and consultants harmless from and against any and all claims, liabilities, suits, demands, losses, damages, costs, and expenses, including, but not limited to, reasonable attorneys' fees and all legal expenses and fees incurred through appeal, and all interest thereon, accruing to or resulting from any and all persons, firms or any other legal entities on account of any damages or losses to property or persons, including, but not limited to, injuries, death or economic losses, arising out of Transferee's or Others' use, reuse, transfer, or modification of the Data, except where a court or forum of competent jurisdiction determines that Gensler is solely liable for such damages or losses.
6. If Transferee fails to perform or observe any of the terms of this Agreement, Gensler may demand, and Transferee immediately shall return, the Data and any copies thereof.
7. To the extent the Data include building information models ("Models"), the parties agree to the following additional terms: (i) The Models are intended for the purpose of communicating design intent. While they may be helpful to illustrate conflicts or inconsistencies in the design, the Models may not detect all conflicts or inconsistencies. (ii) Any use of the Models for the purpose of generating quantity take-offs or cost estimates, or for fabrication, will be at the Transferee's sole risk. (iii) As with Gensler's other services and deliverables, the Models will be prepared using that degree of skill and care exercised by licensed professionals practicing in the same community, under the same or similar circumstances. The Models may contain, or be based upon, data or information provided by others. Gensler has relied upon such data or information as it consistent with this standard of care. (iv) Information contained in the Models will not be construed to dictate construction means or methods, which will remain the contractor's responsibility. (v) To the extent of any conflict between information contained in, or generated by, the Models and Gensler's drawings and specifications, the latter documents will prevail.
8. This Agreement shall be governed by the law of the location of Gensler's office, Insert city, state of Gensler's office.
9. In any legal proceeding to enforce this Agreement, the prevailing party shall be entitled to recover its reasonable attorneys' fees and costs of defense.
10. Unless otherwise explicitly agreed to in writing by the parties, this Agreement shall govern any and all data transfers to Transferee by Gensler.

Gensler Authorization by	Date Signed
_____ Input Principal or Managing Principal's name here	
Transferee Authorization by	Date Signed
_____ Input Client signatory's name here	

Project	RFI Number	
To	Date	
Attention	Project Number	
From	File	6RFI
Issued By	Drawing Sheet / Location	
Subject	Detail	
Distribution	Specifications Page Number	
	This is page	1 of

Problem, Cause and Proposed Solution (attach sketches as necessary)

Effect on Schedule

Effect on Cost

Reply

Reply Needed by

Signature

Date

Substitution Request

Gensler

Project	Date
Project Location	Project Number
General Contractor	File 6S
Prepared by	This is page 1 of

We certify that the following product is equal or superior to the specified product in appearance, durability, performance, and in every other respect, and we hereby submit it for your consideration as a substitute for the specified item for the above-mentioned project:

1. Specified Item	Section
2. Proposed Substitution	
3. Reason for Substitution	
4. Costs (Provide a complete breakdown of costs, including the cost amount to be DEDUCTED from the Contract Sum if the proposed substitution is accepted. Include documentation for both materials and labor.)	
5. Schedule (Describe substitution's affect on construction schedule)	
6. Supporting Data Cutsheets: Attach complete technical data, including laboratory tests, if applicable. Installation: Include complete information on changes to Drawings and/or Specifications describing the steps that the proposed substitution will require for its proper installation. Samples: Submit with request all necessary samples and substantiating data clearly marked to prove equal quality and performance to that which is specified.	
7. List ways in which the substitution affects dimensions shown on Drawings	
8. List affects of proposed substitution on other trades	
9. List ways in which proposed substitution will be affected by applicable code requirements and agency approval	
10. List differences between proposed substitution and specified item	
11. Manufacturer's warranties of the proposed and specified items are:	☐ Same ☐ Different
Explain:	

12. List information on availability of maintenance service and source of replacement materials

13. Certification of, and Assumption of Liability for, Equivalent Performance

The undersigned certifies that the function, appearance and quality of the proposed substitution is equivalent or superior to the specified item and is in full compliance with the Contract Documents and applicable regulatory requirements.

Supplier	_____	Signature	_____
Telephone No.	_____	Date	_____

Signature must be by person authorized to legally bind his/her firm to the above terms. Failure to provide legally binding signature will result in retraction of approval.

General Contractor	_____	Signature	_____
Telephone No.	_____	Date	_____

Project			Date		
Project Location			Architect's Project Number		
Owner/Client			File 6BL This is page 1 of		
To			Attention		
Address					
City		State		Zip Code	
Delivered via:					
☐ Messenger ☐ Hand carried ☐ Facsimile					
☐ Express ☐ Pick-up ☐ E-mail Address					
☐ Mail ☐ UPS ☐ Website Address					
This Bulletin Conveys to Contractor (Check one of the following five choices.):					
☐ Architect's Authorization for Minor Changes Architect recommends modifications to the Work as described below.					
☐ Architect's Clarification / Supplemental Instructions (Use this Bulletin form in place of <i>Architect's Supplemental Instructions</i> form.) Contractor shall carry out the Work in accordance with the following supplemental instructions.					
☐ Architect's Confirmation of a Field Order (Use this Bulletin form in place of a <i>Field Order</i> form.) This confirms Architect's verbal instructions to (individual's name) _____ on (date) _____, as described below. Note: The above three choices are each subject to the following terms: The change(s), clarification(s) and/or confirmation(s) described below is/are issued in accordance with the Contract Documents, without change in Contract Sum and/or Time.					
☐ Architect's Request for Contractor's Proposal (Use this Bulletin form in place of an <i>Estimate Request</i> form.) Please submit an itemized proposal for changes in the Contract Sum and/or Time for proposed modifications to the Contract Documents described herein. Submit proposal within _____ days or notify the Architect in writing of the date on which you anticipate submitting your proposal. This is not a Change Order or a Construction Change Directive or a direction to proceed with the Work described in the proposed modifications.					
☐ Other: As described below.					
Attachments					
Requested by					
☐ Architect ☐ Owner ☐ Contractor ☐ Other (specify): _____					
Issued by Gensler by			Date Signed		
Issued by Owner by			Date Signed		
☐ Required; Please return signed copy to Gensler			☐ Not Required		
Accepted by Contractor by			Date Signed		
☐ Required; Please return signed copy to Gensler			☐ Not Required		
Distribution					
Prepared by Gensler by			Date Signed		
Instructions / Description / References / Dates					

Begin text here...

SECTION 01 10 00 - SUMMARY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Work covered by Contract Documents.
2. Use of the premises.
3. Work under separate contracts.
4. Owner-furnished products.
5. Occupancy requirements prior to Substantial Completion.
6. Specifications format.

1.2 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to all Sections. The Contract Documents are complementary, and what is required by one shall be as binding as if required by all.
- B. Conflicts or discrepancies among the Contract Documents shall be resolved in the following order of priority:
1. Contract modifications (such as Change Orders) of later date take precedence over those of earlier date;
 2. the Agreement;
 3. the Supplementary Conditions;
 4. The General Conditions;
 5. Drawings and Specifications; Drawings govern Specifications for quantity and location. Specifications govern Drawings for quality and performance. In the event of ambiguity or conflicts, the greater quantity and the better quality shall govern.

1.3 WORK COVERED BY CONTRACT DOCUMENTS

- A. Project Identification: The Project consists of exterior and interior improvements for a new branch bank facility for Bank of America.
- B. Owner Identification: Bank of America.
- C. Owner's Representative: JLL.
- D. Architect Identification: The Contract Documents dated January 22, 2021 were prepared for this Project by Gensler.
- E. Sustainable Design Project: Project is designed to comply with the Silver Certification Level according to the U.S. Green Building Council's Leadership in Energy & Environmental Design

(LEED) Rating System. Comply with requirements specified in Division 01 Section "Sustainable Design Requirements."

1.4 WORK SEQUENCE

- A. The Work shall be conducted in a single phase. Coordinate construction schedule and operations with the Owner.

1.5 USE OF PREMISES

- A. General: Access to project site and hours of work operation shall be coordinated with the Owner.
- B. Contractor shall have full use of the work area and local premises for construction operations, including designated use of Project site, during construction period. Contractor's use of premises is limited only by Owner's right to perform work or to retain other contractors on portions of Project.
 - 1. Do not disturb portions of Project site beyond areas in which the Work is indicated.
 - 2. Driveways and Entrances: Keep driveways, parking areas, loading areas, and entrances serving premises clear and available to Owner, employees, building occupants, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.
 - a. Schedule deliveries to minimize use of driveways and entrances.
 - b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
 - 3. Subcontractor's use of premises must be coordinated with the Contractor and is limited only by Owner's right to perform work or to retain other contractors on portions of Project.
 - 4. Confine operations at the site to areas permitted by law, ordinances, permits and the Contract Documents. Do not unreasonably encumber the Site with any materials or equipment.
- C. Access: At all times, provide the Architect and Owner easy and safe access to the Work wherever it is in preparation and progress. Provide such access so the Architect may perform their functions.
- D. Environmental Requirements: The following requirements are in addition to all applicable laws and regulations.
 - 1. No burning will be permitted on the Site.
 - 2. Control dust by water sprinkling, temporary enclosures, or other methods acceptable to the Owner. Comply with governing regulations.
- E. Owner's Rules: Conform at all times to Owner's requirements for protection of plant, materials, equipment, and noise levels.

1.6 WORK RESTRICTIONS

- A. General: Comply with Owner's requirements.
- B. Existing Utility Interruptions: Do not interrupt utilities serving occupied facilities unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
 - 1. Notify Owner not less than 72 hours in advance of proposed utility interruptions.
 - 2. Do not proceed with utility interruptions without Owner's written permission.

1.7 WORK UNDER OTHER CONTRACTS

- A. Separate Contract: Owner will award separate contracts for performance of certain construction operations at Project site. Those operations are scheduled to be completed during the same period as work under this Contract. The separate contracts will include the following:
 - 1. Security and data systems (Contractor to furnish and install empty conduits with a junction box where indicated on the Contract Documents).
 - 2. Telephone systems (Contractor to furnish and install empty conduits with a junction box where indicated on the Contract Documents).
 - 3. Fixtures, furnishings, and equipment to the extent not identified in the Contract Documents.
 - 4. Precast concrete vault equipment.
 - 5. ATM's and night deposit equipment.
 - 6. Safe deposit boxes.
 - 7. Copiers.
 - 8. Equipment Racks.
 - 9. Furniture systems.
 - 10. Undercounter equipment.
 - 11. Que line.
 - 12. Signage to the extent indicated.
 - 13. Walk-Off Mats.
- B. Cooperate fully with separate contractors so work on those contracts may be carried out smoothly, without interfering with or delaying work under this Contract.

1.8 OCUPANCY REQUIREMENTS PRIOR TO SUBSTANTIAL COMPLETION

- A. Partial Owner Occupancy: Owner reserves the right to occupy and to place and install equipment in completed areas of building, before Substantial Completion, provided such occupancy does not interfere with completion of the Work. Such placement of equipment and partial occupancy shall not constitute acceptance of incomplete portions of the Work, nor shall it relieve the Contractor of his responsibility for completion of the Work in accordance with the Contract Documents.
 - 1. Contractor is responsible for protecting Owner's items from damage during storage and handling, including damage from exposure to the elements.
 - 2. If Owner's items are damaged as a result of Contractor's operations, Contractor shall repair or replace them.

3. Owner will prepare a Certificate of Substantial Completion for each specific portion of the Work to be occupied before Owner occupancy.
4. Obtain a Certificate of Occupancy from authorities having jurisdiction before Owner occupancy.
5. Before partial Owner occupancy, mechanical and electrical systems shall be fully operational, and required tests and inspections shall be successfully completed. On occupancy, Owner will provide, operate, and maintain mechanical and electrical systems serving occupied portions of building.
6. On occupancy, Owner will assume responsibility for maintenance and custodial service for occupied portions of building.

1.9 TAXES

- A. Contractor shall pay sales, consumer, use and similar taxes for the Work or portions thereof provided by the Contractor which are legally enacted at the time Bids are received or negotiations concluded, whether or not yet effective or merely scheduled to go into effect.

1.10 PERMITS

- A. Contractor shall secure and pay for the building permit, and other permits and governmental fees, licenses and inspections necessary for the proper execution and completion of the Work which are customarily secured after execution of the Contract and which are legally required at the time the Bids are received or negotiations concluded.
- B. If required by governmental authority, Owner will make application for permits and licenses using forms obtained and prepared by the Contractor and with all costs paid by the Contractor.
- C. The Contractor shall comply with and give notices required by laws, ordinances, rules, regulations and lawful orders of public authorities bearing on performance of the Work. Any provisions hereof to the contrary notwithstanding, Contractor shall observe and abide by and perform all of its obligations hereunder in accordance with all applicable laws, rules, and regulations of all governmental authorities having jurisdiction, including the Federal Occupational, Safety and Health Act. Contractor shall comply with all laws regarding trench excavations in excess of 5 feet in depth, including employing engineers, if needed. Such expenses shall be included in the cost of the work.

1.11 PROJECT COORDINATION

- A. General: Refer to the General Conditions for requirements pertaining to coordination. The Contractor shall be the sole coordinator of the Work.
 1. The Architect has exercised reasonable care in coordinating the Contract Documents between disciplines. Carefully study and compare the Contract Documents, site, Owner furnished data, and local conditions and report at once any discrepancies, errors, or omissions in the Contract Documents prior to the award of the Contract. Failure to report any discrepancies, errors, or omissions in the Contract Documents shall be a waiver to any claim by the successful bidder for expense made necessary by reason of later interpretation of the Contract Documents by the Architect.

- B. Coordinate construction operations included in various Sections of these Specifications to assure efficient and orderly installation of each part of the Work. Coordinate construction operations included under different Sections that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in the sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components to assure maximum accessibility for required maintenance, service, and repair.
 - 3. Make provisions to accommodate items scheduled for later installation.
- C. Existing Conditions:
 - 1. Conduct a thorough examination of the site, the Contract Documents, and Owner furnished data of existing conditions before proceeding with the Work. The Contractor shall formulate from its examinations its own conclusions as to the extent of the existing conditions and the complexities that may be encountered in the execution of the Work.
 - 2. Owner Furnished Data: Portions of the Contract Documents were prepared from data received from the Owner by the Architect. Such data is available from the Owner and represents all existing conditions known to the Owner. Such data will be furnished only for the information and convenience of the Contractor, and the accuracy or completeness of this data is not guaranteed. Field verify all existing dimensions. Other conditions, of which no record exists, may be encountered during construction.

1.12 SPECIFICATION FORMATS AND CONVENTIONS

- A. Specification Format: The Specifications are organized into Divisions and Sections using the 50-division format of the Construction Specifications Institute's (CSI) 2004 edition of the "MasterFormat" numbering system.
 - 1. Division 01: Sections in Division 01 govern the execution of the Work of all Sections in the Specifications.
- B. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
 - 1. Abbreviated Language: Language used in the Specifications and other Contract Documents is abbreviated. Words and meanings shall be interpreted as appropriate. Words implied, but not stated, shall be inferred as the sense requires. Singular words shall be interpreted as plural, and plural words shall be interpreted as singular where applicable as the context of the Contract Documents indicates.
 - 2. Imperative mood and streamlined language are generally used in the Specifications. Requirements expressed in the imperative mood are to be performed by Contractor. Occasionally, the indicative or subjunctive mood may be used in the Section Text for clarity to describe responsibilities that must be fulfilled indirectly by Contractor or by others when so noted.

- a. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
- C. Specification Coordination with Drawings: The following types of annotations are indicated on Drawings to identify products and materials included in the work and to identify corresponding specification sections that govern products, materials, quality, performance, and execution of work:
 1. By numbering system or sequence: The MasterFormat number for the corresponding specification section included in the Project Manual with a suffix to distinguish two or more products included in the same specification section.
 - a. Example: 081416.C.
 2. By naming conventions: Generic, commonly used, terminology or description that is understood throughout the design and construction industry.
 - a. Example: Flush Wood Door.
 3. By combination: A numbering system or sequence combined with a conventional name.
 - a. Example: 081416.C Flush Wood Door.

1.13 CODES AND STANDARDS

- A. All references to codes, specifications and standards referred to in the Contract Documents shall mean, and are intended to be, the edition indicated in the corresponding construction subcode that governs the work or portion of the work indicated.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 01 10 00

SECTION 01 17 00 – EROSION AND SEDIMENTATION CONTROL PLAN

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section describes Erosion and Sedimentation Control plan goals and includes administrative and procedural requirements for the development and execution of an Erosion and Sedimentation Control Plan.
- B. Related Sections include the following:
 - 1. Division 1 Section "Submittal Procedures" for required submittal procedures.
 - 2. Division 1 Section "Temporary Facilities and Controls" requirements for installation, maintenance and removal of temporary utilities, controls, and facilities during construction.
 - 3. Division 1 Section "LEED Requirements" for special requirements for LEED certification

1.3 EROSION AND SEDIMENTATION CONTROL SUMMARY

- A. Erosion control strategies must be designed in accordance with US Environmental Protection Agency (EPA) no. EPA 832/r-92-005 (1992), storm water management for construction activities, Chapter 3: Sedimentation and Erosion Control, or local erosion and sedimentation control standards and codes, whichever is more stringent.
- B. The purpose of this procedure is to control erosion in order to reduce negative impacts on water and air quality. Proactive measures will address ongoing maintenance of a facility's site as well as provide for future construction and repairs to the site.
- C. The erosion and sedimentation control plan must meet the following objectives:
 - 1. Prevent loss of soil during construction by storm water runoff and/or wind erosion, including protecting topsoil by stockpiling for reuse.
 - 2. Prevent sedimentation of storm sewer or receiving streams.
 - 3. Prevent polluting the air with dust and particular matter.
 - 4. Building operations and maintenance activity will be logged to ensure that plan has been followed.
- D. Establish an erosion and sediment control policy that conforms to set practices set by the US EPA or other more stringent municipal standards. Provide a method for tracking and documenting that the policies have been followed.

- E. Procedure and strategies include a policy that mandates implementation of erosion and sediment control techniques and requires the techniques' inclusion into contract documents for any construction projects carried out on site. Consider employing strategies that address temporary and permanent landscaping issues and changes; erosion caused by pedestrian traffic; and stormwater overflow. Ongoing identification and elimination of these causes of erosion on sites are important components of addressing erosion and sedimentation.
- F. A facility manager will be responsible for the ongoing implementation and will sign off the facility sedimentation and erosion policy.

1.4 SUBMITTALS

- A. Provide copies of the project drawings to document the erosion and sedimentation control measures implemented on the site.
- B. Provide confirmation regarding the compliance path taken by the project (NPDES Compliance or Local Erosion Control Standards).
- C. Provide a narrative to describe the Erosion and Sedimentation control measures implemented on the project. If a local standard has been followed, provide specific information to demonstrate that the local standard is equal to or more stringent than the reference NPDES program.

1.5 EROSION AND SEDIMENTATION CONTROL PLAN

- A. Contractor shall install erosion controls as shown on the plan and/or other project specifications, all in compliance with local governing agencies, EPA. Contractor shall file and give notice to the appropriate parties at a minimum 48 hours prior to construction. It is the obligation of the operator/contractor, subcontractor, and permittee to understand and comply with any required federal and/or local governing agencies.
- B. The operator or operators involved with construction activities including clearing, grading, and excavating that result in land disturbance will need to implement pollutant control measures identified on the drawings and must comply with the requirements of EPA and local governing agency having jurisdiction concerning erosion and sedimentation control, along with any additional documents or amendments.
- C. Post a signed copy of the construction site notice at the construction site in a location where it is readily available for viewing by the general public, local, state, and federal authorities, prior to commencing construction activities, and maintain the notice in that location until completion of the construction activity.
- D. Provide a copy of the signed and certified construction site notice to the operator of any municipal separate storm sewer system receiving the discharge at least two days prior to commencement of construction activities.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 IMPLEMENTATION OF EROSION AND SEDIMENTATION CONTROL PLAN

- A. Construct rock pads for construction entrance/exit. This will be the first construction work on the project.
- B. Install sediment barriers down slope from construction activities that disturb site soil.
- C. Construct rock surface for temporary parking.
- D. A rock filter dam will be placed at the outfall of any proposed detention/storm water quality pond as temporary outfall protection and provide filtration of larger soil particles.
- E. Clear and grub the improvement areas. Sediment barriers will already be in place down slope.
- F. Excavation and embankment to form drainage channels.
- G. Excavation and embankment to form the building pad and pavement areas.
- H. Underground Utilities - Sediment barriers will be utilized as required to bound the down slope side of utility construction and soil stockpiles.
- I. Final Grading - Sediment barriers will be maintained down slope from disturbed soil during this operation.
- J. Completion of on-site stabilization. (Contractor must obtain a minimum of 70% vegetation or the minimum requirement by local governing agency.) The actual schedule for implementing pollutant control measures will be determined by project construction progress. Down slope protective measures must always be in place before soil is disturbed.

END OF SECTION 01 17 00

SECTION 01 25 00 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Sections:
 - 1. Section 01 60 00 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.
 - 2. Divisions 03 through 49 Sections for specific requirements and limitations for substitutions.

1.3 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.
 - 1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
 - 2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required in order to meet other Project requirements but may offer advantage to Contractor or Owner.

1.4 ACTION SUBMITTALS

- A. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution Request Form: Use form provided as Section 00 60 06 "Substitution Request."
 - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.
 - b. Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors, necessary to accommodate proposed substitution.

- c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
 - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - e. Samples, where applicable or requested.
 - f. Certificates and qualification data, where applicable or requested.
 - g. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.
 - h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - i. Research reports evidencing compliance with building code in effect for Project, from a model code organization acceptable to authorities having jurisdiction.
 - j. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
 - k. Cost information, including a proposal of change, if any, in the Contract Sum.
 - l. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
 - m. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
- a. Forms of Acceptance: Change Order, Construction Change Directive, or Bulletin for minor changes in the Work.
 - b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.5 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage qualified testing agency to perform compatibility tests recommended by manufacturers.

1.6 PROCEDURES

- A. Coordination: Modify or adjust affected work as necessary to integrate work of the approved substitutions.

PART 2 - PRODUCTS

2.1 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately upon discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
 - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
 - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - b. Requested substitution provides sustainable design characteristics that specified product provided for achieving LEED prerequisites and credits.
 - c. Substitution request is fully documented and properly submitted.
 - d. Requested substitution will not adversely affect Contractor's construction schedule.
 - e. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - f. Requested substitution is compatible with other portions of the Work.
 - g. Requested substitution has been coordinated with other portions of the Work.
 - h. Requested substitution provides specified warranty.
 - i. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- B. Substitutions for Convenience: Architect will consider requests for substitution if received within 30 days after commencement of the Work. Requests received after that time may be considered or rejected at discretion of Architect.
 - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
 - a. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
 - b. Requested substitution does not require extensive revisions to the Contract Documents.

- c. Requested substitution is consistent with the Contract Documents and will produce indicated results.
- d. Requested substitution provides sustainable design characteristics that specified product provided for achieving LEED prerequisites and credits.
- e. Substitution request is fully documented and properly submitted.
- f. Requested substitution will not adversely affect Contractor's construction schedule.
- g. Requested substitution has received necessary approvals of authorities having jurisdiction.
- h. Requested substitution is compatible with other portions of the Work.
- i. Requested substitution has been coordinated with other portions of the Work.
- j. Requested substitution provides specified warranty.
- k. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 01 25 00

SECTION 01 26 00 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for handling and processing Contract modifications.
- B. Related Requirements:
 - 1. Section 01 25 00 "Substitution Procedures" for administrative procedures for handling requests for substitutions made after the Contract award.

1.3 MINOR CHANGES IN THE WORK

- A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Architect's Supplemental Instructions, "Bulletin" form included as Section 00 60 07, or form acceptable to Owner.

1.4 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Proposal Requests issued by Architect are for information only. Do not consider them instructions either to stop work in progress or to execute the proposed change.
 - 2. Within 20 days after receipt of Proposal Request, when not otherwise specified, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and supervision directly attributable to the change.
 - d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.

- B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.
1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 4. Include costs of labor and supervision directly attributable to the change.
 5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 6. Comply with requirements in Section 01 25 00 "Substitution Procedures" if the proposed change requires substitution of a specified product or system.
- C. Proposal Request Form: Use AIA Document G709, Proposal Request.

1.5 ADMINISTRATIVE CHANGE ORDERS

1.6 CHANGE ORDER PROCEDURES

- A. Upon Owner's approval of a Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701, Change Order.

1.7 CONSTRUCTION CHANGE DIRECTIVES

- A. Construction Change Directive: Owner may issue an Architect prepared Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

Gensler

057.7202.950

Bank of America / BAC Specification / Specification Update / 01-27-14

January 22, 2021
Issue for Construction

Bank of America
BAC Centerville GU
Centerville, UT

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 01 26 00

SECTION 01 26 13 – REQUESTS FOR INTERPRETATION (RFI)

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for handling and processing Requests for Interpretation.

1.2 DEFINITIONS

- A. Requests for Interpretation (RFI): Contractor initiated written instrument related to the execution of the Work that is addressed to the Architect. The RFI shall be used by the Contractor as the means to ask questions related to the Work; subject to the conditions contained within this Section.

1.3 ACTION SUBMITTALS

- A. Requests for Interpretation: Include a detailed, legible description of an item needing information or interpretation and the following:
 - 1. Project name.
 - 2. Project number.
 - 3. Date.
 - 4. Name of Contractor.
 - 5. Name of Architect.
 - 6. RFI number, numbered sequentially.
 - 7. RFI subject.
 - 8. Reference to appropriate documents:
 - a. Specification Section number and title and related paragraphs.
 - b. Drawing number and detail references.
 - c. Schedule.
 - d. Bulletin number.
 - e. Other Contract Documents, if any.
 - 9. Field dimensions and conditions, as appropriate.
 - 10. Contractor's suggested resolution. If Contractor's suggested resolution impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
 - 11. Contractor's and RFI Manager's signature.
 - 12. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
 - a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.
- B. RFI Forms: Use "Request for Interpretation" form bound in Section 00 60 00 "Forms."

1.4 INFORMATIONAL SUBMITTALS

- A. RFI Log: Prepare, maintain, and submit a tabular log of RFI organized by the RFI number. Submit log weekly. Include the following:
1. Project name.
 2. Name and address of Contractor.
 3. Name and address of Architect.
 4. RFI number including RFIs that were returned without action or withdrawn.
 5. RFI description.
 6. Date the RFI was submitted.
 7. Date Architect's response was received.

1.5 QUALITY ASSURANCE

- A. Authorship: Prior to the commencement of the RFI process, designate a full time "RFI Manager" whose duties shall include the responsibility for enforcing the Request for Interpretation provisions of this Section, to maintain an up-to-date log of all RFI, advise the Architect, in writing, of the status and disposition of all RFI at the progress meetings, and be a member of the Contractor's staff. The RFI Manager shall be experienced in administration and supervision of the type of Work indicated on the Contract Documents.
1. RFI Manager may be the Contractor's Job Superintendent.
 2. Each RFI shall originate solely from the RFI Manager. An RFI submitted to the Architect by an entity, or individual, other than the RFI Manager shall be returned to the Contractor.

1.6 ADMINISTRATIVE REQUIREMENTS

- A. Processing Time: Allow five working days for Architect's response for each RFI.
1. Allow additional time if coordination with other work is required. Architect will advise Contractor when a RFI being processed must be delayed for coordination.
 2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt of additional information.
- B. Architect's action on RFI that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Proposal Request according to Section 01 26 00 "Contract Modification Procedures."
1. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.
- C. Frivolous RFI:
1. RFI shall not be used for the following:
 - a. Request for approval of submittals.
 - b. Request approval of substitutions.
 - c. Requests for approval of Contractor's means and methods.

- d. Request for adjustment in the Contract Time or the Contract Sum.
 - e. Requests for interpretation of Architect's actions on submittals.
 - f. Requests for coordination information already indicated in the Contract Documents, or to transfer coordination responsibility from the Contractor to the Owner or Architect.
 - g. Incomplete RFI or inaccurately prepared RFI.
- 2. The Owner reserves the right to assess the Contractor for the cost (based on time and materials) of a RFI response performed by the Architect, and any of its consultants, which is deemed by the Owner and the Architect as being frivolous or unnecessary.
 - 3. Frivolous RFI shall be removed from the RFI log.

1.7 COORDINATION

- A. Coordination: Coordinate preparation and processing of RFI with performance of construction activities.
 - 1. Submit RFI with such promptness as to cause no delays in the Work. No adjustments of Contract Time or Contract Sum will be granted because of failure to have an RFI submitted with sufficient time to allow for the orderly processing of a response by the Architect.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 CONTRACTOR'S ACTION

- A. General: Immediately on discovery of the need for additional information or interpretation of the Contract Documents, prepare and submit an RFI in the form specified.
- B. Prior to submission of the RFI, coordinate the nature of the inquiry with the requirements of other Sections or trades as related thereto and responses to previous RFI.
- C. Complete each blank on the RFI form.
- D. In preparing each RFI, verify the applicable dimension(s), field conditions, Drawing requirements (small through large scale details), and/or Specification Section requirements pertaining thereto.
- E. Each RFI shall be reviewed, and signed by the RFI Manager prior to transmitting to the Architect.
- F. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within seven days if Contractor disagrees with response.

3.2 ARCHITECT'S ACTION

- A. Architect's Action: Architect will review each RFI, determine action required, and respond.
 - 1. Frivolous RFI will be returned without action.
- B. RFI which fail to conform to requirements, (for example, is incomplete or contain numerous errors) shall be returned to the Contractor without a response. No adjustments for Contract Time or Contract Sum shall be granted for an RFI failing to conform to requirements.

END OF SECTION 01 26 13

SECTION 01 29 00 – PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section specifies administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Sections include the following:
 - 1. Section 01 26 00 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.

1.3 DEFINITIONS

- A. Site Visit: Architect's visits to the site at intervals necessary in the judgment of Architect to become generally familiar with the progress and quality of the Work completed and to determine in general if the Work completed is in accordance with the Contract Documents. Architect will not be required to make exhaustive or continuous on-site inspections to check the quality or quantity of the Work.
- B. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

1.4 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the Schedule of Values with preparation of Contractor's Construction Schedule.
 - 1. Correlate line items in the Schedule of Values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with Continuation Sheets.
 - b. Submittals Schedule.
 - c. Items required to be indicated as separate activities in Contractor's Construction Schedule.
 - 2. Submit the Schedule of Values to Owner at earliest possible date but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
 - 3. Subschedules for Phased Work: Where the Work is separated into phases requiring separately phased payments, provide subschedules showing values correlated with each phase of payment.
- B. Format and Content: Use the Project Manual table of contents as a guide to establish line items for the Schedule of Values. Provide at least one line item for each Specification Section.

1. Identification: Include the following Project identification on the Schedule of Values:
 - a. Project name and location.
 - b. Name of Architect.
 - c. Architect's project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
2. Arrange schedule of values consistent with format of AIA Document G703.
3. Arrange the Schedule of Values in tabular form with separate columns to indicate the following for each item listed:
 - a. Related Specification Section or Division.
 - b. Description of the Work.
 - c. Name of subcontractor.
 - d. Name of manufacturer or fabricator.
 - e. Name of supplier.
 - f. Change Orders (numbers) that affect value.
 - g. Dollar value of the following, as a percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.
 - 1) Labor.
 - 2) Materials.
 - 3) Equipment.
4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with the Project Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five percent of Contract Sum.
 - a. Include separate line items under principal subcontracts for labor, materials, LEED documentation and other Project closeout requirements.
5. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
6. Provide a separate line item in the Schedule of Values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - a. Differentiate between items stored on-site and items stored off-site only if permitted under the Construction Contract. Include evidence of insurance or bonded warehousing for items stored off-site when permitted.
7. Provide separate line items in the Schedule of Values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
8. Allowances: Provide a separate line item in the Schedule of Values for each allowance. Show line-item value of unit-cost allowances, as a product of the unit cost, multiplied by measured quantity. Use information indicated in the Contract Documents to determine quantities.
9. Each item in the Schedule of Values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
 - a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the Schedule of Values or distributed as general overhead expense, at Contractor's option.
10. Schedule Updating: Update and resubmit the Schedule of Values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.5 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
 - 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: Progress payments shall be submitted to Owner on the 1st day of the month. The period covered by each Application for Payment is one month, ending on the last day of the month.
- C. Payment Application Review:
 - 1. Submit draft (pencil) copy of the Application for Payment at least ten days prior to due date for review by Owner.
 - 2. On the 25th day of each month, the Owner and Contractor shall meet to review the draft (pencil) copy of the Application for Payment. Questions resulting from this review shall be answered by the Contractor and clarified prior to receipt of the final copy of the Application for Payment.
 - 3. Upon receipt of the final Application for Payment and other documentation as required by the Owner, including the updated Schedule of Values and the updated Contractor's Construction Schedule, the Owner shall review the documents received to determine if they correspond to the agreements reached during the draft (pencil) copy review. Upon completion of the Owner's review, the Owner shall revise and execute the Applications and Certificate for Payment to correspond to the agreements reached and forward the executed copies to the Contractor.
 - 4. In taking action on the Contractor's Application for Payment, the Owner will rely on the accuracy and completeness of the information furnished by the Contractor and will not be deemed to represent that he has made audits of the supporting data.
- D. Payment Application Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
- E. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Owner will return incomplete applications without action.
 - 1. Entries shall match data on the Schedule of Values and Contractor's Construction Schedule. Use updated schedules if revisions were made.
 - 2. Include amounts of work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
 - 3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
 - 4. Indicate separate amounts for work being carried out under Owner-requested project acceleration, if any.
- F. Stored Materials and Equipment: Payments will not be made for materials and equipment stored off-site, except at the Owner's discretion and prior approval. When the Application for Payment includes amounts for materials or equipment purchased or fabricated and stored off-site, the Application for Payment shall be accompanied by a statement certifying:
 - 1. Description of item(s) being stored.

2. Location of the bonded warehouse(s) where materials or equipment is stored.
 3. Affidavit of Storage.
 4. Bill of sale made to Owner stating there will be no additional cost for transportation and delivery of the stored item(s).
 5. Statement certifying that item or any part thereof will not be installed in any construction other than Work under this Contract.
 6. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment, for stored materials.
 7. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
 8. Provide summary documentation for stored materials indicating the following:
 - a. Materials previously stored and included in previous Applications for Payment.
 - b. Work completed for this Application utilizing previously stored materials.
 - c. Additional materials stored with this Application.
 - d. Total materials remaining stored, including materials with this application.
- G. Transmittal: Submit 3 signed and notarized original copies of each Application for Payment to Owner by a method ensuring receipt within 24 hours. One copy shall include waivers of lien and similar attachments if required.
1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- H. Waivers of Mechanic's Lien: With each Application for Payment, submit notarized waivers of mechanic's lien from every entity who is lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
1. Submit partial waivers on each item for amount requested, before deduction for retainage, on each item.
 2. When an application shows completion of an item, submit final or full waivers.
 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
 4. Waiver Delays: Submit each Application for Payment with Contractor's waiver of mechanic's lien for construction period covered by the application.
 - a. Submit final Application for Payment with or preceded by final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
 5. Waiver Forms: Submit waivers of lien on forms, executed in a manner acceptable to Owner.
- I. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
1. List of subcontractors, principal suppliers and fabricators.
 2. Schedule of Values.
 3. LEED submittal for project materials cost data.
 4. LEED action plans.
 5. Contractor's Construction Schedule (preliminary if not final).
 6. Products list (preliminary if not final).
 7. Schedule of unit prices.
 8. Submittals Schedule (preliminary if not final).
 9. List of Contractor's staff assignments.

10. List of Contractor's principal consultants.
 11. Copies of building permits.
 12. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 13. Initial progress report.
 14. Report of preconstruction conference.
 15. Certificates of insurance and insurance policies.
 16. Data needed to acquire Owner's insurance.
 17. Performance and payment bonds, if provided under the Construction Contract.
 18. Construction Waste Management Program.
- J. Application for Payment at Substantial Completion: After issuance of the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 2. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
 3. Submit occupancy permits and similar approvals or certifications by governing authorities and franchised services, assuring Owner's full access and use of completed work.
 4. Submit executed warranty and maintenance agreements.
 5. Deliver extra materials.
- K. Final Payment Application: Submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
1. Evidence of completion of Project closeout requirements, including, but not limited to:
 - a. Transmittal of required Project Record Documents to Owner.
 - b. Evidence of completion of demonstration and training.
 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 3. Updated final statement, accounting for final changes to the Contract Sum.
 4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
 5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
 6. AIA Document G707, "Consent of Surety to Final Payment."
 7. Evidence that claims have been settled.
 8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
 9. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 01 29 00

SECTION 01 31 00 – PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
 - 1. General project coordination procedures.
 - 2. Conservation.
 - 3. Coordination Drawings.
 - 4. Administrative and supervisory personnel.
 - 5. Project meetings.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Section 01 73 00 "Execution" for procedures for coordinating general installation and field-engineering services.
 - 2. Section 01 77 00 "Closeout Procedures" for coordinating Contract closeout.

1.3 COORDINATION

- A. Coordination: Coordinate construction operations included in various Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components with other contractors to ensure maximum accessibility for required maintenance, service, and repair.
 - 3. Make adequate provisions to accommodate items scheduled for later installation.
- B. If necessary, prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
 - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.

- C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other contractors to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
 - 1. Preparation of Contractor's Construction Schedule.
 - 2. Preparation of Contractor's Submittal Schedule.
 - 3. Preparation of the Schedule of Values.
 - 4. Installation and removal of temporary facilities and controls.
 - 5. Delivery and processing of submittals.
 - 6. Progress meetings.
 - 7. Preinstallation conferences.
 - 8. Project closeout activities.
- D. Conservation: Coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials.

1.4 SUBMITTALS

- A. Coordination Drawings: Prepare Coordination Drawings if limited space availability necessitates maximum utilization of space for efficient installation of different components or if coordination is required for installation of products and materials fabricated by separate entities.
 - 1. Indicate relationship of components shown on separate Shop Drawings.
 - 2. Indicate required installation sequences.
 - 3. Refer to Divisions in the Facility Services Subgroup for specific Coordination Drawing requirements for mechanical and electrical installations.
- B. Staff Names: Within 15 days of starting construction operations, submit a list of principal staff assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers, including home and office telephone numbers. Provide names, addresses, and telephone numbers of individuals assigned as standbys in the absence of individuals assigned to Project.
 - 1. Post copies of list in Project meeting room, in temporary field office, and by each temporary telephone.

1.5 ADMINISTRATIVE AND SUPERVISORY PERSONNEL

- A. General: In addition to Project superintendent, provide other administrative and supervisory personnel as required for proper performance of the Work. Refer to General Conditions for additional requirements.

1.6 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site, unless otherwise indicated.

1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
 3. Minutes: Record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within 3 days of the meeting.
 4. Notification: Inform participants 3 days prior to meetings not regularly scheduled.
- B. Preconstruction Conference: Schedule a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement. Hold the conference at Project site or another convenient location. Conduct the meeting to review responsibilities and personnel assignments.
1. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; manufacturers; suppliers; testing laboratory representatives; and other concerned parties shall attend the conference. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 2. Agenda: Discuss items of significance that could affect progress, including the following:
 - a. Requirements in individual Specification Sections for preconstruction responsibilities.
 - b. Tentative construction schedule.
 - c. Project coordination.
 - d. Phasing, if any.
 - e. Critical work sequencing.
 - f. Designation of responsible personnel.
 - g. Procedures for processing Requests for Interpretation (RFI's.)
 - h. Procedures for processing Bulletins.
 - i. Procedures for processing submittals.
 - j. Procedures for processing substitutions.
 - k. Procedures for processing field decisions, proposal requests and Change Orders.
 - l. Procedures for processing Applications for Payment.
 - m. Distribution of the Contract Documents.
 - n. LEED or sustainable design requirements.
 - o. Preparation of Record Documents.
 - p. Use of the premises.
 - q. Responsibility for temporary facilities and controls.
 - r. Parking availability.
 - s. Office, work, and storage areas.
 - t. Equipment deliveries and priorities.
 - u. First aid.
 - v. Security.
 - w. Progress cleaning.
 - x. Working hours.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.

1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect of scheduled meeting dates.
 2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
 - a. Contract Documents.
 - b. Options.
 - c. Related Requests for Interpretation.
 - d. Related Change Orders.
 - e. Purchases.
 - f. Deliveries.
 - g. Submittals.
 - h. LEED or sustainable design requirements.
 - i. Review of mockups.
 - j. Possible conflicts.
 - k. Compatibility requirements for materials.
 - l. Time schedules.
 - m. Weather limitations.
 - n. Manufacturer's written recommendations.
 - o. Warranty requirements.
 - p. Acceptability of substrates.
 - q. Temporary facilities and controls.
 - r. Space and access limitations.
 - s. Regulations of authorities having jurisdiction.
 - t. Testing and inspecting requirements.
 - u. Installation procedures.
 - v. Coordination with other work.
 - w. Required performance results.
 - x. Protection of adjacent work.
 - y. Protection of construction and personnel.
 3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
 4. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
 5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.
- D. Progress Meetings: Conduct progress meetings at weekly intervals. Coordinate dates of meetings with preparation of payment requests. Schedule and administer special meetings as required.
1. Attendees: In addition to representatives of Owner, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work. Architect may attend.

2. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's Construction Schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - b. Review present and future needs of each entity present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Status of LEED or sustainable design documentation.
 - 5) Deliveries.
 - 6) Off-site fabrication.
 - 7) Access.
 - 8) Site utilization.
 - 9) Temporary facilities and controls.
 - 10) Work hours.
 - 11) Hazards and risks.
 - 12) Progress cleaning.
 - 13) Quality and work standards.
 - 14) Status of Change Orders.
 - 15) Documentation of information for payment requests.
 - 16) Testing and inspection requirements.
 - 17) Status of Requests for Interpretation.
 - 18) Other business relating to the Work.
3. Reporting: Distribute minutes of the meeting to each party present and to parties who should have been present. Include a brief summary, in narrative form, of progress since the previous meeting and report.
 - a. Schedule Updating: Revise Contractor's Construction Schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.
- E. Coordination Meetings: Conduct Project coordination meetings at weekly intervals. Project coordination meetings are in addition to specific meetings held for other purposes, such as progress meetings and preinstallation conferences.
 1. Attendees: Every entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work. Owner and Architect may attend.
 2. Agenda: Review and correct or approve minutes of the previous coordination meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.

- a. Combined Contractor's Construction Schedule: Review progress since the last coordination meeting. Determine whether each contract is on time, ahead of schedule, or behind schedule, in relation to Combined Contractor's Construction Schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - b. Schedule Updating: Revise Combined Contractor's Construction Schedule after each coordination meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with report of each meeting.
 - c. Review present and future needs of each contractor present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Deliveries.
 - 5) Off-site fabrication.
 - 6) Access.
 - 7) Site utilization.
 - 8) Temporary facilities and controls.
 - 9) Work hours.
 - 10) Hazards and risks.
 - 11) Progress cleaning.
 - 12) Quality and work standards.
 - 13) Change Orders.
3. Reporting: Record meeting results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from each meeting.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 01 31 00

SECTION 01 32 00 – CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
 - 1. Contractor's construction schedule.
 - 2. Contractor's submittal schedule.
 - 3. Daily construction reports.
 - 4. Site condition reports.
 - 5. Special reports.
 - 6. Construction photographs.
- B. Related Sections include the following:
 - 1. Section 01 29 00 "Payment Procedures" for submitting the Schedule of Values.
 - 2. Section 01 31 00 "Project Management and Coordination" for submitting and distributing meeting and conference minutes.

1.3 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.
 - 1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
 - 2. Predecessor Activity: An activity that precedes another activity in the network.
 - 3. Successor Activity: An activity that follows another activity in the network.
- B. Cost Loading: The allocation of the schedule of values for the completion of an activity as scheduled. The sum of costs for all activities must equal the total Contract Sum unless otherwise approved by Architect.
- C. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.
- D. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.

- E. Event: The starting or ending point of an activity.
- F. Float: The measure of leeway in starting and completing an activity.
 - 1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.
 - 2. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
 - 3. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.
- G. Fragnet: A partial or fragmentary network that breaks down activities into smaller activities for greater detail.
- H. Major Area: A story of construction, a separate building, or a similar significant construction element.
- I. Milestone: A key or critical point in time for reference or measurement.
- J. Network Diagram: A graphic diagram of a network schedule, showing activities and activity relationships.
- K. Resource Loading: The allocation of manpower and equipment necessary for the completion of an activity as scheduled.

1.4 INFORMATIONAL SUBMITTALS

- A. Format for Submittals: Submit required submittals in the following format:
 - 1. Working electronic copy of schedule file, where indicated.
 - 2. PDF electronic file.
- B. Contractor's Construction Schedule: Submit three paper copies of initial schedule, large enough to display entire schedule for entire construction period.
 - 1. Submit a working electronic copy of schedule, labeled to comply with requirements for submittals. Include type of schedule (initial or updated) and date on label.
- C. CPM Reports: Concurrent with CPM schedule, submit three paper copies of each of the following computer-generated reports. Format for each activity in reports shall contain activity number, activity description, original duration, remaining duration, early start date, early finish date, late start date, late finish date, and total float in calendar days.
 - 1. Activity Report: List of all activities sorted by activity number and then early start date, or actual start date if known.
 - 2. Logic Report: List of preceding and succeeding activities for all activities, sorted in ascending order by activity number and then early start date, or actual start date if known.
 - 3. Total Float Report: List of all activities sorted in ascending order of total float.

- D. Daily Construction Reports: Submit two copies plus a PDF electronic file at monthly intervals.
- E. Site Condition Reports: Submit two copies plus a PDF electronic file at time of discovery of differing conditions.
- F. Construction Waste Management Report: Submit two copies plus a PDF electronic file at monthly intervals.
- G. Special Reports: Submit two copies plus a PDF electronic file at time of unusual event.

1.5 QUALITY ASSURANCE

- A. Scheduling Consultant Qualifications: Engage an experienced specialist or consultant to provide planning, evaluation, and reporting using CPM scheduling with capability of producing CPM reports and diagrams within 24 hours of request.
 - 1. In-House Option: Contractor may employ skilled personnel with experience in CPM scheduling and reporting techniques.
 - 2. Meetings: Scheduling consultant shall attend all meetings related to Project progress, alleged delays, and time impact.

1.6 COORDINATION

- A. Coordinate preparation and processing of schedules and reports with performance of construction activities and with scheduling and reporting of separate contractors.
- B. Coordinate Contractor's construction schedule with the schedule of values, list of subcontracts, submittal schedule, progress reports, payment requests, and other required schedules and reports.
 - 1. Secure time commitments for performing critical elements of the Work from parties involved.
 - 2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

PART 2 - PRODUCTS

2.1 CONTRACTOR'S SUBMITTALS SCHEDULE

- A. Preparation: Submit a schedule of submittals, arranged in chronological order by dates required by Construction Schedule. Include time required for review, resubmittal, ordering, manufacturing, fabrication, and delivery when establishing dates. Include the following information:
 - 1. Submittal category (action or informational).
 - 2. Description of the Work covered.
 - 3. Specification Section (number and title) to which submittal relates.

4. Subcontractor, fabricator or supplier responsible for preparing the submittal.
 5. Anticipated date of Architect's receipt of submittal.
 6. Number of business days allowed for Architect's review of submittal.
 7. Scheduled date for Architect's final release or approval.
 8. Provide blank columns for actual date of submittal, re-submittal, and final-review status.
- B. Coordinate Submittals Schedule with the Schedule of Values and Contractor's Construction Schedule.
- C. Initial Submittal: Submit within 10 days of Owner's authorization or Notice to Proceed with construction. Include submittals required during the first 60 days of construction. List those required to maintain orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
- D. Final Submittal: Submit concurrently with the first complete submittal of Contractor's Construction Schedule.
- E. Revisions: Notify Architect two weeks prior to any revisions to approved Final Submittal Schedule.

2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Procedures: Comply with procedures contained in AGC's "Construction Planning & Scheduling."
- B. Time Frame: Extend schedule from date established for commencement of the Work or a Notice to Proceed to date of Final Completion.
1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- C. Activities: Treat each story or separate area as a separate numbered activity for each principal element of the Work. Comply with the following:
1. Procurement Activities: Include procurement process activities for long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
 2. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Include selection process activities for finishes and products specified by allowances or specified to be selected during the sample review process. Coordinate submittal review times in Contractor's Construction Schedule with Submittals Schedule.
 3. Startup and Testing Time: Include not less than 5 days for startup and testing.
 4. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
 5. Punch List and Final Completion: Include not more than 15 days for completion of punch list items and final completion.

6. Building Flush-Out: Include at least 5 days for building flush-out as indicated in Section 01 81 19 "Indoor Air Quality (IAQ) Management."
 7. Demonstration and Training: Training of Owner's personnel as indicated in Division 01 Section 01 79 00 "Demonstration and Training."
- D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.
1. Phasing: Arrange list of activities on schedule by phase.
 2. Work under More Than One Contract: Include a separate activity for each contract.
 3. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
 4. Products Ordered in Advance: Include a separate activity for each product. Delivery dates indicated stipulate the earliest possible delivery date.
 5. Owner-Furnished Products: Include a separate activity for each product. Delivery dates indicated stipulate the earliest possible delivery date.
 6. Work Restrictions: Show the effect of the following items on the schedule:
 - a. Coordination with existing construction.
 - b. Limitations of continued occupancies.
 - c. Uninterruptible services.
 - d. Partial occupancy before Substantial Completion.
 - e. Use of premises restrictions.
 - f. Provisions for future construction.
 - g. Seasonal variations.
 - h. Environmental control.
 7. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:
 - a. Subcontract awards.
 - b. Submittals.
 - c. Purchases.
 - d. Mockups.
 - e. Fabrication.
 - f. Sample testing.
 - g. Deliveries.
 - h. Installation.
 - i. Tests and inspections.
 - j. Adjusting.
 - k. Curing.
 - l. Building flush-out.
 - m. Startup and placement into final use and operation.
 8. Construction Areas: Identify each major area of construction for each major portion of the Work. Indicate where each construction activity within a major area must be sequenced or integrated with other construction activities to provide for the following:
 - a. Structural completion or structural work.
 - b. Temporary enclosure and space conditioning.

- c. Building envelope or permanent enclosure.
 - d. Completion of HVAC installation.
 - e. Completion of electrical installation.
 - f. Completion of plumbing installation.
 - g. Completion of fire protection installation.
 - h. Completion of communications installations.
 - i. Completion of audio-visual installations.
 - j. Completion of security installations.
 - k. Substantial Completion.
 - E. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the commencement of the Work or Notice to Proceed, Substantial Completion, and Final Completion.
 - F. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:
 - 1. Unresolved issues.
 - 2. Unanswered RFI.
 - 3. Rejected or unreturned submittals.
 - 4. Notations on returned submittals.
 - 5. Pending modifications affecting the Work and Contract Time.
 - G. Computer Software: Prepare schedules using a program that has been developed specifically to manage construction schedules.
 - 1. Compatibility: All software shall comply with Bank of America master scheduling software requirements.
- 2.3 CONTRACTOR'S CONSTRUCTION SCHEDULE (CPM SCHEDULE)
- A. General: Prepare network diagrams using AON (activity-on-node) format.
 - B. Preliminary Network Diagram: Submit diagram within 10 days of date established for commencement of the Work or a Notice to Proceed. Outline significant construction activities for the first 60 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.
 - C. CPM Schedule: Prepare Contractor's Construction Schedule using a time-scaled CPM network analysis diagram for the Work.
 - 1. Develop network diagram in sufficient time to submit CPM schedule so it can be accepted for use no later than 10 days after date established for commencement of the Work or a Notice to Proceed.
 - a. Failure to include any work item required for performance of this Contract shall not excuse Contractor from completing all work within applicable completion dates, regardless of approval of the schedule.

2. Conduct educational workshops to train and inform key Project personnel, including subcontractors' personnel, in proper methods of providing data and using CPM schedule information.
 3. Establish procedures for monitoring and updating CPM schedule and for reporting progress. Coordinate procedures with progress meeting and payment request dates.
 4. Use "one workday" as the unit of time for individual activities. Indicate nonworking days and holidays incorporated into the schedule in order to coordinate with the Contract Time.
- D. CPM Schedule Preparation: Prepare a list of all activities required to complete the Work. Using the preliminary network diagram, prepare a skeleton network to identify probable critical paths.
1. Activities: Indicate the estimated time duration, sequence requirements, and relationship of each activity in relation to other activities. Include estimated time frames for the following activities:
 - a. Preparation and processing of submittals.
 - b. Mobilization and demobilization.
 - c. Purchase of materials.
 - d. Delivery.
 - e. Fabrication.
 - f. Utility interruptions.
 - g. Installation.
 - h. Work by Owner that may affect or be affected by Contractor's activities.
 - i. Testing and commissioning.
 - j. Punch list and final completion.
 2. Critical Path Activities: Identify critical path activities, including those for interim completion dates. Scheduled start and completion dates shall be consistent with Contract milestone dates.
 3. Processing: Process data to produce output data or a computer-drawn, time-scaled network. Revise data, reorganize activity sequences, and reproduce as often as necessary to produce the CPM schedule within the limitations of the Contract Time.
 4. Format: Mark the critical path. Locate the critical path near center of network; locate paths with most float near the edges.
 - a. Subnetworks on separate sheets are permissible for activities clearly off the critical path.
- E. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis using a network fragment to demonstrate the effect of the proposed change on the overall project schedule.
- F. Initial Issue of Schedule: Prepare initial network diagram from a sorted activity list indicating straight "early start-total float." Identify critical activities. Prepare tabulated reports showing the following:
1. Contractor or subcontractor and the Work or activity.
 2. Description of activity.

3. Principal events of activity.
4. Immediate preceding and succeeding activities.
5. Early and late start dates.
6. Early and late finish dates.
7. Activity duration in workdays.
8. Total float or slack time.
9. Average size of workforce.
10. Dollar value of activity (coordinated with the Schedule of Values).

G. **Schedule Updating:** Concurrent with making revisions to schedule, prepare tabulated reports showing the following:

1. Identification of activities that have changed.
2. Changes in early and late start dates.
3. Changes in early and late finish dates.
4. Changes in activity durations in workdays.
5. Changes in the critical path.
6. Changes in total float or slack time.
7. Changes in the Contract Time.

H. **Value Summaries:** Prepare two cumulative value lists, sorted by finish dates.

1. In first list, tabulate activity number, early finish date, dollar value, and cumulative dollar value.
2. In second list, tabulate activity number, late finish date, dollar value, and cumulative dollar value.
3. In subsequent issues of both lists, substitute actual finish dates for activities completed as of list date.
4. Prepare list for ease of comparison with payment requests; coordinate timing with progress meetings.
 - a. In both value summary lists, tabulate "actual percent complete" and "cumulative value completed" with total at bottom.

2.4 REPORTS

A. **Daily Construction Reports:** Prepare a daily construction report recording the following information concerning events at Project site:

1. List of subcontractors at Project site.
2. List of separate contractors at Project site.
3. Approximate count of personnel at Project site.
4. Equipment at Project site.
5. Material deliveries.
6. High and low temperatures and general weather conditions, including rain or snow accumulation.
7. Accidents.
8. Meetings and significant decisions.
9. Unusual events (refer to special reports).
10. Stoppages, delays, shortages, and losses.

11. Meter readings and similar recordings.
12. Tests and inspections, including name(s) of testing and inspection agency(ies).
13. Emergency procedures.
14. Orders and requests of authorities having jurisdiction.
15. Change Orders received and implemented.
16. Services connected and disconnected.
17. Equipment or system tests and startups.
18. Partial Completions and occupancies.
19. Substantial Completions authorized.

- B. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Interpretation. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

2.5 SPECIAL REPORTS

- A. General: Submit special reports directly to Owner within one day of an occurrence. Distribute copies of report to parties affected by the occurrence.
- B. Reporting Unusual Events: When an event of an unusual and significant nature occurs at Project site, whether or not related directly to the Work, prepare and submit a special report. List chain of events, persons participating, response by Contractor's personnel, evaluation of results or effects, and similar pertinent information. Advise Owner in advance when these events are known or predictable.

PART 3 - EXECUTION

3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.
1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
 3. As the Work progresses, indicate Actual Completion percentage for each activity.
 4. Notify Owner and Architect a minimum of one week prior to issuance of updated schedule of all anticipated significant revisions to the project schedule.
- B. Distribution: Distribute copies of approved schedule to Architect, Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
1. Furnish Owner and Architect with an updated electronic version of the project schedule each month.

2. Post electronic copies of the updated project schedule on the project website.
3. Post copies in Project meeting rooms and temporary field offices.
4. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

3.2 CONSTRUCTION PHOTOGRAPHS

- A. Photographer: Engage a qualified photographer to take construction photographs.
- B. General: Take photographs using the maximum range of depth of field, and that are in focus, to clearly show the Work. Photographs with blurry or out-of-focus areas will not be accepted.
 1. Maintain key plan with each set of construction photographs that identifies each photographic location.
- C. Digital Images: Submit digital images exactly as originally recorded in the digital camera, without alteration, manipulation, editing, or modifications using image-editing software.
 1. Digital Images: Provide images in JPG format, produced by a digital camera with minimum sensor size of 8 megapixels, and at an image resolution of not less than 3200 by 2400 pixels.
 2. Date and Time: Include date and time in file name for each image.
 3. Field Office Images: Maintain one set of images accessible in the field office at Project site, available at all times for reference. Identify images in the same manner as those submitted to Architect.
- D. Preconstruction Photographs: Before starting construction and subject to Owner approval, take four color photographs of Project site from different vantage points, as directed by Architect.
- E. Periodic Construction Photographs: Subject to Owner approval, take twelve color photographs monthly, coinciding with cut-off date associated with each Application for Payment. Select interior vantage points to best show status of construction and progress since last photographs were taken.
 1. Subject to Owner approval, take photographs for each submittal from the same viewpoint unless specifically directed otherwise by Architect.
- F. Final Completion Construction Photographs: Subject to Owner approval, take twelve color photographs after date of Substantial Completion for submission as Project Record Documents. Architect will direct photographer for desired vantage points.

END OF SECTION 01 32 00

SECTION 01 33 00 – SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.
- B. Related Sections include the following:
 - 1. Section 01 29 00 "Payment Procedures" for submitting Schedule of Values and Applications for Payment.
 - 2. Section 01 31 00 "Project Management and Coordination" for submitting Coordination Drawings.
 - 3. Section 01 32 00 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's Construction Schedule and construction photographs.
 - 4. Section 01 40 00 "Quality Requirements" for submitting test and inspection reports and for erecting mockups.
 - 5. Section 01 77 00 "Closeout Procedures" for submitting warranties, operation and maintenance manuals, and closeout submittals.
 - 6. Section 01 78 39 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
 - 7. Section 01 81 13 "Sustainable Design Requirements" for submitting documentation identified or required under LEED Submittals.

1.3 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as action submittals.
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as informational submittals.
- C. File Transfer Protocol (FTP): Communications protocol that enables transfer of files to and from another computer over a network and that serves as the basis for standard Internet protocols. An FTP site is a portion of a network located outside of network firewalls within which internal and external users are able to access files.

- D. Portable Document Format (PDF): An open standard file format licensed by Adobe Systems used for representing documents in a device-independent and display resolution-independent fixed-layout document format.

1.4 ACTION SUBMITTALS


- A. Submittal Schedule: Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or modifications to submittals noted by the Architect and additional time for handling and reviewing submittals required by those corrections.
1. Coordinate submittal schedule with list of subcontracts, the schedule of values, and Contractor's construction schedule.
 2. Initial Submittal: Submit concurrently with start-up construction schedule. Include submittals required during the first 14 days of construction. List those submittals required to maintain orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
 3. Final Submittal: Submit concurrently with the first complete submittal of Contractor's construction schedule.
 - a. Submit revised submittal schedule to reflect changes in current status and timing for submittals.
 4. Format: Arrange the following information in a tabular format:
 - a. Scheduled date for first submittal.
 - b. Specification Section number and title.
 - c. Submittal category: Action, informational.
 - d. Name of subcontractor.
 - e. Description of the Work covered.
 - f. Scheduled date for Architect's final release or approval.
 - g. Scheduled dates for purchasing.
 - h. Scheduled dates for installation.
 - i. Activity or event number.
 5. Architect reserves the right to withhold 10 percent of each payment request, in addition to retainage fee if any, until the submittal schedule is received and accepted by the Architect.

1.5 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. Architect's Digital Data Files: At Contractor's written request, electronic copies of Drawings of the Contract Drawings will be provided by Architect for Contractor's use in preparing submittals. Architect makes no representations as to the accuracy or completeness of digital data files as they relate to the Contract Documents.
1. Architect will furnish Contractor one set of digital data drawing files of the Contract Drawings for use in preparing Shop Drawings and Project record drawings.

2. Provide an executed Data Transfer Agreement form included in Section 00 60 00 from each subcontractor and sub-subcontractor or supplier.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.
 3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.
 4. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
 - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- C. Processing Time: Promptly submit Shop Drawings, Product Data, and Samples in accordance with the accepted submittal schedule, as to cause no delay in the Work. Allow enough time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. Architect will document on submittal the date of receipt.
1. Initial Review: Duration of initial submittal review shall be as agreed upon in the final submittal schedule. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination. Delaying submittals to facilitate coordination between submittals shall not constitute a delay of the Work nor shall it be the basis for an extension of time.
 2. Sequential Review: Sequential review is a submittal that requires review by more than one design discipline. Where sequential review of submittals by Architect's consultants, Owner, or other parties is required, submittal schedule shall reflect sequential review.
 3. Direct Transmittal to Consultant for Concurrent Review: Transmit submittals directly to Architect's consultants, provide duplicate copy of transmittal to Architect. Duration of initial submittal review shall be as agreed upon in the final submittal schedule. Submittal will be returned to Architect before being returned to Contractor. Concurrent review of submittals is limited to the following:
 4. If intermediate submittal is necessary, process it in same manner as initial submittal.
 5. Number of days for processing each resubmittal shall be as agreed upon in the final submittal schedule.
 6. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
- D. Identification: Place a permanent label or title block on each submittal for identification.
1. Indicate name of firm or entity that prepared each submittal on label or title block.
 2. Provide a space approximately 5 inches by 6 inches on label or beside title block to record Architect's review markings.
 3. Include the following information on label for processing and recording action taken:

- a. Project name.
- b. Date.
- c. Name and address of Architect.
- d. Name and address of Contractor.
- e. Name and address of subcontractor.
- f. Name and address of supplier.
- g. Name of manufacturer.
- h. Unique identifier, including revision number. Submittals shall be numbered with a three-digit number, followed by a dash, followed by the Section number, followed by another dash, and ending with a sequential submission number as indicated below. The numbering system shall be retained throughout all revisions.
 - 1) Three-Digit Number: Sequential number, beginning with "001", for each submittal transmitted to Architect for each Section.
 - 2) Section Number: Section number where submittal is specified.
 - 3) Submission Number: Use "0" for initial submittal, "1" for first resubmittal, "2" for second resubmittal, and so forth.



- i. Number and title of appropriate Specification Section.
 - j. Drawing number and detail references, as appropriate.
 - k. Location(s) where product is to be installed, as appropriate.
 - l. Other necessary identification.
- E. Options: Identify options requiring selection by the Architect.
- F. Deviations: Highlight, encircle, or otherwise identify deviations from the Contract Documents on submittals.
- G. Additional Paper Copies: Unless corrected copies are required for final submittal due to Architect's observance of noncompliance with provisions of the Contract Documents, initial submittal may serve as final submittal.
1. Submit one copy of submittal to concurrent reviewer in addition to specified number of copies to Architect.
- H. Transmittal: Package each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Architect will discard submittals received from sources other than Contractor.

1. On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Architect on previous submittals, and deviations from requirements of the Contract Documents, including minor variations and limitations. Include the same label information as the related submittal.
 2. Include Contractor's certification stating that information submitted complies with requirements of the Contract Documents.
 3. Include a checklist of submittals required for each section, listing previously submitted, accepted, revised, and outstanding. Each checklist is to be signed by the Contractor.
- I. Transmittal Form: Use the form included in Section 00 60 00 "Forms" with each submittal.
- J. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
1. Note date and content of previous submittal.
 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
 3. Resubmit submittals until they are marked "A" or "B" from Architect's action stamp.
- K. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- L. Use for Construction: Use only final submittals with mark indicating action "A" or "B" taken by Architect in connection with construction.
- M. Substitution requests are not allowed in the form of submittals. Substitution requests must be made in accordance with Section 01 25 00 "Substitution Procedures."

PART 2 - PRODUCTS

2.1 SUBMITTAL PROCEDURES

- A. General: Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.
1. Action Submittals: Submit three paper copies of each submittal, unless otherwise indicated. Architect will return two copies. Mark up and retain one returned copy as a Project Record Document.
 2. Informational Submittals: Submit two paper copies of each submittal, unless otherwise indicated. Architect will not return copies.
 3. Certificates and Certifications Submittals: Provide a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.
 - a. Provide a notarized statement on original paper copy certificates and certifications where indicated.

- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
1. If information must be specially prepared for submittal because standard printed data are not suitable for use, submit as Shop Drawings, not as Product Data.
 2. Clearly mark each copy of each submittal to show which products and options are applicable.
 3. Include the following information, as applicable:
 - a. Manufacturer's catalog cuts.
 - b. Manufacturer's written recommendations.
 - c. Manufacturer's product specifications.
 - d. Standard color charts.
 - e. Mill reports.
 - f. Standard product operating and maintenance manuals.
 - g. Compliance with recognized trade association standards.
 - h. Compliance with recognized testing agency standards.
 - i. Application of testing agency labels and seals.
 - j. Notation of coordination requirements.
 - k. Availability and delivery time information.
 4. For equipment, include the following in addition to the above, as applicable:
 - a. Wiring diagrams showing factory-installed wiring.
 - b. Printed performance curves.
 - c. Operational range diagrams.
 - d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.
 5. Submit Product Data before or concurrent with Samples.
- C. Shop Drawings: Prepare and submit Project-specific information, drawn accurately to scale. Do not reproduce, digitally or otherwise, the Contract Documents and submit them as shop drawings. Contractor, subcontractors, suppliers and all other entities shall not use, copy or reproduce title blocks, dimensions, notes, keynotes, symbols schedules or details from Contract Drawings, digital or otherwise. Use of the Contract Drawings shall be limited to reproduction, digitally or otherwise, of the exterior wall layout, interior partition layout, grid lines, doors, and windows. Do not base Shop Drawings on standard printed data.
1. Preparation: Include the following information, as applicable:
 - a. Dimensions.
 - b. Identification of products.
 - c. Fabrication and installation drawings.
 - d. Roughing-in and setting diagrams.
 - e. Wiring diagrams showing field-installed wiring, including power, signal, and control wiring. Differentiate between manufacturer-installed and field-installed wiring.
 - f. Shopwork manufacturing instructions.
 - g. Templates and patterns.

- h. Schedules.
 - i. Design calculations.
 - j. Compliance with specified standards.
 - k. Notation of coordination requirements.
 - l. Notation of dimensions established by field measurement.
 - m. Relationship and attachment to adjoining construction clearly indicated.
 - n. Seal and signature of professional engineer if specified.
 - 2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches but no larger than 30 by 40 inches.
- D. Samples: Submit physical units of materials or products.
- 1. Comply with requirements in Section 01 40 00 "Quality Requirements" for mockups.
 - 2. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
 - a. Number of Samples: Submit one full set of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return submittal with options selected.
 - 3. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from the same material to be used for the Work, cured and finished in manner specified, and physically identical with the product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
 - a. Number of Samples: Submit three sets of Samples. Architect will retain one Sample set; remainder will be returned. Mark up and retain one returned Sample set as a Project record sample.
 - 1) Submit a single Sample where assembly details, workmanship, fabrication techniques, connections, operation, and other similar characteristics are to be demonstrated.
 - 2) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least three sets of paired units that show approximate limits of variations.
 - 4. Preparation: Mount, display, or package Samples in manner specified to facilitate review of qualities indicated. Prepare Samples to match Architect's sample where so indicated. Attach label on unexposed side that includes the following:
 - a. Generic description of Sample.
 - b. Product name or name of manufacturer.
 - c. Sample source.

5. Submit Samples for review of kind, color, pattern, and texture for a final check of these characteristics with other elements and for a comparison of these characteristics between final submittal and actual component as delivered and installed.
 - a. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
 - b. Refer to individual Specification Sections for requirements for Samples that illustrate workmanship, fabrication techniques, details of assembly, connections, operation, and similar construction characteristics.
6. Systems Submittals: Identify submittals for systems such as fire alarms, exterior walls, and curtain walls, on the transmittal and act upon the system singularly as a combined submittal. If resubmission is required, resubmit entire system submittal.
7. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
 - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.
 - b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
- E. Product Schedule or List: Prepare and submit a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
 1. Type of product. Include unique identifier for each product indicated in the Contract Documents.
 2. Number and name of room or space.
 3. Location within room or space.
 4. Manufacturer and product name, and model number if applicable.
- F. Subcontract List: Prepare and submit a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Submit on the form included in Section 00 60 00 "Forms," "Subcontractors and Major Material Suppliers List."
- G. Coordination Drawings: Comply with requirements specified in Section 01 32 00 "Project Management and Coordination."
- H. Qualification Data: Submit written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- I. Welding Certificates: Prepare and submit written certification that welding procedures and personnel comply with requirements. Submit record of Welding Procedure Specification (WPS) and Procedure Qualification Record (PQR) on AWS forms. Include names of firms and personnel certified.

- J. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements and, where required, is authorized by manufacturer for this specific Project.
- K. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements. Include evidence of manufacturing experience where required.
- L. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements.
- M. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements.
- N. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements.
- O. Preconstruction Test Reports: Prepare and submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements.
- P. Compatibility Test Reports: Prepare and submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
- Q. Field Test Reports: Prepare and submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements.
- R. Product Test Reports: Submit written reports indicating current product produced by manufacturer complies with requirements. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- S. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
 - 1. Name of evaluation organization.
 - 2. Date of evaluation.
 - 3. Time period when report is in effect.
 - 4. Product and manufacturers' names.
 - 5. Description of product.
 - 6. Test procedures and results.
 - 7. Limitations of use.

- T. Maintenance Data: Submit written and graphic instructions and procedures for operation and normal maintenance of products and equipment. Comply with requirements specified in Section 01 77 00 "Closeout Procedures."
- U. Manufacturer's Instructions: Submit written or published information that documents manufacturer's recommendations, guidelines, and procedures for installing or operating a product or equipment. Include name of product and name, address, and telephone number of manufacturer. Include the following, as applicable:
 - 1. Preparation of substrates.
 - 2. Required substrate tolerances.
 - 3. Sequence of installation or erection.
 - 4. Required installation tolerances.
 - 5. Required adjustments.
 - 6. Recommendations for cleaning and protection.
- V. Manufacturer's Field Reports: Prepare and submit written information documenting factory-authorized service representative's tests and inspections. Include the following, as applicable:
 - 1. Name, address, and telephone number of factory-authorized service representative making report.
 - 2. Statement on condition of substrates and their acceptability for installation of product.
 - 3. Statement that products at Project site comply with requirements.
 - 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
 - 5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 - 6. Statement whether conditions, products, and installation will affect warranty.
 - 7. Other required items indicated in individual Specification Sections.
- W. Material Safety Data Sheets: If requested by Owner, submit data sheets directly to Owner. Do not submit data sheets to Architect. Architect will not review data sheets and will not return them to Contractor.
- X. Certified Surveys: Comply with requirements specified in Section 01 73 00 "Execution."
- Y. Extra Stock: Comply with requirements specified in individual Sections for quantity and disposition of delivery of extra stock.

2.2 DELEGATED-DESIGN SERVICES

- A. Design Data: Prepare and submit written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.
- B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit three paper copies of certificate, signed and sealed by the

responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.

1. Indicate that products and systems comply with performance and design criteria in the Contract Documents.
- C. Delegated-Design Submittals: Comply with requirements specified in Section 01 40 00 "Quality Requirements."

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

- A. Review each submittal and check for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, coordinated, checked, and approved for compliance with the Contract Documents.

3.2 ARCHITECT'S ACTION

- A. General: Architect will not review submittals that do not bear Contractor's approval stamp and will return them without action.
- B. Action Submittals: Architect will review each properly executed submittal, make marks to indicate corrections or modifications required, and return it. Architect will reject and return submittals not complying with requirements. Architect will stamp each submittal with a stamp and will mark stamp appropriately to indicate action, as follows:
 1. **A** - No Exceptions Taken. No further review of Submittal required.
 2. **B** - Make Corrections as Noted. Incorporate corrections in Work; resubmittal is not required. If Contractor cannot comply with corrections as noted, revise to respond to exceptions and resubmit.
 3. **C** - Revise as Noted and Resubmit. Revise as noted & resubmit for further review.
 4. **D** - Resubmit Properly. Submittal not reviewed because it does not contain Contractor's signature indicating its review and approval, and/or is not in proper condition for review. Resubmit.
 5. **E** - Not Reviewed. Submittal is not required by Contract Documents.
 6. **F** - Received for Client's Record Only. Submittal not reviewed.
- C. Informational Submittals: Architect will review each submittal and will not return it, or will reject and return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- D. Incomplete submittals are not acceptable, will be considered nonresponsive, and will be returned without review.

1. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.
- E. Submittals not required by the Contract Documents will not be reviewed and may be discarded or returned marked "Not Reviewed."
- F. Substitution items received as product data, shop drawing, or sample submittals required by individual Sections will be returned to Contractor without review. Comply with requirements in Section 01 25 00 "Substitution Procedures" for submission of substitution request.

END OF SECTION 01 33 00

- ☐ **NO EXCEPTIONS TAKEN.**
- ☐ **MAKE CORRECTIONS AS NOTED.** Resubmittal not required unless Contractor cannot comply with corrections noted.
- ☐ **REVISE AS NOTED AND RESUBMIT.**
- ☐ **RESUBMIT PROPERLY.** Submittal not reviewed for reasons noted.
- ☐ **NOT REVIEWED.** Submittal not required by Contract Documents.
- ☐ **RECEIVED FOR CLIENT'S RECORD ONLY.** Submittal not reviewed.

Gensler has reviewed this Submittal, but only for the purpose of checking for conformance with the design intent expressed in the Contract Documents. Gensler's action on a specific item does not indicate approval of an assembly of which the item is a component, nor of an item as delivered and installed if it does not conform to the Contract Documents.

Contractor is responsible for checking for deviations between this Submittal and differing information or conditions in the Contract Documents and field conditions; for determining or substantiating the accuracy and completeness of other details such as dimensions and quantities; for substantiating instructions for installation or performance of equipment or systems designed by Contractor; for construction means, methods, techniques, schedules, sequences, procedures, and fabrication processes; for errors and omissions in Submittals; for coordination of the Work of the trades, safety precautions and performing the Work in a safe and satisfactory manner and in conformance with the Contract Documents.

If more than one submittal review stamp appears on this Submittal, the most stringent action and notations thereon apply. Signature of a submittal review stamp by Gensler or a consultant does not imply that it has reviewed work not within its professional discipline or scope of services.

By: _____ **Date:** _____

Project No: _____

Submittal: _____

SECTION 01 40 00 – QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specific quality-control requirements for individual construction activities are specified in the Sections that specify those activities. Requirements in those Sections may also cover production of standard products.
 - 2. Specified tests, inspections, and related actions do not limit Contractor's quality-control procedures that facilitate compliance with the Contract Document requirements.
 - 3. Requirements for Contractor to provide quality-control services required by Architect, Owner, Commissioning Authority or authorities having jurisdiction are not limited by provisions of this Section.
- C. Related Sections:
 - 1. Section 01 73 29 "Cutting and Patching" for repair and restoration of construction disturbed by testing and inspecting activities.
 - 2. Section 01 78 39 "Project Record Documents" for assembling miscellaneous record submittals.
 - 3. Divisions 03 through 33 Sections for specific test and inspection requirements.

1.3 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and ensure that proposed construction complies with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that completed construction complies with requirements. Services do not include contract enforcement activities performed by Architect.
- C. Mockups: Full-size physical assemblies that are constructed on-site, unless indicated otherwise. Mockups are constructed to verify selections made under Sample submittals; to demonstrate aesthetic effects and, where indicated, qualities of materials and execution; to review

coordination, testing, or operation; to show interface between dissimilar materials; and to demonstrate compliance with specified installation tolerances. Mockups are not Samples. Unless otherwise indicated, approved mockups establish the standard by which the Work will be judged.

1. Integrated Exterior Mockups: Mockups of the exterior envelope erected separately from the building but on Project site, consisting of multiple products, assemblies, and subassemblies.
 2. Room Mockups: Mockups of typical interior spaces complete with wall, floor, and ceiling finishes, doors, windows, millwork, casework, specialties, furnishings and equipment, and lighting.
 3. Benchmark Samples: A type of mockup used to illustrate the application and aesthetic effect of finishes and coatings. Benchmark Samples establish the standard by which the Work will be judged.
- D. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.
- E. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- F. Source Quality-Control Testing: Tests and inspections that are performed at the source (e.g., plant, mill, factory, or shop).
- G. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- H. Testing Agency: An entity independent of the Owner's and Contractor's operations, engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- I. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).
- J. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.
- K. Professional Engineer: Engineer currently licensed to practice in the State of Utah.

1.4 CONFLICTING REQUIREMENTS

- A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.5 DELEGATED DESIGN

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
 - 1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.

1.6 INFORMATIONAL SUBMITTALS

- A. General: Format and assemble miscellaneous record submittals to comply with requirements specified in Section 01 78 39 "Project Record Documents."
 - 1. Distribution: Comply with the following as applicable:
 - a. Owner: One copy.
 - b. Contractor: Three copies.
 - c. Architect: One copy.
 - d. Consulting Engineer: One copy.
 - e. Authority having jurisdiction: One copy or as otherwise requested by the Authority.
- B. Contractor's Quality-Control Plan: For quality-assurance and quality-control activities and responsibilities.
- C. Qualification Data: For Contractor's quality-control personnel.
- D. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility sent to authorities having jurisdiction before starting work on the following systems:
 - 1. Seismic-force-resisting system, designated seismic system, or component listed in the designated seismic system.
 - 2. Main wind-force-resisting system or a wind-resisting component listed in the wind-force-resisting system.

- E. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.
- F. Delegated-Design Submittal: In addition to Shop Drawings, Product Data, and other required submittals, submit a statement, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional, indicating that the products and systems are in compliance with performance and design criteria indicated. Include list of codes, loads, and other factors used in performing these services.
- G. Schedule of Tests and Inspections: Prepare in tabular form and include the following:
 - 1. Specification Section number and title.
 - 2. Description of test and inspection.
 - 3. Identification of applicable standards.
 - 4. Identification of test and inspection methods.
 - 5. Number of tests and inspections required.
 - 6. Time schedule or time span for tests and inspections.
 - 7. Entity responsible for performing tests and inspections.
 - 8. Requirements for obtaining samples.
 - 9. Unique characteristics of each quality-control service.
- H. Testing Agency and Inspection Reports: Prepare and submit certified written reports that include the following:
 - 1. Date of issue.
 - 2. Project title and number.
 - 3. Name, address, and telephone number of testing agency.
 - 4. Dates and locations of samples and tests or inspections.
 - 5. Names of individuals making tests and inspections.
 - 6. Description of the Work and test and inspection method.
 - 7. Identification of product and Specification Section.
 - 8. Complete test or inspection data.
 - 9. Test and inspection results and an interpretation of test results.
 - 10. Ambient conditions at time of sample taking and testing and inspecting.
 - 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
 - 12. Name and signature of laboratory inspector.
 - 13. Recommendations on retesting and reinspecting.
- I. Manufacturer's Technical Representative's Field Reports: Prepare written information documenting manufacturer's technical representative's tests and inspections specified in other Sections. Include the following:
 - 1. Name, address, and telephone number of technical representative making report.
 - 2. Statement on condition of substrates and their acceptability for installation of product.
 - 3. Statement that products at Project site comply with requirements.
 - 4. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.

5. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 6. Statement whether conditions, products, and installation will affect warranty.
 7. Other required items indicated in individual Specification Sections.
- J. Factory-Authorized Service Representative's Reports: Prepare written information documenting manufacturer's factory-authorized service representative's tests and inspections specified in other Sections. Include the following:
1. Name, address, and telephone number of factory-authorized service representative making report.
 2. Statement that equipment complies with requirements.
 3. Results of operational and other tests and a statement of whether observed performance complies with requirements.
 4. Statement whether conditions, products, and installation will affect warranty.
 5. Other required items indicated in individual Specification Sections.
- K. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.
- 1.7 CONTRACTOR'S QUALITY-CONTROL PLAN
- A. Quality-Control Plan, General: Submit quality-control plan within ten days of Notice to Proceed, and not less than five days prior to preconstruction conference. Submit in format acceptable to Owner. Identify personnel, procedures, controls, instructions, tests, records, and forms to be used to carry out Contractor's quality-assurance and quality-control responsibilities. Coordinate with Contractor's construction schedule.
- B. Quality-Control Personnel Qualifications: Engage qualified full-time personnel trained and experienced in managing and executing quality-assurance and quality-control procedures similar in nature and extent to those required for Project.
1. Project quality-control manager may also serve as Project superintendent.
- C. Submittal Procedure: Describe procedures for ensuring compliance with requirements through review and management of submittal process. Indicate qualifications of personnel responsible for submittal review.
- D. Testing and Inspection: In quality-control plan, include a comprehensive schedule of Work requiring testing or inspection, including the following:
1. Contractor-performed tests and inspections including subcontractor-performed tests and inspections. Include required tests and inspections and Contractor-elected tests and inspections.
 2. Special inspections required by authorities having jurisdiction and indicated on the "Statement of Special Inspections."
 3. Owner-performed tests and inspections indicated in the Contract Documents, including tests and inspections indicated to be performed by the Commissioning Authority.

- E. Continuous Inspection of Workmanship: Describe process for continuous inspection during construction to identify and correct deficiencies in workmanship in addition to testing and inspection specified. Indicate types of corrective actions to be required to bring work into compliance with standards of workmanship established by Contract requirements and approved mockups.
- F. Monitoring and Documentation: Maintain testing and inspection reports including log of approved and rejected results. Include work Architect has indicated as nonconforming or defective. Indicate corrective actions taken to bring nonconforming work into compliance with requirements. Comply with requirements of authorities having jurisdiction.

1.8 QUALITY ASSURANCE

- A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Fabricator Qualifications: A firm experienced and expert in producing products similar to those indicated for this Project and with a three-year record of successful in-service performance, as well as sufficient production capacity to produce required units.
- C. Factory-Authorized Service Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- D. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a three-year record of successful in-service performance.
- E. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a five-year record of successful in-service performance.
- F. Manufacturer's Technical Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- G. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or products that are similar to those indicated for this Project in material, design, and extent.
- H. Specialists: Certain sections of the Specifications require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.

1. Requirement for specialists shall not supersede building codes and similar regulations governing the Work, nor interfere with local trade-union jurisdictional settlements and similar conventions.
- I. Testing Agency Qualifications: An NRTL, an NVLAP-accredited, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented by ASTM E 329, and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities..
 1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
 2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.
- J. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:
 1. Contractor responsibilities include the following:
 - a. Provide test specimens and assemblies representative of proposed products and construction.
 - b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
 - c. Provide sizes and configurations of test assemblies and mockups to adequately demonstrate capability of products to comply with performance requirements.
 - d. Fabricate and install test assemblies and mockups using installers who will perform the same tasks for Project.
 - e. When testing is complete, remove test specimens, assemblies, and mockups; do not reuse products on Project.
 2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect and Commissioning Authority when applicable, with copy to Contractor. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.
- K. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish specified in individual Sections, to comply with the following requirements, using materials indicated for the completed Work:
 1. Build mockups in location and of size indicated or, if not indicated, as directed by Architect.
 2. Notify Architect seven days in advance of dates and times when mockups will be constructed.
 3. Employ supervisory personnel who will oversee mockup construction. Employ workers that will be employed during the construction at Project.
 4. Demonstrate the proposed range of aesthetic effects and workmanship.
 5. Obtain Architect's approval of mockups before starting work, fabrication, or construction.
 - a. Allow seven days for initial review and each re-review of each mockup.

6. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
 7. Demolish and remove mockups when directed, unless otherwise indicated.
- L. Integrated Exterior Mockups: Construct integrated exterior mockup according to design indicated on Drawings. Coordinate installation of exterior envelope materials and products for which mockups are required in individual Specification Sections, along with supporting materials.
1. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
 2. Demolish and remove mockups when directed, unless otherwise indicated.
- M. Room Mockups: Construct room mockups incorporating required materials and assemblies, finished according to requirements. Provide required lighting and additional lighting where required to enable Architect to evaluate quality of the Work. Construct room mockups according to design indicated on Drawings.
1. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
 2. Demolish and remove mockups when directed, unless otherwise indicated.

1.9 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of the types of testing and inspecting they are engaged to perform.
 2. Payment for these services will be made from testing and inspecting allowances, as authorized by Change Orders.
 3. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor, and the Contract Sum will be adjusted by Change Order.
- B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.
1. Unless otherwise indicated, provide quality-control services specified and those required by authorities having jurisdiction. Perform quality-control services required of Contractor by authorities having jurisdiction, whether specified or not.
 2. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.
 - a. Contractor shall not employ the same entity engaged by Owner, unless agreed to in writing by Owner.

3. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
 4. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
 5. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
 6. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
 7. Provide quality assurance and control services required due to changes in the Work proposed by or made by the Contractor.
 8. Provide quality control services for Work done contrary to the Contract Documents, without prior notice, when so specified, or without proper supervision.
 9. Overtime expenses and schedule delays accruing as a result of executing quality control services shall be the Contractor's responsibility and shall not be charged to the Owner.
- C. **Manufacturer's Field Services:** Where indicated, engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing as specified in Division 01 Section "Submittal Procedures."
- D. **Manufacturer's Technical Services:** Where indicated, engage a manufacturer's technical representative to observe and inspect the Work. Manufacturer's technical representative's services include participation in preinstallation conferences, examination of substrates and conditions, verification of materials, observation of Installer activities, inspection of completed portions of the Work, and submittal of written reports.
- E. **Retesting/Reinspecting:** Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that revised or replaced Work that failed to comply with requirements established by the Contract Documents. Architect retains the right to require the use of a different testing agency for retesting and reinspecting.
- F. **Testing Agency Responsibilities:** Cooperate with Architect, Commissioning Authority and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
1. Notify Architect, Commissioning Authority when applicable, and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
 2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
 5. Do not release, revoke, alter, or increase requirements of the Contract Documents or approve or accept any portion of the Work.
 6. Do not perform any duties of Contractor.
 7. Attend Project progress meetings as requested by Owner.

- G. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
1. Access to the Work.
 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
 4. Facilities for storage and field-curing of test samples.
 5. Delivery of samples to testing agencies or arranging for pick-up of test samples after normal business hours.
 6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
 7. Security and protection for samples and for testing and inspecting equipment at Project site.
- H. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and quality control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
1. Schedule times for tests, inspections, obtaining samples, and similar activities.
- I. Schedule of Tests and Inspections: Prepare a schedule of tests, inspections, and similar quality-control services required by the Contract Documents as a component of Contractor's quality-control plan. Coordinate and submit schedule concurrently with Contractor's Construction Schedule as specified in Division 01 Section "Construction Progress Documentation."
1. Distribution: Distribute schedule to Owner, Architect, Commissioning Authority when applicable, testing agencies, and each party involved in performance of portions of the Work where tests and inspections are required.

1.10 SPECIAL TESTS AND INSPECTIONS

- A. Special Tests and Inspections: Owner will engage a qualified testing agency or special inspector to conduct special tests and inspections required by authorities having jurisdiction as the responsibility of Owner, and as follows:
1. Verifying that manufacturer maintains detailed fabrication and quality-control procedures and reviews the completeness and adequacy of those procedures to perform the Work.
 2. Notifying Architect, Commissioning Authority when applicable, and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
 3. Submitting a certified written report of each test, inspection, and similar quality-control service to Architect and Commissioning Authority when applicable, with copy to Contractor and to authorities having jurisdiction.
 4. Submitting a final report of special tests and inspections at Substantial Completion, which includes a list of unresolved deficiencies.
 5. Interpreting tests and inspections and stating in each report whether tested and inspected work complies with or deviates from the Contract Documents.
 6. Retesting and reinspecting corrected work.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 TEST AND INSPECTION LOG

A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:

1. Date test or inspection was conducted.
2. Description of the Work tested or inspected.
3. Date test or inspection results were transmitted to Architect.
4. Identification of testing agency or special inspector conducting test or inspection.

B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's and Commissioning Authority's, reference during normal working hours.

3.2 REPAIR AND PROTECTION

A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.

1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for Division 01 Section "Cutting and Patching."

B. Protect construction exposed by or for quality-control service activities.

C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 01 40 00

SECTION 01 42 00 – REFERENCES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "approved," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Operations at Project site including unloading, temporarily storing, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Installer": Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations. Installers shall be experienced in the operation they are engaged to perform.
 - 1. Using a term such as "carpentry" does not imply that certain construction activities must be performed by accredited or unionized individuals of a corresponding generic name, such as "carpenter." It also does not imply that requirements specified apply exclusively to tradespeople of the corresponding generic name.

- J. "Experienced": When used with an entity, "experienced" means having successfully completed a minimum of five previous projects similar in size and scope to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.
- K. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.
- L. "As Required": As required by regulatory bodies, by referenced standards, by existing conditions, by generally accepted construction practice or by the Contract Documents. In the event of ambiguity or conflicts, the most stringent requirements shall apply.
- M. "By Others" refers to work that is not a part of the Contract.
- N. "N.I.C.": "Not in Contract" means the work or the item indicated is not a part of the Contract and will be provided by the Owner.
- O. "Day": Unless stated otherwise, "day" means a calendar day.

1.3 INDUSTRY STANDARDS

- A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.
- B. Publication Dates: Comply with editions of standards referenced in the corresponding construction subcode for the work or portion of the work indicated.
- C. Conflicting Requirements: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer uncertainties and requirements that are different, but apparently equal, to Architect for a decision before proceeding.
 - 1. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.
- D. Copies of Standards: Each entity engaged in construction on Project must be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.
 - 1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source and make them available on request.

1.4 ABBREVIATIONS AND ACRONYMS

- A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. Names, telephone numbers, and Web site addresses are subject to change and are believed to be accurate and up-to-date as of the date of the Contract Documents.
1. Where abbreviations and acronyms used in Specifications or other Contract Documents are not defined herein, they shall mean the recognized name of the entities indicated in Gale Research's "Encyclopedia of Associations" or in Columbia Books' "National Trade & Professional Associations of the U.S." available in most public libraries.

AA	Aluminum Association, Inc. (The) www.aluminum.org	(703) 358-2960
AAADM	American Association of Automatic Door Manufacturers www.aaadm.com	(216) 241-7333
AABC	Associated Air Balance Council www.aabchq.com	(202) 737-0202
AAMA	American Architectural Manufacturers Association www.aamanet.org	(847) 303-5664
AASHTO	American Association of State Highway and Transportation Officials www.transportation.org	(202) 624-5800
AATCC	American Association of Textile Chemists and Colorists www.aatcc.org	(919) 549-8141
ABAA	Air Barrier Association of America www.airbarrier.org	(866) 956-5888
ABMA	American Bearing Manufacturers Association www.abma-dc.org	(202) 367-1155
ACI	American Concrete Institute www.concrete.org	(248) 848-3700
ACPA	American Concrete Pipe Association www.concrete-pipe.org	(972) 506-7216
ADC	Air Diffusion Council www.flexibleduct.org	(847) 706-6750
AEIC	Association of Edison Illuminating Companies, Inc. (The) www.aeic.org	(205) 257-2530

AF&PA	American Forest & Paper Association www.afandpa.org	(800) 878-8878 (202) 463-2700
AGA	American Gas Association www.aga.org	(202) 824-7000
AGC	Associated General Contractors of America (The) www.agc.org	(703) 548-3118
AHA	American Hardboard Association http://domensino.com/AHA/	(847) 934-8800
AHAM	Association of Home Appliance Manufacturers www.aham.org	(202) 872-5955
AI	Asphalt Institute www.asphaltinstitute.org	(859) 288-4960
AIA	American Institute of Architects (The) www.aia.org	(800) 242-3837
AISC	American Institute of Steel Construction www.aisc.org	(800) 644-2400 (312) 670-2400
ASI	American Iron and Steel Institute www.steel.org	(202) 452-7100
AITC	American Institute of Timber Construction www.aitc-glulam.org	(303) 792-9559
ALCA	Associated Landscape Contractors of America (Now PLANET – Professional Landscape Network)	
ALSC	American Lumber Standard Committee, Incorporated www.alsc.org	(301) 972-1700
AMCA	Air Movement and Control Association International, Inc. www.amca.org	(847) 394-0150
ANLA	American Nursery & Landscape Association (Formerly: AAN - American Association of Nurserymen) www.anla.org	(202) 789-2900
ANSI	American National Standards Institute www.ansi.org	(202) 293-8020
AOSA	Association of Official Seed Analysts, Inc. www.aosaseed.com	(405) 780-7372

APA EWS	APA - The Engineered Wood Association www.apawood.org	(253) 565-6600
APA	Architectural Precast Association www.archprecast.org	(239) 454-6989
API	American Petroleum Institute www.api.org	(202) 682-8000
APWA	American Public Works Association www.apwa.net	(800) 848-2792
ARI	Air-Conditioning & Refrigeration Institute (now AHRI)	
ARMA	Asphalt Roofing Manufacturers Association www.asphaltroofing.org	(202) 207-0917
ASA	Acoustical Society of America http://asa.aip.org	(516) 576-2360
ASC	Adhesive and Sealant Council, The www.ascouncil.org	301-986-9700
ASCA	Architectural Spray Coaters Association	(609) 848-6120
ASCE	American Society of Civil Engineers www.asce.org	(800) 548-2723
ASHRAE	American Society of Heating, Refrigerating and Air- Conditioning Engineers www.ashrae.org	(703) 295-6300 (800) 527-4723 (404) 636-8400
ASME	ASME International (The American Society of Mechanical Engineers International) www.asme.org	(800) 843-2763 (973) 882-1170
ASPE	American Society of Plumbing Engineers www.aspe.org	(773) 693-2773
ASSE	American Society of Sanitary Engineering www.asse-plumbing.org	(440) 835-3040
ASTM	ASTM International (American Society for Testing and Materials International) www.astm.org	(610) 832-9500
AWCI	Association of the Wall and Ceiling Industries International www.awci.org	(703) 534-8300

AWCMA	American Window Covering Manufacturers Association (now WCMA)	
AWI	Architectural Woodwork Institute www.awinet.org	(571) 323-3636
AWPA	American Wood Protection Association (formerly American Wood-Preservers' Association) www.awpa.com	(205) 733-4077
AWS	American Welding Society www.aws.org	(800) 443-9353 (305) 443-9353
AWWA	American Water Works Association www.awwa.org	(800) 926-7337 (303) 794-7711
BHMA	Builders Hardware Manufacturers Association www.buildershardware.com	(212) 297-2122
BIA	Brick Industry Association (The) www.bia.org	(703) 620-0010
BICSI	BICSI, Inc. www.bicsi.org	(800) 242-7405 (813) 979-1991
BIFMA	BIFMA International(Business and Institutional Furniture Manufacturer'sAssociation International) www.bifma.com	(616) 285-3963
BISSI	Baking Industry Sanitation Standards Committee www.bissc.org	(866) 342-4772
CCC	Carpet Cushion Council www.carpetcushion.org	(610) 527-3880
CCFSS	Center for Cold-Formed Steel Structures www.ccfsonline.org	(573) 341-4471
CDA	Copper Development Association Inc. www.copper.org	(212) 251-7200
CEA	Consumer Electronics Association www.ce.org	(866) 858-1555 (703) 907-7600
CFFA	Chemical Fabrics & Film Association, Inc. www.chemicalfabricsandfilm.com	(216) 241-7333

CFI	International Certified Floorcovering Installers Association www.cfi-installers.org	(816) 231-4646
CGA	Compressed Gas Association www.cganet.com	(703) 788-2700
CIMA	Cellulose Insulation Manufacturers Association www.cellulose.org	(888) 881-2462 (937) 222-2462
CISCA	Ceilings & Interior Systems Construction Association www.cisca.org	(630) 584-1919
CISPI	Cast Iron Soil Pipe Institute www.cispi.org	(423) 892-0137
CLFMI	Chain Link Fence Manufacturers Institute www.chainlinkinfo.org	(301) 596-2583
CPA	Composite Panel Association www.pbmdf.com	(703) 724-1128
CPPA	Corrugated Polyethylene Pipe Association www.cppa-info.org	(800) 510-2772
CRI	Carpet & Rug Institute (The) www.carpet-rug.com	(706) 278-3176
CRRC	Cool Roof Rating Council www.coolroofs.org	(866) 465-2523
CRSI	Concrete Reinforcing Steel Institute www.crsi.org	(847) 517-1200
CSI	Construction Specifications Institute (The) www.csinet.org	(800) 689-2900 (703) 684-2900
DHI	Door and Hardware Institute www.dhi.org	(703) 222-2010
EIA	Electronic Industries Alliance www.eia.org	(703) 907-7500
EIMA	EIFS Industry Members Association www.eima.com	(800) 968-7945 (770) 968-7945
EJMA	Expansion Joint Manufacturers Association, Inc. www.eima.com	(914) 332-0400

ESD	ESD Association (Electrostatic Discharge Association) www.esda.org	(315) 339-6937
FM Approvals	FM Approvals LLC www.fmglobal.com	(781) 762-4300
FMGlobal	(formerly FMG – FMGlobal) www.fmglobal.com	(401) 275-3000
FSA	Fluid Sealing Association www.fluidsealing.com	(610) 971-4850
FSC	Forest Stewardship Council www.fsc.org	49 228 367 66 0
GA	Gypsum Association www.gypsum.org	(301) 277.8686
GANA	Glass Association of North America (formerly: FGMA - Flat Glass Marketing Association) www.glasswebsite.com	(785) 271-0208
GBCI	Green Building Certification Institute www.gbci.org	(800) 795-1746
GS	Green Seal www.greenseal.org	(202) 872-6400
GSI	Geosynthetic Institute www.geosynthetic-institute.org	(610) 522-8440
GTA	Glass Tempering Division of Glass Association of North America (see GANA)	
HI	Hydraulic Institute www.pumps.org	(973) 267-9700
HI	Hydronics Institute www.gamanet.org	(908) 464-8200
HMMA	Hollow Metal Manufacturers Association (part of NAAMM)	
HPVA	Hardwood Plywood & Veneer Association www.hpva.org	(703) 435-2900
HPW	H. P. White Laboratory, Inc. www.hpwhite.com	(410) 838-6550

ICEA	Insulated Cable Engineers Association, Inc. www.icea.net	(770) 830-0369
ICRI	International Concrete Repair Institute www.icri.org	(847) 827-0830
IEC	International Electrotechnical Commission www.iec.ch	41 22 919 02 11
IEEE	Institute of Electrical and Electronics Engineers, Inc. (The) www.ieee.org	(212) 419-7900
IESNA	Illuminating Engineering Society of North America www.iesna.org	(212) 248-5000
IEST	Institute of Environmental Sciences and Technology www.iest.org	(847) 255-1561
IGCC	Insulating Glass Certification Council www.igcc.org	(315) 646-2234
IGMA	Insulating Glass Manufacturers Alliance www.igmaonline.org	(613) 233-1510
ILI	Indiana Limestone Institute of America, Inc. www.iliai.com	(812) 275-4426
ISO	International Organization for Standardization www.iso.ch Available from ANSI www.ansi.org	41 22 749 01 11 (202) 293-8020
ISSFA	International Solid Surface Fabricators Association www.issfa.net	(877) 464-7732 (702) 567-8150
ITS	Intertek Testing Services (now ETL Semco)	
ITU	International Telecommunication Union www.itu.int/home	41 22 730 51 11
KCMA	Kitchen Cabinet Manufacturers Association www.kcma.org	(703) 264-1690
LPI	Lightning Protection Institute www.lightning.org	(800) 488-6864
MBMA	Metal Building Manufacturers Association www.mbma.com	(216) 241-7333

MFMA	Maple Flooring Manufacturers Association www.maplefloor.org	(888) 480-9138
MFMA	Metal Framing Manufacturers Association, Inc. www.metalframingmfg.org	(312) 644-6610
MGPHO	Medical Gas Professional Healthcare Organization, Inc. www.mgpho.org	(877) 238-5157 (913) 681-6548
MHIA	Material Handling Industry of America www.mhia.org	(800) 345-1815 (704) 676-1190
MIA	Marble Institute of America www.marble-institute.com	(440) 250-9222
MIA	Masonry Institute of America www.masonryinstitute.org	(213) 388-0472
MSS	Manufacturers Standardization Society of The Valve and Fittings Industry Inc. www.mss-hq.com	(703) 281-6613
NAAMM	National Association of Architectural Metal Manufacturers www.naamm.org	(630) 942-6591
NACE	NACE International (National Association of Corrosion Engineers International) www.nace.org	(800) 797-6623 (281) 228-6200
NADCA	National Air Duct Cleaners Association www.nadca.com	(202) 737-2926
NAIMA	North American Insulation Manufacturers Association www.naima.org	(703) 684-0084
NBGQA	National Building Granite Quarries Association Inc. www.nbgqa.com	(800) 557-2848
NCMA	National Concrete Masonry Association www.ncma.org	(703) 713-1900
NCPI	National Clay Pipe Institute www.ncpi.org	(262) 248-9094
NCTA	National Cable & Telecommunications Association www.ncta.com	(202) 775-2300
NEBB	National Environmental Balancing Bureau www.nebb.org	(301) 977-3698

NECA	National Electrical Contractors Association www.necanet.org	(301) 657-3110
NeLMA	Northeastern Lumber Manufacturers' Association www.nelma.org	(207) 829-6901
NEMA	National Electrical and Medical Imaging Equipment Manufacturers Association www.nema.org	(703) 841-3200
NETA	InterNational Electrical Testing Association www.netaworld.org	(888) 300-6382 (269) 488-6382
NFPA	NFPA (National Fire Protection Association) www.nfpa.org	(800) 344-3555 (617) 770-3000
NFRC	National Fenestration Rating Council www.nfrc.org	(301) 589-6372
NGA	National Glass Association www.glass.org	(866) 342-5642 (703) 442-4890
NHLA	National Hardwood Lumber Association www.natlhardwood.org	(800) 933-0318 (901) 377-1818
NLGA	National Lumber Grades Authority www.nlga.org	(604) 524-2393
NOFMA	NOFMA: The Wood Flooring Manufacturers Association) (formerly National Oak Flooring Manufacturers Association) www.nofma.org	(901) 526-5016
NOMMA	National Ornamental & Miscellaneous Metals Association www.nomma.org	(888) 516-8585
NRCA	National Roofing Contractors Association www.nrca.net	(800) 323-9545 (847) 299-9070
NRMCA	National Ready Mixed Concrete Association www.nrmca.org	(888) 846-7622 (301) 587-1400
NSSGA	National Stone, Sand and Gravel Association (NSSA) www.nssga.org	(800) 342-1415 (703) 525-8788
NTMA	National Terrazzo and Mosaic Association, Inc. (The) www.ntma.com	(800) 323-9736 (540) 751-0930
NWWDA	National Wood Window and Door Association (now WDMA)	

PCA	Portland Cement Association www.cement.org	(847) 966-6200
PCI	Precast/Prestressed Concrete Institute www.pci.org	(312) 786-0300
PDCA	Painting and Decorating Contractors of America www.pdca.com	(800) 332-7322 (314) 514-7322
PDI	Plumbing & Drainage Institute www.pdionline.org	(800) 589-8956 (978) 557-0720
PGI	PVC Geomembrane Institute http://pgi-tp.ce.uiuc.edu	(217) 333-3929
PLANET	Professional Landcare Network (Formerly: ACLA – Associated Landscape Contractors of America) www.landcarenetwork.org	(703) 736-9666
PTI	Post-Tensioning Institute www.post-tensioning.org	(602) 870-7540
RCSC	Research Council on Structural Connections www.boltcouncil.org	
RFCI	Resilient Floor Covering Institute www.rfci.com	(706) 882-3833
RIS	Redwood Inspection Service www.redwoodinspection.com	(925) 935-1499
RMA	Rubber Manufacturers Association www.rma.org	(800) 220-7620 (202) 682-4800
SAE	SAE International www.sae.org	(877) 606-7323 (724) 776-4841
SDI	Steel Deck Institute www.sdi.org	(847) 458-4647
SDI	Steel Door Institute www.steeldoor.org	(847) 458-4647
SEFA	Scientific Equipment and Furniture Association www.sefalabs.com	(877) 294-5424 (516) 294-5424
SGCC	Safety Glazing Certification Council www.sgcc.org	(315) 646-2234

SIA	Security Industry Association www.siaonline.org	(866) 817-8888 (703) 683-2075
SIGMA	Sealed Insulating Glass Manufacturers Association	(312) 644-6610
SJI	Steel Joist Institute www.steeljoist.org	(843) 626-1995
SMA	Screen Manufacturers Association www.smacentral.org	(561) 533-0991
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association www.smacna.org	(703) 803-2980
SMPTE	Society of Motion Picture and Television Engineers www.smpte.org	(914) 761-1100
SPFA	Spray Polyurethane Foam Alliance www.sprayfoam.org	(800) 523-6154
SPIB	Southern Pine Inspection Bureau www.spib.org	(850) 434-2611
SPRI	Single Ply Roofing Institute www.spri.org	(781) 647-7026
SSINA	Specialty Steel Industry of North America www.ssina.com	(800) 982-0355 (202) 342-8630
SSMA	Steel Stud Manufacturers Association (Formerly: ML/SFA - Metal Lath/Steel Framing Association) www.ssma.com	(630) 942-6592
SSPC	SSPC: The Society for Protective Coatings www.sspc.org	(877) 281-7772 (412) 281-2331
STI	Steel Tank Institute www.steeltank.com	(847) 438-8265
SWI	Steel Window Institute www.steelwindows.com	(216) 241-7333
SWRI	Sealant, Waterproofing, and Restoration Institute www.swrionline.org	(816) 472-7974
TCNA	Tile Council of North America, Inc. www.tileusa.com	(864) 646-8453

TIA/EIA	Telecommunications Industries Alliance www.tiaonline.org	Industry Association/Electronic	(703) 907-7700
TMS	The Masonry Society www.masonrysociety.org		(303) 939-9700
TPI	Truss Plate Institute, Inc. www.tpinst.org		(703) 683-1010
TPI	Turfgrass Producers International www.turfgrassod.org		(800) 405-8873 (847) 649-5555
TRI	Tile Roofing Institute www.tilerroofing.org		(312) 670-4177
UFAC	Upholstered Furniture Action Council www.ufac.org		(336) 885-5065
UL	Underwriters Laboratories Inc. www.ul.com		(877) 854-3577 (847) 272-8800
UNI	Uni-Bell PVC Pipe Association www.uni-bell.org		(972) 243-3902
USGBC	United States Green Building Council www.usgbc.org		(800) 795-1747
USITT	United States Institute for Theatre Technology, Inc. www.usitt.org		(800) 938-7488 (315) 463-6463
WASTEC	Waste Equipment Technology Association www.wastec.org		(800) 424-2869 (202) 244-4700
WCLIB	West Coast Lumber Inspection Bureau www.wclib.org		(800) 283-1486 (503) 639-0651
WCMA	Window Covering Manufacturers Association www.wcmanet.org		(212) 297-2122
WDMA	Window & Door Manufacturers Association www.wdma.com		(800) 223-2301 (312) 321-6802
WI	Woodwork Institute (formerly Woodwork Institute of California) www.wicnet.org		(916) 372-9943
WMMPA	Wood Moulding & Millwork Producers Association www.wmmpa.com		(800) 550-7889 (530) 661-9591

WSRCA	Western States Roofing Contractors Association www.wsrca.com	(800) 725-0333 (650) 570-5441

WWPA	Western Wood Products Association www.wwpa.org	(503) 224-3930

- B. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. Names, telephone numbers, and Web site addresses are subject to change and are believed to be accurate and up-to-date as of the date of the Contract Documents.

IAPMO	International Association of Plumbing and Mechanical Officials www.iapmo.org	(909) 472-4100

ICC	International Code Council www.iccsafe.org	(888) 422-7233

ICC-ES	ICC Evaluation Service, Inc. www.icc-es.org	(800) 423-6587 (562) 699-0543

- C. Federal Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list. Names, telephone numbers, and Web site addresses are subject to change and are believed to be accurate and up-to-date as of the date of the Contract Documents.

CE	Army Corps of Engineers www.usace.army.mil	(202) 761-0011

CPSC	Consumer Product Safety Commission www.cpsc.gov	(800) 638-2772 (301) 504-7923

DOC	Department of Commerce www.commerce.gov	(202) 482-2000

DOD	Department of Defense http://.dodssp.daps.dla.mil	(215) 697-6257

DOE	Department of Energy www.energy.gov	(202) 586-9220

EPA	Environmental Protection Agency www.epa.gov	(202) 260-2090

FAA	Federal Aviation Administration www.faa.gov	(866) 835-5322

FCC	Federal Communications Commission www.fcc.gov	(888) 225-5322
FDA	Food and Drug Administration www.fda.gov	(888) 463-6332
GSA	General Services Administration www.gsa.gov	(202) 708-5082
HUD	Department of Housing and Urban Development www.hud.gov	(202) 708-1112
LBL	Lawrence Berkeley National Laboratory www.lbl.gov	(510) 486-4000
NCHRP	National Cooperative Highway Research Program (See TRB)	
NIST	National Institute of Standards and Technology www.nist.gov	(301) 975-6478
OSHA	Occupational Safety & Health Administration www.osha.gov	(202) 693-1999
PBS	Public Buildings Service (See GSA)	
PHS	Office of Public Health and Science www.hhs.gov/ophs	(202) 690-7694
RUS	Rural Utilities Service (See USDA)	(202) 720-9540
SD	State Department www.state.gov	(202) 647-4000
TRB	Transportation Research Board www.trb.org	(202) 334-2934
USDA	Department of Agriculture www.usda.gov	(202) 720-2791
USPS	Postal Service www.usps.com	(202) 268-2000

- D. Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the standards and regulations in the following list. Names, telephone numbers, and Web sites are subject to change and are believed to be accurate and up-to-date as of the date of the Contract Documents.

ADAAG	Americans with Disabilities Act (ADA) Architectural Barriers Act (ABA) Accessibility Guidelines for Buildings and Facilities Available from U.S. Access Board www.access-board.gov	(800) 872-2253 (202) 272-0080
CFR	Code of Federal Regulations Available from Government Printing Office www.gpoaccess.gov/cfr/index.html	(866) 512-1800 (202) 512-1800
DOD	Department of Defense Military Specifications and Standards Available from Department of Defense Single Stock Point http://dodssp.daps.dla.mil	(215) 697-2664
DSCC	Defense Supply Center Columbus (See FS)	
FED-STD	Federal Standard (See FS)	
FS	Federal Specification Available from Department of Defense Single Stock Point http://dodssp.daps.dla.mil Available from Defense Standardization Program www.dps.dla.mil Available from General Services Administration www.gsa.gov Available from National Institute of Building Sciences www.wbdg.org/ccb	(215) 697-2664 (202) 619-8925 (202) 289-7800
FTMS	Federal Test Method Standard (See FS)	
MIL	(See MILSPEC)	
MIL-STD	(See MILSPEC)	
MILSPEC	Military Specification and Standards Available from Department of Defense Single Stock Point http://dodssp.daps.dla.mil	(215) 697-2664
UFAS	Uniform Federal Accessibility Standards Available from Access Board www.access-board.gov	(800) 872-2253 (202) 272-0080

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 42 00

SECTION 01 50 00 – TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes requirements for temporary facilities and controls, including temporary utilities, support facilities, and security and protection facilities.
- B. Related Sections include the following:
 - 1. Section 01 33 00 "Submittal Procedures" for procedures for submitting copies of implementation and termination schedule and utility reports.
 - 2. Section 01 73 00 "Execution" for progress cleaning requirements.
 - 3. Section 01 74 19 "Construction Waste Management and Disposal."
 - 4. Divisions 02 through 28 Sections for temporary heat, ventilation, and humidity requirements for products in those Sections.

1.3 DEFINITIONS

- A. Permanent Enclosure: As determined by Architect, permanent or temporary roofing is complete, insulated, and weathertight; exterior walls are insulated and weathertight; and all openings are closed with permanent construction or substantial temporary closures.

1.4 USE CHARGES

- A. General: Installation and removal of and use charges for temporary facilities are not chargeable to Owner or Architect and shall be included in the Contract Sum, unless otherwise indicated. Allow other entities to use temporary services and facilities without cost, including, but not limited to, the following:
 - 1. Owner's construction forces.
 - 2. Architect.
 - 3. Commissioning Authority.
 - 4. Testing agencies.
 - 5. Personnel of authorities having jurisdiction.
- B. Sewer Service: Pay sewer service use charges for sewer usage by all parties engaged in construction operations at the Project site.
- C. Water Service: Pay water service use charges, whether metered or otherwise, for water used by all parties and entities engaged in construction operations at the Project site.

- D. Electric Power Service: Pay electric power service use charges, whether metered or otherwise, for electricity used by all parties and entities engaged in construction operations at the Project site.

1.5 INFORMATIONAL SUBMITTALS

- A. Site Plan: Show temporary facilities, utility hookups, staging areas, and parking areas for construction personnel.
- B. Erosion- and Sedimentation-Control Plan: Show compliance with requirements of EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent.
- C. Fire-Safety Program: Show compliance with requirements of NFPA 241 and authorities having jurisdiction. Indicate Contractor personnel responsible for management of fire-prevention program.
- D. Moisture-Protection Plan: Describe procedures and controls for protecting materials and construction from water absorption and damage.
 - 1. Describe delivery, handling, and storage provisions for materials subject to water absorption or water damage.
 - 2. Indicate procedures for discarding water-damaged materials, protocols for mitigating water intrusion into completed Work, and replacing water-damaged Work.
 - 3. Indicate sequencing of work that requires water, such as sprayed fire-resistive materials, plastering, and terrazzo grinding, and describe plans for dealing with water from these operations. Show procedures for verifying that wet construction has dried sufficiently to permit installation of finish materials.
- E. Dust- and HVAC-Control Plan: Submit coordination drawing and narrative that indicates the dust- and HVAC-control measures proposed for use, proposed locations, and proposed time frame for their operation. Identify further options if proposed measures are later determined to be inadequate. Include the following:
 - 1. Locations of dust-control partitions at each phase of work.
 - 2. HVAC system isolation schematic drawing.
 - 3. Location of proposed air-filtration system discharge.
 - 4. Waste handling procedures.
 - 5. Other dust-control measures.
- F. Temporary Utility Reports: Submit reports of tests, inspections, meter readings, and similar procedures performed on temporary utilities.
- G. Implementation and Termination Schedule: Within 15 days of date established for submittal of Contractor's Construction Schedule, submit a schedule indicating implementation and termination of each temporary utility.

1.6 QUALITY ASSURANCE

- A. Standards: Comply with ANSI A10.6, NECA's "Temporary Electrical Facilities," and NFPA 241.

1. Trade Jurisdictions: Assigned responsibilities for installation and operation of temporary utilities are not intended to interfere with trade regulations and union jurisdictions.
 2. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.

1.7 PROJECT CONDITIONS

- A. Temporary Utilities: At earliest feasible time, when acceptable to Owner, change over from use of temporary service to use of permanent service.
1. Temporary Use of Permanent Facilities: Installer of each permanent service shall assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.
- B. Conditions of Use: The following conditions apply to use of temporary services and facilities by all parties engaged in the Work:
1. Keep temporary services and facilities clean and neat.
 2. Relocate temporary services and facilities as required by progress of the Work.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Provide materials suitable for use intended.
- B. Pavement: Comply with Division 32 paving Sections.
- C. Portable Chain-Link Fencing: Minimum 2 inch, 0.148 inch thick, galvanized steel, chain-link fabric fencing; minimum 6 feet high with galvanized steel pipe posts; minimum 2-3/8 inch OD line posts and 2-7/8 inch OD corner and pull posts, with 1-5/8-inch OD top and bottom rails. Provide concrete bases for supporting posts.
- D. Lumber and Plywood: Comply with requirements in Section 06 10 00 "Rough Carpentry."
- E. Gypsum Board: Minimum 1/2 inch thick by 48 inches wide by maximum available lengths; regular-type panels with tapered edges. Comply with ASTM C 36 or ASTM C 1396.
- F. Insulation: Unfaced mineral-fiber blanket, manufactured from glass, slag wool, or rock wool; with maximum flame-spread and smoke-developed indices of 25 and 50, respectively.
- G. Paint: Comply with requirements in Division 09 Section "Painting."
- H. Polyethylene Sheet: Reinforced, fire-resistive sheet, 10 mil minimum thickness, with flame-spread rating of 15 or less per ASTM E 84 and passing NFPA 701 Test Method 2.

- I. Tarpaulins: Fire-resistive labeled with flame-spread rating of 15 or less.
- J. Dust-Control Adhesive-Surface Walk-off Mats: Provide mats minimum 36 by 60 inches.
- K. Water: Potable.

2.2 TEMPORARY FACILITIES

- A. Field Offices: Prefabricated or mobile units with lockable entrances, operable windows, and serviceable finishes; heated and air conditioned; on foundations adequate for normal loading.
- B. Common-Use Field Office: Of sufficient size to accommodate needs of Owner, Architect, Consulting Engineers, Commissioning Authority, and construction personnel office activities and to accommodate Project meetings specified in other Division 01 Sections. Keep office clean and orderly. Furnish and equip offices as follows:
 - 1. Furniture required for Project-site documents including file cabinets, plan tables, plan racks, and bookcases.
 - 2. Conference room of sufficient size to accommodate meetings of 10 individuals. Provide electrical power service and 120-V ac duplex receptacles, with no less than one receptacle on each wall. Furnish room with conference table, chairs, and 4 foot square tack and marker boards.
 - 3. Drinking water and private toilet.
 - 4. Coffee machine and supplies.
 - 5. Heating and cooling equipment necessary to maintain a uniform indoor temperature of 68 to 72 degrees F.
 - 6. Lighting fixtures capable of maintaining average illumination of 20 fc at desk height.
- C. Storage and Fabrication Sheds: Provide sheds sized, furnished, and equipped to accommodate materials and equipment for construction operations.
 - 1. Store combustible materials apart from building. Comply with NFPA 241.

2.3 EQUIPMENT

- A. Fire Extinguishers: Hand carried, portable, UL rated. Provide class and extinguishing agent as indicated or a combination of extinguishers of NFPA-recommended classes for exposures.
 - 1. Comply with NFPA 10 and NFPA 241 for classification, extinguishing agent, and size required by location and class of fire exposure.
- B. Self-Contained Toilet Units: Single-occupant units of chemical, aerated recirculation or combustion type; vented; fully enclosed with a glass-fiber-reinforced polyester shell or similar nonabsorbent material.
- C. Drinking-Water Fixtures: Containerized, tap-dispenser, bottled-water drinking-water units, including paper cup supply.

- D. Electrical Outlets: Properly configured, NEMA-polarized outlets to prevent insertion of 110- to 120-V plugs into higher-voltage outlets; equipped with ground-fault circuit interrupters, reset button, and pilot light.
- E. Power Distribution System Circuits: Where permitted and overhead and exposed for surveillance, wiring circuits, not exceeding 125-V ac, 20-A rating, and lighting circuits may be nonmetallic sheathed cable.
- F. HVAC Equipment: Permanent HVAC system may be used subject to coordination and approval by the Owner. Permanent systems that are used for temporary facilities including ductwork shall be cleaned at Project Closeout; replace all filters.
 - 1. Heating Units: Listed and labeled for type of fuel being consumed, by a qualified testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.
 - a. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
 - 2. Permanent HVAC System: If Owner authorizes use of permanent HVAC system for temporary use during construction, provide filter with MERV of 8 at each return air grille in system and remove at end of construction.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.
- B. Provide each facility ready for use when needed to avoid delay. Maintain and modify as required. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Engage appropriate local utility company to install temporary service or connect to existing service. Where utility company provides only part of the service, provide the remainder with matching, compatible materials and equipment. Comply with utility company recommendations.
 - 1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.
 - 2. Provide adequate capacity at each stage of construction. Before temporary utility is available, provide trucked-in services.
- B. Sewers and Drainage: If sewers are available, provide temporary connections to remove effluent that can be discharged lawfully. If sewers are not available or cannot be used, provide

drainage ditches, dry wells, stabilization ponds, and similar facilities. If neither sewers nor drainage facilities can be lawfully used for discharge of effluent, provide containers to remove and dispose of effluent off-site in a lawful manner.

1. Filter out excessive soil, construction debris, chemicals, oils, and similar contaminants that might clog sewers or pollute waterways before discharge.
 2. Connect temporary sewers to permanent systems as directed by authorities having jurisdiction.
 3. Maintain temporary sewers and drainage facilities in a clean, sanitary condition. After heavy use, restore normal conditions promptly.
- C. Water Service: Install water service and distribution piping in sizes and pressures adequate for construction until permanent water service is in use. Sterilize temporary water piping before use.
- D. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking-water for use of construction personnel. Comply with regulations and health codes for type, number, location, operation, and maintenance of fixtures and facilities.
1. Disposable Supplies: Provide toilet tissue, paper towels, paper cups, and similar disposable materials for each facility. Maintain adequate supply. Provide covered waste containers for disposal of used material.
 2. Toilet Facilities for New Construction Projects: Install self-contained toilet units. Shield toilets to ensure privacy. Provide separate facilities for male and female personnel.
 3. Drinking-Water Facilities: Provide bottled-water, drinking-water units.
- E. Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment from that specified that will not have a harmful effect on completed installations or elements being installed.
- F. Ventilation and Humidity Control: Provide temporary ventilation required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed. Coordinate ventilation requirements to produce ambient condition required and minimize energy consumption.
- G. Electric Power Service: Provide weatherproof, grounded electric power service and distribution system of sufficient size, capacity, and power characteristics during construction period. Include meters, transformers, overload-protected disconnecting means, automatic ground-fault interrupters, and main distribution switchgear.
1. Install electric power service underground, unless overhead service must be used.
 2. Install power distribution wiring overhead and rise vertically where least exposed to damage.
- H. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.

1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.
 2. Install lighting for Project identification sign.
- I. Telephone Service: Provide temporary telephone service throughout construction period in common-use facilities used by all personnel engaged in construction activities. Install separate telephone line for each field office and first-aid station.
1. Provide additional telephone lines for the following:
 - a. Provide a dedicated telephone line for each facsimile machine and computer with modem in each field office.
 2. At each telephone, post a list of important telephone numbers.
 - a. Police and fire departments.
 - b. Ambulance service.
 - c. Contractor's home office and emergency after-hours telephone number.
 - d. Architect's office.
 - e. Engineers' and consultants' offices.
 - f. Owner's office.
 - g. Commissioning Authority's office(s).
 3. Principal subcontractors' field and home offices. Provide an answering machine, voice-mail service, or messaging service on superintendent's telephone.
 4. Provide a portable cellular telephone or two-way radio for superintendent's use in making and receiving telephone calls when away from field office.
- J. Internet Service: Provide computer with broadband modem, router and ISP, equipped with hardware firewall, providing minimum 384 Kbps upload and 1 Mbps download speeds for superintendent's use in sending and receiving e-mail.

3.3 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:
1. Provide construction for temporary offices, shops, and sheds located within construction area or within 30 feet of building lines that is noncombustible according to ASTM E 136. Comply with NFPA 241.
 2. Maintain support facilities until Architect schedules Substantial Completion inspection. Remove before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.
- B. Temporary Use of Permanent Roads and Paved Areas: Construct and maintain temporary roads and paved areas adequate to support loads and to withstand exposure to traffic during construction period. Locate temporary roads and paved areas in same location as permanent roads and paved areas. Extend temporary roads and paved areas, within construction limits indicated, as necessary for construction operations.

1. Coordinate elevations of temporary roads and paved areas with permanent roads and paved areas.
 2. Prepare subgrade and install subbase and base for temporary roads and paved areas according to Division 31 Section "Earth Moving."
 3. Recondition base after temporary use, including removing contaminated material, regrading, proofrolling, compacting, and testing.
- C. Vehicular Parking: Construction personnel may park on premises in existing stalls located beyond limits of new work.
- D. Dewatering Facilities and Drains: Comply with requirements of authorities having jurisdiction and in applicable Division 31 Sections for temporary drainage and dewatering facilities and operations not directly associated with construction activities included in individual Sections. Where feasible, use same facilities. Maintain Project site, excavations, and construction free of water.
1. Dispose of rainwater in a lawful manner that will not result in flooding Project or adjoining property nor endanger permanent Work or temporary facilities.
 2. Before connection and operation of permanent drainage piping system, provide temporary drainage where roofing or similar waterproof deck construction is completed.
 3. Remove snow and ice as required to minimize accumulations.
- E. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Containerize and clearly label hazardous, dangerous, or unsanitary waste materials separately from other waste. Comply with requirements of authorities having jurisdiction. Comply with requirements specified in Section 01 74 19 "Construction Waste Management and Disposal."
1. If required by authorities having jurisdiction, provide separate containers, clearly labeled, for each type of waste material to be deposited.
 2. Develop a construction waste management plan for Work performed on Project. Indicate types of waste materials Project will produce and estimate quantities of each type. Provide detailed information for on-site waste storage and separation of recyclable materials. Provide information on destination of each type of waste material and means to be used to dispose of all waste materials.

3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.
- B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction in ways and by methods that comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects
1. Comply with work restrictions specified in Division 01 Section "Summary."

2. Avoid using tools and equipment that produce harmful noise.
- C. Temporary Erosion and Sedimentation Control: Provide measures to prevent soil erosion and discharge of soil-bearing water runoff and airborne dust to undisturbed areas and to adjacent properties and walkways, according to erosion- and sedimentation-control Drawings, requirements of 2003 EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent.
1. Verify that flows of water redirected from construction areas or generated by construction activity do not enter or cross tree- or plant- protection zones.
 2. Inspect, repair, and maintain erosion- and sedimentation-control measures during construction until permanent vegetation has been established.
 3. Clean, repair, and restore adjoining properties and roads affected by erosion and sedimentation from Project site during the course of Project.
 4. Remove erosion and sedimentation controls and restore and stabilize areas disturbed during removal.
- D. Stormwater Control: Comply with requirements of authorities having jurisdiction. Provide barriers in and around excavations and subgrade construction to prevent flooding by runoff of stormwater from heavy rains.
- E. Tree and Plant Protection: Install temporary fencing located as indicated or outside the drip line of trees to protect vegetation from damage from construction operations. Protect tree root systems from damage, flooding, and erosion.
- F. Site Enclosure Fence: Before construction operations begin, install site enclosure fence with lockable entrance gates. Install in a manner that will prevent people, dogs, and other animals from easily entering site except by entrance gates.
1. Extent of Fence: As required to enclose entire Project site or portion determined sufficient to accommodate construction operations.
 2. Provide gates in sizes and at locations necessary to accommodate delivery vehicles and other construction operations.
 3. Maintain security by limiting number of keys and restricting distribution to authorized personnel. Furnish one set of keys to Owner.
- G. Security Enclosure and Lockup: Install substantial temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each work day.
- H. Barricades, Warning Signs, and Lights: Comply with requirements of authorities having jurisdiction for erecting structurally adequate barricades, including warning signs and lighting. Paint with appropriate colors, graphics, and warning signs to inform personnel and public of possible hazard.
- I. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.

1. Where heating or cooling is needed and permanent enclosure is not complete, provide insulated temporary enclosures. Coordinate enclosure with ventilating and material drying or curing requirements to avoid dangerous conditions and effects.
- J. Temporary Fire Protection: Until fire-protection needs are supplied by permanent facilities, install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire-prevention program.
 1. Prohibit smoking in construction area.
 2. Provide fire extinguishers, installed on walls on mounting brackets, visible and accessible from space being served, with sign mounted above.
 - a. Field Offices: Class A stored-pressure water-type extinguishers.
 - b. Other Locations: Class ABC dry-chemical extinguishers or a combination of extinguishers of NFPA-recommended classes for exposures.
 - c. Locate fire extinguishers where convenient and effective for their intended purpose; provide not less than one extinguisher on each floor at or near each usable stairwell.
 3. Store combustible materials in containers in fire-safe locations.
 4. Maintain unobstructed access to fire extinguishers, fire hydrants, and other access routes for firefighting.
 5. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition.
 6. Develop and supervise an overall fire-prevention and first-aid fire-protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.
- A. MOISTURE AND MOLD CONTROL Contractor's Moisture-Protection Plan: Avoid trapping water in finished work. Document visible signs of mold that may appear during construction.
- B. Exposed Construction Phase: Before installation of weather barriers, when materials are subject to wetting and exposure and to airborne mold spores, protect as follows:
 1. Protect porous materials from water damage.
 2. Protect stored and installed material from flowing or standing water.
 3. Keep porous and organic materials from coming into prolonged contact with concrete.
 4. Remove standing water from decks.
 5. Keep deck openings covered or dammed.
- C. Partially Enclosed Construction Phase: After installation of weather barriers but before full enclosure and conditioning of building, when installed materials are still subject to infiltration of moisture and ambient mold spores, protect as follows:
 1. Do not load or install drywall or other porous materials or components, or items with high organic content, into partially enclosed building.
 2. Keep interior spaces reasonably clean and protected from water damage.
 3. Periodically collect and remove waste containing cellulose or other organic matter.

4. Discard or replace water-damaged material.
5. Do not install material that is wet.
6. Discard, replace, or clean stored or installed material that begins to grow mold.
7. Perform work in a sequence that allows any wet materials adequate time to dry before enclosing the material in drywall or other interior finishes.

D. **Controlled Construction Phase of Construction:** After completing and sealing of the building enclosure but prior to the full operation of permanent HVAC systems, maintain as follows:

1. Control moisture and humidity inside building by maintaining effective dry-in conditions.
2. Use permanent HVAC system to control humidity.
3. Comply with manufacturer's written instructions for temperature, relative humidity, and exposure to water limits.
 - a. Hygroscopic materials that may support mold growth, including wood and gypsum-based products, that become wet during the course of construction and remain wet for 48 hours are considered defective.
 - b. Measure moisture content of materials that have been exposed to moisture during construction operations or after installation. Record readings beginning at time of exposure and continuing daily for 48 hours. Identify materials containing moisture levels higher than allowed. Report findings in writing to Architect.
 - c. Remove materials that cannot be completely restored to their manufactured moisture level within 48 hours.

3.6 OPERATION, TERMINATION, AND REMOVAL

- A. **Supervision:** Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. **Maintenance:** Maintain facilities in good operating condition until removal. Protect from damage caused by freezing temperatures and similar elements.
 1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.
 2. Prevent water-filled piping from freezing. Maintain markers for underground lines. Protect from damage during excavation operations.
- C. **Temporary Facility Changeover:** Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.
- D. **Termination and Removal:** Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
 1. Materials and facilities that constitute temporary facilities are the property of Contractor. Owner reserves right to take possession of Project identification signs.

2. Remove temporary paving not intended for or acceptable for integration into permanent paving. Where area is intended for landscape development, remove soil and aggregate fill that do not comply with requirements for fill or subsoil. Remove materials contaminated with road oil, asphalt and other petrochemical compounds, and other substances that might impair growth of plant materials or lawns. Repair or replace street paving, curbs, and sidewalks at temporary entrances, as required by authorities having jurisdiction.
3. At Substantial Completion, repair, clean and renovate permanent facilities used during construction period. Comply with final cleaning requirements in Division 01 Section "Closeout Procedures."

END OF SECTION 01 50 00

SECTION 01 60 00 – PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes administrative and procedural requirements for the following:
 - 1. Product selection.
 - 2. Product delivery, storage, and handling.
 - 3. Product warranties.
 - 4. Comparable products.
- B. Related Sections:
 - 1. Section 01 25 00 "Substitution Procedures" for requests for substitutions.
 - 2. Section 01 77 00 "Closeout Procedures" for submitting warranties for contract closeout.
 - 3. Divisions 03 through 49 Sections for specific requirements for warranties on products and installations specified to be warranted.

1.3 DEFINITIONS

- A. Products: Items purchased for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation, shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility, except that products consisting of recycled-content materials are allowed, unless explicitly stated otherwise. Products salvaged or recycled from other projects are not considered new products.
 - 3. Comparable Product: Product that is demonstrated and approved through submittal process, or where indicated as a product substitution, to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: Where a specific manufacturer's product is named and accompanied by the words "basis of design," including make or model number or other designation, to establish the significant qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics for purposes of evaluating comparable products of other named manufacturers.

- C. **Manufacturer's Warranty:** Preprinted written warranty published by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
- D. **Special Warranty:** Written warranty required by or incorporated into the Contract Documents, either to extend time limit provided by manufacturer's warranty or to provide more rights for Owner.
- E. **Low VOC Content Levels:** Comply with requirements specified in Section 018113 – Sustainable Design Requirements. Except as otherwise indicated in Section 018113 or where more restricted in Divisions 03 through 28 Specifications Sections for limits of VOC contents in products and materials, the following shall constitute the maximum levels of volatile organic compounds.

1. Form Release Agents	350 g/L VOC content
2. Plastic Laminate Adhesive	20 g/L VOC content
3. Casework and Millwork Adhesives	20 g/L VOC content
4. Transparent Wood Finish Systems	350 g/L VOC content
5. Cast Resin Countertop silicone Sealant	20 g/L VOC content
6. Garage Deck Sealer	600 g/L VOC content
7. Water based Joint Sealants	50 g/L VOC content
8. Non-water based Joint Sealants	350 g/L VOC content
9. Portland Cement Plaster	20 g/L VOC content
10. Gypsum Drywall Joint Compound	20 g/L VOC content
11. Terrazzo Sealer	250 g/L VOC content
12. Acoustic Panel Ceiling Finish	50 g/L VOC content
13. Resilient Tile Flooring Adhesive	100 g/L VOC content
14. Vinyl Flooring Adhesives	100 g/L VOC content
15. Carpet Adhesive	50 g/L VOC content
16. Carpet Seam Sealer	50 g/L VOC content
17. Water-based Paint & Polychromatic finish coatings	150 g/L VOC content
18. Solvent -based Paint	380 g/L VOC content
19. High Performance Water-Based Acrylic coatings	250 g/L VOC content
20. Pigmented Acrylic Sealers	250 g/L VOC content
21. Catalyzed Epoxy coatings	250 g/L VOC content
22. High Performance Silicone	250 g/L VOC content
23. Casework Sealant	50 g/L VOC content
24. Liquid membrane-forming curing & sealing compound	350 g/L VOC content

1.4 ACTION SUBMITTALS

- A. **Comparable Product Requests:** Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Include data to indicate compliance with the requirements specified in "Comparable Products" Article.
 - 2. **Architect's Action:** If necessary, Architect will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable

product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.

- a. Form of Approval: As specified in Section 01 33 00 "Submittal Procedures."
- b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.

- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Section 01 33 00 "Submittal Procedures." Show compliance with requirements.

1.5 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, product selected shall be compatible with products previously selected, even if previously selected products were also options.

1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

1. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
4. Inspect products on delivery to ensure compliance with the Contract Documents and to ensure that products are undamaged and properly protected.
5. Store products to allow for inspection and measurement of quantity or counting of units.
6. Store materials in a manner that will not endanger Project structure.
7. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
8. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
9. Protect stored products from damage and liquids from freezing.
10. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

1.7 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.

2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution. Submit a draft for approval before final execution.
 1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
 2. Specified Form: Forms are included with the Specifications. Prepare a written document using appropriate form properly executed.
 3. Refer to Divisions 03 through 49 Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements Section 01 77 00 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

1. General Product Requirements: Provide products that comply with the Contract Documents, that are undamaged, and unless otherwise indicated, that are new at time of installation. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 2. Standard Products: Unless custom products or nonstandard options are specified, provide products of both quality and type that have been used successfully in similar situations on equal quality projects.
 3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
 4. Where products are accompanied by the term "as selected," Architect will make selection.
 5. Where products are accompanied by the term "match sample," sample to be matched is Architect's.
 6. Descriptive, performance, and reference standard requirements in the Specifications establish "salient characteristics" of products.
- B. Product Selection Procedures: Procedures for product selection include the following:
 1. Product: Where Specification paragraphs or subparagraphs titled "Product" name a single product and manufacturer, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 2. Manufacturer/Source: Where Specification paragraphs or subparagraphs titled "Manufacturer" or "Source" name single manufacturers or sources, provide a product by the manufacturer or from the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 3. Products: Where Specification paragraphs or subparagraphs titled "Products" introduce a list of names of both products and manufacturers, provide one of the products listed that

complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered, unless otherwise indicated.

4. **Manufacturers:** Where Specification paragraphs or subparagraphs titled "Manufacturers" introduce a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered, unless otherwise indicated.
5. **Available Products:** Where Specification paragraphs or subparagraphs titled "Available Products" introduce a list of names of both products and manufacturers, provide one of the products listed or an unnamed product that complies with requirements. Comply with provisions in "Comparable Products" Article for consideration of an unnamed product.
6. **Available Manufacturers:** Where Specification paragraphs or subparagraphs titled "Available Manufacturers" introduce a list of manufacturers' names, provide a product by one of the manufacturers listed or another manufacturer that complies with requirements. Comply with provisions in "Comparable Products" Article for consideration of an unnamed manufacturer's product.
7. **Product Options:** Where Specification paragraphs titled "Product Options" indicate that size, profiles, and dimensional requirements on Drawings are based on a specific product or system, provide either the specific product or system indicated or a comparable product or system by another manufacturer. Comply with requirements in Section 01 25 00 "Substitution Procedures" for proposal of product.
8. **Basis-of-Design Products:** Where Specification paragraphs or subparagraphs titled "Basis-of-Design Product" are included and also introduce or refer to a list of manufacturers' names, provide either the specified product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with provisions in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.
9. **Visual Matching Specification:** Where Specifications require matching an established Sample, provide a product (and manufacturer) that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches satisfactorily.
 - a. If no product available within specified category matches satisfactorily and complies with other specified requirements, comply with requirements in Section 01 25 00 "Substitution Procedures" for proposal of product.
10. **Visual Selection Specification:**
 - a. **Standard Range:** Where Specifications include the phrase "as selected by Architect from manufacturer's standard range" or similar phrase, Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that does not include premium items.
 - b. **Full Range:** Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

A. Conditions for Consideration: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:

1. Evidence that the proposed product does not require extensive revisions to the Contract Documents that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
3. Evidence that proposed product provides specified warranty.
4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
5. Samples, if requested.

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 01 60 00

SECTION 01 73 00 – EXECUTION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes general procedural requirements governing execution of the Work including, but not limited to, the following:
 - 1. Construction layout.
 - 2. Field engineering and surveying.
 - 3. General installation of the Work.
 - 4. Coordination of Owner-installed products.
 - 5. Progress cleaning.
 - 6. Starting and adjusting.
 - 7. Protection of installed construction.
 - 8. Repair of the Work.
- B. Related Sections include the following:
 - 1. Section 01 31 00 "Project Management and Coordination" for procedures for coordinating field engineering with other construction activities.

1.3 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For land surveyor.
- B. Certificates: Submit certificate signed by land surveyor certifying that location and elevation of improvements comply with requirements.
- C. Certified Surveys: Submit two copies signed by land surveyor.
- D. Final Property Survey: Submit 10 copies showing the Work performed and record survey data.
- A. **QUALITY ASSURANCE** Land Surveyor Qualifications: A professional land surveyor who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing land-surveying services of the kind indicated.
- B. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of products and equipment.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Existing Conditions: The existence and location of underground utilities, site improvements, and other construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of underground utilities, site improvements, mechanical and electrical systems, existing construction and other services affecting the Work.
1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, water-service piping, underground electrical services, and other utilities.
 2. Furnish location data for work related to Project that must be performed by public utilities serving Project site.
- B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
 2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
 3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Written Report: Where a written report listing conditions detrimental to performance of the Work is required by other Sections, include the following:
1. Description of the Work.
 2. List of detrimental conditions, including substrates.
 3. List of unacceptable installation tolerances.
 4. Recommended corrections.
- D. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Existing Utility Information: Furnish information to Owner for issue to local utility that is necessary to adjust, move, or relocate existing utility structures, utility poles, lines, services, or

other utility appurtenances located in or affected by construction. Coordinate with authorities having jurisdiction.

- B. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- C. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- D. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents caused by differing field conditions outside the control of Contractor, submit a request for interpretation to Architect according to Section 01 26 13 "Request for Interpretation." Include a detailed description of problem encountered, together with recommendations for necessary modifications that may be required.

3.3 CONSTRUCTION LAYOUT

- A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to the property survey, existing benchmarks, control and reference points. If discrepancies are discovered, notify Architect promptly.
- B. General: Engage a land surveyor to lay out the Work using accepted surveying practices.
 - 1. Establish benchmarks and control points to set lines and levels at each story of construction and elsewhere as needed to locate each element of Project.
 - 2. Establish limits on use of Project site.
 - 3. Establish dimensions within tolerances indicated. Do not scale Drawings to obtain required dimensions.
 - 4. Inform installers of lines and levels to which they must comply.
 - 5. Check the location, level and plumb, of every major element as the Work progresses.
 - 6. Notify Architect when deviations from required lines and levels exceed allowable tolerances.
 - 7. Close site surveys with an error of closure equal to or less than the standard established by authorities having jurisdiction.
- C. Site Improvements: Locate and lay out site improvements, including pavements, grading, fill and topsoil placement, utility slopes, and rim and invert elevations.
- D. Building Lines and Levels: Locate and lay out control lines and levels for structures, building foundations, column grids, and floor levels, architectural elements, including those required for mechanical and electrical work. Transfer survey markings and elevations for use with control lines and levels. Level foundations and piers from two or more locations.
- E. Record Log: Maintain a log of layout control work. Record deviations from required lines and levels. Include beginning and ending dates and times of surveys, weather conditions, name and duty of each survey party member, and types of instruments and tapes used. Make the log available for reference by Architect.

3.4 FIELD ENGINEERING

- A. Identification: Owner will identify existing benchmarks, control points, and property corners.
- B. Reference Points: Locate existing permanent benchmarks, control points, and similar reference points before beginning the Work. Preserve and protect permanent benchmarks and control points during construction operations.
 - 1. Do not change or relocate existing benchmarks or control points without prior written approval of Architect. Report lost or destroyed permanent benchmarks or control points promptly. Report the need to relocate permanent benchmarks or control points to Architect before proceeding.
 - 2. Replace lost or destroyed permanent benchmarks and control points promptly. Base replacements on the original survey control points.
- C. Benchmarks: Establish and maintain a minimum of two permanent benchmarks on Project site, referenced to data established by survey control points. Comply with authorities having jurisdiction for type and size of benchmark.
 - 1. Record benchmark locations, with horizontal and vertical data, on Project Record Documents.
 - 2. Where the actual location or elevation of layout points cannot be marked, provide temporary reference points sufficient to locate the Work.
 - 3. Remove temporary reference points when no longer needed. Restore marked construction to its original condition.
- D. Certified Survey: On completion of foundation walls, major site improvements, and other work requiring field-engineering services, prepare a certified survey showing dimensions, locations, angles, and elevations of construction and sitework.
- E. Final Property Survey: Engage a land surveyor to prepare a final property survey showing significant features (real property) for Project. Include on the survey a certification, signed by land surveyor, that principal metes, bounds, lines, and levels of Project are accurately positioned as shown on the survey.
 - 1. Show boundary lines, monuments, streets, site improvements and utilities, existing improvements and significant vegetation, adjoining properties, acreage, grade contours, and the distance and bearing from a site corner to a legal point.
 - 2. Recording: At Substantial Completion, have the final property survey recorded by or with authorities having jurisdiction as the official "property survey."

3.5 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
 - 1. Make vertical work plumb and make horizontal work level.
 - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
 - 3. Conceal pipes, ducts, and wiring in finished areas, unless otherwise indicated.

4. Maintain minimum headroom clearances indicated.
 - B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
 - C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
 - D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
 - E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on site and placement in permanent locations.
 - F. Tools and Equipment: Do not use tools or equipment that produces harmful noise levels.
 - G. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
 - H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions
 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
 2. Allow for building movement, including thermal expansion and contraction.
 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.
 - I. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
 - J. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.
 - 3.6 Protect adjacent property and adjoining work, including sealant bond surfaces, from spillage or blow-over of coatings, paints, sprayed fire-resistive material, and other spray-applied products. Cover adjoining and nearby surfaces, including live plants and grass, if there is possibility of spray-applied products being deposited on surfaces.
- OWNER-INSTALLED PRODUCTS**
- A. Site Access: Provide access to Project site for Owner's construction forces.
 - B. Coordination: Coordinate construction and operations of the Work with work performed by Owner's construction forces.

1. Construction Schedule: Inform Owner of Contractor's preferred construction schedule for Owner's portion of the Work. Adjust construction schedule based on a mutually agreeable timetable. Notify Owner if changes to schedule are required due to differences in actual construction progress.
2. Preinstallation Conferences: Include Owner's construction forces at preinstallation conferences covering portions of the Work that are to receive Owner's work. Attend preinstallation conferences conducted by Owner's construction forces if portions of the Work depend on Owner's construction.

3.7 PROGRESS CLEANING

- A. General: Clean Project site and work areas daily, including common areas. Coordinate progress cleaning for joint-use areas where more than one installer has worked. Enforce requirements strictly. Dispose of materials lawfully.
 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
 2. Do not hold materials more than 7 days during normal weather or 3 days if the temperature is expected to rise above 80 degrees F.
 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
 1. Remove liquid spills promptly.
 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.
- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.
- F. Exposed Surfaces: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- G. Waste Disposal: Burying or burning waste materials on-site will not be permitted. Washing waste materials down sewers or into waterways will not be permitted. Comply with Section 01 74 19 "Construction Waste Management and Disposal" and Section 01 50 00 "Temporary Facilities and Controls."
- H. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.

- I. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- J. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.8 STARTING AND ADJUSTING

- A. Coordinate startup and adjusting of equipment and operating components with requirements in Section 01 91 13 "General Commissioning Requirements."
- B. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- C. Adjust operating components for proper operation without binding. Adjust equipment for proper operation.
- D. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- E. Manufacturer's Field Service: If a factory-authorized service representative is required to inspect field-assembled components and equipment installation, comply with qualification requirements in Section 01 40 00 "Quality Requirements" and additional requirements specified in Division 3 thru Division 49 Specification Sections.

3.9 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.

END OF SECTION 01 73 00

SECTION 01 73 29 - CUTTING AND PATCHING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes procedural requirements for cutting and patching.
- B. Related Sections include the following:
 - 1. Divisions 3 through 28 Sections for specific requirements and limitations applicable to cutting and patching individual parts of the Work.
 - 2. Requirements in this Section apply to mechanical and electrical installations. Refer to Divisions 21 through 28 for other requirements and limitations applicable to cutting and patching mechanical and electrical installations.

1.3 DEFINITIONS

- A. Cutting: Removal of in-place or existing construction necessary to permit installation or performance of other Work.
- B. Patching: Fitting and repair work required to restore construction to original conditions after installation of other Work.

1.4 QUALITY ASSURANCE

- A. Structural Elements: Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection. Shore, brace, and support structural elements during cutting and patching.
- B. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety. Operational elements include, but are not limited to, the following:
 - 1. Primary operational systems and equipment.
 - 2. Primary air and water distribution systems and equipment.
 - 3. Control systems.
 - 4. Communication systems.
 - 5. Electrical wiring systems.
- C. Miscellaneous Elements: Do not cut and patch the following elements or related components in a manner that could change their load-carrying capacity, that results in reducing their capacity

to perform as intended, or that results in increased maintenance or decreased operational life or safety.

1. Water, moisture, or vapor barriers.
 2. Membranes and flashings.
 3. Exterior wall elements.
 4. Equipment supports.
 5. Piping, ductwork, vessels, and equipment.
 6. Noise- and vibration-control elements and systems.
- D. Visual Requirements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.
- E. Existing Warranties: Do not cut and patch in-place or existing construction by methods or in any manner that may void existing warranties.

PART 2 - PRODUCTS

2.1 PATCHING MATERIALS

- A. New Materials: Comply with requirements specified in Division 3 through 28 Sections of these Specifications.
1. For projects requiring compliance with sustainable design and construction practices and procedures, use products for patching that comply with requirements in Division 01 Section, "Sustainable Design Requirements."
- B. In-Place or Existing Materials: Use materials identical to in-place or existing materials. For exposed surfaces, use materials that visually match in-place or existing adjacent surfaces to the fullest extent possible and that are approved by Architect.
1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place or existing materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine surfaces to be cut and patched and conditions under which cutting and patching are to be performed.
1. Compatibility: Before patching, verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
 2. Proceed with installation only after unsafe or unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Temporary Support: Provide temporary support of Work to be cut.
- B. Protection: Protect in-place or existing construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- C. Adjoining Areas: Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.
- D. General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 - 1. Cut in-place or existing construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- E. Cutting: Cut existing construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
 - 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 - 2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
 - 3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
 - 4. Excavating and Backfilling: Comply with requirements in applicable Division 31 Sections where required by cutting and patching operations.
 - 5. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
 - 6. Proceed with patching after construction operations requiring cutting are complete.
- F. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other Work. Patch with durable seams that are as invisible as possible. Provide materials and comply with installation requirements specified in other Sections of these Specifications.
 - 1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
 - 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will minimize evidence of patching and refinishing.
 - 3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place or existing

floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.

- a. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch. Provide additional coats until patch blends with adjacent surfaces.
4. Ceilings: Patch, repair, or rehang in-place or existing ceilings as necessary to provide an even-plane surface of uniform appearance.
5. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition and ensures thermal and moisture integrity of building enclosure.
- G. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

END OF SECTION 01 73 29

SECTION 01 74 19 – CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes requirements for waste reduction and for the recycling of non-hazardous, recyclable, construction and demolition debris.
 - 1. Reduce waste by minimizing factors that contribute to waste.
 - 2. Use reasonable and legal means to divert construction and demolition debris from landfills and incinerators by facilitating their recycling or reuse through a Contractor developed, and Owner reviewed, construction waste management program.
- B. Related Sections
 - 1. Division 1 Section 01 81 13 "Sustainable Design Requirements" for LEED credit requirements.

1.2 DEFINITIONS

- A. Waste Reduction: Construction practices that achieve the most efficient use of resources and materials; uses water efficiently; avoids practices such as over-packaging, improper storage, ordering errors, poor planning, breakage, mishandling and contamination.
- B. Construction and Demolition Debris: Solid wastes arising from demolition or removal, excess or unusable construction materials, packing materials for construction products, and other materials generated on site during the construction process but not incorporated into the Work.
- C. Recyclable Materials: Construction and demolition debris that can be recovered and processed into new products or materials. Recyclable materials include, but are not limited to, the following:
 - 1. Metals: Ferrous (iron, steel, stainless steel, galvanized steel) and non-ferrous (copper, brass, bronze, aluminum) types and containers made from metals such as pails, buckets and beverage cans.
 - 2. Asphaltic concrete paving.
 - 3. Concrete.
 - 4. Gypsum wallboard.
 - 5. Paper products such as generated from field office activities and clean corrugated packaging cardboard.
 - 6. Wood products, including untreated dimensional lumber, plywood, oriented strand board, hardboard, particleboard and crates and pallets made from wood products.
 - 7. Brick and stone masonry.
 - 8. Carpet and padding.
 - 9. Plastics and containers made from plastics such as pails, buckets, and beverage bottles.
 - 10. Copper wiring.
 - 11. Glass: Glass beverage containers, window and mirror glass.

12. Clean and uncontaminated, excavated soils not intended for other on-site use.
13. Stumps and trees removed as a part of land clearing operations.
14. NOTE: Excavated soils, stumps and trees removed as part of land clearing can not be included in the LEED MRc2 calculations.

- D. Non-Recyclable Materials: Construction and demolition debris not capable of being reused or reprocessed, exclusive of the recyclable materials listed above.
- E. Hazardous Materials: Construction and demolition debris that are regulated for disposal by local, city, county, state, or Federal authorities.

1.3 SUBMITTALS

- A. Construction Waste Management Program: Submit the proposed waste management program appended to the bid. The program shall include the following:

1. Identification of Contractor's staff responsible for enforcing construction waste management.
2. Actions that will be taken to reduce solid waste generation.
3. Description of the specific methods to be used in recycling/reuse of the various construction and demolition debris generated, including the areas and equipment, to be used for processing, sorting, and temporary storage of debris.
4. Characterization, including estimated types and quantities of the construction and demolition debris to be generated. Include percentages of recyclable and non-recyclable debris.
5. List of specific construction and demolition debris materials that will be salvaged for resale, salvaged and reused, or recycled.
6. Name(s) of landfill and incinerator to be used and the estimated costs for use, for construction and demolition debris that is unable to be recycled or reused.
7. Identification of local and regional reuse programs, including non-profit organizations such as schools, local housing agencies, and organizations that accept used and excess construction materials such as materials exchange networks and Habitat for Humanity.
8. Identification of local recycling facilities that will accept construction and demolition debris.
9. Identification of construction and demolition debris that cannot be recycled/reused with an explanation or justification.
10. Anticipated net cost savings determined by subtracting Contractor program management costs and the cost of disposal from the revenue generated by sale of the construction and demolition debris and avoided landfill and incineration costs.

- B. Waste Management Reports: With each Application for Payment submit a Waste Management Report in a form acceptable to the Architect and Owner. Attach manifests, weight tickets, receipts and invoices. Organize and maintain records to document the following:

1. Quantity of debris generated, for each material recycled, reused or salvaged.
2. Quantity of debris diverted through sale, reuse, or recycling, in tons or cubic yards.
3. Quantity of debris disposed by landfill or incineration.
4. Name and location of each firm accepting the debris, including:
 - a. Types of debris accepted.

- b. Net weights of each type.
 - c. Date of acceptance.
- 5. Transportation cost for removal of debris from job site.
- 6. Amount of money paid or received for the recycled, reused or salvaged materials.
- 7. Net total cost or savings of recycling, reusing or salvaging materials.
- C. Project Closeout: Upon project completion submit the Waste Management Records to the Owner.
 - 1. Submit evidence that non-hazardous construction and demolition has been recycled and salvaged. Calculations can be done by weight or volume, but must be consistent throughout.

1.4 QUALITY ASSURANCE

- A. Construction Waste Management: Prior to bid, prepare a program that minimizes waste and diverts construction and demolition debris from landfills and incinerators by facilitating their reuse or recycling. Name the waste material processors who will accept the construction and demolition debris, the condition of the construction and demolition debris required by the waste material processors, the method proposed to provide the construction and demolition debris in suitable condition and in a quantity acceptable to the disposal sites and waste material processors whom will receive them, and the impact on the project schedule. The Contractor shall be responsible for implementation of any special programs involving rebates or similar incentives related to the recycling of waste. Revenues or other savings obtained from sale, reuse, and recycling operations shall accrue to the Contractor.
- B. Disposal Sites and Waste Material Processors: Use only facilities with valid legal permits for disposal, recycling and waste processing issued by the jurisdictions in which they are located.
- C. Pre-Construction Waste Management Meeting: Prior to beginning site preparation, schedule and conduct a meeting to review the waste management program. The meeting shall include the Contractor, the Architect, the Owner and any of the Contractor's subcontractors or suppliers whose work will interface with the program. The agenda shall include a discussion of procedures, schedules and specific requirements for construction and demolition debris, sale, reuse, recycling, and disposal. Make any revisions to the program that are agreed to as a part of the meeting and submit the revised program and the meeting minutes to the Architect and Owner for their records.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 WASTE MANAGEMENT PLAN IMPLEMENTATION

- A. Distribution: The Contractor shall distribute copies of the Waste Management Plan to the Job Site Foreman, each Subcontractor, the Owner and the Architect.

- B. General: For the duration of the project implement and maintain construction waste management. During the prosecution of the Work encourage the practice of efficient waste reduction when sizing, cutting, and installing products and materials.
- C. Transportation: Arrange for the regular collection, transport from the site, and delivery of the construction wastes and debris to the designated recyclers, and waste material processors and disposal sites.
- D. Separation Facilities: The Contractor shall provide on-site instruction of appropriate separation, handling separation, handling, and recycling, salvage, reuse and return methods to be used by all parties at the appropriate stages of the Project. Provide and designate an on-site area for the separation of construction and demolition debris for reuse and recycling. Locate the area in order that non-recyclable debris will not contaminate materials to be reused or recycled. Provide containers and bins in the designated area to facilitate separation, storage and handling which are clearly and appropriately marked. Cut all items to lengths and sizes to fit within the containers or bins provided. Where there is sufficient quantity of a specific recyclable debris item (for example; salvaged metal doors and frames or duct work), make arrangements for items to be bundled, banded or tied, and stack in a designated location for a special pick-up. Maintain the separation facilities in an orderly condition to prevent contamination of materials placed therein and to maximize reuse and recyclability of debris. Separate construction and demolition debris at the project site by one of the following methods:
 - 1. Source Separated Method: Construction and demolition debris, that is reusable and recyclable, are separated from non-recyclable debris and sorted into appropriately marked separated containers or bins and then transported to the designated recycling facility for further processing. Non-recyclable debris is transported to a landfill or incinerator.
 - 2. Co-Mingled Method: All construction and demolition debris is placed into containers or bins and then transported to a recycling facility where recyclable and salvageable materials are removed, sorted, and processed and the remaining waste is transported to a landfill or incinerator.

END OF SECTION 01 74 19

SECTION 01 77 00 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Substantial Completion procedures.
 - 2. Final completion procedures.
 - 3. Warranties.
 - 4. Final cleaning.
- B. Related Requirements:
 - 1. Section 017300 "Execution" for progress cleaning of Project site.
 - 2. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.
 - 3. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
 - 4. Section 017900 "Demonstration and Training" for requirements for instructing Owner's personnel.

1.3 ACTION SUBMITTALS

- A. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- B. Certified List of Incomplete Items: Final submittal at Final Completion.

1.4 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.
- C. Field Report: For pest control inspection.

1.5 SUBSTANTIAL COMPLETION PROCEDURES

- A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.

- B. Submittals Prior to Substantial Completion: Complete the following a minimum of ten days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
 2. Submit closeout submittals specified in other Division 01 Sections, including project record documents, operation and maintenance manuals, final completion construction photographic documentation, damage or settlement surveys, property surveys, and similar final record information.
 3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 4. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Owner. Label with manufacturer's name and model number where applicable.
 5. Submit test/adjust/balance records.
 6. Submit sustainable design submittals required in Section 018113 "Sustainable Design Requirements" and in individual Sections.
 7. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
 8. Submit pest-control final inspection report.
- C. Procedures Prior to Substantial Completion: Complete the following a minimum of ten days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
1. Advise Owner of pending insurance changeover requirements.
 2. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
 3. Complete startup and testing of systems and equipment.
 4. Perform preventive maintenance on equipment used prior to Substantial Completion.
 5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems.
 6. Advise Owner of changeover in heat and other utilities.
 7. Participate with Owner in conducting inspection and walkthrough with local emergency responders.
 8. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
 9. Complete final cleaning requirements, including touchup painting.
 10. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.
 11. Complete repair and restoration operations.
- D. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of ten days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
2. Results of completed inspection will form the basis of requirements for final completion.

E. Certificate Form: AIA Document G704, Certificate of Substantial Completion.

1.6 FINAL COMPLETION PROCEDURES

- A. Submittals Prior to Final Completion: Before requesting final inspection for determining final completion, complete the following:
1. Submit a final Application for Payment according to Section 012900 "Payment Procedures."
 2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
 3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
- B. Inspection: Submit a written request for final inspection to determine acceptance a minimum of ten days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.7 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
1. Organize list of spaces in sequential order, starting with exterior areas first and proceeding from lowest floor to highest floor.
 2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
 3. Include the following information at the top of each page:
 - a. Project name.
 - b. Date.
 - c. Name of Architect.
 - d. Name of Contractor.
 - e. Page number.
 4. Submit list of incomplete items in one of the following electronic formats:
 - a. MS Excel electronic file. Architect will return annotated file.
 - b. PDF electronic file. Architect will return annotated file.
 5. Additional copies: In addition to submission of electronic files, submit three paper copies.

1.8 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated, or when delay in submittal of warranties might limit Owner's rights under warranty.
- B. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.
 - 1. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
 - 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
 - 3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
- C. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.
 - 1. Use cleaning products that comply with applicable State VOC restrictions.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.

- b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
- c. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
- d. Remove tools, construction equipment, machinery, and surplus material from Project site.
- e. Remove snow and ice to provide safe access to building.
- f. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.
- g. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
- h. Sweep concrete floors broom clean in unoccupied spaces.
- i. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean according to manufacturer's recommendations if visible soil or stains remain.
- j. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.
- k. Remove labels that are not permanent.
- l. Wipe surfaces of mechanical and electrical equipment and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
- m. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
- n. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
- o. Clean ducts, blowers, and coils if units were operated without filters during construction or that display contamination with particulate matter on inspection.
- p. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency.
- q. Leave Project clean and ready for occupancy.

END OF SECTION 01 77 00

SECTION 01 78 23 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
 - 1. Operation and maintenance documentation directory.
 - 2. Emergency manuals.
 - 3. Operation manuals for systems, subsystems, and equipment.
 - 4. Product maintenance manuals.
 - 5. Systems and equipment maintenance manuals.
- B. Related Requirements:
 - 1. Section 019113 "General Commissioning Requirements" for verification and compilation of data into operation and maintenance manuals.

1.3 DEFINITIONS

- A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.
- B. Subsystem: A portion of a system with characteristics similar to a system.

1.4 CLOSEOUT SUBMITTALS

- A. Manual Content: Operations and maintenance manual content is specified in individual Specification Sections to be reviewed at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.
 - 1. Architect will comment on whether content of operations and maintenance submittals are acceptable.
 - 2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.
- B. Format: Submit operations and maintenance manuals in the following format:
 - 1. PDF electronic file. Assemble each manual into a composite electronically indexed file. Submit on digital media acceptable to Architect.

- a. Name each indexed document file in composite electronic index with applicable item name. Include a complete electronically linked operation and maintenance directory.
 - b. Enable inserted review comments on draft submittals.
- C. Initial Manual Submittal: Submit draft copy of each manual to Owner at least 30 days before commencing demonstration and training. Owner will comment on whether general scope and content of manual are acceptable.
- D. Final Manual Submittal: Submit each manual in final form to Owner prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Owner will return copy with comments.
 1. Correct or revise each manual to comply with Owner's comments. Submit copies of each corrected manual at least 5 days prior to commencing demonstration and training.

PART 2 - PRODUCTS

2.1 OPERATION AND MAINTENANCE DOCUMENTATION DIRECTORY

- A. Directory: Prepare a single, comprehensive directory of emergency, operation, and maintenance data and materials, listing items and their location to facilitate ready access to desired information. Include a section in the directory for each of the following:
 1. List of documents.
 2. List of systems.
 3. List of equipment.
 4. Table of contents.
- B. List of Systems and Subsystems: List systems alphabetically. Include references to operation and maintenance manuals that contain information about each system.
- C. List of Equipment: List equipment for each system, organized alphabetically by system. For pieces of equipment not part of system, list alphabetically in separate list.
- D. Tables of Contents: Include a table of contents for each emergency, operation, and maintenance manual.
- E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation according to ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

2.2 REQUIREMENTS FOR EMERGENCY, OPERATION, AND MAINTENANCE MANUALS

- A. Organization: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:
 - 1. Title page.
 - 2. Table of contents.
 - 3. Manual contents.
- B. Title Page: Include the following information:
 - 1. Subject matter included in manual.
 - 2. Name and address of Project.
 - 3. Name and address of Owner.
 - 4. Date of submittal.
 - 5. Name and contact information for Contractor.
 - 6. Name and contact information for Architect.
 - 7. Name and contact information for Commissioning Authority.
 - 8. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
 - 9. Cross-reference to related systems in other operation and maintenance manuals.
- C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.
- D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.
- E. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic PDF file for each manual type required.
 - 1. Electronic Files: Use electronic files prepared by manufacturer where available. Where scanning of paper documents is required, configure scanned file for minimum readable file size.
 - 2. File Names and Bookmarks: Enable bookmarking of individual documents based on file names. Name document files to correspond to system, subsystem, and equipment names used in manual directory and table of contents. Group documents for each system and subsystem into individual composite bookmarked files, then create composite manual, so that resulting bookmarks reflect the system, subsystem, and equipment names in a readily navigated file tree. Configure electronic manual to display bookmark panel on opening file.

2.3 EMERGENCY MANUALS

- A. Content: Organize manual into a separate section for each of the following:
 - 1. Type of emergency.
 - 2. Emergency instructions.
 - 3. Emergency procedures.
- B. Type of Emergency: Where applicable for each type of emergency indicated below, include instructions and procedures for each system, subsystem, piece of equipment, and component:
 - 1. Fire.
 - 2. Flood.
 - 3. Gas leak.
 - 4. Water leak.
 - 5. Power failure.
 - 6. Water outage.
 - 7. System, subsystem, or equipment failure.
 - 8. Chemical release or spill.
- C. Emergency Instructions: Describe and explain warnings, trouble indications, error messages, and similar codes and signals. Include responsibilities of Owner's operating personnel for notification of Installer, supplier, and manufacturer to maintain warranties.
- D. Emergency Procedures: Include the following, as applicable:
 - 1. Instructions on stopping.
 - 2. Shutdown instructions for each type of emergency.
 - 3. Operating instructions for conditions outside normal operating limits.
 - 4. Required sequences for electric or electronic systems.
 - 5. Special operating instructions and procedures.

2.4 OPERATION MANUALS

- A. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:
 - 1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.
 - 2. Performance and design criteria if Contractor has delegated design responsibility.
 - 3. Operating standards.
 - 4. Operating procedures.
 - 5. Operating logs.
 - 6. Wiring diagrams.
 - 7. Control diagrams.
 - 8. Piped system diagrams.
 - 9. Precautions against improper use.
 - 10. License requirements including inspection and renewal dates.
- B. Descriptions: Include the following:
 - 1. Product name and model number. Use designations for products indicated on Contract Documents.
 - 2. Manufacturer's name.
 - 3. Equipment identification with serial number of each component.

4. Equipment function.
 5. Operating characteristics.
 6. Limiting conditions.
 7. Performance curves.
 8. Engineering data and tests.
 9. Complete nomenclature and number of replacement parts.
- C. Operating Procedures: Include the following, as applicable:
1. Startup procedures.
 2. Equipment or system break-in procedures.
 3. Routine and normal operating instructions.
 4. Regulation and control procedures.
 5. Instructions on stopping.
 6. Normal shutdown instructions.
 7. Seasonal and weekend operating instructions.
 8. Required sequences for electric or electronic systems.
 9. Special operating instructions and procedures.
- D. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.
- E. Piped Systems: Diagram piping as installed, and identify color-coding where required for identification.

2.5 PRODUCT MAINTENANCE MANUALS

- A. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
- B. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.
- C. Product Information: Include the following, as applicable:
1. Product name and model number.
 2. Manufacturer's name.
 3. Color, pattern, and texture.
 4. Material and chemical composition.
 5. Reordering information for specially manufactured products.
- D. Maintenance Procedures: Include manufacturer's written recommendations and the following:
1. Inspection procedures.
 2. Types of cleaning agents to be used and methods of cleaning.
 3. List of cleaning agents and methods of cleaning detrimental to product.
 4. Schedule for routine cleaning and maintenance.
 5. Repair instructions.

- E. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.
- F. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
 - 1. Include procedures to follow and required notifications for warranty claims.

2.6 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

- A. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranty and bond information, as described below.
- B. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.
- C. Manufacturers' Maintenance Documentation: Manufacturers' maintenance documentation including the following information for each component part or piece of equipment:
 - 1. Standard maintenance instructions and bulletins.
 - 2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
 - 3. Identification and nomenclature of parts and components.
 - 4. List of items recommended to be stocked as spare parts.
- D. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:
 - 1. Test and inspection instructions.
 - 2. Troubleshooting guide.
 - 3. Precautions against improper maintenance.
 - 4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - 5. Aligning, adjusting, and checking instructions.
 - 6. Demonstration and training video recording, if available.
- E. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.
 - 1. Scheduled Maintenance and Service: Tabulate actions for daily, weekly, monthly, quarterly, semiannual, and annual frequencies.
 - 2. Maintenance and Service Record: Include manufacturers' forms for recording maintenance.
- F. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.

- G. Maintenance Service Contracts: Include copies of maintenance agreements with name and telephone number of service agent.
- H. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
 - 1. Include procedures to follow and required notifications for warranty claims.

PART 3 - EXECUTION

3.1 MANUAL PREPARATION

- A. Emergency Manual: Assemble a complete set of emergency information indicating procedures for use by emergency personnel and by Owner's operating personnel for types of emergencies indicated.
- B. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.
- C. Operation and Maintenance Manuals: Assemble a complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.
 - 1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
 - 2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.
- D. Manufacturers' Data: Where manuals contain manufacturers' standard printed data, include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
 - 1. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.
- E. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.
 - 1. Do not use original project record documents as part of operation and maintenance manuals.
 - 2. Comply with requirements of newly prepared record Drawings in Section 017839 "Project Record Documents."

END OF SECTION 01 78 23

SECTION 01 78 39 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for project record documents, including the following:
 - 1. Record Drawings.
 - 2. Record Specifications.
 - 3. Record Product Data.
 - 4. Miscellaneous record submittals.
- B. Related Requirements:
 - 1. Section 017300 "Execution" for final property survey.
 - 2. Section 017700 "Closeout Procedures" for general closeout procedures.
 - 3. Section 017823 "Operation and Maintenance Data" for operation and maintenance manual requirements.

1.3 CLOSEOUT SUBMITTALS

- A. Record Drawings: Submit one set of marked-up record prints.
- B. Record Specifications: Submit one paper copy of Project's Specifications, including addenda and contract modifications.
- C. Record Product Data: Submit one paper copy of each submittal.
 - 1. Where record Product Data are required as part of operation and maintenance manuals, submit duplicate marked-up Product Data as a component of manual.
- D. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Submit one paper copy of each submittal.

PART 2 - PRODUCTS

2.1 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.

1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
 - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
 - b. Accurately record information in an acceptable drawing technique.
 - c. Record data as soon as possible after obtaining it.
 - d. Record and check the markup before enclosing concealed installations.
 - e. Cross-reference record prints to corresponding archive photographic documentation, if any.
 2. Content: Types of items requiring marking include, but are not limited to, the following:
 - a. Dimensional changes to Drawings.
 - b. Revisions to details shown on Drawings.
 - c. Depths of foundations below first floor.
 - d. Locations and depths of underground utilities.
 - e. Revisions to routing of piping and conduits.
 - f. Revisions to electrical circuitry.
 - g. Actual equipment locations.
 - h. Duct size and routing.
 - i. Locations of concealed internal utilities.
 - j. Changes made by Change Order or Construction Change Directive.
 - k. Changes made following Architect's written orders.
 - l. Details not on the original Contract Drawings.
 - m. Field records for variable and concealed conditions.
 - n. Record information on the Work that is shown only schematically.
 3. Mark the Contract Drawings and Shop Drawings completely and accurately and cross reference Shop Drawings to Contract Drawings. Use personnel proficient at recording graphic information in production of marked-up record prints.
 4. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
 5. Mark important additional information that was either shown schematically or omitted from original Drawings.
 6. Note alternate numbers, Change Order numbers, Construction Change Directive numbers, and similar identification, where applicable.
- B. Newly Prepared Record Drawings: Prepare new Drawings instead of preparing record Drawings where Architect determines that neither the original Contract Drawings nor Shop Drawings are suitable to show actual installation.
1. New Drawings may be required when a Change Order is issued as a result of accepting an alternate, substitution, or other modification.
 2. Consult Architect for proper scale and scope of detailing and notations required to record the actual physical installation and its relation to other construction. Integrate newly prepared record Drawings into record Drawing sets; comply with procedures for formatting, organizing, copying, binding, and submitting.

- C. Format: Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.
 - 1. Record Prints: Organize record prints and newly prepared record Drawings into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
 - 2. Identification: As follows:
 - a. Project name.
 - b. Date.
 - c. Designation "PROJECT RECORD DRAWINGS."
 - d. Name of Architect.
 - e. Name of Contractor.

2.2 RECORD SPECIFICATIONS

- A. Preparation: Mark Specifications to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
 - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 - 2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
 - 3. Record the name of manufacturer, supplier, Installer, and other information necessary to provide a record of selections made.
 - 4. For each principal product, indicate whether record Product Data has been submitted in operation and maintenance manuals instead of submitted as record Product Data.
 - 5. Note related Change Orders, record Product Data, and record Drawings where applicable.
- B. Format: Maintain format of original Project Manual organized sequentially by Specification Section number and title.

2.3 RECORD PRODUCT DATA

- A. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.
 - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 - 2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
 - 3. Note related Change Orders, record Specifications, and record Drawings where applicable.
- B. Format: Include record Product Data directory organized sequentially by Specification Section number and title.

2.4 MISCELLANEOUS RECORD SUBMITTALS

- A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference. Miscellaneous record submittals include, but are not limited to, the following:
1. Certificates.
 2. Reports.
 3. Inspection data.
 4. Test results.
 5. Design data.
 6. Engineering analysis.
 7. Informational submittals.
- B. Format: Include miscellaneous record submittals directory organized sequentially by Specification Section number and title.

PART 3 - EXECUTION

3.1 RECORDING AND MAINTENANCE

- A. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.
- B. Maintenance of Record Documents and Samples: Store record documents and Samples in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Architect's reference during normal working hours.

END OF SECTION 01 78 39

SECTION 01 79 00 - DEMONSTRATION AND TRAINING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:
 - 1. Demonstration of operation of systems, subsystems, and equipment.
 - 2. Training in operation and maintenance of systems, subsystems, and equipment.

1.3 INFORMATIONAL SUBMITTALS

- A. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.

1.4 QUALITY ASSURANCE

- A. Facilitator Qualifications: A firm or individual experienced in training or educating maintenance personnel in a training program similar in content and extent to that indicated for this Project, and whose work has resulted in training or education with a record of successful learning performance.
- B. Instructor Qualifications: A factory-authorized service representatives or individuals experienced in operation and maintenance procedures and training.

1.5 COORDINATION

- A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations and to ensure availability of Owner's personnel.
- B. Coordinate instructors, including providing notification of dates, times, length of instruction time, and course content.
- C. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data has been reviewed and approved by Owner.

PART 2 - PRODUCTS

2.1 INSTRUCTION PROGRAM

- A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.
- B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:
 - 1. Basis of System Design, Operational Requirements, and Criteria: Include the following:
 - a. System, subsystem, and equipment descriptions.
 - b. Performance and design criteria if Contractor is delegated design responsibility.
 - c. Operating standards.
 - d. Regulatory requirements.
 - e. Equipment function.
 - f. Operating characteristics.
 - g. Limiting conditions.
 - h. Performance curves.
 - 2. Documentation: Review the following items in detail:
 - a. Emergency manuals.
 - b. Operations manuals.
 - c. Maintenance manuals.
 - d. Project record documents.
 - e. Identification systems.
 - f. Warranties and bonds.
 - g. Maintenance service agreements and similar continuing commitments.
 - 3. Emergencies: Include the following, as applicable:
 - a. Instructions on meaning of warnings, trouble indications, and error messages.
 - b. Instructions on stopping.
 - c. Shutdown instructions for each type of emergency.
 - d. Operating instructions for conditions outside of normal operating limits.
 - e. Sequences for electric or electronic systems.
 - f. Special operating instructions and procedures.
 - 4. Operations: Include the following, as applicable:
 - a. Startup procedures.
 - b. Equipment or system break-in procedures.
 - c. Routine and normal operating instructions.
 - d. Regulation and control procedures.
 - e. Control sequences.

- f. Safety procedures.
 - g. Instructions on stopping.
 - h. Normal shutdown instructions.
 - i. Operating procedures for emergencies.
 - j. Operating procedures for system, subsystem, or equipment failure.
 - k. Seasonal and weekend operating instructions.
 - l. Required sequences for electric or electronic systems.
 - m. Special operating instructions and procedures.
- 5. Adjustments: Include the following:
 - a. Alignments.
 - b. Checking adjustments.
 - c. Noise and vibration adjustments.
 - d. Economy and efficiency adjustments.
- 6. Troubleshooting: Include the following:
 - a. Diagnostic instructions.
 - b. Test and inspection procedures.
- 7. Maintenance: Include the following:
 - a. Inspection procedures.
 - b. Types of cleaning agents to be used and methods of cleaning.
 - c. List of cleaning agents and methods of cleaning detrimental to product.
 - d. Procedures for routine cleaning
 - e. Procedures for preventive maintenance.
 - f. Procedures for routine maintenance.
 - g. Instruction on use of special tools.
- 8. Repairs: Include the following:
 - a. Diagnosis instructions.
 - b. Repair instructions.
 - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
 - d. Instructions for identifying parts and components.
 - e. Review of spare parts needed for operation and maintenance.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Section 017823 "Operation and Maintenance Data."

3.2 INSTRUCTION

- A. Facilitator: Engage a qualified facilitator to prepare instruction program and training modules, to coordinate instructors, and to coordinate between Contractor and Owner for number of participants, instruction times, and location.
- B. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
- C. Scheduling: Provide instruction at mutually agreed on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.
 - 1. Schedule training directly with Owner with at least seven days' advance notice.
- D. Training Location and Reference Material: Conduct training on-site in the completed and fully operational facility using the actual equipment in-place. Conduct training using final operation and maintenance data submittals.
- E. Cleanup: Collect used and leftover educational materials and remove from Project site. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

END OF SECTION 01 79 00

SECTION 01 81 13.13 - SUSTAINABLE DESIGN REQUIREMENTS - LEED FOR NEW CONSTRUCTION AND MAJOR RENOVATIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.
 - 1. Related Sections:
 - a. Section 01 74 10 "Erosion and Sedimentation."
 - b. Section 01 74 19 "Construction Waste Management and Disposal."
 - c. Section 01 81 19 "Indoor Air Quality (IAQ) Management."
 - d. Section 01 91 13 "General Commissioning Requirements."
 - e. Section 01 91 14 "Commissioning of the Building Envelope"
 - f. Divisions 03 through 49 Sections for LEED Requirements specific to the Work of each of these Sections. These requirements may or may not include reference to LEED.

1.2 SUMMARY

- A. Section includes general requirements and procedures for compliance with certain USGBC LEED prerequisites and credits needed for Project to obtain LEED-Certified to Silver certification based on USGBC's "LEED-NC Retail v2009 Green Building Design and Construction."
 - 1. Other LEED prerequisites and credits needed to obtain LEED certification depend on product selections and may not be specifically identified as LEED requirements. Compliance with requirements needed to obtain LEED prerequisites and credits may be used as one criterion to evaluate substitution requests and comparable product requests.
 - 2. Additional LEED prerequisites and credits needed to obtain the indicated LEED certification depend on Architect's design and other aspects of Project that are not part of the Work of the Contract.
 - 3. A copy of the LEED Prototype checklist is attached at the end of this Section for information only.
 - 4. Specific requirements for LEED are included in greater detail in other Sections.

1.3 DEFINITIONS

- A. LEED-NC Retail v2009: Leadership in Energy and Environmental Design – Green Building Design and Construction Retail Supplement version 2009. LEED is a national rating system for green buildings created by the US Green Building Council. All references to LEED throughout the Construction Documents shall mean LEED-NC Retail v2009.
- B. Chain-of-Custody Certificates: Certificates signed by manufacturers certifying that wood used to make products was obtained from forests certified by an FSC-accredited certification body to

comply with FSC STD-01-001, "FSC Principles and Criteria for Forest Stewardship." Certificates shall include evidence that manufacturer is certified for chain of custody by an FSC-accredited certification body.

- C. Composite Wood and Agri-fiber Board: Manufactured materials made from wood or agricultural fibers manufactured with bonding agents. Composite wood materials include particle board, medium density fiberboard (MDF), plywood, strawboard, wheatboard, panel substrates and door cores.
- D. Regional Materials: Materials that have been extracted, harvested, or recovered, as well as manufactured, within 500 miles (800 km) of Project site. If only a fraction of a product or material is extracted/harvested/recovered and manufactured locally, then only that percentage (by weight) shall contribute to the regional value.
- E. Recycled Content: The recycled content value of a material assembly shall be determined by weight. The recycled fraction of the assembly is then multiplied by the cost of assembly to determine the recycled content value.
 - 1. "Post-consumer" material is defined as waste material generated by households or by commercial, industrial, and institutional facilities in their role as end users of the product, which can no longer be used for its intended purpose.
 - 2. "Pre-consumer" material is defined as material diverted from the waste stream during the manufacturing process. Excluded is reutilization of materials such as rework, regrind, or scrap generated in a process and capable of being reclaimed within the same process that generated it.

1.4 ADMINISTRATIVE REQUIREMENTS

- A. Respond to questions and requests from Architect and the USGBC regarding LEED credits that are the responsibility of the Contractor, that depend on product selection or product qualities, or that depend on Contractor's procedures until the USGBC has made its determination on the project's LEED certification application. Document responses as informational submittals.

1.5 ACTION SUBMITTALS

- A. General: Submit additional LEED submittals required by other Specification Sections.
- B. LEED submittals are in addition to other submittals. If submitted item is identical to that submitted to comply with other requirements, submit duplicate copies as a separate submittal to verify compliance with indicated LEED requirements.
- C. Project Materials Cost Data: Provide the necessary cost data requested on the LEED Criteria Sheet and the LEED Materials and Resources Calculator, including the total Project materials cost and itemized costs of specific materials being tracked for LEED credits. All material costs exclude labor, overhead, profit, shipping, tax, equipment, and the total materials cost is exclusive of Specialties, and Mechanical and Electrical components.
- D. LEED Documentation Submittals:
 - 1. Prerequisite SS1 – Construction Activity Pollution Prevention:

- a. Erosion and sedimentation control action plan
 - b. Weekly inspection checklists and photos indicating erosion and sedimentation control plan was implemented and maintained throughout construction
2. Credit SS7.2: Heat Island Effect, Roof: LEED Criteria Sheet and product data sheet for roofing materials indicating solar reflectance index (SRI).
3. Credit WE 1: Water Efficient Irrigation: Cut sheets of irrigation system components and controls contributing to water savings. Provide list and photographs of the installed drought-tolerant plants
4. Prerequisite WE 1 and Credit WE 3: Water Use Reduction: Cut sheets for all faucets, and toilets indicating flow rates (gallons/minute) and flush volumes (gallons/flush) and Plumbing Fixture Log listing all plumbing equipment installed in the banking center.
5. Prerequisite EA 3: Fundamental Refrigerant Management: Cut sheets for HVAC&R equipment indicating refrigerant type.
6. Credit MR 2 Construction Waste Management: Comply with Section 017419 "Construction Waste Management and Disposal." For Co-Mingled Off-Site Sorting Method or Source Separated On-Site Sorting Method the following is required:
 - a. Construction Waste Management Action Plan.
 - b. Complete final LEED construction waste calculations.
 - c. Itemized waste hauling trip tickets/receipts for all waste removed from the Project site and documentation of recycling recovery rate for off-site sorting facilities (if waste is commingled).
 - d. Weekly inspection checklists and photos indicating construction waste management plan was implemented and maintained throughout construction.
 - e. For Source Separated On-Site Sorting provide the project specific diversion rates from the sorting facility.
 - f. For Co-Mingled Off-Site Sorting provide project specific diversion rates from the sorting facility or documentation from the regulating body with the facility's average rate of recycling.
7. Credit MR 4 Recycled Content: Product data or certification letter from product manufacturers indicating percentages by weight of post-consumer and pre-consumer recycled content for products having recycled content. Include statement indicating material cost for each product having recycled content.
 - a. Provide detailed cost breakdown for divisions 3-10 and exterior site and infrastructure work by utilizing LEED Materials and Resources Calculator. Exterior site and infrastructure work shall include but not be limited to the following:
 - 1) Foundation.
 - 2) Paving.
 - 3) Site improvements.
 - 4) Planting.
 - b. LEED Criteria Sheet.
 - c. Complete On-Site Materials Checklist to confirm materials installed.

8. Complete Recycled Content Verification Checklist to confirm materials installed Credit MR 5 Regional Materials: Regional Materials: Product data for regional materials indicating location and distance from Project of material manufacturer and point of extraction, harvest, or recovery for each raw material. Include statement indicating cost for each regional material and the fraction by weight that is considered regional.
 - a. Complete the Regional materials portion of the LEED Materials and Resources Calculator including the value (\$) of each product as well as distance from point of extraction and distance from manufacturer to the project site.
 - b. LEED Criteria Sheet.
 - c. Complete On-Site Materials Checklist to confirm materials installed.
9. Credit MR 7 Certified Wood: Product data and chain-of-custody certificates for products containing certified wood. Include statement indicating cost for each certified wood product.
 - a. Provide vendor invoices for all new wood products on a line item basis. Include the value (\$) of each product highlighting the chain of custody number
 - b. The invoice or the letter must state whether the products are FSC Pure; FSC Mixed Credit; or FSC Mixed [NN]. An optional narrative can be submitted describing any special circumstances or considerations regarding the project's credit approach. Comprehensive guidelines can be found on the USGBC website at: <https://www.usgbc.org/ShowFile.aspx?DocumentID=4027>
 - c. FSC chain-of-custody certificates for each certified wood product with chain-of-custody number indicated
 - d. Complete the FSC portion of the LEED Materials and Resources Calculator including the value (\$) of each product as well as the chain of custody number (COC).
 - e. LEED Criteria Sheet.
 - f. Complete On-Site Materials Checklist to confirm materials installed.
10. Credit IEQ 3.1 Construction Indoor Air Quality Management Plan – During Construction: Comply with Section 018119 “Indoor Air Quality (IAQ) Management”
 - a. Construction indoor-air-quality management action plan.
 - b. Product data for temporary filtration media.
 - c. Product data for filtration media used during occupancy.
 - d. Weekly inspection checklists and photos indicating indoor air quality management plan was implemented and maintained throughout construction.
11. Credit IEQ 4.1: Low-Emitting Materials, Adhesives and Sealants:
 - a. Product data for adhesives and sealants used inside the weatherproofing system indicating VOC content of each product used and verifying that each product meets the LEED requirements (Refer to “Low Emitting Materials” paragraph in Part 2). Indicate VOC content in grams/liter (g/l) calculated according to:
 - 1) South Coast Air Quality Management District (SCAQMD) Rule #1168, July 1, 2005 and rule amendment date of January 7, 2005

- b. Complete the Low-Emitting Material Log listing of all installed adhesives and sealants including manufacturer, quantity used in gallons and VOC content.
 - c. Complete the LEED Materials and Resources – Indoor Air Quality Tracker including the VOC Content of each product.
 - d. LEED Criteria Sheet.
 - e. Complete On-Site Materials Checklist to confirm materials installed.
12. Credit IEQ 4.2: Low-Emitting Materials, Paints and Coatings:
- a. Product data for paints and coatings used inside the weatherproofing system indicating VOC content of each product used indicating the VOC content of each product and verifying that each product meets the LEED requirements (Refer to “Low Emitting Materials” paragraph in Part 2). Indicate VOC content in grams/liter (g/l) calculated according to:
 - 1) Architectural paints & coatings: Green Seal Standard GS-11, Paints, First Edition, May 20, 1993.
 - 2) Anti-corrosive and anti-rust paints: Green Seal Standard GC-03, Anti-Corrosive Paints, Second Edition, January 7, 1997.
 - 3) Clear wood finishes, floor coatings, stains, primers, and shellacs: South Coast Air Quality Management District (SCAQMD) Rule 1113, January 1, 2004.
 - b. Complete the Low-Emitting Material Log listing all of installed paints including manufacturer, quantity used in gallons and VOC content.
 - c. Complete the IEQ portion of the Materials and Resources Calculator including the VOC Content of each product.
 - d. LEED Criteria Sheet.
13. Credit IEQ 4.3 Flooring Systems:
- a. Product data for all flooring installed in the building interior indicating that each product meets the LEED requirements (Refer to “Low Emitting Materials” paragraph in Part 2).
 - b. Complete the LEED Material and Resources – Indoor Air Quality Tracker including the testing protocol for each product.
 - c. Complete On-Site Materials Checklist to confirm materials installed.
 - d. LEED Criteria Sheet.
14. Credit IEQ 4.4: Composite Wood and Agrifiber Products:
- a. Product data for products containing composite wood or agrifiber products or wood glues indicating that they do not contain urea-formaldehyde resin.
 - b. Complete the LEED Materials and Resources – Indoor Air Quality Tracker confirming the products have no-added urea-formaldehyde.
 - c. Complete On-Site Materials Checklist to confirm materials installed.
 - d. LEED Criteria Sheet.
15. Credit IEQ 4.5: Ceiling and Walls Systems:

- a. Product data for gypsum board, insulation, acoustical ceiling systems and wall coverings installed in the building interior indicating that each product meets the LEED requirements (Refer to "Low Emitting Materials" paragraph in Part 2).
 - b. Complete the LEED Materials and Resources – Indoor Air Quality Tracker including the testing protocol for each product.
 - c. Complete On-Site Materials Checklist to confirm materials installed.
 - d. LEED Criteria Sheet.
16. Credit IEQ 6.1: Controllability of Systems - Lighting
- a. Cut sheets of lighting control systems serving regularly occupied areas of the building.
17. Credit IDc1.5: Innovation in Design: Reduced Mercury Lamps:
- a. Cut sheets for all mercury-containing light bulbs.
 - b. Light Bulb Log.

1.6 INFORMATIONAL SUBMITTALS

- A. Project Materials Cost Data: Provide statement indicating total cost for materials used for Project. Costs exclude labor, overhead, and profit. Include breakout of costs for the following categories of items:
1. Plumbing.
 2. Mechanical.
 3. Electrical.
 4. Specialty items such as elevators and equipment.
 5. Wood-based construction materials.
- B. LEED Action Plans: Provide preliminary submittals within 30 days of date established for the Notice to Proceed indicating how the following requirements will be met:
1. Credit MR 2: Waste management action plan complying with Section 017419 "Construction Waste Management and Disposal."
 2. Credit IEQ 3.1: Construction indoor-air-quality management action plan.
 3. Prerequisite SS1 – Construction Activity Pollution Prevention action plan
- C. LEED Progress Reports: Concurrent with each Application for Payment, submit reports comparing actual construction and purchasing activities with LEED action plans for the following:
1. Credit MR 2: Waste reduction progress reports complying with Section 017419 "Construction Waste Management and Disposal."
 2. Credit MR 4: Recycled content.
 3. Credit MR 5: Regional Materials.
 4. Credit MR 7: Certified wood products.
 5. Credit IEQ 3.1: Construction IAQ Management Plan: Construction indoor air quality management reports complying with Section 01 81 19 "Indoor Air Quality Management."

6. Credit IEQ 4: Low-Emitting Materials: Summary of product data collected for all adhesives, sealants, paints, coatings, carpeting, composite wood materials, laminating adhesives, gypsum board, insulation, acoustical ceiling systems and wall coverings used to fabricate composite wood assemblies that are installed inside of the building's moisture barrier.
7. Credit ID 1.5: Reduced Mercury in Lamps: Summary of lamps purchased and installed.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

- A. Provide products and procedures necessary to obtain LEED credits required in this Section. Although other Sections may specify some requirements that contribute to LEED credits, the Contractor shall determine additional materials and procedures necessary to obtain LEED credits indicated.

2.2 RECYCLED CONTENT OF MATERIALS

- A. Credit MR 4: Building materials shall have recycled content such that post-consumer recycled content plus one-half of pre-consumer recycled content for Project constitutes a minimum of 20 percent of cost of materials used for Project.
 1. Cost of post-consumer recycled content plus one-half of pre-consumer recycled content of an item shall be determined by dividing weight of post-consumer recycled content plus one-half of pre-consumer recycled content in the item by total weight of the item and multiplying by cost of the item.
 2. Do not include furniture, plumbing, mechanical and electrical components, and specialty items such as elevators and equipment in the calculation.
 3. Include only materials permanently installed on the project.

2.3 REGIONAL MATERIALS

- A. Credit MR 5: Building materials shall be manufactured within 500 miles of the project site for a minimum of 20 percent, based on cost, of the total materials value and extracted, harvested or recovered, within 500 miles of the project site for a minimum of 10 percent, based on cost, of the total materials value.
 1. If only a fraction of the product or material is extracted, harvested or recovered and manufactured locally, then only that percentage (by weight) must contribute to the regional value.
 2. Do not include furniture, plumbing, mechanical and electrical components, and specialty items such as elevators and equipment in the calculation.
 3. Include only materials permanently installed on the project.

2.4 CERTIFIED WOOD

- A. Credit MR 7 Certified Wood: Use a minimum of 50 percent (based on cost) of wood-based materials and products that are certified in accordance with the Forest Stewardship Council's principals and criteria for wood building components.

1. Wood-based materials include, but are not limited to, the following materials when made from wood, engineered wood products, or wood-based panel products:
 - a. Rough carpentry.
 - b. Miscellaneous carpentry.
 - c. Heavy timber construction.
 - d. Wood decking.
 - e. Metal-plate-connected wood trusses.
 - f. Structural glued-laminated timber.
 - g. Finish carpentry.
 - h. Architectural woodwork.
 - i. Wood paneling.
 - j. Wood veneer wall covering.
 - k. Wood flooring.
 - l. Wood lockers.
 - m. Wood cabinets.

2.5 LOW-EMITTING MATERIALS

- A. Credit IEQ 4.1: For field applications that are inside the weatherproofing system, adhesives and sealants shall comply with South Coast Air Quality Management District (SCAMD) Rule #1168 including the following VOC content limits:

1. Wood Glues: _____ 30 g/L.
2. Metal-to-Metal Adhesives: _____ 30 g/L.
3. Adhesives for Porous Materials (Except Wood): _____ 50 g/L.
4. Subfloor Adhesives: _____ 50 g/L.
5. Plastic Foam Adhesives: _____ 50 g/L.
6. Carpet Adhesives: _____ 50 g/L.
7. Carpet Pad Adhesives: _____ 50 g/L.
8. VCT and Asphalt Tile Adhesives: _____ 50 g/L.
9. Cove Base Adhesives: _____ 50 g/L.
10. Gypsum Board and Panel Adhesives: _____ 50 g/L.
11. Rubber Floor Adhesives: _____ 60 g/L.
12. Ceramic Tile Adhesives: _____ 65 g/L.
13. Multipurpose Construction Adhesives: _____ 70 g/L.
14. Fiberglass Adhesives: _____ 80 g/L.
15. Contact Adhesive: _____ 80 g/L.
16. Structural Glazing Adhesives: _____ 100 g/L.
17. Wood Flooring Adhesive: _____ 100 g/L.
18. Structural Wood Member Adhesive: _____ 140 g/L.
19. Single-Ply Roof Membrane Adhesive: _____ 250 g/L.
20. Special-Purpose Contact Adhesive (contact adhesive that is used to bond melamine-covered board, metal, unsupported vinyl, rubber, or wood veneer 1/16 inch or less in thickness to any surface): _____ 250 g/L.
21. Top and Trim Adhesive: _____ 250 g/L.
22. Plastic Cement Welding Compounds: _____ 250 g/L.
23. ABS Welding Compounds: _____ 325 g/L.
24. CPVC Welding Compounds: _____ 490 g/L.
25. PVC Welding Compounds: _____ 510 g/L.

26. Adhesive Primer for Plastic: _____ 550 g/L.
27. Sheet-Applied Rubber Lining Adhesive: _____ 850 g/L.
28. Aerosol Adhesive, General-Purpose Mist Spray: _____ 65 percent by weight.
29. Aerosol Adhesive, General-Purpose Web Spray: _____ 55 percent by weight.
30. Special-Purpose Aerosol Adhesive (All Types): _____ 70 percent by weight.
31. Other Adhesives: _____ 250 g/L.
32. Architectural Sealants: _____ 250 g/L.
33. Nonmembrane Roof Sealants: _____ 300 g/L.
34. Single-Ply Roof Membrane Sealants: _____ 450 g/L.
35. Other Sealants: _____ 420 g/L.
36. Sealant Primers for Nonporous Substrates: _____ 250 g/L.
37. Sealant Primers for Porous Substrates: _____ 775 g/L.
38. Modified Bituminous Sealant Primers: _____ 500 g/L.
39. Other Sealant Primers: _____ 750 g/L.

- B. Credit IEQ 4.2: For field applications that are inside the weatherproofing system, paints and coatings shall comply with the following VOC content limits when calculated according to 40 CFR 59, Subpart D (EPA Method 24):

IEQc4.2 APPLICABLE VOC LIMITS		
Product Type	Referenced Standard	VOC Limit (g/L minus water)
Interior Flat Coating or Primer	Green Seal GS-11, 1993	50
Interior Non-Flat Coating or Primer	Green Seal GS-11, 1993	150
Anti-Corrosive/Anti-Rust Paint	Green Seal GC-03, 2nd Ed., 1997	250
Clear Wood Finish: Lacquer	SCAQMD Rule 113, 2004	550
Clear Wood Finish :Sanding Sealer	SCAQMD Rule 113, 2004	350
Clear Wood Finish: Varnish	SCAQMD Rule 113, 2004	350
Clear Brushing Lacquer	SCAQMD Rule 113, 2004	680
Floor Coatings	SCAQMD Rule 113, 2004	100
Sealers and Undercoaters	SCAQMD Rule 113, 2004	200
Shellac: Clear	SCAQMD Rule 113, 2004	730
Shellac: Pigmented	SCAQMD Rule 113, 2004	550
Stain	SCAQMD Rule 113, 2004	250
Concrete Curing Compounds	SCAQMD Rule 113, 2004	350
Japanese Faux Finishing	SCAQMD Rule 113, 2004	350
Magnesite Cement Coatings	SCAQMD Rule 113, 2004	450
Pigmented Lacquer	SCAQMD Rule 113, 2004	550
Waterproofing Sealers	SCAQMD Rule 113, 2004	250
Waterproofing Concrete/Masonry Sealers	SCAQMD Rule 113, 2004	400
Wood Preservatives	SCAQMD Rule 113, 2004	350
Low-Solids Coatings	SCAQMD Rule 113, 2004	120

- C. Credit IEQ 4.3: All carpet and carpet cushion installed in the building interior must meet the requirements of the Carpet and Rug Institute's Green Label Plus program. Carpet adhesive must

meet requirements of Credit IEQ4.1. All hard surface flooring must meet the requirements of FloorScore.

IEQc4.3 APPLICATION CRITERIA	
Product Type	Referenced Standard
Carpet	Carpet and Rug Institute's Green Label Plus program
Carpet Cushion	Carpet and Rug Institute's Green Label Plus program
Carpet Adhesive	reference Credit IEQ 4.1
Hard Surface flooring	FloorScore
Concrete sealer, stain and finish	SCAQMD Rule 1113, 2004
Wood Preservatives	SCAQMD Rule 1113, 2004
Bamboo sealer, stain and finish	SCAQMD Rule 1113, 2004
Cork sealer, stain and finish	SCAQMD Rule 1113, 2004
Tile setting adhesives	SCAQMD Rule 1113, 2004
Tile setting grout	SCAQMD Rule 1113, 2004
Note: Mineral-based finish flooring products such as tile, masonry, terrazzo and cut stone without integral organic-based coatings and sealants and unfinished/untreated solid wood flooring qualify for credit without any IAQ testing requirements	

- D. Credit IEQ 4.4: Composite wood and agrifiber products installed inside the exterior moisture barrier shall contain no added urea-formaldehyde resins. Laminating adhesives used to fabricate on-site and shop-applied composite wood and agrifiber assemblies shall contain no added urea-formaldehyde resins.
- E. Credit IEQ 4.6: All gypsum board, insulation, acoustical ceiling systems and wall coverings installed in the building interior shall comply with the California Section 01359 Testing and Product Requirements and shall be GREENGUARD Gold Certification.

2.6 RECYCLED CONTENT

- A. Credit MR 4: The table below represents a range of recycled content for products and is meant to be referenced as a guide - actual percentages may vary based on manufacturer:

Material	Post-Consumer % Range		Pre-Consumer % Range	
	Low	High	Low	High
03 30 00 Cast-In-Place Concrete	50%	56%	25%	35%
03 30 00 Cast-In-Place Concrete - Rebar	70%	90%	10%	30%
05 12 00 Structural Steel	25%	87%	13%	36%
05 21 00 Steel Joists Framing	25%	87%	13%	36%
05 31 00 Steel Decking	25%	87%	13%	36%
06 40 23 Interior Architectural Woodwork - ParticleBoard			100%	100%
07 42 43 Composite Wall Panels	30%	40%	40%	47%
08 11 13 Hollow Metal Doors and Frames	12%	35%	27%	40%
08 41 13 Aluminum-Framed Entrances and Storefronts	30%	40%	30%	40%
08 80 00 Glazing			20%	40%

09 22 16 Non-Structural Metal Framing	26%	37%	6%	17%
09 29 00 Gypsum Board	3%	5%	83%	96%
09 51 10 Acoustical Ceilings - Tile	4%	13%	35%	64%
09 51 10 Acoustical Ceilings - Grid	20%	39%	7%	25%
07210 Drywall - Insulation	9%		20%	26%
09 68 16 Sheet Carpeting		10%		42%
10 75 00 Flagpoles	56%	70%	5%	10%
12 48 13 Entrance Floor Mats and Frames				50%

2.7 REDUCED MERCURY IN LAMPS

- A. Credit ID1.5: Innovation in Design: Reduced Mercury Lamps - Maintain a mercury content for all mercury-containing light bulbs below 80 picograms per lumen hour of light output (picogram /lumen hour), on weighted average, for all mercury-containing light bulbs acquired for the project.

PART 3 - EXECUTION

3.1 COMMISSIONING

- A. Prerequisite EA 1: Basic Commissioning. Participate in the Commissioning process and provide any required materials to verify that the building's energy related systems are installed, calibrated, and perform according to the Contract Documents.
- B. Credit EA 3: Enhanced Commissioning. Participate in the Commissioning Process with an Independent Commissioning Authority and provide required materials to verify that the building's energy related systems are installed, calibrated, and perform according to the Contract Documents.

3.2 REFRIGERANT AND CLEAN-AGENT FIRE-EXTINGUISHING-AGENT REMOVAL

- A. Prerequisite EA 3: Fundamental Refrigerant Management: Remove CFC-based refrigerants from existing HVAC&R equipment indicated to remain and replace with refrigerants that are not CFC based. Replace or adjust existing equipment to accommodate new refrigerant as described in HVAC Sections.
- B. Credit EA 4: Remove clean-agent fire-extinguishing agents that contain HCFCs or halons and replace with agent that does not contain HCFCs or halons. See Section 212200 "Clean-Agent Fire-Extinguishing Systems" for additional requirements.

3.3 CONSTRUCTION WASTE MANAGEMENT

- A. Credit MR 2: Comply with Section 017419 "Construction Waste Management and Disposal."

3.4 CONSTRUCTION INDOOR-AIR-QUALITY MANAGEMENT

- A. Credit IEQ 3.1: Comply with SMACNA's "SMACNA IAQ Guideline for Occupied Buildings under Construction."

1. Comply with Division 1 Section 01 81 19 "Construction Indoor Air Quality Management."
2. Comply with the recommended Control measures of the SMACNA IAQ Guidelines for Occupied Buildings under Construction, 2nd Edition 2007, ANSI/SMACNA 008-2008
3. Protect stored on-site or installed absorptive materials from moisture damage.
4. If Owner authorizes use of permanent heating, cooling, and ventilating systems during construction period as specified in Section 015000 "Temporary Facilities and Controls", install filter media having a MERV 8 according to ASHRAE 52.2 at each return-air inlet for the air-handling system used during construction.
5. Replace all air filters immediately prior to occupancy with MERV 13 filters

- B. Credit IEQ 3.2: Comply with Division 1 Section 01 18 19 "Construction Indoor Air Quality Management

3.5 CONSTRUCTION ACTIVITY POLLUTION PREVENTION

1. Comply with Division 1 Section "Erosion and Sedimentation Control Plan."
2. Conform to 2003 EPA Construction General Permit OR local standards and codes, whichever is more stringent.

END OF SECTION 01 81 13.13

SECTION 01 81 13.16 - SUSTAINABLE DESIGN REQUIREMENTS - LEED FOR COMMERCIAL INTERIORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.
 - 1. Related Sections:
 - a. Section 01 74 19 "Construction Waste Management and Disposal."
 - b. Section 01 81 19 "Indoor Air Quality (IAQ) Management."
 - c. Section 01 91 13 "General Commissioning Requirements."
 - d. Section 01 91 14 "Commissioning of the Building Envelope"
 - e. Divisions 03 through 49 Sections for LEED Requirements specific to the Work of each of these Sections. These requirements may or may not include reference to LEED.

1.2 SUMMARY

- A. Section includes general requirements and procedures for compliance with certain USGBC LEED prerequisites and credits needed for Project to obtain LEED-Certified to Silver certification based on the USGBC's "LEED CI Retail v2009 Green Interior Design and Construction."
 - 1. Other LEED prerequisites and credits needed to obtain LEED certification depend on product selections and may not be specifically identified as LEED requirements. Compliance with requirements needed to obtain LEED prerequisites and credits may be used as one criterion to evaluate substitution requests and comparable product requests.
 - 2. Additional LEED prerequisites and credits needed to obtain the indicated LEED certification depend on Architect's design and other aspects of Project that are not part of the Work of the Contract.
 - 3. A copy of the LEED Project checklist is attached at the end of this Section for information only.
 - 4. Specific requirements for LEED are also included in other Sections.

1.3 DEFINITIONS

- A. LEED-CI Retail v2009: Leadership in Energy and Environmental Design – Green Interior Design and Construction Retail Supplement version 2009. LEED is a national rating system for green buildings created by the US Green Building Council. All references to LEED throughout the Construction Documents shall mean LEED-CI Retail v2009.
- B. Chain-of-Custody Certificates: Certificates signed by manufacturers certifying that wood used to make products was obtained from forests certified by an FSC-accredited certification body to comply with FSC STD-01-001, "FSC Principles and Criteria for Forest Stewardship."

Certificates shall include evidence that manufacturer is certified for chain of custody by an FSC-accredited certification body.

- C. Composite Wood and Agri-fiber Board: Manufactured materials made from wood or agricultural fibers manufactured with bonding agents. Composite wood materials include particle board, medium density fiberboard (MDF), plywood, strawboard, wheatboard, panel substrates and door cores.
- D. Regional Materials: Materials that have been extracted, harvested, or recovered, as well as manufactured, within 500 miles (800 km) of Project site. If only a fraction of a product or material is extracted/harvested/recovered and manufactured locally, then only that percentage (by weight) shall contribute to the regional value.
- E. Recycled Content: The recycled content value of a material assembly shall be determined by weight. The recycled fraction of the assembly is then multiplied by the cost of assembly to determine the recycled content value.
 - 1. "Post-consumer" material is defined as waste material generated by households or by commercial, industrial, and institutional facilities in their role as end users of the product, which can no longer be used for its intended purpose.
 - 2. "Pre-consumer" material is defined as material diverted from the waste stream during the manufacturing process. Excluded is reutilization of materials such as rework, regrind, or scrap generated in a process and capable of being reclaimed within the same process that generated it.

1.4 ADMINISTRATIVE REQUIREMENTS

- A. Respond to questions and requests from Architect and the USGBC regarding LEED credits that are the responsibility of the Contractor, that depend on product selection or product qualities, or that depend on Contractor's procedures until the USGBC has made its determination on the project's LEED certification application. Document responses as informational submittals.

1.5 ACTION SUBMITTALS

- A. General: Submit additional LEED submittals required by other Specification Sections.
- B. LEED submittals are in addition to other submittals. If submitted item is identical to that submitted to comply with other requirements, submit duplicate copies as a separate submittal to verify compliance with indicated LEED requirements.
- C. Project Materials Cost Data: Provide the necessary cost data requested on the LEED Criteria Sheet and LEED Materials and Resources Calculator, including the total Project materials cost and itemized costs of specific materials being tracked for LEED credits. All material costs exclude labor, overhead, profit, shipping, tax, equipment, and the total materials cost is exclusive of Specialties, Conveying Systems and Mechanical and Electrical components.
- D. LEED Documentation Submittals:
 - 1. Prerequisite WE 1 and Credit WE 1: Water Use Reduction: Cut sheets for all faucets, toilets and urinals indicating flow rates (gallons/minute) and flush volumes

- (gallons/flush) and Plumbing Fixture Log listing all plumbing equipment installed in the banking center.
2. Prerequisite EA 3: Fundamental Refrigerant Management: Cut sheets for HVAC&R equipment indicating refrigerant type.
 3. Credit MR 2 Construction Waste Management: Comply with Section 017419 "Construction Waste Management and Disposal."
 - a. Construction Waste Management Action Plan.
 - b. Complete final LEED construction waste calculations.
 - c. Itemized waste hauling trip tickets/receipts for all waste removed from the Project site and documentation of recycling recovery rate for off-site sorting facilities (if waste is commingled).
 - d. Weekly inspection checklists and photos indicating construction waste management plan was implemented and maintained throughout construction. For Co-Mingled Off-Site Sorting Method or Source Separated On-Site Sorting Method the following is required:
 - 1) Construction Waste Management Action Plan.
 - 2) Complete final LEED construction waste calculations.
 - 3) Itemized waste hauling trip tickets/receipts for all waste removed from the Project site.
 - 4) Weekly inspection checklists and photos indicating construction waste management plan was implemented and maintained throughout construction.
 - 5) For Source Separated On-Site Sorting provide the project specific diversion rates from the sorting facility.
 4. For Co-Mingled Off-Site Sorting provide project specific diversion rates from the sorting facility or documentation from the regulating body with the facility's average rate of recycling.
 5. Credit MR 4 Recycled Content: Product data or certification letter from product manufacturers indicating percentages by weight of post-consumer and pre-consumer recycled content for products having recycled content. Include statement indicating material cost for each product having recycled content.
 - a. Provide detailed cost breakdown for divisions 3-10 and exterior site and infrastructure work by utilizing the LEED Materials and Resources Calculator. Exterior site and infrastructure work shall include but not be limited to the following:
 - 1) Foundation.
 - 2) Paving.
 - 3) Site improvements.
 - 4) Planting.
 - b. LEED Criteria Sheet.
 - c. Complete On-Site Materials Checklist to confirm materials installed

6. Credit MR 5 Regional Materials: Regional Materials: Product data for regional materials indicating location and distance from Project of material manufacturer and point of extraction, harvest, or recovery for each raw material. Include statement indicating cost for each regional material and the fraction by weight that is considered regional.
 - a. Complete the Regional materials portion of the LEED Materials and Resources Calculator including the value (\$) of each product as well as distance from point of extraction and distance from manufacturer to the project site.
 - b. LEED Criteria Sheet.
 - c. Complete On-Site Materials Checklist to confirm materials installed.
7. Credit MR 7 Certified Wood: Product data and chain-of-custody certificates for products containing certified wood. Include statement indicating cost for each certified wood product.
 - a. Provide vendor invoices for all new wood products on a line item basis. Include the value (\$) of each product highlighting the chain of custody number
 - b. The invoice or the letter must state whether the products are FSC Pure; FSC Mixed Credit; or FSC Mixed [NN]. An optional narrative can be submitted describing any special circumstances or considerations regarding the project's credit approach. Comprehensive guidelines can be found on the USGBC website at: <https://www.usgbc.org/ShowFile.aspx?DocumentID=4027>
 - c. FSC chain-of-custody certificates for each certified wood product with chain-of-custody number indicated
 - d. Complete the FSC portion of the Materials and Resources Calculator including the value (\$) of each product as well as the chain of custody number (COC)
 - e. LEED Criteria Sheet
 - f. Complete On-Site Materials Checklist to confirm materials installed.
8. Credit IEQ 3.1 Construction Indoor Air Quality Management Plan – During Construction: Comply with Section 018119 “Indoor Air Quality (IAQ) Management”
 - a. Construction indoor-air-quality management action plan.
 - b. Product data for temporary filtration media.
 - c. Product data for filtration media used during occupancy.
 - d. Weekly inspection checklists and photos indicating indoor air quality management plan was implemented and maintained throughout construction.
9. Credit IEQ 4.1: Low-Emitting Materials, Adhesives and Sealants:
 - a. Product data for adhesives and sealants used inside the weatherproofing system indicating VOC content of each product used and verifying that each product meets the LEED requirements (Refer to “Low Emitting Materials” paragraph in Part 2). Indicate VOC content in grams/liter (g/l) calculated according to:
 - 1) South Coast Air Quality Management District (SCAQMD) Rule #1168, July 1, 2005 and rule amendment date of January 7, 2005
 - 2) Complete the Low-Emitting Material Log listing of all installed adhesives and sealants including manufacturer, quantity used in gallons and VOC content.

- 3) Complete the LEED Materials and Resources – Indoor Air Quality Tracker including the VOC Content of each product.
- 4) Complete On-Site Materials Checklist to confirm materials installed.
- 5) LEED Criteria Sheet.

10. Credit IEQ 4.2: Low-Emitting Materials, Paints and Coatings:

- a. Product data for paints and coatings used inside the weatherproofing system indicating VOC content of each product used indicating the VOC content of each product and verifying that each product meets the LEED requirements (Refer to “Low Emitting Materials” paragraph in Part 2). Indicate VOC content in grams/liter (g/l) calculated according to:
 - 1) Architectural paints & coatings: Green Seal Standard GS-11, Paints, First Edition, May 20, 1993.
 - 2) Anti-corrosive and anti-rust paints: Green Seal Standard GC-03, Anti-Corrosive Paints, Second Edition, January 7, 1997.
 - 3) Clear wood finishes, floor coatings, stains, primers, and shellacs: South Coast Air Quality Management District (SCAQMD) Rule 1113, January 1, 2004.
- b. Complete the Low-Emitting Material Log listing of all installed paints including manufacturer, quantity used in gallons and VOC content.
- c. Complete the LEED Materials and Resources – Indoor Air Quality Tracker including the VOC Content of each product.
- d. Complete On-Site Materials Checklist to confirm materials installed.
- e. LEED Criteria Sheet.

11. Credit IEQ 4.3 Flooring Systems

- a. Product data for all flooring installed in the building interior indicating that each product meets the LEED requirements (Refer to “Low Emitting Materials” paragraph in Part 2)
- b. Complete the LEED Material and Resources – Indoor Air Quality Tracker including the testing protocol for each product
- c. Complete On-Site Materials Checklist to confirm materials installed
- d. LEED Criteria Sheet

12. Credit IEQ 4.4: Low-Emitting Materials, Composite Wood and Agrifiber Products:

- a. Product data for products containing composite wood or agrifiber products or wood glues indicating that they do not contain urea-formaldehyde resin.
- b. Complete the LEED Materials and Resources – Indoor Air Quality Tracker confirming the products have no-added urea-formaldehyde.
- c. Complete On-Site Materials Checklist to confirm materials installed.
- d. LEED Criteria Sheet.

13. Credit IEQ 4.6 Ceiling and Walls Systems:

- a. Product data for gypsum board, insulation, acoustical ceiling systems and wall coverings installed in the building interior indicating that each product meets the LEED requirements (Refer to “Low Emitting Materials” paragraph in Part 2).
- b. Complete the LEED Materials and Resources – Indoor Air Quality Tracker including the testing protocol for each product.
- c. Complete On-Site Materials Checklist to confirm materials installed.
- d. LEED Criteria Sheet.

14. Credit IEQ 6.1: Controllability of Systems Lighting

- a. Cut sheets of lighting control systems serving regularly occupied areas of the building.

15. Credit ID 1.5 Innovation in Design: Reduced Mercury Lamps:

- a. Cut sheets for all mercury-containing light bulbs.
- b. Light Bulb Log.

1.6 INFORMATIONAL SUBMITTALS

- A. Project Materials Cost Data: Provide statement indicating total cost for materials used for Project. Costs exclude labor, overhead, and profit. Include breakout of costs for the following categories of items:

1. Plumbing.
2. Mechanical.
3. Electrical.
4. Specialty items such as elevators and equipment.
5. Wood-based construction materials.

- B. LEED Action Plans: Provide preliminary submittals within 30 days of date established for the Notice to Proceed indicating how the following requirements will be met:

1. Credit MR 2: Waste management action plan complying with Section 017419 "Construction Waste Management and Disposal."
2. Credit IEQ 3.1: Construction indoor-air-quality management action plan complying with Section 01 81 19 "Indoor Air Quality Management."

- C. LEED Progress Reports: Concurrent with each Application for Payment, submit reports comparing actual construction and purchasing activities with LEED action plans for the following:

1. Credit MR 2: Waste reduction progress reports complying with Section 017419 "Construction Waste Management and Disposal."
2. Credit MR 4: Recycled content.
3. Credit MR 5: Regional Materials.
4. Credit MR 7: Certified wood products.
5. Credit IEQ 3.1: Construction IAQ Management Plan: Construction indoor air quality management reports complying with Division 1 Section "Construction Indoor Air Quality."

6. Credit IEQ 4: Low-Emitting Materials: Summary of product data collected for all adhesives, sealants, paints, coatings, carpeting, composite wood materials and laminating adhesives, gypsum board, insulation, acoustical ceiling systems and wall coverings used to fabricate composite wood assemblies that are installed inside of the building's moisture barrier.
7. Credit ID 1.5: Reduced Mercury in Lamps: Summary of lamps purchased and installed.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

- A. Provide products and procedures necessary to obtain LEED credits required in this Section. Although other Sections may specify some requirements that contribute to LEED credits, the Contractor shall determine additional materials and procedures necessary to obtain LEED credits indicated.

2.2 RECYCLED CONTENT OF MATERIALS

- A. Credit MR 4: Building materials shall have recycled content such that post-consumer recycled content plus one-half of pre-consumer recycled content for Project constitutes a minimum of 20 percent of cost of materials used for Project.
 1. Cost of post-consumer recycled content plus one-half of pre-consumer recycled content of an item shall be determined by dividing weight of post-consumer recycled content plus one-half of pre-consumer recycled content in the item by total weight of the item and multiplying by cost of the item.
 2. Do not include plumbing, mechanical and electrical components, and specialty items such as elevators and equipment in the calculation.
 3. Include only materials permanently installed on the project.

2.3 REGIONAL MATERIALS

- A. Credit MR 5: Building materials shall be manufactured within 500 miles of the project site for a minimum of 20 percent, based on cost, of the total materials value and extracted, harvested or recovered, within 500 miles of the project site for a minimum of 10 percent, based on cost, of the total materials value.
 1. If only a fraction of the product or material is extracted, harvested or recovered and manufactured locally, then only that percentage (by weight) must contribute to the regional value.
 2. Do not include furniture, plumbing, mechanical and electrical components, and specialty items such as elevators and equipment in the calculation.
 3. Include only materials permanently installed on the project.

2.4 CERTIFIED WOOD

- A. Credit MR 7 Certified Wood: Use a minimum of 50 percent (based on cost) of wood-based materials and products that are certified in accordance with the Forest Stewardship Council's principals and criteria for wood building components.

1. Wood-based materials include, but are not limited to, the following materials when made from wood, engineered wood products, or wood-based panel products:
 - a. Rough carpentry.
 - b. Miscellaneous carpentry.
 - c. Heavy timber construction.
 - d. Wood decking.
 - e. Metal-plate-connected wood trusses.
 - f. Structural glued-laminated timber.
 - g. Finish carpentry.
 - h. Architectural woodwork.
 - i. Wood paneling.
 - j. Wood veneer wall covering.
 - k. Wood flooring.
 - l. Wood lockers.
 - m. Wood cabinets.
 - n. Furniture.

2.5 LOW-EMITTING MATERIALS

- A. Credit IEQ 4.1: For field applications that are inside the weatherproofing system, adhesives and sealants shall comply with South Coast Air Quality Management District (SCAMD) Rule #1168 including the following VOC content limits:

1. Wood Glues: _____ 30 g/L.
2. Metal-to-Metal Adhesives: _____ 30 g/L.
3. Adhesives for Porous Materials (Except Wood): _____ 50 g/L.
4. Subfloor Adhesives: _____ 50 g/L.
5. Plastic Foam Adhesives: _____ 50 g/L.
6. Carpet Adhesives: _____ 50 g/L.
7. Carpet Pad Adhesives: _____ 50 g/L.
8. VCT and Asphalt Tile Adhesives: _____ 50 g/L.
9. Cove Base Adhesives: _____ 50 g/L.
10. Gypsum Board and Panel Adhesives: _____ 50 g/L.
11. Rubber Floor Adhesives: _____ 60 g/L.
12. Ceramic Tile Adhesives: _____ 65 g/L.
13. Multipurpose Construction Adhesives: _____ 70 g/L.
14. Fiberglass Adhesives: _____ 80 g/L.
15. Contact Adhesive: _____ 80 g/L.
16. Structural Glazing Adhesives: _____ 100 g/L.
17. Wood Flooring Adhesive: _____ 100 g/L.
18. Structural Wood Member Adhesive: _____ 140 g/L.
19. Single-Ply Roof Membrane Adhesive: _____ 250 g/L.
20. Special-Purpose Contact Adhesive (contact adhesive that is used to bond melamine-covered board, metal, unsupported vinyl, rubber, or wood veneer 1/16 inch or less in thickness to any surface): _____ 250 g/L.
21. Top and Trim Adhesive: _____ 250 g/L.
22. Plastic Cement Welding Compounds: _____ 250 g/L.
23. ABS Welding Compounds: _____ 325 g/L.
24. CPVC Welding Compounds: _____ 490 g/L.

25. PVC Welding Compounds: _____ 510 g/L.
26. Adhesive Primer for Plastic: _____ 550 g/L.
27. Sheet-Applied Rubber Lining Adhesive: _____ 850 g/L.
28. Aerosol Adhesive, General-Purpose Mist Spray: _____ 65 percent by weight.
29. Aerosol Adhesive, General-Purpose Web Spray: _____ 55 percent by weight.
30. Special-Purpose Aerosol Adhesive (All Types): _____ 70 percent by weight.
31. Other Adhesives: _____ 250 g/L.
32. Architectural Sealants: _____ 250 g/L.
33. Nonmembrane Roof Sealants: _____ 300 g/L.
34. Single-Ply Roof Membrane Sealants: _____ 450 g/L.
35. Other Sealants: _____ 420 g/L.
36. Sealant Primers for Nonporous Substrates: _____ 250 g/L.
37. Sealant Primers for Porous Substrates: _____ 775 g/L.
38. Modified Bituminous Sealant Primers: _____ 500 g/L.
39. Other Sealant Primers: _____ 750 g/L.

- B. Credit IEQ 4.2: For field applications that are inside the weatherproofing system, paints and coatings shall comply with the following VOC content limits when calculated according to 40 CFR 59, Subpart D (EPA Method 24):

IEQc4.2 APPLICABLE VOC LIMITS		
Product Type	Referenced Standard	VOC Limit (g/L minus water)
Interior Flat Coating or Primer	Green Seal GS-11, 1993	50
Interior Non-Flat Coating or Primer	Green Seal GS-11, 1993	150
Anti-Corrosive/Anti-Rust Paint	Green Seal GC-03, 2nd Ed., 1997	250
Clear Wood Finish: Lacquer	SCAQMD Rule 113, 2004	550
Clear Wood Finish :Sanding Sealer	SCAQMD Rule 113, 2004	350
Clear Wood Finish: Varnish	SCAQMD Rule 113, 2004	350
Clear Brushing Lacquer	SCAQMD Rule 113, 2004	680
Floor Coatings	SCAQMD Rule 113, 2004	100
Sealers and Undercoaters	SCAQMD Rule 113, 2004	200
Shellac: Clear	SCAQMD Rule 113, 2004	730
Shellac: Pigmented	SCAQMD Rule 113, 2004	550
Stain	SCAQMD Rule 113, 2004	250
Concrete Curing Compounds	SCAQMD Rule 113, 2004	350
Japanese Faux Finishing	SCAQMD Rule 113, 2004	350
Magnesite Cement Coatings	SCAQMD Rule 113, 2004	450
Pigmented Lacquer	SCAQMD Rule 113, 2004	550
Waterproofing Sealers	SCAQMD Rule 113, 2004	250
Waterproofing Concrete/Masonry Sealers	SCAQMD Rule 113, 2004	400
Wood Preservatives	SCAQMD Rule 113, 2004	350
Low-Solids Coatings	SCAQMD Rule 113, 2004	120

- C. Credit IEQ 4.3: All carpet and carpet cushion installed in the building interior must meet the requirements of the Carpet and Rug Institute's Green Label Plus program. Carpet adhesive must meet requirements of Credit IEQ4.1. All hard surface flooring must meet the requirements of FloorScore.

IEQc4.3 APPLICATION CRITERIA	
Product Type	Referenced Standard
Carpet	Carpet and Rug Institute's Green Label Plus program
Carpet Cushion	Carpet and Rug Institute's Green Label Plus program
Carpet Adhesive	reference Credit IEQ 4.1
Hard Surface flooring	FloorScore
Concrete sealer, stain and finish	SCAQMD Rule 1113, 2004
Wood Preservatives	SCAQMD Rule 1113, 2004
Bamboo sealer, stain and finish	SCAQMD Rule 1113, 2004
Cork sealer, stain and finish	SCAQMD Rule 1113, 2004
Tile setting adhesives	SCAQMD Rule 1113, 2004
Tile setting grout	SCAQMD Rule 1113, 2004
Note: Mineral-based finish flooring products such as tile, masonry, terrazzo and cut stone without integral organic-based coatings and sealants and unfinished/untreated solid wood flooring qualify for credit without any IAQ testing requirements	

- D. Credit IEQ 4.4: Composite wood and agrifiber products installed inside the exterior moisture barrier shall contain no added urea-formaldehyde resins. Laminating adhesives used to fabricate on-site and shop-applied composite wood and agrifiber assemblies shall contain no added urea-formaldehyde resins.
- E. Credit IEQ 4.6: All gypsum board, insulation, acoustical ceiling systems and wall coverings installed in the building interior shall comply with the California Section 01359 Testing and Product Requirements and shall be GREENGUARD Gold Certification.

2.6 RECYCLED CONTENT

- A. Credit MR 4: The table below represents a range of recycled content for products and is meant to be referenced as a guide - actual percentages may vary based on manufacturer:

Material	Post-Consumer % Range		Pre-Consumer % Range	
	Low	High	Low	High
03 30 00 Cast-In-Place Concrete	50%	56%	25%	35%
03 30 00 Cast-In-Place Concrete - Rebar	70%	90%	10%	30%
05 12 00 Structural Steel	25%	87%	13%	36%
05 21 00 Steel Joists Framing	25%	87%	13%	36%
05 31 00 Steel Decking	25%	87%	13%	36%
06 40 23 Interior Architectural Woodwork - ParticleBoard			100%	100%
07 42 43 Composite Wall Panels	30%	40%	40%	47%
08 11 13 Hollow Metal Doors and Frames	12%	35%	27%	40%

08 41 13 Aluminum-Framed Entrances and Storefronts	30%	40%	30%	40%
08 80 00 Glazing			20%	40%
09 22 16 Non-Structural Metal Framing	26%	37%	6%	17%
09 29 00 Gypsum Board	3%	5%	83%	96%
09 51 10 Acoustical Ceilings - Tile	4%	13%	35%	64%
09 51 10 Acoustical Ceilings - Grid	20%	30%	7%	25%
07210 Drywall - Insulation	9%		20%	26%
09 68 16 Sheet Carpeting		10%		42%
10 75 00 Flagpoles	56%	70%	5%	10%
12 48 13 Entrance Floor Mats and Frames				50%

2.7 REDUCED MERCURY IN LAMPS

- A. Credit ID1.5: Innovation in Design: Reduced Mercury Lamps - Maintain a mercury content for all mercury-containing light bulbs below 80 picograms per lumen hour of light output (picogram /lumen hour), on weighted average, for all mercury-containing light bulbs acquired for the project.

PART 3 - EXECUTION

3.1 COMMISSIONING

- A. Prerequisite EA 1: Basic Commissioning. Participate in the Commissioning process and provide any required materials to verify that the building's energy related systems are installed, calibrated, and perform according to the Contract Documents.
- B. Credit EA 2: Enhanced Commissioning. Participate in the Commissioning Process with an Independent Commissioning Authority and provide and required materials to verify that the building's energy related systems are installed, calibrated, and perform according to the Contract Documents.

3.2 REFRIGERANT AND CLEAN-AGENT FIRE-EXTINGUISHING-AGENT REMOVAL

- A. Prerequisite EA 3: Fundamental Refrigerant Management: Remove CFC-based refrigerants from existing HVAC&R equipment indicated to remain and replace with refrigerants that are not CFC based. Replace or adjust existing equipment to accommodate new refrigerant as described in HVAC Sections.
- B. Credit EA 4: Enhanced Refrigerant Management: Remove clean-agent fire-extinguishing agents that contain HCFCs or halons and replace with agent that does not contain HCFCs or halons. See Section 212200 "Clean-Agent Fire-Extinguishing Systems" for additional requirements.

3.3 CONSTRUCTION WASTE MANAGEMENT

- A. Credit MR 2: Comply with Section 017419 "Construction Waste Management and Disposal."

3.4 CONSTRUCTION INDOOR-AIR-QUALITY MANAGEMENT

- A. Credit IEQ 3.1: Comply with SMACNA's "SMACNA IAQ Guideline for Occupied Buildings under Construction."
1. Comply with Division 1 Section "Construction Indoor Air Quality."
 2. Comply with the recommended Control measures of the SMACNA IAQ Guidelines for Occupied Buildings under Construction, 1996, Chapter 3.
 3. Protect stored on-site or installed absorptive materials from moisture damage.
 4. If Owner authorizes use of permanent heating, cooling, and ventilating systems during construction period as specified in Section 015000 "Temporary Facilities and Controls", install filter media having a MERV 8 according to ASHRAE 52.2 at each return-air inlet for the air-handling system used during construction.
 5. Replace all air filters immediately prior to occupancy with MERV 13 filters

END OF SECTION 01 81 13.16

SECTION 01 81 19 – INDOOR AIR QUALITY (IAQ) MANAGEMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

- 1. Special requirements for Indoor Air Quality (IAQ) management during construction operations.
 - a. Control of emissions during construction.
 - b. Moisture control during construction.
- 2. Procedures for testing baseline IAQ. Baseline IAQ requirements specify maximum indoor pollutant concentrations for acceptance of the facility.

- B. Related Sections:

- 1. Division 1 Section "Submittal Procedures" for required submittal procedures.
- 2. Division 1 Section "Temporary Facilities and Controls" requirements for installation, maintenance and removal of temporary utilities, controls, and facilities during construction.
- 3. Division 1 Section 01 81 13 "Sustainable Design Requirements" for LEED credit requirements.
- 4. Division 1 Section 01 91 13 "General Commissioning" for coordination with commissioning activities.
- 5. Division 1 Section "Product Requirements" procedures for storage of interior materials to prevent exposure to moisture and pollutants.
- 6. Division 15 Section "Basic Mechanical Materials and Methods" for duct cleaning procedures.

1.3 IAQ MANAGEMENT SUMMARY

- A. The Owner has established that the contractor shall prevent indoor air quality problems resulting from the construction process, to sustain long term installer and occupant health and comfort.
- B. Protect the ventilation system components during construction and clean contaminated components after construction is complete.

- C. Control sources of potential IAQ pollutants by controlling selection of materials and processes used in project construction.

1.4 REFERENCES

- A. Definitions: Definitions pertaining to sustainable development: As defined in ASTM E 2114.
 - 1. Adequate Ventilation: Ventilation, including air circulation and air changes, required to cure materials, dissipate humidity, and prevent accumulation of particulates, dust, fumes, vapors, or gases.
 - 2. Hazardous Materials: Any material that is regulated as a hazardous material in accordance with 49 CFR 173, requires a Material Safety Data Sheet (MSDS) in accordance with 29 CFR 1910.1200, or which during end use, treatment, handling, storage, transportation or disposal meets or has components which meet or have the potential to meet the definition of a Hazardous Waste in accordance with 40 CFR 261.
 - a. Hazardous materials include: pesticides, biocides, and carcinogens as listed by recognized authorities, such as the Environmental Protection Agency (EPA) and the International Agency for Research on Cancer (IARC).
 - 3. Indoor Air Quality (IAQ): The composition and characteristics of the air in an enclosed space that affect the occupants of that space. The indoor air quality of a space refers to the relative quality of air in a building with respect to contaminants and hazards and is determined by the level of indoor air pollution and other characteristics of the air, including those that impact thermal comfort such as air temperature, relative humidity and air speed.
 - 4. Interior Final Finishes: Materials and products that will be exposed at interior, occupied spaces; including flooring, wallcovering, finish carpentry, ceilings, and sealants.
 - 5. Packaged Dry Products: Materials and products that are installed in dry form and are delivered to the site in manufacturer's packaging; including carpets, resilient flooring, ceiling tiles, and insulation.
 - 6. Wet Products: Materials and products installed in wet form, including paints, sealants, adhesives, special coatings, and other materials which require curing.

1.5 ADMINISTRATIVE REQUIREMENTS

- A. Preconstruction Conference: After award of Contract and prior to the commencement of the Work, schedule and conduct meeting with Owner, Construction Manager, and Architect to discuss the proposed IAQ Management Plan and to develop mutual understanding relative to details of environmental protection.

1.6 SUBMITTALS

- A. Indoor Air Quality (IAQ) Management Plan: Not less than 10 days before the preconstruction conference, prepare and submit an IAQ Management Plan including, but not limited to, the following:
 - 1. Procedures for control of emissions during construction.
 - a. Identify schedule for application of interior finishes.

2. Procedures for moisture control during construction.
 - a. Identify porous materials and absorptive materials.
 - b. Identify schedule for inspection of stored and installed absorptive materials.
3. Revise and resubmit Plan as required by Construction Manager.
 - a. Approval of Contractor's Plan will not relieve the Contractor of responsibility for compliance with applicable environmental regulations.
- B. Photographs documenting construction IAQ management measures implemented during construction such as duct protection measures and measures to protect on-site stored or installed absorptive materials from moisture.
- C. Cut sheets of filtration media used during construction with MERV values highlighted.
 1. Substitutions are not allowed unless approved by the LEED Advocate, in unique circumstances.
- D. Provide completed On-Site Materials Checklist – Purchase and Installation Verification Log for on-site Sub-contractor Check-in and on-site photographs documenting construction IAQ management measures to LEED Advocate for review and storage on the LEED SharePoint.
- E. Product Data:
 1. Submit product data for filtration media used during construction and during operation. Include Minimum Efficiency Reporting Value (MERV).
 2. Submit air pressure difference maps for each mode of operation of HVAC.
 3. Material Safety Data Sheets: Submit MSDSs for inclusion in Operation and Maintenance Manual for the following products.
 - a. Adhesives.
 - b. Floor and wall patching/leveling materials.
 - c. Caulking and sealants.
 - d. Insulating materials.
 - e. Fireproofing and firestopping.
 - f. Carpet.
 - g. Paint.
 - h. Clear finish for wood surfaces.
 - i. Lubricants.
 - j. Cleaning products.
 - k. Acoustical ceiling tile.
 - l. Gypsum board.
 - m. Wall coverings.
- F. Inspection and Test Reports:
 1. Moisture control inspections.
 2. Moisture content testing.
 3. Moisture penetration testing.

4. Microbial growth testing.
5. Baseline Indoor Air Quality test report.

1.7 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Minimum of 5 years experience in performing the types of testing specified herein.

PART 2 - PRODUCTS

2.1 GENERAL ENVIRONMENTAL ISSUES

- A. Mold and Mildew: Materials that have evidence of growth of molds or mildew are not acceptable, including both stored and installed materials. Immediately remove from site and dispose of properly.
- B. Moisture Stains: Materials that have evidence of moisture damage, including stains, are not acceptable, including both stored and installed materials. Immediately remove from site and dispose of properly.

2.2 AIR FILTRATION MEDIA

- A. Minimum Efficiency Reporting Value (MERV) as determined by ASHRAE 52.2:
 1. MERV-8 for filtration media used at each return air grill, if used during construction.
 2. MERV-13, for filtration media installed at the end of construction and prior to occupancy.

2.3 CLEANING PRODUCTS

- A. Use low-toxic and lowest-emitting spot removers and cleaning agents for surfaces, equipment, and workers' personal use.
- B. Use HEPA-filter equipped vacuum cleaners for the final cleaning.

PART 3 - EXECUTION

3.1 IAQ MANAGEMENT - EMISSIONS CONTROL

- A. LEED Credit EQ 3.1: During construction operations, follow the recommendations in SMACNA "IAQ Guidelines for Occupied Buildings under Construction."
- B. HVAC Protection:
 1. Fit all return air grilles with temporary filters with a Minimum Efficiency Reporting Value (MERV) of 8.
 2. Isolate the return side of the HVAC system from the surrounding environment as much as possible (e.g., place all tiles for the ceiling plenum, repair all ducts and air handler leaks).

3. Damper off the return system in the heaviest work areas and seal the return system openings with plastic.
 4. Provide temporary exhaust during construction operations
 5. Upgrade the filter efficiency where major loading is expected to affect operating HVAC system.
 6. Clean permanent return air ductwork per National Air Duct Cleaning Association standards upon completion of all construction and finish installation work.
 7. Replace all filtration media prior to occupancy.
- C. Source Control:
1. Provide low and zero VOC materials as specified.
 2. Do not use products in combination with or in contact with other products that can be identified as combining to form toxic fumes or sustained odors.
- D. Pathway Interruption: Isolate areas of work as necessary to prevent contamination of clean or occupied spaces. Provide pressure differentials and/or physical barriers to protect clean or occupied spaces.
1. Use 100% outside air ventilation (when outside temperatures are between 55 degrees F and 85 degrees F and humidity is between 30% and 60%) with air exhausted directly to the outside during installation of finishes and other VOC emitting materials.
 2. Erect barrierS between work areas or between the inside and outside of the building to prevent unwanted airflow from dirty to clean areas.
- E. Housekeeping: During construction, maintain project and building products and systems to prevent contamination of building spaces.
- F. Temporary Ventilation: Provide an ACH (air changes per hour) of 1.5 or more and as follows:
1. Provide minimum 48-hour pre-ventilation of packaged dry products prior to installation. Remove from packaging and ventilate in a secure, dry, well-ventilated space free from strong contaminant sources and residues. Provide a temperature range of 60 deg F minimum to 90 deg F maximum continuously during the ventilation period. Do not ventilate within limits of Work unless otherwise approved by Architect.
 2. Provide adequate ventilation during and after installation of interior wet products and interior final finishes.
 3. Provide filtration media with a Minimum Efficiency Reporting Value (MERV) of 8 as determined by ASHRAE 52.2 during construction and during Owner occupancy. Coordinate with Work of Division 23, Heating, Ventilating, and Air Conditioning (HVAC).
 - a. Replace filters during construction as necessary to protect equipment and indoor air quality.
- G. Scheduling: Schedule construction operations involving wet products prior to packaged dry products to the greatest extent possible.

1. Do not use solvents within interior areas that may penetrate and be retained in absorptive materials such as concrete, gypsum board, wood, cellulose products, fibrous material, and textiles.

- H. Inspect ductwork for refuse, contaminants, moisture, and other foreign contamination prior to commissioning by Owner. Notify Owner of satisfactory inspection prior to beginning of commissioning.

3.2 IAQ MANAGEMENT – IMPLEMENTATION OF PLAN

- A. Manager: The Contractor shall designate an on-site party (or parties) responsible for instructing workers and overseeing the IAQ Management Plan for the Project.
 1. Report all issues to General Contractor for immediate correction.
- B. Progress Meetings: Construction related IAQ procedures shall be included in the pre-construction and construction progress meeting agendas.
- C. Distribution: The Contractor shall distribute copies of the IAQ Management Plan to the Job Site Foreman, each Subcontractor, the Owner, and the Architect.
- D. Instruction: The Contractor shall provide on-site instruction of the IAQ procedures and ensure that all participants in the construction process understand the importance of the goals of the IAQ Management Plan.
- E. Verification: Project Manager to fill out the Construction IAQ Management Plan Inspection Checklist with photographs of the measures in place during weekly site visits.
- F. On-site Check-in Procedures: General Contractor and Sub Contractor to review and agree on specified products and VOC limits before Sub Contractor begins work using the On-Site Materials Checklist - Purchase and Verification Log.

3.3 IAQ MANAGEMENT - MOISTURE CONTROL

- A. Housekeeping:
 1. Keep materials dry. Protect stored on-site and installed absorptive materials from moisture damage.
 2. Verify that installed materials and products are dry prior to sealing and weatherproofing the building envelope.
 3. Install interior absorptive materials only after building envelope is sealed and weatherproofed.
- B. Inspections: Document and report results of inspections; state whether or not inspections indicate satisfactory conditions.
 1. Examine materials for dampness as they arrive. If acceptable to Construction Manager, dry damp materials completely prior to installation; otherwise, reject materials that arrive damp.

2. Examine materials for mold as they arrive and reject materials that arrive contaminated with mold.
 3. Inspect stored and installed absorptive materials regularly for dampness and mold growth. Inspect weekly.
 - a. Where stored on-site or installed absorptive materials become wet, notify Construction Manager. Inspect for damage. If acceptable to Construction Manager, dry completely prior to closing in assemblies; otherwise, remove and replace with new materials.
 4. Basement: Monitor basement and crawlspace humidity, and dehumidify when relative humidity is greater than 85 percent for more than two weeks, or at the first sign of mold growth.
 5. Site Drainage: Verify that final grades of site work and landscaping drain surface water and ground water away from the building.
 6. Weatherproofing: Inspect moisture control materials as they are being installed. Include the following:
 - a. Air Barrier: Verify air barrier is installed without punctures and/or other damage. Verify air barrier is sealed completely.
 - b. Flashing: Verify correct shingling of the flashing for roof, walls, windows, doors, and other penetrations.
 - c. Insulation Layer: Verify insulation is installed without voids.
 - d. Roofing: In accordance with ASTM D 7186.
 7. Plumbing: Verify satisfactory pressure test of pipes and drains is performed before closing in and insulating lines.
 8. HVAC: Inspect HVAC system as specified in Section 01 91 13 "General Commissioning." And, inspect HVAC to verify:
 - a. condensate pans are sloped and plumbed correctly;
 - b. access panels are installed to allow for inspection and cleaning of coils and ductwork downstream of coils;
 - c. ductwork and return plenums are air sealed;
 - d. duct insulation is installed and sealed; and
 - e. chilled water line and refrigerant line insulation are installed and sealed.
- C. Schedule:
1. Schedule work such that absorptive materials, including but not limited to porous insulations, paper-faced gypsum board, ceiling tile, and finish flooring, are not installed until they can be protected from rain and construction-related water.
 2. Weatherproof as quickly as possible. Schedule installation of moisture-control materials, including but not limited to air barriers, flashing, exterior sealants and roofing, at the earliest possible time.
- D. Testing for Moisture Content: Test moisture content of porous materials and absorptive materials to ensure that they are dry before sealing them into an assembly. Document and report results of testing. Where tests are not satisfactory, dry materials and retest. If satisfactory results cannot be obtained with retest, remove and replace with new materials.

1. Concrete: Moisture test as per one or more of the following; unless otherwise indicated, acceptable upper limits for concrete are less than 4 percent top inch; less than 85 percent headspace RH; less than 3 lbs/1000 sq. ft./day:
 - a. ASTM D 4263 - Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method.
 - b. ASTM F 1869 - Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride.
 - c. ASTM F 2170 - Test Method for Determining Relative Humidity in Concrete Floor Slabs Using In Situ Probes.
 2. Wood: Moisture test as per ASTM D 4444 - Standard Test Methods for Use and Calibration of Hand-Held Moisture Meters; unless otherwise indicated, acceptable upper limits for wood products are less than 20 percent at center of piece; less than 15 percent at surface.
 3. Gypsum Board, Insulation, and Other Absorptive Materials: Moisture test with a Pinless Moisture Meter to assess patterns of moisture, if any.
- E. Testing for Moisture Penetration:
1. Windows: Test as per ASTM E 1105 - Test Method for Field Determination of Water Penetration of Installed Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform or Cyclic Static Air Pressure Difference; unless otherwise indicated, acceptable upper limits are no leakage for 15 minutes.
 2. Horizontal Waterproofing (not roofing): Test as per ASTM D 5957 - Standard Guide for Flood Testing Horizontal Waterproofing Installations; acceptable upper limits are no leakage for 15 minutes.
 3. Masonry: Test as per ASTM C 1601 - Standard Test Method for Field Determination of Water Penetration of Masonry Wall Surfaces; acceptable upper limits are no leakage for 15 minutes.
 4. Exterior Walls:
 - a. Air Tightness of the Enclosure Test: ASTM E 779 - Standard Test Method for Determining Air Leakage Rate by Fan Pressurization or ASTM E 1827 - Standard Test Methods for Determining Air tightness of Buildings Using an Orifice Blower Door; acceptable upper limits are.
 - b. Water Leakage: Review as per ASTM E 2128 - Standard Guide for Evaluating Water Leakage of Building Walls.
- F. Testing for Support of Microbial Growth: Test and report in accordance with ASTM D 6329 - Standard Guide for Developing Methodology for Evaluating the Ability of Indoor Materials to Support Microbial Growth Using Static Environmental Chambers. Indicate susceptibility of product or material to colonization and amplification of microorganisms. Identify microorganisms and conditions of testing.
1. Normal Conditions: Perform testing at 35 degrees C and 50 percent relative humidity.
 2. Extreme Conditions: Perform worst-case scenarios screening tests by providing an atmosphere where environmental conditions may be favorable for microbial growth.
 3. Perform testing for the following:

- a. Fireproofing material on appropriate substrate.
- b. Acoustical ceilings.
- c. Wallcovering.

END OF SECTION 01 81 19

SECTION 01 91 13 - GENERAL COMMISSIONING REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.
- B. OPR and BoD documentation are included by reference for information only.

1.2 SUMMARY

- A. Section includes general requirements that apply to implementation of commissioning without regard to specific systems, assemblies, or components.
- B. Related Sections:
 - 1. Division 1 Section 01 81 13 "Sustainable Design Requirements" for LEED credit requirements.
 - 2. Section 23 08 00 "Commissioning of HVAC" for commissioning process activities for HVAC&R systems, assemblies, equipment, and components.
 - 3. Section "Commissioning of Building Envelope" for commissioning process activities for the building envelope systems, assemblies, equipment, and components.
 - 4. Section "Commissioning of Mechanical and Plumbing Systems" for commissioning process activities for the heating, ventilating, air conditioning, and domestic hot water systems, assemblies, equipment, and components.
 - 5. Section "Commissioning of Lighting Systems" for commissioning process activities for lighting systems, assemblies, equipment, and components.

1.3 DEFINITIONS

- A. Acceptance Criteria: A document that specifies the acceptable performance of testable systems from which the Pre-functional Checklists and Functional Tests are derived.
- B. BoD: Basis of Design. A document that records concepts, calculations, decisions, and product selections used to meet the OPR and to satisfy applicable regulatory requirements, standards, and guidelines. The document includes both narrative descriptions and lists of individual items that support the design process.
- C. Commissioning Plan: A document that outlines the organization, schedule, allocation of resources, and documentation requirements of the commissioning process.
- D. CxA: Commissioning Authority.

- E. Cx Team Members appointed by Contractor(s): Individuals, each having authority to act on behalf of the entity he or she represents, explicitly organized to implement the commissioning process through coordinated actions. The commissioning team shall include, but not be limited to, the Contractor's project superintendent, Division 07, 15, and 16 installing contractors, and equipment suppliers.
- F. Functional Test (FT): A documented test of the dynamic functioning and operation of equipment and systems with the goal of verifying that the Acceptance Criteria are met. Test requirements are included in the construction documents. Test results are documented by the Commissioning Authority. Test procedures are completed by the Contractor.
- G. OPR: Owner's Project Requirements. A document that details the functional requirements of a project and the expectations of how it will be used and operated. These include Project goals, measurable performance criteria, cost considerations, benchmarks, success criteria, and supporting information.
- H. Pre-functional Checklist (PC): A written checklist that includes checks and tests prerequisite to the equipment's Functional Test. Checklists are included in the technical sections listed in paragraph 1.2. The Checklists are completed by the Contractors and verified by the Commissioning Authority.
- I. Systems, Subsystems, Equipment, and Components: Where these terms are used together or separately, they shall mean "as-built" systems, subsystems, equipment, and components.

1.4 COMMISSIONING TEAM

- A. Members Appointed by Contractor(s): Individuals, each having the authority to act on behalf of the entity he or she represents, explicitly organized to implement the commissioning process through coordinated action. The commissioning team shall consist of, but not be limited to, representatives of [each] Contractor, including Project superintendent and subcontractors, installers, suppliers, and specialists deemed appropriate by the CxA.
- B. Members Appointed by Owner:
 - 1. CxA: The designated person, company, or entity that plans, schedules, and coordinates the commissioning team to implement the commissioning process. Owner will engage the CxA under a separate contract.
 - 2. Representatives of the facility user and operation and maintenance personnel.
 - 3. Architect and engineering design professionals.

1.5 OWNER'S RESPONSIBILITIES

- A. Provide the OPR documentation to the CxA and each Contractor for information and use.
- B. Assign operation and maintenance personnel and schedule them to participate in commissioning team activities.
- C. Provide the BoD documentation, prepared by Architect and approved by Owner, to the CxA and each Contractor for use in developing the commissioning plan, systems manual, and operation and maintenance training plan.

1.6 EACH CONTRACTOR'S RESPONSIBILITIES

- A. Each Contractor shall assign representatives with expertise and authority to act on its behalf and shall schedule them to participate in and perform commissioning process activities including, but not limited to, the following:
 - 1. Evaluate performance deficiencies identified in test reports and, in collaboration with entity responsible for system and equipment installation, recommend corrective action.
 - 2. Cooperate with the CxA for resolution of issues recorded in the Issues Log.
 - 3. Attend commissioning team meetings held on a biweekly basis.
 - 4. Integrate and coordinate commissioning process activities with construction schedule.
 - 5. Review and accept construction checklists provided by the CxA.
 - 6. Complete electronic construction checklists as Work is completed and provide to the Commissioning Authority on a weekly basis.
 - 7. Review and accept commissioning process test procedures provided by the Commissioning Authority.
 - 8. Complete commissioning process test procedures.
- B. The following Systems, Assemblies, Equipment, and Components will be commissioned:
 - 1. Packaged Units
 - 2. Air Distribution Equipment & Air Balance
 - 3. HVAC Controls
 - 4. Wall Heater
 - 5. Exhaust Fans
 - 6. Plumbing Piping
 - 7. Instantaneous Water Heaters
 - 8. Storage Water Heater
 - 9. Lighting Fixtures & Controls
 - 10. Building Envelope
- C. Coordination
 - 1. Assign a representative with expertise and authority to act on behalf of the Contractor and schedule subcontractors to participate in and perform commissioning process activities including, but not limited to, the following:
 - a. Attend and participate in the following 3 commissioning team meetings: pre-construction, mid-construction, and functional test pre-action. Commissioning Team member appointed by the Contractor shall attend commissioning meetings.
 - b. Integrate and coordinate commissioning process activities with construction schedule. Include a 2-day activity in the construction schedule called Building Commissioning which shall occur 2 weeks prior to open doors date. This activity shall include completion of functional test procedures.
 - c. Provide the commissioning authority with access to a copy of the approved submittals and shop drawings during the CxA's mid-construction site visit.
 - d. Complete prefunctional checklists as Work is completed.
 - e. Provide progress copies of the Prefunctional checklists to the Owner on a weekly basis during the last 4 weeks of the construction schedule.
 - f. Accomplish commissioning functional test procedures under the CxA's direction.

- g. Evaluate performance deficiencies identified during functional testing and, in collaboration with entity responsible for system and equipment installation, recommend corrective action.
- h. Cooperate with the CxA for resolution of issues recorded in “Issues Log.”
- i. Participate in a post-occupancy site visit with the Commissioning Team 8-10 months from building turnover.

1.7 CxA'S RESPONSIBILITIES

- A. Organize and lead the commissioning team.
- B. Provide commissioning plan.
- C. Convene commissioning team meetings.
- D. Provide Project-specific construction checklists and commissioning process test procedures.
- E. Verify the execution of commissioning process activities using random sampling. The sampling rate may vary from 1 to 100 percent. Verification will include, but is not limited to, equipment submittals, construction checklists, training, operating and maintenance data, tests, and test reports to verify compliance with the OPR. When a random sample does not meet the requirement, the CxA will report the failure in the Issues Log.
- F. Prepare and maintain the Issues Log.
- G. Prepare and maintain completed construction checklist log.
- H. Witness systems, assemblies, equipment, and component startup.
- I. Compile test data, inspection reports, and certificates; include them in the systems manual and commissioning process report.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 PREFUNCTIONAL CHECKLISTS

- A. Complete Pre-functional Checklists as described in the technical sections listed in paragraph 1.2.

3.2 FUNCTIONAL TESTING

- A. Perform functional test procedures as described in the technical sections listed in paragraph 1.2.

3.3 DEFERRED TESTING

- A. Some tests may need to be performed later, after substantial completion, due to partial occupancy, equipment, seasonal requirements, design or other site conditions; performance of these tests remains the Contractor's responsibility regardless of timing.

END OF SECTION 01 91 13

SECTION 01 91 14 - COMMISSIONING OF THE BUILDING ENVELOPE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes requirements that apply to the commissioning process for the building envelope.
- B. Related Sections:
 - 1. Section 230800 "Commissioning of HVAC" for commissioning process activities for HVAC&R systems, assemblies, equipment, and components.

1.3 DEFINITIONS

- A. Testing Agent: The subcontractor responsible for the work defined by this section.
- B. Commissioning Plan: A document that outlines the organization, schedule, allocation of resources, and documentation requirements of the commissioning process.
- C. Systems, Subsystems, Equipment, and Components: Where these terms are used together or separately, they shall mean "as-built" systems, subsystems, equipment, and components.
- D. CxA: Commissioning Authority.

1.4 BUILDING ENVELOPE COMMISSIONING TEAM

- A. Members Appointed by Contractor: Individuals, each having the authority to act on behalf of the entity he or she represents, explicitly organized to implement the commissioning process through coordinated action. The commissioning team shall consist of, but not be limited to, representatives of each Contractor.
- B. All work is to be performed by contractors that are recommended by the local chapter of the Mechanical Contractors Association or are certified for air balancing, air infiltration, water penetration, and energy loss with either the NEBB or the AABC.
- C. Members Appointed by Owner:
 - 1. CxA: The designated person, company, or entity that plans, schedules, and coordinates the commissioning team to implement the commissioning process. Owner will engage the CxA under a separate contract.
 - 2. Representatives of the facility user and operation and maintenance personnel.
 - 3. Architect and engineering design professionals.

1.5 CONTRACTOR'S RESPONSIBILITIES

- A. Contractor shall assign representatives with expertise and authority to act on its behalf and shall schedule them to participate in and perform commissioning process activities including, but not limited to, the following:
1. Evaluate performance deficiencies identified in test reports and, in collaboration with entity responsible for system and equipment installation, recommend corrective action.
 2. Cooperate with the CxA for resolution of issues recorded in the Issues Log.
 3. Attend commissioning team meetings held on a biweekly basis.
 4. Integrate and coordinate commissioning process activities with construction schedule.
 5. Review and accept construction checklists provided by the CxA.
 6. Complete electronic construction checklists as Work is completed and provide to the Commissioning Authority on a weekly basis.
 7. Review and accept commissioning process test procedures provided by the CxA.
 8. Complete commissioning process test procedures.
 - a. The functional tests shall be performed in a manner that duplicates the checking, testing, and inspection methods established in other Division 7, 8, & 9 Sections. Where checking, testing, and inspection methods are not specified in other Sections, methods shall be established which will provide the information required by the contractor and submitted to the CxA for review. Requirements in related Sections are independent from the requirements of this Section and shall not be used to satisfy any of the requirements specified in this Section. A functional test shall be aborted if any system deficiency prevents the successful completion of the test or if any participating commissioning team member of whom participation is specified is not present for the test.
 - b. Functional Tests shall be performed to demonstrate compliance with the Acceptance Criteria listed in this section. Functional Tests shall begin only after the Functional Test pre-action meeting is conducted.
9. Resolve differences:
- a. Upon failure of any Functional Test item, the Contractor shall correct deficiencies in accordance with the applicable contract requirements. The item shall then be retested until it has been completed with no errors.
 - b. In some systems, maladjustments, misapplied equipment, and deficient performance under varying loads will result in additional work being required to commission systems. Complete Work under direction of the Owner with input from the CxA.
 - c. Whereas all members will have input and opportunity to discuss the Work and resolve problems, the Owner will have final authority on necessary work to be done to achieve performance.
 - 1) Complete corrective work to permit completion of commissioning process.
 - 2) If deadlines pass without resolution of the problems, the Owner reserves right to obtain supplementary services and equipment to resolve problems. Costs incurred to solve problems in an expeditious manner will be the Contractor's responsibility.

1.6 COMMISSIONING AUTHORITY RESPONSIBILITIES

- A. Designate Contractor team members to participate in the Functional Test specified by the CxA. The team members shall be as follows:
 - 1. Contractor's Wall Representative
 - 2. Contractor's Roofing Representative
 - 3. Owner's Project Manager
 - 4. Owner's Property Manager
 - 5. Owner's Commissioning Authority
- B. Provide commissioning plan.
- C. Convene commissioning team meetings.
- D. Provide Project-specific construction checklists and commissioning process test procedures.
- E. Prepare and maintain the Issues Log.
- F. Compile test data, inspection reports, and certificates; include them in the systems manual and commissioning process report.
- G. Complete Functional Tests by the appropriate sub-contractor under direct guidance of the Contractor and final review by the Commissioning Authority. Acceptance by each sub-contractor and general contractor of each Prefunctional Checklist shall be indicated by signature and date. Acceptance by each sub-contractor and contractor of each functional test shall be indicated by signature and date.

PART 2 - PRODUCTS

2.1 TEST EQUIPMENT

- A. Provide test equipment necessary for performing building envelope tests listed by the CxA. Test equipment shall be of sufficient quality and accuracy to test and/or measure system performance to the accuracy required by the Acceptance Criteria. Test the building envelope with a commercial-quality automated blower-door assembly as manufactured by "Retrotec" or approved equal.
 - 1. ASTM E 779 ASTM E 1186
 - a. E779: Air leakage rate by fan pressurization
 - b. E1186: Air leakage in building envelopes / air barrier systems

PART 3 - EXECUTION

3.1 GENERAL

- A. Services prior to the tests. One inspection trip is required prior to test day to provide the following:
 - 1. The extent of building envelope sealing that has been completed and what will be needed prior to testing.
 - 2. A review of the Architect's plans and a calculation made from them to determine the leakage amount (cfm) based upon the Acceptance Criteria.
 - 3. Provide a complete list of all preparations to the General Contractor that is needed prior to Test Day including the extent of temporary sealing of equipment located on the roof on Test Day.
 - 4. Provide an estimate of the time needed to perform testing on Test Day to the General Contractor.
- B. Services on the Test Day at the job site
 - 1. Furnish all labor, transportation, tools and instruments, and perform all operations in connection with the Blower Door Test.
 - 2. Insure that all interior doors are open during the test and the exterior double-door is locked to prevent false readings from intrusion.
 - 3. Provide a multi-point test with a minimum of five points of data. Measure and record the inside and outside air temperature during the test.
 - 4. If the first test fails, be prepared to assist the Contractor in remediating the conditions where leakage is occurring at the wall and roof penetrations.
 - 5. Within three days of testing provide a brief, signed summary of the test procedure and results.

3.2 MEETINGS

- A. Attend a pre-construction commissioning meeting where the commissioning process and schedule will be reviewed. Meeting may take place via telephone.
- B. Attend a mid-construction commissioning meeting. Conduct a site visit with commissioning personnel, including demonstration of different types of building envelope construction details.
- C. Attend a functional test pre-action meeting. This meeting shall occur approximately 28 days prior to the Open Door Date. Ensure that the individual who attends this meeting has the authority to schedule personnel who will be completing the functional tests.

3.3 EXAMINATION

- A. Examine conditions, with CxA and Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. All instruments used shall be in proper operating condition and accurately calibrated. Any part of the equipment that is calibrated shall have a calibration sticker with a due date of no less than one month.

3.4 SCHEDULING

- A. Building Envelope Preliminary Testing shall occur upon the completed installation of the air barrier, roof and window assemblies, but prior to the installation of the exterior facade finishes and interior finishes.
- B. Building Envelope Functional Testing shall occur between 14 and 21 days before the Open Door Date and prior to the Bank Turn Over date.

3.5 ACCEPTANCE CRITERIA

- A. When pressurized to -50Pa (0.2" w.g.), the Test Agent shall demonstrate that the Building Envelope maintains less than 0.4CFM of leakage per square foot of exterior wall and roof area.

END OF SECTION 01 91 14

SECTION 03 54 16 - HYDRAULIC CEMENT UNDERLAYMENT

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Hydraulic-cement-based, polymer-modified, self-leveling underlayment for application below interior floor coverings.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. Regional Materials Information.
 - d. LEED Materials and Resources Calculator.

C. Shop Drawings: Include plans indicating substrates, locations, and average depths of underlayment based on survey of substrate conditions.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For qualified Installer.

B. Product Certificates: Signed by manufacturers of underlayment and floor-covering systems certifying that products are compatible.

C. Minutes of preinstallation conference.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: Installer shall have successfully installed work similar in extent to that required for the Project, in not less than five projects of similar scope to the satisfaction of the Architect.

B. Product Compatibility: Manufacturers of underlayment and floor-covering systems certify in writing that products are compatible.

- C. Preinstallation Conference: Conduct conference at Project site.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Store materials to comply with manufacturer's written instructions to prevent deterioration from moisture or other detrimental effects.

1.6 PROJECT CONDITIONS

- A. Environmental Limitations: Comply with manufacturer's written instructions for substrate temperature, ventilation, ambient temperature and humidity, and other conditions affecting underlayment performance.
 - 1. Place hydraulic-cement-based underlayments only when ambient temperature and temperature of substrates are between 50 and 80 deg F.

1.7 COORDINATION

- A. Coordinate application of underlayment with requirements of floor-covering products and adhesives, to ensure compatibility of products.

PART 2 - PRODUCTS

2.1 HYDRAULIC-CEMENT-BASED UNDERLAYMENTS

- A. Hydraulic Cement Underlayment: Polymer-modified, self-leveling, hydraulic cement product that can be applied in minimum uniform thickness of 1/4 inch and that can be feathered at edges to match adjacent floor elevations.
 - 1. Cement Binder: ASTM C 150, portland cement, or hydraulic or blended hydraulic cement as defined by ASTM C 219.
 - 2. Compressive Strength: Not less than 4000 psi at 28 days when tested according to ASTM C 109/C 109M.
 - 3. Underlayment Additive: Resilient-emulsion product of underlayment manufacturer, formulated for use with underlayment when applied to substrate and conditions indicated.
- B. Water: Potable and at a temperature of not more than 70 deg F.
- C. Primer: Product of underlayment manufacturer recommended in writing for substrate, conditions, and application indicated.
 - 1. Primer shall have a VOC content of 200 g/L or less when calculated according to 40 CFR 59, Subpart D.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, with Installer present, for conditions affecting performance.

1. Proceed with application only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. General: Prepare and clean substrate according to manufacturer's written instructions.
 1. Treat nonmoving substrate cracks according to manufacturer's written instructions to prevent cracks from telegraphing (reflecting) through underlayment.
 2. Fill substrate voids to prevent underlayment from leaking.
- B. Concrete Substrates: Mechanically remove, according to manufacturer's written instructions, laitance, glaze, efflorescence, curing compounds, form-release agents, dust, dirt, grease, oil, and other contaminants that might impair underlayment bond.
 1. Moisture Testing: Perform anhydrous calcium chloride test, ASTM F 1869. Proceed with installation only after substrates do not exceed a maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
- C. Adhesion Tests: After substrate preparation, test substrate for adhesion with underlayment according to manufacturer's written instructions.

3.3 APPLICATION

- A. General: Mix and apply underlayment components according to manufacturer's written instructions.
 1. Close areas to traffic during underlayment application and for time period after application recommended in writing by manufacturer.
 2. Coordinate application of components to provide optimum underlayment-to-substrate and intercoat adhesion.
 3. At substrate expansion, isolation, and other moving joints, allow joint of same width to continue through underlayment.
- B. Apply primer over prepared substrate at manufacturer's recommended spreading rate.
- C. Apply underlayment to produce uniform, level surface.
 1. Feather edges to match adjacent floor elevations.
- D. Cure underlayment according to manufacturer's written instructions. Prevent contamination during application and curing processes.
- E. Do not install floor coverings over underlayment until after time period recommended in writing by underlayment manufacturer.
- F. Remove and replace underlayment areas that evidence lack of bond with substrate, including areas that emit a "hollow" sound when tapped.

3.4 PROTECTION

- A. Protect underlayment from concentrated and rolling loads for remainder of construction period.

END OF SECTION 03 54 16

SECTION 04 47 00 - MANUFACTURED MASONRY VENEER

PART 1 - I GENERAL

1.01 SUMMARY

- A. Section Includes: Portland cement based manufactured stone veneer and trim.
- B. Related Sections:
 - 1. 06 16 00–Wall Sheathing.
 - 2. 07 27 26–Fluid Applied Membrane Air Barriers
 - 3. 07 60 00–Flashing and Sheet Metal.
 - 4. 07 92 00–Joint Sealants.
 - 5. 09 24 00–Portland Cement Plastering.

1.02 REFERENCES

- A. American National Standards Institute (ANSI):
 - 1. ANSI A118.4 Specifications for Latex-Portland Cement Mortar.
- B. American Society for Testing and Materials (ASTM):
 - 1. ASTM C 39 – Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens.
 - 2. ASTM C 67 – Standard Test Methods for Sampling and Testing Brick and Structural Clay Tile.
 - 3. ASTM C 144 – Standard Specification for Aggregate for Masonry Mortar.
 - 4. ASTM C 177 – Standard Test Method for Steady-State Head Flux Measurements and Thermal Transmission Properties by Means of the Guarded-Hot-Plate Apparatus.
 - 5. ASTM C 207 – Standard Specification for Hydrated Lime for Masonry Purposes.
 - 6. ASTM C 270 – Standard Specification for Mortar for Unit Masonry.
 - 7. ASTM C 482 – Standard Test Method for Bond Strength of Ceramic Tile to Portland Cement.
 - 8. ASTM C 567 – Standard Test Method for Determining Density of Structural Lightweight Concrete.
 - 9. ASTM C 847 – Standard Specification for Metal Lath.
 - 10. ASTM C 932 – Standard Specification for Surface-Applied Bonding Compounds for Exterior Plastering.
 - 11. ASTM C 979 – Standard Specification for Pigments for Integrally Colored Concrete.
 - 12. ASTM C 1032 – Standard Specification for Woven Wire Plaster Base.
 - 13. ASTM C 1059 – Standard Specification for Latex Agents for Bonding Fresh To Hardened Concrete.
 - 14. ASTM D 226 – Standard Specification for Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing.
 - 15. ASTM C1063 –Standard Specification for Installation of Lathing and Furring to Receive Interior and Exterior Portland Cement-Based Plaster
 - 16. ASTM C1329 Standard specification for Portland cement
 - 17. ASTM C578 – Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation

18. ASTM C1289 – Standard Specification for Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board
19. ASTM E2556/E2556M – Standard Specification for Vapor Permeable Flexible Sheet Water-Resistive Barriers Intended for Mechanical Attachment

C. Other Standards:

1. UBC Standard No. 14-1, Kraft Waterproof Building Paper
2. ICC AC38 Acceptance Criteria for Water Resistive Barriers
3. UU-B-790 Building Paper, Vegetable Based, Kraft , waterproofed, water repellent and fireproof

D. International Code Council (ICC):

1. ESR Report.

E. LEED: US Green Building Council's Leadership in Energy and Environmental Design Green Building Rating System.

F. Underwriter's Laboratory (UL): Building Materials Directory.

1.03 SUBMITTALS

A. Reference Section 01 33 00–Submittal Procedures; submit following items:

1. Product Data.
2. Samples:
 - a. Standard sample board consisting of small-scale pieces of veneer units showing full range of textures and colors.
3. Quality Assurance/Control Submittals:
 - a. Qualifications:
 - 1) Proof of installer qualifications.
 - b. Regulatory Requirements: Evaluation reports.
 - c. Veneer manufacturer's installation instructions.
 - d. Installation instructions for other materials.
4. LEED Submittals;
 - a. Credit MR 4.1, 4.2 Recycled Content: Provide percentage of recycled content (post-consumer and pre-consumer).
 - b. Credit MR 5.1, 5.2 Regional Materials:
 - 1) Provide distance between Project site and extraction site.
 - 2) Provide distance between Project site and final manufacturing location.

B. Closeout Submittals: Reference Section 01 78 00–Closeout Submittals; submit following items:

1. Maintenance Instructions.
2. Special Warranties.

1.04 QUALITY ASSURANCE

A. Qualifications:

1. Installer Qualifications: Experienced mason familiar with installation procedures and related local, state and federal codes masonry.

B. Certifications:

1. ICC Evaluation Service – Evaluation Report ESR-1215.

2. ASTM C1670
3. UL – Classification listing in Building Materials Directory: UL 546T (F8002).

C. Field Sample:

1. Prepare 4 by 4 foot sample at a location on the structure as selected by the Architect. Use approved selection sample materials and colors. Include corner detail.
2. Obtain Architect's approval.
3. Protect and retain sample as a basis for approval of completed manufactured stone work. Approved sample may be incorporated into completed work.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Reference Section 01 66 00–Product Storage and Handling Requirements.
- B. Follow manufacturer's instructions.

1.06 PROJECT/SITE CONDITIONS

- A. Environmental Requirements: When air temperature is 40 degrees F (4.5 degrees C) or below, consult local building code for Cold-Weather Construction requirements.

1.07 WARRANTY

- A. Special Warranty: Manufacturer's standard warranty coverage against defects in materials when installed in accordance with manufacturer's installation instructions.

PART 2 - PRODUCTS

2.01 MANUFACTURER (BASIS OF DESIGN)

A. Eldorado Stone, LLC 1370 Grand Ave., Bldg. B San Marcos, CA 92069	Tel: (800) 925-1491 Fax: (760) 736-3840 E-Mail: customerservice@eldoradostone.com Website: www.eldoradostone.com

2.02 MATERIALS

- A. Stone Veneer:
 1. Profile: Stacked Stone ,“Daybreak”. Include matching corner pieces.
- B. Veneer Unit properties: Precast veneer units consisting of portland cement, lightweight aggregates, and mineral oxide pigments.
 1. Compressive Strength: ASTM C 192 and ASTM C 39, 5 sample average: greater than 1,800 psi (12.4MPa).
 2. Shear Bond: ASTM C 482: 50 psi (345kPa), minimum.
 3. Freeze-Thaw Test: ASTM C 67: Less than 3 percent weight loss and no disintegration.
 4. Thermal Resistance: ASTM C 177: 0.473 at 1.387 inches thick
 5. Weight per square foot: 2012 IBC and 2012 IRC, ASTM C1670, 15 pounds, saturated.

- C. Weather Barrier: [ASTM D 226, Type 1, No. 15, non-perforated asphalt-saturated felt paper] [UBC Standard 14-1, kraft waterproof building paper] or [UBC Standard No. 14-1, Kraft Waterproof Building Paper] or [ICC AC-38, synthetic house wrap]
- D. Reinforcing: [ASTM C 847, 2.5lb/yd² (1.4kg/m²) galvanized expanded metal lath] [ASTM C 847, 3.4lb (1.8 kg/m²) galvanized 3/8" rib lath] [ASTM C 1032, 17 gauge (1.3 mm) woven wire mesh] complying with code agency requirements for the type of substrate over which stone veneer is installed.
- E. Mortar:
 - 1. Cement: Portland cement complying with ASTM C 1329.
 - 2. Lime: ASTM C 207.
 - 3. Sand: ASTM C 144, natural or manufactured sand.
 - 4. Color Pigment: ASTM C 979, mineral oxide pigments.
 - 5. Water: Potable.
 - 6. Pre-Packaged Latex-Portland Cement Mortar: ANSI A118.4.
- F. Bonding Agent: Exterior integral bonding agent meeting [ASTM C 932] [ASTM C 1059 Type II]
- G. Water Repellent: Water based silane or siloxane masonry water repellent

2.03 MORTAR MIXES

- A. Jointless/Dry-Stacked Installation:
 - 1. Polymer modified mortar complying with ANSI A118.4
 - 2. Mortar prepared to comply with ASTM C270. Type S mortar.
 - a. Add color pigment in accordance with pigment manufacturer's instructions.

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Examine substrates upon which work will be installed.
- B. Coordinate with responsible entity to perform corrective work on unsatisfactory substrates.
- C. Commencement of work by installer is acceptance of substrate.

3.02 PREPARATION

- A. Protection: Protect adjacent work from contact with mortar.
- B. Surface Preparation: Prepare substrate in accordance with manufacturer's installation instructions for the type of substrate being covered.

3.03 INSTALLATION

- A. Install and clean stone in accordance with manufacturer's installation instructions for Standard Installation (Grouted Joint) or Jointless/Dry-Stacked installation as specified above.
- B. Apply repellent in accordance with repellent manufacturer's application instructions.

3.04 CLEANING

- A. Reference Section 01 74 00–Cleaning and Waste Management.
- B. Remove protective coverings from adjacent work.
- C. Cleaning Veneer Units:
 - 1. Wash with soft bristle brush and water/granulated detergent solution
 - 2. Rinse immediately with clean water
- D. Removing Efflorescence:
 - 1. Allow veneer to dry thoroughly
 - 2. Scrub with soft bristle brush and clean water
 - 3. Rinse immediately with clean water; allow to dry
 - 4. If efflorescence is still visible, contact ES Customer Service for assistance

END OF SECTION¹

¹ This specification was prepared specifically for Eldorado Stone Corporation by ASC Specification Consultants. Comments or suggestions for improvement should be addressed to Eldorado Stone via the contact information on page one.

Revised: APRIL 30, 2018

SECTION 05 50 00 - METAL FABRICATIONS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Steel framing and supports for countertops.
 - 2. Steel framing and supports for mechanical and electrical equipment.
 - 3. Steel framing and supports for applications where framing and supports are not specified in other Sections.
 - 4. Metal ladders.
 - 5. Metal bollards and HDPE bollard sleeve.
- B. Products furnished, but not installed, under this Section:
 - 1. Anchor bolts, steel pipe sleeves, slotted-channel inserts, and wedge-type inserts indicated to be cast into concrete or built into unit masonry.
- C. Related Sections:
 - 1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Design ladders, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.
- B. Structural Performance of Counter Tops and Vanities: Provide countertop and vanity framing capable of withstanding the following structural loads without exceeding the allowable design working stress of the materials involved, including anchors and connections, or of exhibiting excessive deflections in any of the components making up the countertops and vanities:
 - 1. All deadloads.
 - 2. 500 pound live load placed on the countertop and vanity.
 - 3. Deflection at Midspan: L/1000 times span or 1/8" whichever is less.
- C. Structural Performance of Operable Partition Framing: Fabricate and install operable partition framing so that, when installed, it is capable of supporting all deadloads and withstanding the live loads imposed on it from the operation of the operable partition.
- D. Structural Performance of All-Glass Entrances and Storefront Framing: Fabricate and install support framing capable of supporting all deadloads and withstanding live loads imposed from functioning operations.
- E. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes acting on exterior metal fabrications by preventing buckling, opening of joints, overstressing of components, failure of connections, and other detrimental effects.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

1.3 ACTION SUBMITTALS

A. Product Data: For the following:

1. Nonslip aggregates and nonslip-aggregate surface finishes.
2. Paint products.
3. Grout.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Low Emitting Materials Information.
 - d. Regional Materials Information.
 - e. LEED Materials and Resources Calculator.

C. Samples for Verification: For each component indicated, provide Samples of size and finish indicated below.

1. HDPE, Bollard Sleeves: Provide 3-inch square sample of each type, and color specified.

D. Shop Drawings: Show fabrication and installation details for metal fabrications.

1. Include plans, elevations, sections, and details of metal fabrications and their connections. Show anchorage and accessory items.

E. Delegated-Design Submittal: For installed products indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1.4 INFORMATIONAL SUBMITTALS

A. Qualification Data: For qualified professional engineer.

B. Welding certificates.

C. Paint Compatibility Certificates: From manufacturers of topcoats applied over shop primers certifying that shop primers are compatible with topcoats.

1.5 QUALITY ASSURANCE

A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

1.6 PROJECT CONDITIONS

- A. Field Measurements: Verify actual locations of walls and other construction contiguous with metal fabrications by field measurements before fabrication.

1.7 COORDINATION

- A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written recommendations to ensure that shop primers and topcoats are compatible with one another.
- B. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

PART 2 - PRODUCTS

2.1 METALS, GENERAL

- A. Metal Surfaces, General: Provide materials with smooth, flat surfaces unless otherwise indicated. For metal fabrications exposed to view in the completed Work, provide materials without seam marks, roller marks, rolled trade names, or blemishes.

2.2 FERROUS METALS

- A. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M.
- B. Steel Tubing: ASTM A 500, cold-formed steel tubing.
- C. Steel Pipe: ASTM A 53/A 53M, standard weight (Schedule 40) unless otherwise indicated.
 - 1. Black finish, unless otherwise indicated.
 - 2. Galvanized finish for exterior installations and where indicated.
- D. Slotted Channel Framing: Cold-formed metal box channels (struts) complying with MFMA-4.
 - 1. Size of Channels: 1-5/8 by 1-5/8 inches.
 - 2. Material: Galvanized steel, ASTM A 653/A 653M, structural steel, Grade 33, with G90 coating; 0.108-inch (12 gauge) nominal thickness.
- E. Cast Iron: Either gray iron, ASTM A 48/A 48M, or malleable iron, ASTM A 47/A 47M, unless otherwise indicated.

2.3 FASTENERS

- A. General: Unless otherwise indicated, provide Type 304 stainless-steel fasteners for exterior use and zinc-plated fasteners with coating complying with ASTM B 633 or ASTM F 1941, Class Fe/Zn 5, at exterior walls. Select fasteners for type, grade, and class required.

1. Provide stainless-steel fasteners for fastening stainless steel.
 - B. Steel Bolts and Nuts: Regular hexagon-head bolts, ASTM A 307, Grade A; with hex nuts, ASTM A 563; and, where indicated, flat washers.
 - C. Stainless-Steel Bolts and Nuts: Regular hexagon-head annealed stainless-steel bolts, ASTM F 593; with hex nuts, ASTM F 594; and, where indicated, flat washers; Alloy Group 1.
 - D. Anchor Bolts: ASTM F 1554, Grade 36, of dimensions indicated; with nuts, ASTM A 563; and, where indicated, flat washers.
 1. Hot-dip galvanize or provide mechanically deposited, zinc coating where item being fastened is indicated to be galvanized.
 - E. Eyebolts: ASTM A 489.
 - F. Machine Screws: ASME B18.6.3.
 - G. Lag Screws: ASME B18.2.1.
 - H. Wood Screws: Flat head, ASME B18.6.1.
 - I. Plain Washers: Round, ASME B18.22.1.
 - J. Lock Washers: Helical, spring type, ASME B18.21.1.
 - K. Anchors, General: Anchors capable of sustaining, without failure, a load equal to six times the load imposed when installed in unit masonry and four times the load imposed when installed in concrete, as determined by testing according to ASTM E 488, conducted by a qualified independent testing agency.
 - L. Cast-in-Place Anchors in Concrete: Either threaded type or wedge type unless otherwise indicated; galvanized ferrous castings, either ASTM A 47/A 47M malleable iron or ASTM A 27/A 27M cast steel. Provide bolts, washers, and shims as needed, all hot-dip galvanized per ASTM F 2329.
 - M. Post-Installed Anchors: Torque-controlled expansion anchors.
 1. Material for Interior Locations: Carbon-steel components zinc plated to comply with ASTM B 633 or ASTM F 1941, Class Fe/Zn 5, unless otherwise indicated.
 2. Material for Exterior Locations and Where Stainless Steel is Indicated: Alloy Type 304 stainless-steel bolts, ASTM F 593, and nuts, ASTM F 594.
- 2.4 MISCELLANEOUS MATERIALS
- A. Welding Rods and Bare Electrodes: Select according to AWS specifications for metal alloy welded.
 - B. Shop Primers: Provide primers that comply with Division 09 Section "Exterior Painting" and Division 09 Section "Interior Painting."

- C. Galvanizing Repair Paint: High-zinc-dust-content paint complying with SSPC-Paint 20 and compatible with paints specified to be used over it.
- D. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D 1187.
- E. Nonshrink, Nonmetallic Grout: Factory-packaged, nonstaining, noncorrosive, nongaseous grout complying with ASTM C 1107. Provide grout specifically recommended by manufacturer for interior and exterior applications.
- F. Concrete: Comply with requirements in Division 03 Section "Cast-in-Place Concrete" for normal-weight, air-entrained, concrete with a minimum 28-day compressive strength of 3000 psi.

2.5 FABRICATION, GENERAL

- A. Shop Assembly: Preassemble items in the shop to greatest extent possible. Disassemble units only as necessary for shipping and handling limitations. Use connections that maintain structural value of joined pieces. Clearly mark units for reassembly and coordinated installation.
- B. Cut, drill, and punch metals cleanly and accurately. Remove burrs and ease edges to a radius of approximately 1/32 inch unless otherwise indicated. Remove sharp or rough areas on exposed surfaces.
- C. Form bent-metal corners to smallest radius possible without causing grain separation or otherwise impairing work.
- D. Form exposed work with accurate angles and surfaces and straight edges.
- E. Weld corners and seams continuously to comply with the following:
 - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.
- F. Form exposed connections with hairline joints, flush and smooth, using concealed fasteners or welds where possible. Where exposed fasteners are required, use Phillips flat-head (countersunk) fasteners unless otherwise indicated. Locate joints where least conspicuous.
- G. Fabricate seams and other connections that will be exposed to weather in a manner to exclude water. Provide weep holes where water may accumulate.
- H. Cut, reinforce, drill, and tap metal fabrications as indicated to receive finish hardware, screws, and similar items.

- I. Provide for anchorage of type indicated; coordinate with supporting structure. Space anchoring devices to secure metal fabrications rigidly in place and to support indicated loads.
 - 1. Where units are indicated to be cast into concrete or built into masonry, equip with integrally welded steel strap anchors, 1/8 by 1-1/2 inches, with a minimum 6-inch embedment and 2-inch hook, not less than 8 inches from ends and corners of units and 24 inches o.c., unless otherwise indicated.

2.6 MISCELLANEOUS FRAMING AND SUPPORTS

- A. General: Provide steel framing and supports not specified in other Sections as needed to complete the Work.
 - 1. Miscellaneous framing and supports shall include but not be limited to assembly of overhead lobby door frames, ceiling hung televisions and VCR cradles, and tube framing for partial height walls, mechanical and electrical equipment.
- B. Fabricate units from steel shapes, plates, and bars of welded construction unless otherwise indicated. Fabricate to sizes, shapes, and profiles indicated and as necessary to receive adjacent construction. Cut, drill, and tap units to receive hardware, hangers, and similar items.
 - 1. Fabricate units from slotted channel framing where indicated.
 - 2. Furnish inserts for units installed after concrete is placed.
- C. Galvanize miscellaneous framing and supports at exterior locations; prime paint miscellaneous framing and supports at interior locations.
- D. Galvanize exterior miscellaneous framing and supports.
- E. Prime interior miscellaneous framing and supports with primer specified in Division 09 Section "Interior Painting."

2.7 METAL LADDERS

- A. General:
 - 1. Comply with ANSI A14.3 unless otherwise indicated.
- B. Steel Ladders:
 - 1. Space siderails 16 inches apart unless otherwise indicated.
 - 2. Siderails: Continuous, 3/8-by-2-1/2-inch steel flat bars, with eased edges.
 - 3. Rungs: 3/4-inch-diameter steel bars.
 - 4. Fit rungs in centerline of siderails; plug-weld and grind smooth on outer rail faces.
 - 5. Provide nonslip surfaces on top of each rung, either by coating rung with aluminum-oxide granules set in epoxy-resin adhesive or by using a type of manufactured rung filled with aluminum-oxide grout.
 - 6. Support each ladder at top and bottom and not more than 60 inches o.c. with welded or bolted steel brackets.
 - 7. Factory Finished: Baked enamel or powder coat.

- a. Color: Black.

2.8 MISCELLANEOUS STEEL TRIM

- A. Unless otherwise indicated, fabricate units from steel shapes, plates, and bars of profiles shown with continuously welded joints and smooth exposed edges. Miter corners and use concealed field splices where possible.
- B. Provide cutouts, fittings, and anchorages as needed to coordinate assembly and installation with other work.
 1. Provide with integrally welded steel strap anchors for embedding in concrete or masonry construction.
- C. Galvanize miscellaneous steel trim.

2.9 METAL BOLLARDS

- A. Fabricate metal bollards from Schedule 80 steel pipe.
 1. Interior Diameter: As indicated on Drawings.
 2. Height: As indicated on Drawings.
- B. Fabricate sleeves for bollard anchorage from steel pipe with 1/4-inch- thick steel plate welded to bottom of sleeve. Make sleeves not less than 8 inches deep and 3/4 inch larger than OD of bollard.
 1. Where bollards are to be anchored to sloping concrete slabs, angle baseplates for plumb alignment of bollards.
 2. Paint base plate gray matching existing floor construction, unless otherwise indicated.
- C. Prime bollards with zinc-rich primer.
- D. Accessories:
 1. HDPE, Bollard Sleeve: Provide post guards sleeves fabricated from high density polyethylene (HDPE) that has been warranted against fading or color change for a period of five years from the date of substantial completion and complying with the following:
 - a. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Encore Commercial Products, Inc. / Tel: (866) 737-8900; "Post Guards" bollard covers with reflective stripes.
 - a) Color: Gray; Pantone color Cool Gray 3C.
 - b) Tape Color: Red reflective stripes.
 - 2) Innoplast / Tel: (800) 516-9287; "BollardGard Bollard Covers" with reflective stripes.

- a) Color: Light Gray.
 - b) Tape Color: Red reflective stripes.
 - 3) Bollard Cover USA / Tel: (800) 352-6609; "BC-Series" bollard covers with reflective stripes.
 - a) Color: Light Gray.
 - b) Tape Color: Red reflective stripes.
 - b. Nominal Thickness: 1/8-inch.
 - c. Bollard Sleeve Size:
 - 1) Height: Provide bollard covers that fully encapsulate metal bollards. Refer to Drawings for metal bollard heights.
 - 2) Diameter: Provide bollard covers that fit the following metal bollard diameter sizes:
 - a) 4-inch Diameter Metal Bollards: 4.5-inch diameter bollard covers.
 - b) 6-inch Diameter Metal Bollards: 7-inch diameter bollard covers.
 - d. Reflective Tape: Provide 2 rows of bollards manufacturer's standard reflective tape for each bollard sleeve.
 - e. Performance Requirements:
 - 1) High molecular weight material. designed for optimum balance of density, molecular weight and molecular weight distribution demonstrating maximum property advantages for large products that require high impact resistance.
 - 2) Ultraviolet Protection Additive: Five (5) Year UV stabilizer package. Warranty 5 Years.
 - 3) Anti Static Package. Combined in manufacturing process of HDPE.
 - 4) Abrasion Resistant.
 - 5) Environmental Stress Cracks Resistant.
 - 6) Flexural Modulus: 200,000 psi.
 - 7) Tensile Strength: 4,000 psi.
- 2. HDPE, Sign Bollard Sleeve: Provide sign bollard sleeves fabricated from high density polyethylene (HDPE) that has been warranted against fading or color change for a period of five years from the date of substantial completion and complying with the following:
 - a. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Encore Commercial Products, Inc. / Tel: (866) 737-8900; "Post Guards" bollard covers with reflective stripes.
 - a) Color: Gray; Pantone color Cool Gray 3C.
 - b) Tape Color: Red reflective stripes.
 - 2) Innoplast / Tel: (800) 516-9287; "BollardGard Bollard Covers" with reflective stripes.

- a) Color: Light Gray.
 - b) Tape Color: Red reflective stripes.
 - 3) Bollard Cover USA / Tel: (800) 352-6609; "BC-Series" bollard covers with reflective stripes.
 - a) Color: Light Gray.
 - b) Tape Color: Red reflective stripes.
 - b. Nominal Thickness: 1/8-inch.
 - c. Bollard Sleeve Size:
 - 1) Height: Provide bollard covers that fully encapsulate metal bollards. Refer to Drawings for metal bollard heights.
 - 2) Outside Diameter: Provide bollard covers that fit metal bollard diameter.
 - d. Reflective Tape: Provide 2 rows of bollards manufacturer's standard reflective tape for each bollard sleeve.
 - e. Performance Requirements:
 - 1) High molecular weight material. designed for optimum balance of density, molecular weight and molecular weight distribution demonstrating maximum property advantages for large products that require high impact resistance.
 - 2) Ultraviolet Protection Additive: Five (5) Year UV stabilizer package. Warranty 5 Years.
 - 3) Anti Static Package. Combined in manufacturing process of HDPE.
 - 4) Abrasion Resistant.
 - 5) Environmental Stress Cracks Resistant.
 - 6) Flexural Modulus: 200,000 psi.
 - 7) Tensile Strength: 4,000 psi.
 - f. Field Cut Opening: Field drill openings of diameters required to provide clearance for insertion of signage post.
 - 1) Coordinate with Drawings for size and profile of signage post.
 - E. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
 - F. Finish metal fabrications after assembly.
 - G. Finish exposed surfaces to remove tool and die marks and stretch lines, and to blend into surrounding surface.
- 2.10 STEEL AND IRON FINISHES
- A. Galvanizing: Hot-dip galvanize items as indicated to comply with ASTM A 153/A 153M for steel and iron hardware and with ASTM A 123/A 123M for other steel and iron products.

1. Do not quench or apply post galvanizing treatments that might interfere with paint adhesion.
- B. Shop prime iron and steel items not indicated to be galvanized unless they are to be embedded in concrete, sprayed-on fireproofing, or masonry, or unless otherwise indicated.
 1. Shop prime with universal shop primer unless zinc-rich primer is indicated.
- C. Preparation for Shop Priming: Prepare surfaces to comply with requirements indicated below:
 1. Exterior Items: SSPC-SP 6/NACE No. 3, "Commercial Blast Cleaning."
 2. Other Items: SSPC-SP 3, "Power Tool Cleaning."
- D. Shop Priming: Apply shop primer to comply with SSPC-PA 1, "Paint Application Specification No. 1: Shop, Field, and Maintenance Painting of Steel," for shop painting.
 1. Stripe paint corners, crevices, bolts, welds, and sharp edges.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Cutting, Fitting, and Placement: Perform cutting, drilling, and fitting required for installing metal fabrications. Set metal fabrications accurately in location, alignment, and elevation; with edges and surfaces level, plumb, true, and free of rack; and measured from established lines and levels.
- B. Fit exposed connections accurately together to form hairline joints. Weld connections that are not to be left as exposed joints but cannot be shop welded because of shipping size limitations. Do not weld, cut, or abrade surfaces of exterior units that have been hot-dip galvanized after fabrication and are for bolted or screwed field connections.
- C. Field Welding: Comply with the following requirements:
 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 2. Obtain fusion without undercut or overlap.
 3. Remove welding flux immediately.
 4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.
- D. Fastening to In-Place Construction: Provide anchorage devices and fasteners where metal fabrications are required to be fastened to in-place construction. Provide threaded fasteners for use with concrete and masonry inserts, toggle bolts, through bolts, lag screws, wood screws, and other connectors.
- E. Provide temporary bracing or anchors in formwork for items that are to be built into concrete, masonry, or similar construction.

3.2 INSTALLING MISCELLANEOUS FRAMING AND SUPPORTS

- A. General: Install framing and supports to comply with requirements of items being supported, including manufacturers' written instructions and requirements indicated on Shop Drawings.
- B. Anchor supports for operable partitions securely to and rigidly brace from building structure.

3.3 INSTALLING METAL BOLLARDS

- A. Fill metal-capped bollards solidly with concrete and allow concrete to cure seven days before installing.
- B. Anchor bollards to existing construction with anchor bolts. Provide four 3/4-inch bolts at each bollard unless otherwise indicated.
 - 1. Embed anchor bolts at least 4 inches in concrete.
- C. Anchor bollards in place with concrete footings. Center and align bollards in holes 3 inches above bottom of excavation. Place concrete and vibrate or tamp for consolidation. Support and brace bollards in position until concrete has cured.
- D. Fill bollards solidly with concrete, mounding top surface to shed water.
- E. Install post guard bollard sleeves in accordance to bollard sleeve manufactures written instruction.
 - 1. Sleeves not complying with specified requirements shall be replaced at no cost to the Owner.

3.4 ADJUSTING AND CLEANING

- A. Touchup Painting: Immediately after erection, clean field welds, bolted connections, and abraded areas. Paint uncoated and abraded areas with the same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.
 - 1. Apply by brush or spray to provide a minimum 2.0-mil dry film thickness.
- B. Galvanized Surfaces: Clean field welds, bolted connections, and abraded areas and repair galvanizing to comply with ASTM A 780.

END OF SECTION 05 50 00

SECTION 06 10 00 - ROUGH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Wood blocking and nailers.
2. Plywood backing panels.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 DEFINITIONS

A. Lumber grading agencies, and the abbreviations used to reference them, include the following:

1. NeLMA: Northeastern Lumber Manufacturers' Association.
2. NLGA: National Lumber Grades Authority.
3. SPIB: The Southern Pine Inspection Bureau.
4. WCLIB: West Coast Lumber Inspection Bureau.
5. WWPA: Western Wood Products Association.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used and net amount of preservative retained.
2. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Include physical properties of treated materials based on testing by a qualified independent testing agency.
3. For fire-retardant treatments, include physical properties of treated lumber both before and after exposure to elevated temperatures, based on testing by a qualified independent testing agency according to ASTM D 5664.
4. Include copies of warranties from chemical treatment manufacturers for each type of treatment.
5. For products receiving a waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.
6. Include copies of warranties from chemical treatment manufacturers for each type of treatment.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. Regional Materials Information.
 - d. LEED Materials and Resources Calculator
 - e. FSC Chain of Custody Certificates

1.4 INFORMATIONAL SUBMITTALS

- A. Evaluation Reports: For the following, from ICC-ES:
 1. Wood-preservative-treated wood.
 2. Fire-retardant-treated wood.
 3. Power-driven fasteners.
 4. Powder-actuated fasteners.
 5. Expansion anchors.

1.5 QUALITY ASSURANCE

- A. Testing Agency Qualifications: For testing agency providing classification marking for fire-retardant treated material, an inspection agency acceptable to authorities having jurisdiction that periodically performs inspections to verify that the material bearing the classification marking is representative of the material tested.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Stack lumber flat with spacers beneath and between each bundle to provide air circulation. Protect lumber from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

- A. Lumber: DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, provide lumber that complies with the applicable rules of any rules-writing agency certified by the ALSC Board of Review. Provide lumber graded by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.
 1. Factory mark each piece of lumber with grade stamp of grading agency.
 2. Where nominal sizes are indicated, provide actual sizes required by DOC PS 20 for moisture content specified. Where actual sizes are indicated, they are minimum dressed sizes for dry lumber.
 3. Provide dressed lumber, S4S, unless otherwise indicated.
- B. Maximum Moisture Content of Lumber: 19 percent maximum moisture content at time of dressing for 2-inches nominal thickness or less, unless otherwise indicated.

2.2 WOOD-PRESERVATIVE-TREATED LUMBER

- A. Preservative Treatment by Pressure Process: AWP A U1; Use Category UC2 for interior construction not in contact with the ground, Use Category UC3b for exterior construction not in contact with the ground, and Use Category UC4a for items in contact with the ground.
 - 1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.
- B. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or that does not comply with requirements for untreated material.
- C. Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board of Review.
- D. Application: Treat items indicated on Drawings, and the following:
 - 1. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.
 - 2. Wood framing members that are less than 18 inches above the ground in crawlspaces or unexcavated areas.
 - 3. Wood floor plates that are installed over concrete slabs-on-grade.

2.3 FIRE-RETARDANT-TREATED MATERIALS

- A. General: Where fire-retardant-treated materials are indicated, use materials complying with requirements in this article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified as determined by testing identical products per test method indicated by a qualified testing agency.
- B. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Products with a flame spread index of 25 or less when tested according to ASTM E 84, and with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet beyond the centerline of the burners at any time during the test.
 - 1. Use treatment that does not promote corrosion of metal fasteners.
 - 2. Exterior Type: Treated materials shall comply with requirements specified above for fire-retardant-treated lumber and plywood by pressure process after being subjected to accelerated weathering according to ASTM D 2898. Use for exterior locations and where indicated.
 - 3. Interior Type A: Treated materials shall have a moisture content of 28 percent or less when tested according to ASTM D 3201 at 92 percent relative humidity. Use where exterior type is not indicated.
 - 4. Design Value Adjustment Factors: Treated lumber shall be tested according to ASTM D 5664 and design value adjustment factors shall be calculated according to ASTM D 6841.
- C. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Kiln-dry plywood after treatment to a maximum moisture content of 15 percent.

- D. Identify fire-retardant-treated wood with appropriate classification marking of qualified testing agency.
- E. Application: Treat items indicated on Drawings, and the following:
 - 1. Concealed blocking.
 - 2. Roof construction.
 - 3. Plywood backing panels.

2.4 MISCELLANEOUS LUMBER

- A. General: Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:
 - 1. Blocking.
 - 2. Nailers.
 - 3. Rooftop equipment bases and support curbs.
 - 4. Cants.
- B. For items of dimension lumber size, provide Construction or No. 2 grade lumber and any of the following species:
 - 1. Mixed southern pine; SPIB.
 - 2. Western woods; WCLIB or WWPA.
 - 3. Northern species; NLGA.
 - 4. Eastern softwoods; NeLMA.
- C. For concealed boards, provide lumber with 19 percent maximum moisture content and the following species and grades:
 - 1. Mixed southern pine; No. 2 grade; SPIB.
 - 2. Eastern softwoods; No. 2 Common grade; NeLMA.
 - 3. Northern species; No. 2 Common grade; NLGA.
 - 4. Western woods; Construction or No. 2 Common grade; WCLIB or WWPA.
- D. For blocking not used for attachment of other construction, Utility, Stud, or No. 3 grade lumber of any species may be used provided that it is cut and selected to eliminate defects that will interfere with its attachment and purpose.
- E. For blocking and nailers used for attachment of other construction, select and cut lumber to eliminate knots and other defects that will interfere with attachment of other work.
- F. For furring strips for installing plywood or hardboard paneling, select boards with no knots capable of producing bent-over nails and damage to paneling.

2.5 PLYWOOD BACKING PANELS

- A. Equipment Backing Panels: DOC PS 1, Exposure 1, C-D Plugged, fire-retardant treated, in thickness indicated or, if not indicated, not less than 1/2-inch nominal thickness.

2.6 FASTENERS

- A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.
 - 1. Where rough carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A 153/A 153M.
- B. Nails, Brads, and Staples: ASTM F 1667.
- C. Power-Driven Fasteners: NES NER-272.
- D. Wood Screws: ASME B18.6.1.
- E. Lag Bolts: ASME B18.2.1.
- F. Bolts: Steel bolts complying with ASTM A 307, Grade A; with ASTM A 563 hex nuts and, where indicated, flat washers.
- G. Expansion Anchors: Anchor bolt and sleeve assembly of material indicated below with capability to sustain, without failure, a load equal to six times the load imposed when installed in unit masonry assemblies and equal to four times the load imposed when installed in concrete as determined by testing per ASTM E 488 conducted by a qualified independent testing and inspecting agency.
 - 1. Material: Stainless steel with bolts and nuts complying with ASTM F 593 and ASTM F 594, Alloy Group 1 or 2.

2.7 MISCELLANEOUS MATERIALS

- A. Flexible Flashing: Composite, self-adhesive, flashing product consisting of a pliable, butyl rubber or rubberized-asphalt compound, bonded to a high-density polyethylene film, aluminum foil, or spunbonded polyolefin to produce an overall thickness of not less than 0.025 inch.
- B. Adhesives for Gluing Furring to Concrete or Masonry: Formulation complying with ASTM D 3498 that is approved for use indicated by adhesive manufacturer.
 - 1. Adhesives shall have a VOC content of 70 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- C. Water-Repellent Preservative: NWWDA-tested and -accepted formulation containing 3-iodo-2-propynyl butyl carbamate, combined with an insecticide containing chlorpyrifos as its active ingredient.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Set rough carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit rough carpentry to other construction; scribe and cope as needed for accurate fit. Locate furring, nailers, blocking, and similar supports to comply with requirements for attaching other construction.
- B. Install plywood backing panels by fastening to studs; coordinate locations with utilities requiring backing panels. Install fire-retardant treated plywood backing panels with classification marking of testing agency exposed to view.
- C. Provide blocking and framing as indicated and as required to support facing materials, fixtures, specialty items, and trim.
 - 1. Provide metal clips for fastening gypsum board or lath at corners and intersections where framing or blocking does not provide a surface for fastening edges of panels. Space clips not more than 16 inches o.c.
- D. Sort and select lumber so that natural characteristics will not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.
- E. Securely attach rough carpentry work to substrate by anchoring and fastening as indicated, complying with the following:
 - 1. NES NER-272 for power-driven fasteners.
 - 2. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code.
- F. Comply with AWP A M4 for applying field treatment to cut surfaces of preservative-treated lumber.
 - 1. Use inorganic boron for items that are continuously protected from liquid water.
 - 2. Use copper naphthenate for items not continuously protected from liquid water.
- G. Use steel common nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.

3.2 WOOD BLOCKING, AND NAILER INSTALLATION

- A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.
- B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces unless otherwise indicated.

- C. Where wood-preservative-treated lumber is installed adjacent to metal decking, install continuous flexible flashing separator between wood and metal decking.

3.3 PANEL PRODUCT INSTALLATION

- A. General: Comply with applicable recommendations contained in APA Form No. E30K, "APA Design/Construction Guide: Residential & Commercial," and local utility requirements, if any, for plywood backing panels utilized as indicated.
- B. Fastening Methods: Fasten panels as indicated below:
 - 1. Plywood Backing Panels: Secure to wall using proper fastening devices for substrates encountered spaced 12 inches on center maximum at perimeter 1/2 inch from corners and three rows of 3 fasteners each in the backerboard field. Countersink fasteners flush with plywood surface. Butt adjacent panels without lapping.

3.4 PROTECTION

- A. Protect rough carpentry from weather. If, despite protection, rough carpentry becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION 06 10 00

SECTION 06 16 00 - SHEATHING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Non Structural wall sheathing.
2. Parapet sheathing.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review structural magnesium cement board sheathing requirements and installation, special details, transitions, protection, and work scheduling that covers structural magnesium cement board sheathing.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1. For structural magnesium cement board sheathing, include manufacturer's technical data and tested physical and performance properties of products.
 - a. Include data for screw pull-out testing for structural magnesium cement board sheathing.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. LEED Materials and Resources Calculator.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Evaluation Reports: For the following, from ICC-ES:
 - 1. Structural magnesium cement board.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer of structural magnesium cement board sheathing.
- B. Installer Qualifications: An installers experienced in the installation of structural magnesium cement board sheathing and who has successfully installed work similar in design and extent to that required for the Project, in not less than three projects of similar scope to the satisfaction of the Architect, and whose work has resulted in construction with a record of successful in-service performance for a period of 3 years.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Stack panels flat with spacers beneath and between each bundle to provide air circulation. Protect sheathing from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Factory mark panels to indicate compliance with applicable standard.

2.2 WALL SHEATHING

- A. Glass-Mat Gypsum Sheathing: ASTM C1177/C1177M.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. CertainTeed Corporation.; "GlasRoc Sheathing."
 - b. Georgia-Pacific Gypsum LLC.; "DensGlass Sheathing."
 - c. National Gypsum Company; "exp Sheathing."
 - d. USG Corporation; "USG Securock Brand, Glass-Mat Sheathing."
 - 2. Type and Thickness: Type X, 5/8 inch thick.
 - 3. Size: 48 by 96 inches for vertical installation.

2.3 PARAPET SHEATHING

- A. Glass-Mat Gypsum Sheathing: ASTM C1177/C1177M.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Georgia-Pacific Gypsum LLC.; "DensDeck Roof Board."
 - b. National Gypsum Company; "DEXcell Glass Mat Roof Board."
 - c. USG Corporation; "USG Securock Brand, Ultralight Glass-Mat Roof Board."
 - 2. Type and Thickness: Regular, 1/2 inch thick.
 - 3. Size: 48 by 96 inches for vertical installation.

2.4 FASTENERS

- A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.
 - 1. For parapet and wall sheathing, provide fasteners with hot-dip zinc coating complying with ASTM A153/A153M.
- B. Screws for Fastening Gypsum Sheathing to Cold-Formed Metal Framing: Steel drill screws, in length recommended by sheathing manufacturer for thickness of sheathing to be attached.
 - 1. For steel framing less than 0.0329 inch thick, use screws that comply with ASTM C1002.
 - 2. For steel framing from 0.033 to 0.112 inch thick, use screws that comply with ASTM C954.
- C. Screws for Fastening Structural Magnesium Cement Board Sheathing to Cold-Formed Metal Framing: Corrosion resistant steel screws with self-countersinking heads of type and size as recommended by sheathing manufacturer for thickness of sheathing to be attached.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Do not use materials with defects that impair quality of sheathing or pieces that are too small to use with minimum number of joints or optimum joint arrangement. Arrange joints so that pieces do not span between fewer than three support members.
- B. Cut panels at penetrations, edges, and other obstructions of work; fit tightly against abutting construction unless otherwise indicated.
- C. Securely attach to substrate by fastening as indicated, complying with the following:
 - 1. Table 2304.9.1, "Fastening Schedule," in the ICC's International Building Code.

- D. Coordinate wall and parapet sheathing installation with flashing and joint-sealant installation so these materials are installed in sequence and manner that prevent exterior moisture from passing through completed assembly.
- E. Do not bridge building expansion joints; cut and space edges of panels to match spacing of structural support elements.
- F. Coordinate sheathing installation with installation of materials installed over sheathing so sheathing is not exposed to precipitation or left exposed at end of the workday when rain is forecast.

3.2 GYPSUM SHEATHING INSTALLATION

- A. Comply with GA-253 and with manufacturer's written instructions.
 - 1. Fasten gypsum sheathing to cold-formed metal framing with screws.
 - 2. Install panels with a 3/8-inch gap where non-load-bearing construction abuts structural elements.
 - 3. Install panels with a 1/4-inch gap where they abut masonry or similar materials that might retain moisture, to prevent wicking.
- B. Apply fasteners so heads bear tightly against face of sheathing, but do not cut into facing.
- C. Horizontal Installation: Install sheathing with V-grooved edge down and tongue edge up. Interlock tongue with groove to bring long edges in contact with edges of adjacent panels without forcing. Abut ends over centers of studs, and stagger end joints of adjacent panels not less than one stud spacing. Attach at perimeter and within field of panel to each stud.
 - 1. Space fasteners approximately 8 inches o.c. and set back a minimum of 3/8 inch from edges and ends of panels.
- D. Vertical Installation: Install vertical edges centered over studs. Abut ends and edges with those of adjacent panels. Attach at perimeter and within field of panel to each stud.
 - 1. Space fasteners approximately 8 inches o.c. and set back a minimum of 3/8 inch from edges and ends of panels.

END OF SECTION 06 16 00

SECTION 06 40 23 - INTERIOR ARCHITECTURAL WOODWORK

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Standing and running trim.
2. Interior frames and jambs.
3. Plastic-laminate-faced architectural cabinets and caseworks.
4. Plastic-laminate countertops.
5. Wall-hung, adjustable open-shelving.
6. Shop finishing of woodwork.

B. Interior architectural woodwork includes wood furring, blocking, shims, and hanging strips, unless concealed within other construction before woodwork installation.

C. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product, including high-pressure decorative laminate, adhesive for bonding plastic laminate, fire-retardant-treated materials and cabinet hardware and accessories.

1. Include data for fire-retardant treatment from chemical-treatment manufacturer and certification by treating plant that treated materials comply with requirements.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. FSC Certified Wood Information.
 - c. FSC Chain of Custody Certificates.
 - d. Recycled Content Information.
 - e. Regional Materials Information.
 - f. Low Emitting Materials Information.
 - g. LEED Materials and Resources Calculator.

C. Shop Drawings: Show location of each item, dimensioned plans and elevations, large-scale details, attachment devices, and other components.

1. Show details full size.
2. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement specified in other Sections.
3. Show locations and sizes of cutouts and holes for electrical switches and outlets and other items installed in architectural woodwork cabinets.

D. Samples for Verification:

1. Plastic laminates, 12 by 12 inches, for each type, color, pattern, and surface finish, with one sample applied to core material and specified edge material applied to one edge.
2. Corner pieces as follows:
 - a. Cabinet-front frame joints between stiles and rails, as well as exposed end pieces, 18 inches high by 18 inches wide by 6 inches deep.
 - b. Miter joints for standing trim.
3. Exposed cabinet hardware and accessories, one unit for each type and finish.

1.3 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For fabricator.
- B. Product Certificates: For each type of product.
- C. Evaluation Reports: Evidence of fire-retardant-treated material's compliance with building code in effect for Project, from a model code organization acceptable to authorities having jurisdiction.

1.4 QUALITY ASSURANCE

- A. Fabricator Qualifications: Shop that employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.
- B. Quality Standard: Fabricate and install all architectural woodwork in accordance with the applicable requirements of Architectural Woodwork Standards, 2nd edition, published jointly by AWI, AWMAC, and WI, unless more stringent requirements are specified or shown.
 1. Provide custom grade woodwork, unless otherwise indicated.
- C. Testing Agency Qualifications: For testing agency providing classification marking for fire-retardant-treated material, an inspection agency acceptable to authorities having jurisdiction that periodically performs inspections to verify that the material bearing the classification marking is representative of the material tested.
- D. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
 1. Build mockups of typical architectural woodwork as shown on Drawings.
 2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Protect woodwork during transit, delivery, storage, and handling to prevent damage, soilage, and deterioration. Do not deliver architectural woodwork until painting, wet work, grinding, and similar operations that could damage, soil, or deteriorate woodwork have been completed in installation areas. If architectural woodwork must be stored in other than installation areas, store only in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

1.6 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install cabinets until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature between 60 and 90 deg F and relative humidity between 25 and 55 percent during the remainder of the construction period.
- B. Field Measurements: Where cabinets are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
 - 1. Locate concealed framing, blocking, and reinforcements that support cabinets by field measurements before being enclosed, and indicate measurements on Shop Drawings.
- C. Established Dimensions: Where architectural woodwork are indicated to fit to other construction, establish dimensions for areas where architectural woodwork are to fit. Provide allowance for trimming at site, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

1.7 COORDINATION

- A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to ensure that architectural woodwork can be supported and installed as indicated.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Wood for Opaque Finish:
 - 1. Species: Any closed-grain hardwood.
- B. Wood Products: Comply with the following:
 - 1. Medium-Density Fiberboard: ANSI A208.2, Grade MD, made with binder containing no urea formaldehyde.
 - 2. Fire-Retardant-Treated Medium-Density Fiberboard: ANSI A208.2, Grade MD, made with binder containing no urea formaldehyde.

3. Particleboard: ANSI A208.1, Grade M-2, made with binder containing no urea formaldehyde.
- C. Transparent Acrylic Glass: ASTM D 4802, Category A-1 (cell cast), Finish 1 (smooth or polished), Type UVF (UV filtering), 0.236 inch thick, unless otherwise indicated.
 1. Refer to Division 08 Section "Plastic Glazing," for additional requirements.
- D. Thermoset Decorative Overlay (Melamine): Particleboard or medium-density fiberboard finished with thermally fused, melamine-impregnated decorative paper complying with the recommendations of the Composite Panel Association's Technical Bulletin "Laminating Composite Panels."
- E. High-Pressure Decorative Laminate: NEMA LD 3.
 1. Products: Subject to compliance with requirements, provide the following laminates:
 - a. Plastic Laminate (PL-1): Wilsonart International; Color: #D354 – Designer White / Finish: 01 – High Gloss.
 - b. Plastic Laminate (PL-2): Wilsonart International; Color: #D354 – Designer White / Finish: 07 – Textured Gloss.
 - c. Plastic Laminate (PL-7): Wilsonart International; Color: #D354 - Designer White / Finish: 60 – Matte / High Wear.
 - d. Plastic Laminate (PL-16): Wilsonart International; Color: #6281 – Satin Brushed Smoke Aluminum / Finish: Satin brushed aluminum.
 - e. Plastic Laminate (PL-17): Formica Corporation; Formica Infiniti, Color: #9283 – Walnut Riftwood / Finish: Super Matte.
 - f. Plastic Laminate (PL-18): Wilsonart International; Color: #4991 – Pressed Linen / Finish: 38 – Fine Velvet Texture / High Wear.
 - g. Plastic Laminate (PL-19): Formica Corporation; Formica Infiniti, Color: #909 – Black / Finish: Super Matte.
 - h. Plastic Laminate (CL-1): Wilsonart International; Color: #1570 – White / Finish: 60 - Matte.

2.2 FIRE-RETARDANT-TREATED MATERIALS

- A. Fire-Retardant-Treated Wood Materials: Where fire-retardant-treated materials are indicated, use materials complying with requirements that are acceptable to authorities having jurisdiction and with fire-test-response characteristics specified as determined by testing identical products according to test method indicated by a qualified testing agency.
 1. Use treated materials that comply with requirements of the Architectural Woodwork Standards. Do not use materials that are warped, discolored, or otherwise defective.
 2. Use fire-retardant-treatment formulations that do not bleed through or otherwise adversely affect finishes. Do not use colorants to distinguish treated materials from untreated materials.
 3. Identify fire-retardant-treated materials with appropriate classification marking of qualified testing agency in the form of removable paper label or imprint on surfaces that will be concealed from view after installation.

- B. Fire-Retardant-Treated Lumber and Plywood: Products with a flame-spread index of 25 or less when tested according to ASTM E 84, with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet beyond the centerline of the burners at any time during the test.
 - 1. Kiln-dry lumber and plywood after treatment to a maximum moisture content of 19 and 15 percent, respectively.
 - 2. Mill lumber before treatment, and implement procedures during treatment and drying processes that prevent lumber from warping and developing discolorations from drying sticks or other causes, marring, and other defects affecting appearance of treated woodwork.
- C. Fire-Retardant Particleboard: Panels made from softwood particles and fire-retardant chemicals mixed together at time of panel manufacture with flame-spread index of 25 or less and smoke-developed index of 25 or less per ASTM E 84.
 - 1. For panels 3/4 inch thick and less, comply with ANSI A208.1 for Grade M-2, except for the following minimum properties: modulus of rupture, 1600 psi; modulus of elasticity, 300,000 psi; internal bond, 80 psi; and screw-holding capacity on face and edge, 250 and 225 lbf, respectively.
 - 2. For panels 13/16 to 1-1/4 inches thick, comply with ANSI A208.1 for Grade M-1, except for the following minimum properties: modulus of rupture, 1300 psi (9 MPa); modulus of elasticity, 250,000 psi; linear expansion, 0.50 percent; and screw-holding capacity on face and edge, 250 and 175 lbf, respectively.
- D. Fire-Retardant Fiberboard: ANSI A208.2 medium-density fiberboard panels made from softwood fibers, synthetic resins, and fire-retardant chemicals mixed together at time of panel manufacture with flame-spread index of 25 or less and smoke-developed index of 200 or less per ASTM E 84.

2.3 CABINET HARDWARE AND ACCESSORIES

- A. General: Provide cabinet hardware and accessory materials for a complete installation of architectural woodwork, except for items specified in Division 08 Section "Door Hardware."
- B. Hardware Standard: Comply with BHMA A156.9 for items indicated by referencing BHMA numbers or items referenced to this standard.
- C. Frameless Concealed Hinges (European Type): BHMA A156.9, B01602, 120 degrees of opening, self-closing.
 - 1. Finish: Bright nickel plated.
- D. Wire Pulls: BHMA A156.9, B02011, back mounted, solid metal, 3 inches center to center, 1-1/4 inch projection width, and 5/16 inch minimum diameter.
 - 1. Finish: Anodized aluminum.
- E. Catches: Elbow catches, BHMA A156.9, B03023

1. Finish: Bright chromium plated.
- F. Shelf Rests: BHMA A156.9, B04013; metal shelf support with grommet to fit a bored hole diameter of 7.5 mm.
1. Finish: Bright nickel plated.
- G. Wall Mounted Adjustable Shelf Standards and Supports: BHMA A156.9, B04102; with shelf brackets, B04112, capacity as required to suit purpose indicated.
1. Slotted channels: Super duty, single slot design channels with 2-inch slot adjustment complying with the following:
 - a. Minimum Capacity: 1060 lbs. per pair.
 - b. Material: 0.105-inch (12 Gauge) Steel.
 - c. Minimum Dimensions: 7/8-inch wide by 11/16-inch.
 - d. Finish: White.
 2. Brackets: Super duty brackets; of depth as required to support shelves.
 - a. Material: 0.105-inch (12 Gauge) Steel.
 - b. Finish: White.
 3. Accessories: Provide shelf rests, fasteners and additional accessories including but not limited to the following:
 - a. End rest.
 - b. Center rest.
 - c. Rubber cushions.
- H. Drawer Slides: Unless noted otherwise, provide positive stop, side-mounted, full-extension, zinc-plated steel drawer slides with steel ball bearings.
1. Pencil Drawer Slides: Partial extension for drawers up to 16-inches wide comply with the following minimum requirements:
 - a. Description: Light duty, ball bearing slide with rail mount drawer member with the following features:
 - 1) Vertical drawer adjustment cam.
 - 2) Hold-in detent.
 - 3) Silenced in and out.
 - 4) Lever disconnect.
 - 5) Progressive movement.
 - b. Mounting: Side mounted.
 - c. Slide Length: Up to 28-inches.
 - d. Slide Travel: As selected by Architect.
 - e. Load Rating: 75 lbs per pair.
 - f. Material and Finish: Clear Zinc.

2. Box Drawer Slides: Full extension for drawers up to 16-inches wide comply with the following minimum requirements:
 - a. Description: Medium duty, ball bearing slide with rail mount drawer member with the following features:
 - 1) Self closing.
 - 2) Vertical drawer adjustment cam.
 - 3) Hold-in detent.
 - 4) Silenced in and out.
 - 5) Lever disconnect.
 - 6) Progressive movement.
 - b. Mounting: Side mounted.
 - c. Slide Length: Up to 26-inches.
 - d. Slide Travel: As selected by Architect.
 - e. Load Rating: 100 lbs per pair.
 - f. Material and Finish: Clear Zinc.
3. Lateral File Drawer Slides: Full extension for drawers up to 24-inches wide comply with the following minimum requirements:
 - a. Description: Heavy duty, ball bearing slide with rail mount drawer member with the following features:
 - 1) Vertical drawer adjustment cam.
 - 2) Hold-in detent.
 - 3) Silenced in and out.
 - 4) Lever disconnect.
 - 5) Positive stop.
 - 6) Progressive movement.
 - b. Mounting: Side mounted.
 - c. Slide Length: Up to 28-inches.
 - d. Slide Travel: As selected by Architect.
 - e. Load Rating: 150 lbs per pair.
 - f. Material and Finish: Clear Zinc.
4. Lateral File Drawer Slides: Full extension for drawers up to 42-inches wide comply with the following minimum requirements:
 - a. Description: Heavy duty, ball bearing slide with rail mount drawer member with the following features:
 - 1) Telescopic movement.
 - 2) Hold-in detent.
 - 3) Silenced in and out.
 - 4) Lever disconnect.
 - 5) Handed mounting rail.

- b. Mounting: Side mounted.
 - c. Slide Length: Up to 28-inches.
 - d. Slide Travel: As selected by Architect.
 - e. Load Rating: 200 lbs per pair.
 - f. Material and Finish: Clear Zinc.
- 5. Keyboard Slides: Partial extension for drawers up to 16-inches wide comply with the following minimum requirements:
 - a. Description: Light duty, ball bearing slide with rail mount drawer member with the following features:
 - 1) Hold-in and hold-out detent.
 - 2) Silenced in and out.
 - 3) Lever disconnect.
 - 4) Variable height mounting bracket.
 - b. Mounting: Suspended mounting style.
 - c. Slide Length: Up to 28-inches.
 - d. Slide Travel: As selected by Architect.
 - e. Load Rating: 75 lbs per pair.
 - f. Material and Finish: Clear Zinc.
- 6. Printer Shelf Slides: Full extension for drawers up to 30-inches wide comply with the following minimum requirements:
 - a. Description: Medium duty, ball bearing slide with rail mount drawer member with the following features:
 - 1) Easy-close action bring drawers to smooth, gentle close.
 - 2) Lever disconnect.
 - 3) Adjustment features permitting vertical and horizontal adjustments for slides and drawers.
 - b. Mounting: Fully concealed under mount.
 - 1) Provide manufacturers standard bottom mount brackets.
 - c. Slide Length: 22-inches.
 - d. Slide Travel: 21-inches.
 - e. Load Rating: 100 lbs per pair.
 - f. Material and Finish: Clear Zinc.
- I. Silencers: Provide felt silencers on jamb and/or head and sill strike areas of all cabinet doors; 2 for paired doors, 3 for single doors.
- J. Door and Drawer Locks:
 - 1. Pin and tumbler slide bolt lock, two keys each.
 - 2. Key all locks inside one room alike and provide masterkey for all locks in project.

3. Finish to match adjacent pull, or as selected by Architect.
4. Cabinet Locks:
 - a. Cabinet Door Lock (MW09, MW11 & MW12): BHMA A156.11, Grade 2; rim latch with spacer for out swing door application. Provide interchangeable core cylinders and accessories including strike.
 - 1) Latch: Self locking deadbolt.
 - 2) Mounting: Rim, surface mounted.
 - 3) Cylinder Length: As selected by Architect.
 - 4) Cylinder Diameter: Not greater than 1-1/8-inches.
 - 5) Material and Finish: Bright Chromium Plated.
 - b. Storage & Vault Cabinet Door Lock (MW02 & MW13): Cabinet lock and lock plug for out swing door application.
 - 1) Latch: Deadbolt.
 - 2) Mounting: Rim, surface mounted.
 - 3) Lock Plug Finish: Satin Nickel.
 - c. Printer Cabinet Draw Lock (MW01): Cabinet lock and lock plug for out swing door application.
 - 1) Latch: Deadbolt.
 - 2) Mounting: Rim, surface mounted.
 - 3) Lock Plug Finish: Satin Nickel.
 - d. Multiple Cabinet Drawers Gang Lock (MW11): Front mounted gang lock with lock plug.
- K. Folding "L" Brackets: BHMA A156.9, zinc coated steel, 16-inch deep folding bracket.
- L. Grommets for Cable Passage through Countertops: 3-inch OD, molded-plastic grommets and matching plastic caps with slot for wire passage.
 1. Colors:
 - a. Black: For countertop finishes PL-5 and PL-6.
 - b. White: For countertop finishes PL-7.
- M. Exposed Hardware Finishes: Complying with BHMA A156.18 for BHMA finish number indicated.
 1. Bright Brass, Clear Coated: BHMA 605 for brass base; BHMA 632 for steel base.
 2. Bright Chromium Plated: BHMA 625 for brass or bronze base; BHMA 651 for steel base.
 3. Anodized Dull Aluminum: BHMA 628 for aluminum base.
 4. Satin Stainless Steel: BHMA 630 for stainless steel base.
 5. Zinc Plated with Clear Chromate Seal: BHMA 663 for steel base.

2.4 INSTALLATION MATERIALS

- A. Furring, Blocking, Shims, and Nailers: Softwood or hardwood lumber, kiln dried to less than 15 percent moisture content.
 - 1. Fire-Retardant Treatment: Complying with requirements; provide where indicated.
- B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide nonferrous-metal or hot-dip galvanized anchors and inserts on inside face of exterior walls and elsewhere as required for corrosion resistance. Provide toothed-steel or lead expansion sleeves for drilled-in-place anchors.

2.5 MISCELLANEOUS MATERIALS

- A. Adhesives, General: Do not use adhesives that contain urea formaldehyde.
- B. VOC Limits for Installation Adhesives and Glues: Use installation adhesives that comply with the following limits for VOC content when calculated according to 40 CFR 59, Subpart D (EPA Method 24):
 - 1. Wood Glues: Not more than 30 g/L.
 - 2. Contact Adhesive: Not more than 80 g/L.
- C. Adhesive for Bonding Plastic Laminate: As recommended by laminate manufacturer for use indicated.
 - 1. Adhesives
 - a. For Laminating Surfaces: Melamine, phenol-resin, or resorcinal-resin complying with FS MMM-A-181; type, grade and class best suited for the purpose.
 - b. Wet Areas: Moisture resistant complying with FS MMM-A-125, Type II, or MMM-A-188, Type I, II or III; type best suited for the purpose.
 - 2. Adhesive for Bonding Edges: Hot-melt adhesive or adhesive specified above for faces.

2.6 FABRICATION

- A. General: Complete fabrication to maximum extent possible before shipment to Project site. Where necessary for fitting at site, provide allowance for scribing, trimming, and fitting.
- B. Wood Moisture Content: Comply with requirements of referenced quality standard for wood moisture content in relation to ambient relative humidity during fabrication and in installation areas.
- C. Sand fire-retardant-treated wood lightly to remove raised grain on exposed surfaces before fabrication.
- D. Complete fabrication, including assembly, finishing, and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for

shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.

1. Notify the Architect seven days in advance of the dates and times woodwork fabrication will be complete.
2. Trial fit assemblies at fabrication shop that cannot be shipped completely assembled. Install dowels, screws, bolted connectors, and other fastening devices that can be removed after trial fitting. Verify that various parts fit as intended and check measurements of assemblies against field measurements indicated on Shop Drawings before disassembling for shipment.

E. Shop-cut openings to maximum extent possible to receive hardware, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

1. Seal edges of openings in countertops with a coat of varnish.

2.7 INTERIOR STANDING AND RUNNING TRIM FOR OPAQUE FINISH

- A. General: Complying with AWS Sections 3 and 6, fabricated from solid hardwood with scarfed joints, profiles as indicated, finishes as indicated.
- B. Wood Species: Any closed-grain hardwood.
- C. Backout or groove backs of flat trim members and kerf backs of other wide, flat members, except for members with ends exposed in finished work.
- D. Assemble casings in plant except where limitations of access to place of installation require field assembly.

2.8 PLASTIC-LAMINATE CABINETS AND CASEWORK

- A. AWI Type of Cabinet Construction: As indicated on Drawings.
- B. Laminate Cladding for Exposed Surfaces: High-pressure decorative laminate complying with the following requirements:
 1. Horizontal Surfaces Other Than Tops: Grade HGS.
 2. Postformed Surfaces: Grade HGP.
 3. Vertical Surfaces: Grade HGS.
 4. Edges: Grade HGS.
- C. Materials for Semiexposed Surfaces:
 1. Surfaces Other Than Drawer Bodies: High-pressure decorative laminate, Grade VGS.
 - a. Edges of Plastic-Laminate Shelves: PVC tape, 0.018-inch minimum thickness, matching laminate in color, pattern, and finish.
 - b. For semiexposed backs of panels with exposed plastic-laminate surfaces, provide surface of high-pressure decorative laminate, Grade VGS.

- D. Colors, Patterns, and Finishes: Refer to "Finish Schedule" located on Drawings for color, pattern, and finish selections.

2.9 PLASTIC-LAMINATE COUNTERTOPS

- A. General: Comply with AWS Section 11 and as follows.
- B. High-Pressure Decorative Laminate Grade: HGS.
- C. Colors, Patterns, and Finishes: Refer to "Finish Schedule" located on Drawings for color, pattern, and finish selections.
- D. Edge Treatment: As indicated on Drawings.
- E. Core Material: Particleboard or medium-density fiberboard.

2.10 CLOSET AND UTILITY SHELVING

- A. General: Comply with AWS Section 10 and as follows.
- B. Shelf Material: 3/4-inch, medium density particle board where indicated for plastic laminate veneer-faced panel product with veneer edge banding, unless otherwise indicated.
 - 1. Color: As indicated on Drawings.

2.11 INTERIOR FRAMES AND JAMBS FOR OPAQUE FINISH

- A. Frames and sidelights shall be constructed in accordance with AWS requirements for interior standards, grade as indicated, provided in sizes as shown. In addition, comply with the following:
 - 1. Construct in accordance with AWS Sections 3, 6, and 12.
 - 2. Frames shall be provided in single piece lengths of solid stock hardwood lumber. Form frames with dados or rabbeted joints, plant assembled for paint finish.
 - 3. Fabricate subframing from solid lumber stock as hereinbefore specified; fire retardant treated.
 - 4. Wood Beads for Light Openings: Manufacturer's standard flush designed, solid wood, rectangular shaped, back beveled or quirked, beads matching veneer species of door faces. Include glazing compounds or tapes sized for back bevel or quirk provided. Include finish nails for removable stops.

2.12 SHOP FINISHING

- A. Finish architectural woodwork at fabrication shop. Defer only final touchup, cleaning, and polishing until after installation.
- B. Priming of interior architectural woodwork with field applied opaque finish required to be performed at fabrication shop are specified in this Section. Refer to Division 09 "Interior Painting" for finishing opaque finished architectural woodwork.

- C. Preparation for Finishing: Comply with referenced quality standard for sanding, filling countersunk fasteners, sealing concealed surfaces, and similar preparations for finishing architectural woodwork, as applicable to each unit of work.
 - 1. Backpriming: Apply one coat of sealer or primer, compatible with finish coats, to concealed surfaces of woodwork. Apply two coats to back of paneling and to end-grain surfaces. Concealed surfaces of plastic-laminate-clad woodwork do not require backpriming when surfaced with plastic laminate, backing paper, or thermoset decorative overlay.
- D. Opaque Finish: Comply with requirements indicated below for grade, finish system, color, effect, and sheen, with sheen measured on 60-degree gloss meter per ASTM D 523.
 - 1. Grade: Custom.
 - 2. AWS System 5: Conversion varnish, unless otherwise indicated.
 - 3. Color: Refer to "Finish Schedule" located on Drawings for color selection.
 - 4. Sheen: Refer to "Finish Schedule" located on Drawings for sheen selection.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Condition woodwork to average prevailing humidity conditions in installation areas and examine and complete work as required, including removal of packing and backpriming before installation.
- B. Quality Standard: Install woodwork to comply with requirements of the AWS for the same grade specified in this Section for type of woodwork involved.
- C. Install woodwork level, plumb, true, and straight to a tolerance of 1/8 inch in 96 inches. Shim as required with concealed shims.
- D. Scribe and cut woodwork to fit adjoining work, and refinish cut surfaces and repair damaged finish at cuts.
- E. Anchor woodwork to anchors or blocking built in or directly attached to substrates. Secure with countersunk, concealed fasteners and blind nailing as required for complete installation. Use fine finishing nails for exposed fastening, countersunk and filled flush with woodwork and matching final finish if transparent finish is indicated.
- F. Standing and Running Trim: Install with minimum number of joints possible, using full-length pieces (from maximum length of lumber available) to greatest extent possible. Do not use pieces less than 96 inches long, except where shorter single-length pieces are necessary. Scarf running joints and stagger in adjacent and related members.
 - 1. Fill gaps, if any, between top of base and wall with plastic wood filler, sand smooth, and finish same as wood base, if finished.

- G. Cabinets: Install cabinets as indicated on Drawings with no more than 1/8 inch in 96-inch sag, bow, or other variation from a straight line.
 - 1. Install plastic glass to comply with applicable requirements in Division 08 Section "Plastic Glazing" and in GANA's "Glazing Manual."
 - 2. Fasten wall cabinets through back, near top and bottom, at ends and not more than 16 inches o.c. with No. 10 wafer-head sheet metal screws through metal backing or metal framing behind wall finish.
- H. Countertops: Anchor securely by screwing through corner blocks of base cabinets or other supports into underside of countertop. Calk space between backsplash and wall with sealant specified in Division 07 Section "Joint Sealants."
 - 1. Align adjacent counter top materials and form seams to comply with manufacturer's written recommendations using adhesive in color to match countertop. Carefully dress joints smooth, remove surface scratches, and clean entire surface.
 - 2. Install countertops with no more than 1/8 inch in 96-inch sag, bow, or other variation from a straight line.
 - a. Cut shelf cleats at ends of shelves about 1/2 inch less than width of countertops and sand exposed ends smooth.
 - b. Install shelf cleats by fastening to framing or backing with finish nails or trim screws, set below face and filled. Space fasteners not more than 16 inches o.c. Use 2 fasteners at each framing member or fastener location for cleats 4 inches nominal in width and wider.
 - 1) Apply a bead of multipurpose construction adhesive to back of shelf cleats right before installing. Remove adhesive that is squeezed out immediately after fastening shelf cleats in place.
 - c. Cut countertops to neatly fit openings with only enough gap to allow countertops to be removed and reinstalled. Install countertops, fully seated on cleats, brackets, and supports.
 - d. Fasten countertops to cleats with finish nails or trim screws, set flush.
- I. Shelving and Hardware Installation: As follows:
 - 1. Install brackets and hardware according to manufacturer's written instructions, spaced not more than 36 inches o.c. Fasten to framing members, blocking, or metal backing, or use toggle bolts or hollow wall anchors.
- J. Touch up finishing work specified in this Section after installation of woodwork. Fill nail holes with matching filler where exposed.

3.2 ADJUSTING AND CLEANING

- A. Repair damaged and defective woodwork, where possible, to eliminate functional and visual defects; where not possible to repair, replace woodwork. Adjust joinery for uniform appearance.
- B. Clean woodwork on exposed and semiexposed surfaces. Touch up shop-applied finishes to restore damaged or soiled areas.

Gensler

057.7202.950

Bank of America / BAC Performance / Bulletin #03-2020 / 09-14-20

January 22, 2021
Issue for Construction

Bank of America
BAC Centerville GU
Centerville, UT

END OF SECTION 06 40 23

SECTION 06 64 00 - PLASTIC PANELING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Plastic sheet paneling.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.

C. Samples: For plastic paneling and trim accessories, in manufacturer's standard sizes.

1.3 QUALITY ASSURANCE

A. Testing Agency: Acceptable to authorities having jurisdiction.

1.4 PROJECT CONDITIONS

- A. Environmental Limitations: Do not deliver or install plastic paneling until spaces are enclosed and weathertight and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Source Limitations: Obtain plastic paneling and trim accessories from single manufacturer.

2.2 PLASTIC SHEET PANELING

- A. Glass-Fiber-Reinforced Plastic Paneling (WC-2): Gelcoat-finished, glass-fiber-reinforced plastic panels complying with ASTM D 5319. Comply with building code flame spread Class-A.
 - 1. Nominal Thickness: Not less than 0.09 inch.
 - 2. Size: 48 inches by 96 inches, unless otherwise indicated.
 - 3. Surface Finish: Molded pebble texture.
 - 4. Color: White.
 - 5. Surface-Burning Characteristics: As follows when tested by a qualified testing agency according to ASTM E 84. Identify products with appropriate markings of applicable testing agency.
 - a. Flame-Spread Index: 25 or less.
 - b. Smoke-Developed Index: 450 or less.

2.3 ACCESSORIES

- A. Trim Accessories: Manufacturer's standard one-piece vinyl extrusions designed to retain and cover edges of panels. Provide division bars, inside corners, outside corners, and caps as needed to conceal edges.
 - 1. Color: Match panels.
- B. Adhesive: As recommended by plastic paneling manufacturer and with a VOC content of 50 g/L or less.
- C. Sealant: Mildew-resistant, single-component, neutral-curing or acid-curing silicone sealant recommended by plastic paneling manufacturer and complying with requirements in Division 07 Section "Joint Sealants."
 - 1. Sealant shall have a VOC content of 250 g/L or less.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean substrates of substances that could impair adhesive bond, including oil, grease, dirt, and dust.

- B. Condition panels by unpacking and placing in installation space before installation according to manufacturer's written recommendations.
- C. Lay out paneling before installing. Locate panel joints to provide equal panels at ends of walls not less than half the width of full panels.
 - 1. Mark plumb lines on substrate at trim accessory locations for accurate installation.
 - 2. Locate trim accessories to allow clearance at panel edges according to manufacturer's written instructions.

3.3 INSTALLATION

- A. Install plastic paneling according to manufacturer's written instructions.
- B. Install panels in a full spread of adhesive.
- C. Install trim accessories with adhesive. Do not fasten through panels.
- D. Fill grooves in trim accessories with sealant before installing panels, and bed inside corner trim in a bead of sealant.
- E. Maintain uniform space between panels and wall fixtures. Fill space with sealant.
- F. Remove excess sealant and smears as paneling is installed. Clean with solvent recommended by sealant manufacturer and then wipe with clean dry cloths until no residue remains.

END OF SECTION 06 64 00

SECTION 07 13 26 - SELF-ADHERING SHEET WATERPROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Modified bituminous sheet waterproofing.
2. Protection course.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, and tested physical and performance properties of waterproofing.
2. Include manufacturer's written instructions for evaluating, preparing, and treating substrate.

LEED Documentation Submittals:

3. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. Regional Materials Information.
 - d. LEED Materials and Resources Calculator.

B. Samples: For each exposed product and for each color and texture specified, including the following products:

1. 8-by-8-inch square of waterproofing and flashing sheet.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Sample Warranties: For special warranties.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by waterproofing manufacturer.

1.5 FIELD CONDITIONS

- A. Environmental Limitations: Apply waterproofing within the range of ambient and substrate temperatures recommended in writing by waterproofing manufacturer. Do not apply waterproofing to a damp or wet substrate.
 - 1. Do not apply waterproofing in snow, rain, fog, or mist.
- B. Maintain adequate ventilation during preparation and application of waterproofing materials.

1.6 WARRANTY

- A. Manufacturer's Warranty:
 - 1. Waterproofing Warranty: Manufacturer agrees to furnish replacement waterproofing material for waterproofing that does not comply with requirements or that fails to remain watertight within specified warranty period.
 - a. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Source Limitations for Waterproofing System: Obtain waterproofing materials, and protection course from single source from single manufacturer.

2.2 MODIFIED BITUMINOUS SHEET WATERPROOFING

- A. Modified Bituminous Sheet Waterproofing: Minimum 60-mil nominal thickness, self-adhering sheet consisting of 56 mils of rubberized asphalt laminated on one side to a 4-mil- thick, polyethylene-film reinforcement, and with release liner on adhesive side; formulated for application with primer or surface conditioner that complies with VOC limits of authorities having jurisdiction.
 - 1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. Carlisle Coating & Waterproofing Inc.; "CCW MiraDRI 860/861."
 - b. GCP Applied Technologies Inc.; "Bituthene."
 - c. Henry Company; "Blueskin WP 200."

d. W.R. Meadows, Inc.; “Mel-Rol.”

2. Physical Properties:

- a. Tensile Strength, Membrane: 250 psi minimum; ASTM D412, Die C, modified.
- b. Ultimate Elongation: 300 percent minimum; ASTM D412, Die C, modified.
- c. Low-Temperature Flexibility: Pass at minus 20 deg F; ASTM D1970/D1970M.
- d. Crack Cycling: Unaffected after 100 cycles of 1/8-inch movement; ASTM C836/C836M.
- e. Puncture Resistance: 40 lbf minimum; ASTM E154/E154M.
- f. Water Absorption: 0.2 percent weight-gain maximum after 48-hour immersion at 70 deg F; ASTM D570.
- g. Water Vapor Permeance: 0.05 perm maximum; ASTM E96/E96M, Water Method.
- h. Hydrostatic-Head Resistance: 200 feet minimum; ASTM D5385.

3. Sheet Strips: Self-adhering, rubberized-asphalt strips of same material and thickness as sheet waterproofing.

2.3 AUXILIARY MATERIALS

- A. Furnish auxiliary materials recommended by waterproofing manufacturer for intended use and compatible with sheet waterproofing.
 - 1. Furnish liquid-type auxiliary materials that comply with VOC limits of authorities having jurisdiction.
- B. Primer: Liquid waterborne primer recommended for substrate by sheet waterproofing material manufacturer.
- C. Liquid Membrane: Elastomeric, two-component liquid, cold fluid applied, of trowel grade or low viscosity.
- D. Substrate Patching Membrane: Low-viscosity, two-component, modified asphalt coating.
- E. Metal Termination Bars: Aluminum bars, approximately 1 by 1/8 inch, predrilled at 9-inch centers.
- F. Protection Course, Asphaltic: ASTM D6506, semirigid sheets of fiberglass or mineral-reinforced-asphaltic core, pressure laminated between two asphalt-saturated fibrous liners and as follows:
 - 1. Thickness: Nominal 1/8 inch for vertical applications; 1/4 inch elsewhere.
 - 2. Adhesive: Rubber-based solvent type recommended by waterproofing manufacturer for protection course type.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements and other conditions affecting performance of waterproofing.
 - 1. Verify that concrete has cured and aged for minimum time period recommended in writing by waterproofing manufacturer.
 - 2. Verify that substrate is visibly dry and within the moisture limits recommended in writing by manufacturer. Test for capillary moisture by plastic sheet method according to ASTM D4263.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean, prepare, and treat substrates according to manufacturer's written instructions. Provide clean, dust-free, and dry substrates for waterproofing application.
- B. Mask off adjoining surfaces not receiving waterproofing to prevent spillage and overspray affecting other construction.
- C. Remove grease, oil, bitumen, form-release agents, paints, curing compounds, and other penetrating contaminants or film-forming coatings from concrete.
- D. Remove fins, ridges, mortar, and other projections.
- E. Fill form tie holes, honeycomb, aggregate pockets, holes, and other voids.
- F. Prepare, fill, prime, and treat joints and cracks in substrates. Remove dust and dirt from joints and cracks according to ASTM D4258.
- G. Bridge and cover isolation joints, expansion joints, and discontinuous deck-to-wall and deck-to-deck joints with overlapping sheet strips of widths according to manufacturer's written instructions.
 - 1. Invert and loosely lay first sheet strip over center of joint. Firmly adhere second sheet strip to first and overlap to substrate.
- H. Corners: Prepare, prime, and treat inside and outside corners in accordance with manufacturer's instructions.
- I. Prepare, treat, and seal vertical and horizontal surfaces at terminations and penetrations through waterproofing and at drains and protrusions.

3.3 INSTALLATION OF MODIFIED BITUMINOUS SHEET WATERPROOFING

- A. Install modified bituminous sheets according to waterproofing manufacturer's written instructions.
- B. Apply primer to substrates at required rate and allow it to dry. Limit priming to areas that will be covered by sheet waterproofing in same day. Reprime areas exposed for more than 24 hours.
- C. Apply and firmly adhere sheets over area to receive waterproofing. Accurately align sheets and maintain uniform 2-1/2-inch- minimum lap widths and end laps. Overlap and seal seams, and stagger end laps to ensure watertight installation.
 - 1. When ambient and substrate temperatures range between 25 and 40 deg F, install self-adhering, modified bituminous sheets produced for low-temperature application. Do not use low-temperature sheets if ambient or substrate temperature is higher than 60 deg F.
- D. Apply continuous sheets over already-installed sheet strips, bridging substrate cracks, construction, and contraction joints.
- E. Seal edges of sheet waterproofing terminations with mastic.
- F. Install sheet waterproofing and auxiliary materials to tie into adjacent waterproofing.
- G. Repair tears, voids, and lapped seams in waterproofing not complying with requirements. Slit and flatten fishmouths and blisters. Patch with sheet waterproofing extending 6 inches beyond repaired areas in all directions.
- H. Immediately install protection course with butted joints over waterproofing membrane.

3.4 PROTECTION, REPAIR, AND CLEANING

- A. Protect waterproofing from damage and wear during remainder of construction period.
- B. Correct deficiencies in or remove waterproofing that does not comply with requirements; repair substrates, reapply waterproofing, and repair sheet flashings.
- C. Clean spillage and soiling from adjacent construction using cleaning agents and procedures recommended in writing by manufacturer of affected construction.

END OF SECTION 07 13 26

SECTION 07 21 00 - THERMAL INSULATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Extruded polystyrene foam-plastic board insulation.
2. Polyisocyanurate foam-plastic board insulation.
3. Mineral-wool blanket insulation.

B. Related Sections

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements

1.2 ACTION SUBMITTALS

A. Product Data: For the following:

1. Extruded polystyrene foam-plastic board insulation.
2. Polyisocyanurate foam-plastic board insulation.
3. Mineral-wool blanket insulation.

B. LEED Submittals:

1. Comply with submittal requirements in Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet
 - b. Low Emitting Materials Information – VOC content and Laboratory Testing or GreenGuard Gold Certificates
 - c. LEED Materials and Resources Calculator
 - d. Recycled Content: For products having recycled content, documentation indicating percentages by weight of postconsumer and preconsumer recycled content. Include statement indicating cost for each product having recycled content.

1.3 INFORMATIONAL SUBMITTALS

A. Installer's Certification: Listing type, manufacturer, and R-value of insulation installed in each element of the building thermal envelope.

1. Sign, date, and post the certification in a conspicuous location on Project site.

B. Product Test Reports: For each product, for tests performed by a qualified testing agency.

- C. Research Reports: For foam-plastic insulation, from ICC-ES.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Protect insulation materials from physical damage and from deterioration due to moisture, soiling, and other sources. Store inside and in a dry location. Comply with manufacturer's written instructions for handling, storing, and protecting during installation.
- B. Protect foam-plastic board insulation as follows:
 - 1. Do not expose to sunlight except to necessary extent for period of installation and concealment.
 - 2. Protect against ignition at all times. Do not deliver foam-plastic board materials to Project site until just before installation time.
 - 3. Quickly complete installation and concealment of foam-plastic board insulation in each area of construction.

PART 2 - PRODUCTS

2.1 EXTRUDED POLYSTYRENE FOAM-PLASTIC BOARD INSULATION

- A. Extruded Polystyrene Board Insulation, Type VII: ASTM C578, Type VII, 60-psi minimum compressive strength.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. DiversiFoam Products.
 - b. Dow Chemical Company (The).
 - c. Owens Corning.
 - 2. Thickness: 2 inches.
 - 3. Edge Treatment: Square edge.
 - 4. Flame-Spread Index: Not more than 25 when tested in accordance with ASTM E84.
 - 5. Smoke-Developed Index: Not more than 450 when tested in accordance with ASTM E84.
 - 6. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches and wider in width.
 - 1. Application: Use board insulation at below-grade applications.

2.2 POLYISOCYANURATE FOAM-PLASTIC BOARD INSULATION

- A. Polyisocyanurate Board Insulation, Foil Faced: ASTM C1289, foil faced, Type I, Class 1 or 2.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Dow Chemical Company (The).
 - b. Johns Manville; a Berkshire Hathaway company.
 - c. Rmax, Inc.
2. Thickness: 3-inch thick with a minimum R-value of not less than 18.
3. Edge Treatment: Square edge.
4. Fire Propagation Characteristics: Passes NFPA 285 testing as part of an approved assembly.
5. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches and wider in width.
6. Factory Score: Factory score board insulation for use in field cutting and fitting between Z-shaped furring members. Scoring shall occur on both face surfaces of board insulation, spaced at 16 inches o.c. and of depth as recommended by insulation manufacture.
7. Application: Use board insulation at cavity wall assemblies.

2.3 MINERAL-WOOL BLANKET INSULATION

- A. Mineral-Wool Blanket Insulation, Unfaced: ASTM C665, Type I (blankets without membrane facing); consisting of fibers; passing ASTM E136 for combustion characteristics.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Johns Manville; a Berkshire Hathaway company.
 - b. Rockwool International.
 - c. Thermafiber, Inc.; an Owens Corning company.
 2. Flame-Spread Index: Not more than 25 when tested in accordance with ASTM E84.
 3. Smoke-Developed Index: Not more than 50 when tested in accordance with ASTM E84.
 4. Labeling: Provide identification of mark indicating R-value of each piece of insulation 12 inches and wider in width.
 5. Application: Use blanket insulation in framed constructions.

2.4 INSULATION FASTENERS

- A. Insulation-Retaining Washers and Fasteners: Self-locking washers of sized as required to hold insulation securely in place, but not less than 1-1/2 inches square or in diameter. Provide manufacturer's standard polymer or other corrosion- protective coated steel screw fasteners for anchoring to metal framing. Fastener length and size based on insulation thickness.
 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

- a. Gemco
- b. Wind-Lock.

2.5 ACCESSORIES

A. Insulation for Miscellaneous Voids:

- 1. Spray Polyurethane Foam Insulation: ASTM C1029, Type II, closed cell, with maximum flame-spread and smoke-developed indexes of 75 and 450, respectively, per ASTM E84.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Clean substrates of substances that are harmful to insulation, including removing projections capable of puncturing insulation or vapor retarders, or that interfere with insulation attachment.

3.2 INSTALLATION, GENERAL

- A. Comply with insulation manufacturer's written instructions applicable to products and applications.
- B. Install insulation that is undamaged, dry, and unsoiled and that has not been left exposed to ice, rain, or snow at any time.
- C. Install insulation with manufacturer's R-value label exposed after insulation is installed.
- D. Extend insulation to envelop entire area to be insulated. Fit tightly around obstructions and fill voids with insulation. Remove projections that interfere with placement.
- E. Provide sizes to fit applications and selected from manufacturer's standard thicknesses, widths, and lengths. Apply single layer of insulation units unless multiple layers are otherwise shown or required to make up total thickness or to achieve R-value.

3.3 INSTALLATION OF SLAB INSULATION

- A. On vertical slab edge and foundation surfaces, set insulation units using manufacturer's recommended adhesive according to manufacturer's written instructions.
 - 1. If not otherwise indicated, extend insulation a minimum of 36 inches below exterior grade line.
- B. On horizontal surfaces, loosely lay insulation units according to manufacturer's written instructions. Stagger end joints and tightly abut insulation units.

1. If not otherwise indicated, extend insulation a minimum of 36 inches in from exterior walls.

3.4 INSTALLATION OF CAVITY-WALL INSULATION

- A. Foam-Plastic Board Insulation: Attach board insulation in the vertical orientation to substrate with Z furring spaced at 16 inches o.c., and as recommended by manufacturer. Fit courses of insulation between furring members and other obstructions, with horizontal edges butted tightly.
 1. Refer to Division 05 Section "Cold-Formed Metal Framing" Z-furring and additional requirements.
- B. Fasteners: Fasten foam board insulation to metal framing members with insulation-retaining washers and fasteners according to anchor manufacturer's written instructions. Space anchors according to insulation manufacturer's written instructions for insulation type, thickness, and application indicated.

3.5 INSTALLATION OF INSULATION IN FRAMED CONSTRUCTION

- A. Blanket Insulation: Install in cavities formed by framing members according to the following requirements:
 1. Use insulation widths and lengths that fill the cavities formed by framing members. If more than one length is required to fill the cavities, provide lengths that will produce a snug fit between ends.
 2. Place insulation in cavities formed by framing members to produce a friction fit between edges of insulation and adjoining framing members.
 3. Maintain 3-inch clearance of insulation around recessed lighting fixtures not rated for or protected from contact with insulation.
 4. For metal-framed wall cavities where cavity heights exceed 96 inches, support unfaced blankets mechanically and support faced blankets by taping flanges of insulation to flanges of metal studs.
- B. Miscellaneous Voids: Install insulation in miscellaneous voids and cavity spaces where required to prevent gaps in insulation using the following materials:
 1. Spray Polyurethane Insulation: Apply according to manufacturer's written instructions.

3.6 PROTECTION

- A. Protect installed insulation from damage due to harmful weather exposures, physical abuse, and other causes.
- B. Provide temporary coverings or enclosures where insulation is subject to abuse and cannot be concealed and protected by permanent construction immediately after installation.

Gensler

057.7202.950

Bank of America / BAC Performance / Bulletin #03-2020 /09-14-20

January 22, 2021
Issue for Construction

Bank of America
BAC Centerville GU
Centerville, UT

END OF SECTION 07 21 00

SECTION 072616 - UNDER-SLAB-ON-GRADE VAPOR RETARDER

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes vapor retarder and installation accessories for installation under concrete slabs on grade.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site two weeks before start of installation of reinforced vapor retarders.
 - 1. Review vapor-retarder installation, protection, and coordination with other work.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated including installation instructions.

1.4 INFORMATIONAL SUBMITTALS

- A. Summary of test results per paragraph 9.3 of ASTM E 1745.
- B. Manufacturer's installation instructions for placement, seaming and penetration repair instructions.

1.5 QUALITY ASSURANCE

- A. Provide vapor retarder and accessories from a single source and single manufacturer. Provide accessories manufactured or approved by vapor retarder manufacturer for application indicated.
- B. All mandatory ASTM E 1745 testing must be performed on a single production roll per ASTM E 1745 Section 8.1.
- C. Coordination: Schedule work such that membrane will not be left exposed to weather for longer than that recommended by the manufacturer.

1.6 DELIVERY, STORAGE AND HANDLING

- A. Deliver materials in labeled packages. Store and handle in strict compliance with manufacturer's instructions. Protect from damage from weather, excessive temperature and construction operations. Remove and dispose of damaged material in accordance with applicable regulations.

PART 2 - PRODUCTS

PART 3 - EXECUTION

3.1 PREPARATION

- A. Examine areas to receive vapor retarders. Notify Architect if areas are not acceptable. Do not begin installation until unacceptable conditions have been corrected.
- B. Ensure that subsoil is smooth, level and compacted with no sharp edges.
 - 1. Level and compact base material.
- C. Ensure that there is no moisture entrapment by vapor retarder due to rainfall or ground water intrusion.

3.2 INSTALLATION

- A. Install vapor retarder in accordance ASTM E 1643 and manufacturer's written instructions.
 - 1. Install vapor retarders continuously at locations under slab. Ensure there are no discontinuities in vapor retarder at seams or penetrations.
 - 2. Unroll vapor retarder with the longest dimension parallel with the direction of the concrete placement and face laps away from the expected direction of the placement whenever possible.
 - 3. Extend vapor retarder over footings and grade beams to a distance acceptable to the structural engineer or stop at impediments such as dowels and waterstops.
 - 4. Seal vapor retarder to foundation wall, grade beam, or slab at an elevation consistent with the top of the slab or terminate at impediments such as waterstops or dowels.
 - 5. Overlap joints 6 inches and seal with manufacturer's tape.
 - 6. Apply tape to a clean and dry vapor barrier.
 - 7. Seal all penetrations with manufactured or field-fabricated boots and with tape according to manufacturer's guidelines. Unsealed penetrations are not allowed.

- 8. Immediately repair damaged areas by cutting patches of vapor retarder, overlapping damaged area 6 inches and taping all sides with tape.
- B. Bituminous Vapor Retarders: Place, protect, and repair bituminous vapor retarder according to manufacturer's written instructions.

3.3 PROTECTION

- A. Protect vapor retarders from damage during installation of reinforcing steel and utilities and during placement of concrete slab.

END OF SECTION 072616

SECTION 072726 - FLUID-APPLIED MEMBRANE AIR BARRIERS

PART 1 - GENERAL

1.1 ACTION SUBMITTALS

- A. Product Data: For each type of product.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Low-Emitting Materials: Products shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

2.2 PERFORMANCE REQUIREMENTS

- A. Air-Barrier Performance: Air-barrier assembly and seals with adjacent construction shall be capable of performing as a continuous air barrier and as a liquid-water drainage plane flashed to discharge to the exterior incidental condensation or water penetration. Air-barrier assemblies shall be capable of accommodating substrate movement and of sealing substrate expansion and control joints, construction material changes, penetrations, and transitions at perimeter conditions without deterioration and air leakage exceeding specified limits.
- B. Air-Barrier Assembly Air Leakage: Maximum 0.04 cfm/sq. ft. of surface area at 1.57 lbf/sq. ft., when tested according to ASTM E 2357.

PART 3 - EXECUTION

3.1 SURFACE PREPARATION

- A. Clean, prepare, treat, fill, and seal substrate and joints and cracks in substrate according to manufacturer's written instructions and details. Provide clean, dust-free, and dry substrate for air-barrier application.
- B. Mask off adjoining surfaces not covered by air barrier to prevent spillage and overspray affecting other construction.

- C. Remove fins, ridges, mortar, and other projections and fill honeycomb, aggregate pockets, holes, and other voids in concrete with substrate-patching material.
- D. Remove excess mortar from masonry ties, shelf angles, and other obstructions.
- E. At changes in substrate plane, apply sealant or termination mastic beads at sharp corners and edges to form a smooth transition from one plane to another.
- F. Bridge isolation joints expansion joints and discontinuous wall-to-wall, deck-to-wall, and deck-to-deck joints with air-barrier accessory material that accommodates joint movement according to manufacturer's written instructions and details.

3.2 INSTALLATION

- A. Install materials according to air-barrier manufacturer's written instructions and details to form a seal with adjacent construction and ensure continuity of air and water barrier.
 - 1. Coordinate the installation of air barrier with installation of roofing membrane and base flashing to ensure continuity of air barrier with roofing membrane.
 - 2. Install transition strip on roofing membrane or base flashing so that a minimum of 3 inches of coverage is achieved over each substrate.
 - 3. Unless manufacturer recommends in writing against priming, apply primer to substrates at required rate and allow it to dry.
 - 4. Apply primer to substrates at required rate and allow it to dry. Limit priming to areas that will be covered by air-barrier material on same day. Reprime areas exposed for more than 24 hours.
- B. Connect and seal exterior wall air-barrier material continuously to roofing-membrane air barrier, concrete below-grade structures, floor-to-floor construction, exterior glazing and window systems, glazed curtain-wall systems, storefront systems, exterior louvers, exterior door framing, and other construction used in exterior wall openings, using accessory materials.
- C. Wall Openings: Prime concealed, perimeter frame surfaces of windows, curtain walls, storefronts, and doors. Apply transition strip so that a minimum of 3 inches of coverage is achieved over each substrate. Maintain 3 inches of full contact over firm bearing to perimeter frames, with not less than 1 inch of full contact.
- D. Repair punctures, voids, and deficient lapped seams in strips and transition strips. Slit and flatten fishmouths and blisters. Patch with transition strips extending 6 inches beyond repaired areas in strip direction.
- E. Do not cover air barrier until it has been tested and inspected by testing agency.
- F. Correct deficiencies in or remove air barrier that does not comply with requirements; repair substrates and reapply air-barrier components.

3.3 CLEANING AND PROTECTION

- A. Protect air-barrier system from damage during application and remainder of construction period, according to manufacturer's written instructions.
- B. Remove masking materials after installation.

END OF SECTION 072726

SECTION 07 42 13.13 - FORMED METAL WALL PANELS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Concealed-fastener, lap-seam metal wall panels.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of panel and accessory.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.
 - d. LEED Materials and Resources Calculator.

C. Shop Drawings:

1. Include fabrication and installation layouts of metal panels; details of edge conditions, joints, panel profiles, corners, anchorages, attachment system, trim, flashings, closures, and accessories; and special details.
2. Accessories: Include details of the flashing, trim, and anchorage systems, at a scale of not less than 1-1/2 inches per 12 inches.

D. Samples for Verification: For each type of exposed finish, prepared on Samples of size indicated below:

1. Metal Panels: 12 inches long by actual panel width. Include fasteners, closures, and other metal panel accessories.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Test Reports: For each product, for tests performed by a qualified testing agency.
- C. Sample Warranties: For special warranties.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For metal panels to include in maintenance manuals.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.
- B. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for fabrication and installation.
 1. Build mockup of typical metal panel assembly as shown on Drawings, including corner, supports, attachments, and accessories.
 2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver components, metal panels, and other manufactured items so as not to be damaged or deformed. Package metal panels for protection during transportation and handling.
- B. Unload, store, and erect metal panels in a manner to prevent bending, warping, twisting, and surface damage.
- C. Stack metal panels horizontally on platforms or pallets, covered with suitable weathertight and ventilated covering. Store metal panels to ensure dryness, with positive slope for drainage of water. Do not store metal panels in contact with other materials that might cause staining, denting, or other surface damage.
- D. Retain strippable protective covering on metal panels during installation.

1.8 FIELD CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit assembly of metal panels to be performed according to manufacturers' written instructions and warranty requirements.
- B. Field Measurements: Verify locations of structural members and wall opening dimensions by field measurements before panel fabrication and indicate measurements on Shop Drawings.
 - 1. Coordinate wall construction to ensure that actual building dimensions, locations of structural members, and openings correspond to established dimensions. Field trimming of panels will not be permitted.

1.9 COORDINATION

- A. Coordinate metal panel installation with rain drainage work, flashing, trim, construction of soffits, and other adjoining work to provide a leakproof, secure, and noncorrosive installation.

1.10 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of metal panel systems that fail in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Structural failures including rupturing, cracking, or puncturing.
 - b. Deterioration of metals and other materials beyond normal weathering.
 - 2. Warranty Period: Two years from date of Substantial Completion.
- B. Special Warranty on Panel Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.
 - 1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:
 - a. Color fading more than 5 Delta E units when tested according to ASTM D2244.
 - b. Chalking in excess of a No. 8 rating when tested according to ASTM D4214.
 - c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.
 - 2. Finish Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Recycled Content: Postconsumer recycled content not less than 20 percent.
- B. Structural Performance: Provide metal panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E1592:
 - 1. Wind Loads: As indicated on Drawings.
 - 2. Other Design Loads: As indicated on Drawings.
 - 3. Deflection Limits: Engineer panel assemblies to withstand test pressures with deflection no greater than 1/480 of the span and no evidence of material failure, structural distress, or permanent deformation exceeding 0.2 percent of the clear span.
 - a. Test Pressures: 150 percent of inward and outward wind-load design pressures.
- C. Air Infiltration: Air leakage of not more than 0.06 cfm/sq. ft. when tested according to ASTM E283 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft.
- D. Water Penetration under Static Pressure: No water penetration when tested according to ASTM E331 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft.
- E. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 - 1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.
- F. Fire-Resistance Ratings: Comply with ASTM E119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Indicate design designations from UL's "Fire Resistance Directory" or from the listings of another qualified testing agency.

2.2 CONCEALED-FASTENER, LAP-SEAM METAL WALL PANELS (EPS-5)

- A. Provide factory-formed metal panels designed to be field assembled by lapping and interconnecting side edges of adjacent panels and mechanically attaching through panel to supports using concealed fasteners in side laps. Include accessories required for weathertight installation.

- B. Flush-Profile, Concealed-Fastener Metal Wall Panels: Formed with vertical panel edges and a flat pan between panel edges; with flush joint between panels.
 - 1. Product: Subject to compliance with requirements, provide “Flush Reveal Wall Panel System” as manufactured by Pure + FreeForm, LLC.
 - a. Color: Roma Noce Matte
 - 2. Aluminum Sheet: Coil-coated sheet, ASTM B209, alloy as standard with manufacturer, with temper as required to suit forming operations and structural performance required.
 - a. Thickness: 0.032 inch.
 - b. Surface: Smooth, flat finish.
 - c. Exterior Finish: FEVE fluoropolymer.
 - 3. Panel Coverage: 9 inches o.c. spacing. Refer to drawings.
 - 4. Profile Depth: 1-1/8 inches, unless otherwise indicated.
 - 5. Concealed Panel Clips: Manufacturer’s standard stainless steel type.

2.3 MISCELLANEOUS MATERIALS

- A. Miscellaneous Metal Subframing and Furring: ASTM C645, cold-formed, metallic-coated steel sheet, ASTM A653/A653M, G90 coating designation or ASTM A792/A792M, Class AZ50 aluminum-zinc-alloy coating designation unless otherwise indicated. Provide manufacturer's standard sections as required for support and alignment of metal panel system.
- B. Panel Accessories: Provide components required for a complete, weathertight panel system including trim, copings, fasciae, mullions, sills, corner units, clips, flashings, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal panels unless otherwise indicated.
 - 1. Closures: Provide closures at eaves and rakes, fabricated of same metal as metal panels.
 - 2. Backing Plates: Provide metal backing plates at panel end splices, fabricated from material recommended by manufacturer.
- C. Flashing and Trim: Provide flashing and trim formed from same material as metal panels as required to seal against weather and to provide finished appearance. Locations include, but are not limited to, bases, drips, sills, jambs, corners, endwalls, framed openings, rakes, fasciae, parapet caps, soffits, reveals, and fillers. Finish flashing and trim with same finish system as adjacent metal panels.
- D. Panel Fasteners: Self-tapping screws designed to withstand design loads. Provide exposed fasteners with heads matching color of metal panels by means of plastic caps or factory-applied coating. Provide EPDM or PVC sealing washers for exposed fasteners.
- E. Panel Sealants: Provide sealant type recommended by manufacturer that are compatible with panel materials, are nonstaining, and do not damage panel finish.

1. Joint Sealant: ASTM C920; elastomeric polyurethane or silicone sealant; of type, grade, class, and use classifications required to seal joints in metal panels and remain weathertight; and as recommended in writing by metal panel manufacturer.

2.4 FABRICATION

- A. Fabricate and finish metal panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.
- B. Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of panel.
- C. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's recommendations and recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, metal, and other characteristics of item indicated.
 1. Form exposed sheet metal accessories that are without excessive oil canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.
 2. Seams for Aluminum: Fabricate nonmoving seams with flat-lock seams. Form seams and seal with epoxy seam sealer. Rivet joints for additional strength.
 3. Seams for Other Than Aluminum: Fabricate nonmoving seams in accessories with flat-lock seams. Tin edges to be seamed, form seams, and solder.
 4. Sealed Joints: Form nonexpansion, but movable, joints in metal to accommodate sealant and to comply with SMACNA standards.
 5. Conceal fasteners and expansion provisions where possible. Exposed fasteners are not allowed on faces of accessories exposed to view.
 6. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal recommended in writing by metal panel manufacturer.
 - a. Size: As recommended by SMACNA's "Architectural Sheet Metal Manual" or metal wall panel manufacturer for application but not less than thickness of metal being secured.

2.5 FINISHES

- A. Protect mechanical and painted finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

C. Aluminum Panels and Accessories:

1. FEVE Fluoropolymer: AAMA 2605. Offset gravure, direct print fluoropolymer finish containing 100 percent fluorinated ethylene vinyl ether (FEVE) resin in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, metal panel supports, and other conditions affecting performance of the Work.
 1. Examine wall framing to verify that girts, angles, channels, studs, and other structural panel support members and anchorage have been installed within alignment tolerances required by metal wall panel manufacturer.
 2. Examine wall sheathing to verify that sheathing joints are supported by framing or blocking and that installation is within flatness tolerances required by metal wall panel manufacturer.
 - a. Verify that air- or water-resistive barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.
- B. Examine roughing-in for components and systems penetrating metal panels to verify actual locations of penetrations relative to seam locations of metal panels before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Miscellaneous Supports: Install subframing, furring, and other miscellaneous panel support members and anchorages according to ASTM C754 and metal panel manufacturer's written recommendations.

3.3 INSTALLATION

- A. Install metal panels according to manufacturer's written instructions in orientation, sizes, and locations indicated. Install panels perpendicular to supports unless otherwise indicated. Anchor metal panels and other components of the Work securely in place, with provisions for thermal and structural movement.
 1. Shim or otherwise plumb substrates receiving metal panels.

2. Flash and seal metal panels at perimeter of all openings. Fasten with self-tapping screws. Do not begin installation until air- or water-resistive barriers and flashings that will be concealed by metal panels are installed.
 3. Install screw fasteners in predrilled holes.
 4. Locate and space fastenings in uniform vertical and horizontal alignment.
 5. Install flashing and trim as metal panel work proceeds.
 6. Locate panel splices over, but not attached to, structural supports. Stagger panel splices and end laps to avoid a four-panel lap splice condition.
 7. Align bottoms of metal panels and fasten with blind rivets, bolts, or self-tapping screws. Fasten flashings and trim around openings and similar elements with self-tapping screws.
 8. Provide weathertight escutcheons for pipe- and conduit-penetrating panels.
- B. Fasteners:
1. Aluminum Panels: Use aluminum or stainless steel fasteners for surfaces exposed to the exterior; use aluminum or galvanized-steel fasteners for surfaces exposed to the interior.
- C. Metal Protection: Where dissimilar metals contact each other or corrosive substrates, protect against galvanic action as recommended in writing by metal panel manufacturer.
- D. Lap-Seam Metal Panels: Fasten metal panels to supports with fasteners at each lapped joint at location and spacing recommended by manufacturer.
1. Lap ribbed or fluted sheets one full rib. Apply panels and associated items true to line for neat and weathertight enclosure.
 2. Provide metal-backed washers under heads of exposed fasteners bearing on weather side of metal panels.
 3. Locate and space exposed fasteners in uniform vertical and horizontal alignment. Use proper tools to obtain controlled uniform compression for positive seal without rupture of washer.
 4. Install screw fasteners with power tools having controlled torque adjusted to compress washer tightly without damage to washer, screw threads, or panels. Install screws in predrilled holes.
 5. Flash and seal panels with weather closures at perimeter of all openings.
- E. Watertight Installation:
1. Apply a continuous ribbon of sealant or tape to seal lapped joints of metal panels, using sealant or tape as recommend by manufacturer on side laps of nesting-type panels; and elsewhere as needed to make panels watertight.
 2. Provide sealant or tape between panels and protruding equipment, vents, and accessories.
 3. At panel splices, nest panels with minimum 6-inch end lap, sealed with sealant and fastened together by interlocking clamping plates.
- F. Accessory Installation: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.

1. Install components required for a complete metal panel system including trim, copings, corners, seam covers, flashings, sealants, gaskets, fillers, closure strips, and similar items. Provide types indicated by metal wall panel manufacturer; or, if not indicated, provide types recommended by metal panel manufacturer.
- G. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that are permanently watertight.
 1. Install exposed flashing and trim that is without buckling and tool marks, and that is true to line and levels indicated, with exposed edges folded back to form hems. Install sheet metal flashing and trim to fit substrates and achieve waterproof performance.
 2. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at a maximum of 10 feet with no joints allowed within 24 inches of corner or intersection. Where lapped expansion provisions cannot be used or would not be sufficiently waterproof, form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with mastic sealant (concealed within joints).

3.4 FIELD QUALITY CONTROL

- A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections.
- B. Water-Spray Test: After installation, test area of assembly as directed by Architect for water penetration according to AAMA 501.2.
- C. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect completed metal wall panel installation, including accessories.
- D. Remove and replace metal wall panels where tests and inspections indicate that they do not comply with specified requirements.
- E. Additional tests and inspections, at Contractor's expense, are performed to determine compliance of replaced or additional work with specified requirements.
- F. Prepare test and inspection reports.

3.5 CLEANING AND PROTECTION

- A. Remove temporary protective coverings and strippable films, if any, as metal panels are installed, unless otherwise indicated in manufacturer's written installation instructions. On completion of metal panel installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.
- B. After metal panel installation, clear weep holes and drainage channels of obstructions, dirt, and sealant.

- C. Replace metal panels that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION 07 42 13.13

SECTION 07 42 13.16 - METAL PLATE WALL PANELS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes metal plate wall panels.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of panel and accessory.
- B. LEED Documentation Submittals:
 - 1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.
 - d. LEED Materials and Resources Calculator.
- C. Shop Drawings:
 - 1. Include fabrication and installation layouts of metal panels; details of edge conditions, joints, panel profiles, corners, anchorages, attachment assembly, trim, flashings, closures, and accessories; and special details.
 - 2. Accessories: Include details of the flashing, trim, and anchorage, at a scale of not less than 1-1/2 inches per 12 inches.
- D. Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below.
 - 1. Metal Panels: 12 inches long by actual panel width. Include fasteners, closures, and other metal panel accessories.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Test Reports: For each product, tests performed by a qualified testing agency.
- C. Sample Warranties: For special warranties.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For metal panels to include in maintenance manuals.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.
- B. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for fabrication and installation.
 - 1. Build mockup of typical metal panel assembly of size and at location as directed by Architect, including supports, attachments, and accessories.
 - 2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 - 3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver components, metal panels, and other manufactured items so as not to be damaged or deformed. Package metal panels for protection during transportation and handling.
- B. Unload, store, and erect metal panels in a manner to prevent bending, warping, twisting, and surface damage.
- C. Stack metal panels horizontally on platforms or pallets, covered with suitable weathertight and ventilated covering. Store metal panels to ensure dryness, with positive slope for drainage of water. Do not store metal panels in contact with other materials that might cause staining, denting, or other surface damage.
- D. Retain strippable protective covering on metal panels during installation.

1.8 FIELD CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit assembly of metal panels to be performed according to manufacturers' written instructions and warranty requirements.

1.9 COORDINATION

- A. Coordinate metal panel installation with rain drainage work, flashing, trim, construction of soffits, and other adjoining work to provide a leakproof, secure, and noncorrosive installation.

1.10 WARRANTY

- A. Special Warranty on Panel Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace metal panels that show evidence of deterioration of factory-applied finishes within specified warranty period.
 - 1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:
 - a. Color fading more than 5 Hunter units when tested according to ASTM D 2244.
 - b. Chalking in excess of a No. 8 rating when tested according to ASTM D 4214.
 - c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.
 - 2. Finish Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Provide metal panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E 330:
 - 1. Wind Loads: As indicated on Drawings.
 - 2. Other Design Loads: As indicated on Drawings.
 - 3. Deflection Limits: For wind loads, no greater than 1/240 of the span.
- B. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 - 1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.
- C. Fire-Resistance Ratings: Comply with ASTM E 119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Indicate design designations from UL's "Fire Resistance Directory" or from the listings of another qualified testing agency.

2.2 METAL PLATE WALL PANELS (SS-1, SS-2, & SS-3)

- A. Metal Plate Wall Base Panels: Provide factory-formed, metal plate wall panels fabricated from single sheets of metal formed into profile for installation method indicated. Include attachment assembly components, and accessories.
- B. Panel Depth: As indicated on Drawings.
- C. Stainless-Steel Sheet: ASTM A 240/A 240M, Type 304, fully annealed.
 1. Nominal Thickness: 0.125 inch.
 2. Exterior Finish: Two-coat fluoropolymer
- D. Attachment Assembly: Rainscreen-principle system.

2.3 MISCELLANEOUS MATERIALS

- A. Miscellaneous Metal Subframing and Furring: ASTM C 645, cold-formed, metallic-coated steel sheet, ASTM A 653/A 653M, G90 coating designation or ASTM A 792/A 792M, Class AZ50 aluminum-zinc-alloy coating designation unless otherwise indicated. Provide manufacturer's standard sections as required for support and alignment of metal panel system.
- B. Panel Accessories: Provide components required for a complete panel system including trim, clips, flashings, fillers, closure strips, and similar items. Match material and finish of metal panels unless otherwise indicated.
- C. Flashing and Trim: Provide flashing and trim formed from same material as metal panels as required to seal against weather and to provide finished appearance. Locations include, but are not limited to, bases, drips, sills, jambs, corners, endwalls, framed openings, rakes, fasciae, parapet caps, soffits, reveals, and fillers. Finish flashing and trim with same finish system as adjacent metal panels.
- D. Panel Fasteners: Self-tapping screws designed to withstand design loads. Provide exposed fasteners with heads matching color of metal panels by means of plastic caps or factory-applied coating. Provide EPDM or PVC sealing washers for exposed fasteners.

2.4 FABRICATION

- A. General: Fabricate and finish metal panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.

- B. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's recommendations and recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, metal, and other characteristics of item indicated.

2.5 FINISHES

- A. Protect mechanical and painted finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.
- C. Stainless-Steel Panels and Accessories:
 - 1. Two-Coat Fluoropolymer: AAMA 2605. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, metal panel supports, and other conditions affecting performance of the Work.
 - 1. Examine wall framing to verify that girts, angles, channels, studs, and other structural panel support members and anchorage have been installed within alignment tolerances required by metal wall panel manufacturer.
 - 2. Examine wall sheathing to verify that sheathing joints are supported by framing or blocking and that installation is within flatness tolerances required by metal wall panel manufacturer.
 - a. Verify that air- or water-resistive barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.
- B. Examine roughing-in for components and systems penetrating metal panels to verify actual locations of penetrations relative to seam locations of metal panels before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Miscellaneous Supports: Install subframing, furring, and other miscellaneous panel support members and anchorages according to ASTM C 754 and metal panel manufacturer's written recommendations.

3.3 INSTALLATION

- A. General: Install metal panels according to manufacturer's written instructions in orientation, sizes, and locations indicated. Install panels perpendicular to supports unless otherwise indicated. Anchor metal panels and other components of the Work securely in place, with provisions for thermal and structural movement.
 - 1. Shim or otherwise plumb substrates receiving metal panels.
 - 2. Flash and seal metal panels at perimeter of all openings. Fasten with self-tapping screws. Do not begin installation until air- or water-resistive barriers and flashings that will be concealed by metal panels are installed.
 - 3. Install screw fasteners in predrilled holes.
 - 4. Locate and space fastenings in uniform vertical and horizontal alignment.
 - 5. Install flashing and trim as metal panel work proceeds.
 - 6. Locate panel splices over, but not attached to, structural supports. Stagger panel splices and end laps to avoid a four-panel lap splice condition.
 - 7. Align bottoms of metal panels and fasten with blind rivets, bolts, or self-tapping screws. Fasten flashings and trim around openings and similar elements with self-tapping screws.
 - 8. Provide weathertight escutcheons for pipe- and conduit-penetrating panels.
- B. Fasteners:
 - 1. Stainless-Steel Panels: Use stainless-steel fasteners.
- C. Metal Protection: Where dissimilar metals contact each other or corrosive substrates, protect against galvanic action as recommended in writing by metal panel manufacturer.
- D. Attachment Assembly, General: Install attachment assembly required to support metal plate wall panels and to provide a complete wall system, including subgirts, perimeter extrusions, tracks, drainage channels, panel clips, and anchor channels.
 - 1. Include attachment to supports, panel-to-panel joinery, and panel-to-dissimilar-material joinery.
- E. Installation: Attach metal plate wall panels to supports at locations, spacings, and with fasteners recommended by manufacturer to achieve performance requirements specified.
 - 1. Rainscreen Systems: Do not apply sealants to joints unless otherwise indicated.
- F. Accessory Installation: Install accessories with positive anchorage to building and provide for thermal expansion. Coordinate installation with flashings and other components.

1. Install components required for a complete metal panel system including trim, flashings, fillers, closure strips, and similar items. Provide types indicated by metal panel manufacturer; or, if not indicated, provide types recommended in writing by metal panel manufacturer.
- G. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that are permanently watertight.
 1. Install exposed flashing and trim that is without buckling and tool marks and that is true to line and levels indicated, with exposed edges folded back to form hems. Install sheet metal flashing and trim to fit substrates and to result in waterproof performance.
 2. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at a maximum of 10 feet with no joints allowed within 24 inches of corner or intersection.

3.4 ERECTION TOLERANCES

- A. Installation Tolerances: Shim and align metal plate wall panel units within installed tolerance of 1/4 inch in 20 feet, non-accumulative, on level, plumb, and location lines as indicated, and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.

3.5 CLEANING AND PROTECTION

- A. Remove temporary protective coverings and strippable films, if any, as metal panels are installed, unless otherwise indicated in manufacturer's written installation instructions. On completion of metal panel installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.
- B. After metal panel installation, clear weep holes and drainage channels of obstructions, dirt, and sealant.
- C. Replace metal panels that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION 07 42 13.16

SECTION 07 42 13.23 - METAL COMPOSITE MATERIAL WALL PANELS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes metal composite material wall panels.
- A. Related Sections:
 - 1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
 - 1. Meet with Owner, Architect, Owner's insurer if applicable, metal composite material panel Installer, metal composite material panel manufacturer's representative, structural-support Installer, and installers whose work interfaces with or affects metal composite material panels, installers of exterior wall components, flashings and joint treatment materials.
 - 2. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
 - 3. Review methods and procedures related to metal composite material panel installation, including manufacturer's written instructions.
 - 4. Examine support conditions for compliance with requirements, including alignment between and attachment to structural members.
 - 5. Review flashings, special siding details, wall penetrations, openings, and condition of other construction that affect metal composite material panels.
 - 6. Review governing regulations and requirements for insurance, certificates, and tests and inspections if applicable.
 - 7. Review temporary protection requirements for metal composite material panel assembly during and after installation.
 - 8. Review procedures for repair of panels damaged after installation.
 - 9. Document proceedings, including corrective measures and actions required, and furnish copy of record to each participant.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of panel and accessory.
- B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section “LEED Sustainable Design Requirements” including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.
 - d. LEED Materials and Resources Calculator.

C. Shop Drawings:

1. Include fabrication and installation layouts of metal composite material panels; details of edge conditions, joints, panel profiles, corners, anchorages, attachment assembly, trim, flashings, closures, and accessories; and special details.
2. Accessories: Include details of the flashing, trim and anchorage, at a scale of not less than 1-1/2 inches per 12 inches.

D. Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below.

1. Metal Composite Material Panels: 12 inches long by actual panel width. Include fasteners, closures, and other metal composite material panel accessories.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Test Reports: For each product, tests performed by a qualified testing agency.
- C. Sample Warranties: For special warranties.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For metal composite material panels to include in maintenance manuals.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.
- B. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for fabrication and installation.
 1. Build mockup of typical metal composite material panel assembly as shown on Drawings, including corner, soffits, supports, attachments, and accessories.
 2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.

3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver components, metal composite material panels, and other manufactured items so as not to be damaged or deformed. Package metal composite material panels for protection during transportation and handling.
- B. Unload, store, and erect metal composite material panels in a manner to prevent bending, warping, twisting, and surface damage.
- C. Stack metal composite material panels horizontally on platforms or pallets, covered with suitable weathertight and ventilated covering. Store metal composite material panels to ensure dryness, with positive slope for drainage of water. Do not store metal composite material panels in contact with other materials that might cause staining, denting, or other surface damage.
- D. Retain strippable protective covering on metal composite material panels during installation.

1.8 FIELD CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit assembly of metal composite material panels to be performed according to manufacturers' written instructions and warranty requirements.

1.9 COORDINATION

- A. Coordinate metal composite material panel installation with rain drainage work, flashing, trim, construction of soffits, and other adjoining work to provide a leakproof, secure, and noncorrosive installation.

1.10 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of metal composite material panel systems that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

- a. Structural failures including rupturing, cracking, or puncturing.
- b. Deterioration of metals and other materials beyond normal weathering.

2. Warranty Period: Two years from date of Substantial Completion.

- B. Special Warranty on Panel Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace metal composite material panels that show evidence of deterioration of factory-applied finishes within specified warranty period.

1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:
 - a. Color fading more than 5 Hunter units when tested according to ASTM D 2244.
 - b. Chalking in excess of a No. 8 rating when tested according to ASTM D 4214.
 - c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.
2. Finish Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Provide metal composite material panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E 330:
 1. Wind Loads: As indicated on Drawings.
 2. Other Design Loads: As indicated on Drawings.
 3. Deflection Limits: Engineer panel assemblies to withstand test pressures with deflection no greater than 1/480 of the span and no evidence of material failure, structural distress, or permanent deformation exceeding 0.2 percent of the clear span.
 - a. Test Pressures: 150 percent of inward and outward wind-load design pressures.
- B. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.
- C. Fire-Resistance Ratings: Comply with ASTM E 119; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 1. Indicate design designations from UL's "Fire Resistance Directory" or from the listings of another qualified testing agency.
- D. Fire Propagation Characteristics: Metal composite material wall panel system passes NFPA 285 testing.

2.2 METAL COMPOSITE MATERIAL WALL PANELS

- A. Metal Composite Material Wall Panel Systems: Provide factory-formed and -assembled, metal composite material wall panels fabricated from two metal facings that are bonded to a solid, extruded thermoplastic core; formed into profile for installation method indicated. Include attachment assembly components, panel stiffeners, and accessories required for weathertight system.

1. Products: Subject to compliance with requirements, provide one of the following:
 - a. Citadel Architectural Products, Inc.; “Envelope 2000 Rainscreen (RS) System.”
 - 1) Color and Finish: Refer to “Legend” located on Building Elevation Drawings.
 - b. Arconic; “Reynobond FR.”
 - 1) Color and Finish: Refer to “Legend” located on building Elevation Drawings.
- B. Aluminum-Faced Composite Wall Panels: Formed with 0.020-inch- thick, aluminum sheet facings.
 1. Panel Thickness: 0.157 inch.
 2. Core: Fire retardant.
- C. Attachment Assembly Components: Formed from extruded aluminum.
- D. Attachment Assembly: Rainscreen principle system.

2.3 MISCELLANEOUS MATERIALS

- A. Miscellaneous Metal Subframing and Furring: ASTM C 645, cold-formed, metallic-coated steel sheet ASTM A 653/A 653M, G90 coating designation or ASTM A 792/A 792M, Class AZ50 aluminum-zinc-alloy coating designation unless otherwise indicated. Provide manufacturer's standard sections as required for support and alignment of metal composite material panel system.
- B. Panel Accessories: Provide components required for a complete, weathertight panel system including trim, copings, fasciae, mullions, sills, corner units, clips, flashings, sealants, gaskets, fillers, closure strips, and similar items. Match material and finish of metal composite material panels unless otherwise indicated.
- C. Flashing and Trim: Provide flashing and trim formed from same material as metal composite material panels as required to seal against weather and to provide finished appearance. Locations include, but are not limited to, bases, drips, sills, jambs, corners, endwalls, framed openings, rakes, fasciae, parapet caps, soffits, reveals, and fillers. Finish flashing and trim with same finish system as adjacent metal composite material panels.
- D. Panel Fasteners: Self-tapping screws designed to withstand design loads. Provide exposed fasteners with heads matching color of metal composite material panels by means of plastic caps or factory-applied coating. Provide EPDM or PVC sealing washers for exposed fasteners.
- E. Panel Sealants: ASTM C 920; elastomeric polyurethane or silicone sealant; of type, grade, class, and use classifications required to seal joints in metal composite material panels and remain weathertight; and as recommended in writing by metal composite material panel manufacturer.

2.4 FABRICATION

- A. General: Fabricate and finish metal composite material panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements.
- B. Sheet Metal Flashing and Trim: Fabricate flashing and trim to comply with manufacturer's recommendations and recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, metal, and other characteristics of item indicated.
 - 1. Form exposed sheet metal accessories that are without excessive oil canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.
 - 2. Seams for Aluminum: Fabricate nonmoving seams with flat-lock seams. Form seams and seal with epoxy seam sealer. Rivet joints for additional strength.
 - 3. Seams for Other Than Aluminum: Fabricate nonmoving seams in accessories with flat-lock seams. Tin edges to be seamed, form seams, and solder.
 - 4. Sealed Joints: Form non-expansion, but movable, joints in metal to accommodate sealant and to comply with SMACNA standards.
 - 5. Conceal fasteners and expansion provisions where possible. Exposed fasteners are not allowed on faces of accessories exposed to view.
 - 6. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal recommended in writing by metal panel manufacturer.
 - a. Size: As recommended by SMACNA's "Architectural Sheet Metal Manual" or metal wall panel manufacturer for application but not less than thickness of metal being secured.

2.5 FINISHES

- A. Protect mechanical and painted finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.
- C. Aluminum Panels and Accessories:
 - 1. Two-Coat Fluoropolymer: AAMA 2605. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, metal composite material panel supports, and other conditions affecting performance of the Work.
 - 1. Examine wall framing to verify that girts, angles, channels, studs, and other structural panel support members and anchorage have been installed within alignment tolerances required by metal composite material wall panel manufacturer.
 - 2. Examine wall sheathing to verify that sheathing joints are supported by framing or blocking and that installation is within flatness tolerances required by metal composite material wall panel manufacturer.
 - a. Verify that air- or water-resistive barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.
- B. Examine roughing-in for components and assemblies penetrating metal composite material panels to verify actual locations of penetrations relative to seam locations of metal composite material panels before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Miscellaneous Supports: Install subframing, furring, and other miscellaneous panel support members and anchorages according to ASTM C 754 and metal composite material panel manufacturer's written recommendations.

3.3 METAL COMPOSITE MATERIAL PANEL INSTALLATION

- A. General: Install metal composite material panels according to manufacturer's written instructions in orientation, sizes, and locations indicated on Drawings. Install panels perpendicular to supports unless otherwise indicated. Anchor metal composite material panels and other components of the Work securely in place, with provisions for thermal and structural movement.
 - 1. Shim or otherwise plumb substrates receiving metal composite material panels.
 - 2. Flash and seal metal composite material panels at perimeter of all openings. Fasten with self-tapping screws. Do not begin installation until air- or water-resistive barriers and flashings that will be concealed by metal composite material panels are installed.
 - 3. Install screw fasteners in predrilled holes.
 - 4. Locate and space fastenings in uniform vertical and horizontal alignment.
 - 5. Install flashing and trim as metal composite material panel work proceeds.
 - 6. Locate panel splices over, but not attached to, structural supports. Stagger panel splices and end laps to avoid a four-panel lap splice condition.

7. Align bottoms of metal composite material panels and fasten with blind rivets, bolts, or self-tapping screws. Fasten flashings and trim around openings and similar elements with self-tapping screws.
 8. Provide weathertight escutcheons for pipe- and conduit-penetrating panels.
- B. Fasteners:
1. Aluminum Panels: Use aluminum or stainless-steel fasteners for surfaces exposed to the exterior; use aluminum or galvanized-steel fasteners for surfaces exposed to the interior.
- C. Metal Protection: Where dissimilar metals contact each other or corrosive substrates, protect against galvanic action as recommended in writing by metal composite material panel manufacturer.
- D. Attachment Assembly, General: Install attachment assembly required to support metal composite material wall panels and to provide a complete weathertight wall system, including subgirts, perimeter extrusions, tracks, drainage channels, panel clips, and anchor channels.
1. Include attachment to supports, panel-to-panel joinery, panel-to-dissimilar-material joinery, and panel-system joint seals.
- E. Rainscreen-Principle Installation: Install using manufacturer's standard assembly with vertical channel that provides support and secondary drainage assembly, draining at base of wall. Notch vertical channel to receive support pins. Install vertical channels supported by channel brackets or adjuster angles and at locations, spacings, and with fasteners recommended by manufacturer. Attach metal composite material wall panels by inserting horizontal support pins into notches in vertical channels and into flanges of panels. Leave horizontal and vertical joints with open reveal.
1. Install wall panels to allow individual panels to be installed and removed without disturbing adjacent panels.
 2. Do not apply sealants to joints unless otherwise indicated.
- F. Accessory Installation: Install accessories with positive anchorage to building and weathertight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.
1. Install components required for a complete metal composite material panel assembly including trim, copings, corners, seam covers, flashings, sealants, gaskets, fillers, closure strips, and similar items. Provide types indicated by metal composite material panel manufacturer; or, if not indicated, provide types recommended in writing by metal composite material panel manufacturer.
 - a. Coping: Mechanically secure metal composite panel copings and seal horizontal and vertical joints between adjacent metal panel material with sealant backing and sealant. Install sealant backing and sealant according to requirements specified in Section 07 92 00 "Joint Sealants."

- G. Flashing and Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that are permanently watertight.
1. Install exposed flashing and trim that is without buckling and tool marks and that is true to line and levels indicated, with exposed edges folded back to form hems. Install sheet metal flashing and trim to fit substrates and to result in waterproof performance.
 2. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at a maximum of 10 feet with no joints allowed within 24 inches of corner or intersection. Where lapped expansion provisions cannot be used or would not be sufficiently waterproof, form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with mastic sealant (concealed within joints).

3.4 ERECTION TOLERANCES

- A. Installation Tolerances: Shim and align metal composite material wall panel units within installed tolerance of 1/4 inch in 20 feet, non-accumulative, on level, plumb, and location lines as indicated, and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.

3.5 CLEANING AND PROTECTION

- A. Remove temporary protective coverings and strippable films, if any, as metal composite material panels are installed, unless otherwise indicated in manufacturer's written installation instructions. On completion of metal composite material panel installation, clean finished surfaces as recommended by metal composite material panel manufacturer. Maintain in a clean condition during construction.
- B. After metal composite material panel installation, clear weep holes and drainage channels of obstructions, dirt, and sealant.
- C. Replace metal composite material panels that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION 07 42 13.23

SECTION 07 54 23 - THERMOPLASTIC POLYOLEFIN (TPO) ROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Adhered TPO membrane roofing system.
2. Roof insulation.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 DEFINITIONS

A. TPO: Thermoplastic polyolefin.

B. Roofing Terminology: See ASTM D 1079 and glossary in NRCA's "The NRCA Roofing and Waterproofing Manual" for definitions of terms related to roofing work in this Section.

1.3 PERFORMANCE REQUIREMENTS

A. General Performance: Installed membrane roofing and base flashings shall withstand specified uplift pressures, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Membrane roofing and base flashings shall remain watertight.

B. Material Compatibility: Provide roofing materials that are compatible with one another under conditions of service and application required, as demonstrated by membrane roofing manufacturer based on testing and field experience.

C. Roofing System Design: Provide a membrane roofing system that is identical to systems that have been successfully tested by a qualified testing and inspecting agency to resist uplift pressure specific to the geographic location of the building as required by the building code authorities having jurisdiction and calculated according to ASCE 7.

D. FM Approvals Listing: Provide membrane roofing, base flashings, and component materials that comply with requirements in FM Approvals 4450 and FM Approvals 4470 as part of a membrane roofing system, and that are listed in FM Approvals' "RoofNav" for Class 1 or noncombustible construction, as applicable. Identify materials with FM Approvals markings.

1. Fire/Windstorm Classification: Class 1A-90.
2. Hail Resistance: SH.

E. Solar Reflectance Index: Not less than 78 when calculated according to ASTM E 1980, based on testing identical products by a qualified testing agency.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. LEED Documentation Submittals:
 - 1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. Solar Reflectance Index requirement.
 - d. Regional Materials Information.
 - e. Recycled Content Information.
 - f. LEED Materials and Resources Calculator.
- C. Shop Drawings: For roofing system. Include plans, elevations, sections, details, and attachments to other work.
 - 1. Base flashings and membrane terminations.
 - 2. Tapered insulation, including slopes.
 - 3. Roof plan showing orientation of steel roof deck and orientation of membrane roofing and fastening spacings and patterns for mechanically fastened membrane roofing.
 - 4. Insulation fastening patterns for corner, perimeter, and field-of-roof locations.
- D. Samples for Verification: For the following products:
 - 1. Sheet roofing, of color specified, including T-shaped side and end lap seam.
 - 2. Roof insulation.
 - 3. Walkway pads or rolls.
 - 4. Metal termination bars.
 - 5. Six insulation fasteners of each type, length, and finish.
 - 6. Six roof cover fasteners of each type, length, and finish.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer and manufacturer.
- B. Manufacturer Certificates: Signed by roofing manufacturer certifying that roofing system complies with requirements specified in "Performance Requirements" Article.
 - 1. Submit evidence of compliance with performance requirements.
- C. Product Test Reports: Based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified testing agency, for components of membrane roofing system.
- D. Research/Evaluation Reports: For components of membrane roofing system as required by authorities having jurisdiction.
- E. Field quality-control reports.

- F. Warranties: Sample of special warranties.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For roofing system to include in maintenance manuals.

1.7 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A qualified manufacturer that is FM Approvals approved for membrane roofing system identical to that used for this Project.
- B. Installer Qualifications: A qualified firm that is approved, authorized, or licensed by membrane roofing system manufacturer to install manufacturer's product and that is eligible to receive manufacturer's special warranty.
 - 1. Installers shall be certified by the FM Global roofing installer program.
- C. Source Limitations: Obtain components including roof insulation for membrane roofing system from same manufacturer as membrane roofing or approved by membrane roofing manufacturer.
- D. Exterior Fire-Test Exposure: ASTM E 108, Class A; for application and roof slopes indicated, as determined by testing identical membrane roofing materials by a qualified testing agency. Materials shall be identified with appropriate markings of applicable testing agency.
- E. Fire-Resistance Ratings: Where indicated, provide fire-resistance-rated roof assemblies identical to those of assemblies tested for fire resistance per ASTM E 119 by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
- F. Preliminary Roofing Conference: Before starting roof deck construction, conduct conference at Project site.
 - 1. Meet with Owner, Architect, Owner's insurer if applicable, testing and inspecting agency representative, roofing Installer, roofing system manufacturer's representative, deck Installer, and installers whose work interfaces with or affects roofing, including installers of roof accessories and roof-mounted equipment.
 - 2. Review methods and procedures related to roofing installation, including manufacturer's written instructions.
 - 3. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
 - 4. Review deck substrate requirements for conditions and finishes, including flatness and fastening.
 - 5. Review structural loading limitations of roof deck during and after roofing.
 - 6. Review base flashings, special roofing details, roof drainage, roof penetrations, equipment curbs, and condition of other construction that will affect roofing system.
 - 7. Review governing regulations and requirements for insurance and certificates if applicable.
 - 8. Review temporary protection requirements for roofing system during and after installation.
 - 9. Review roof observation and repair procedures after roofing installation.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Deliver roofing materials to Project site in original containers with seals unbroken and labeled with manufacturer's name, product brand name and type, date of manufacture, approval or listing agency markings, and directions for storing and mixing with other components.
- B. Store liquid materials in their original undamaged containers in a clean, dry, protected location and within the temperature range required by roofing system manufacturer. Protect stored liquid material from direct sunlight.
 - 1. Discard and legally dispose of liquid material that cannot be applied within its stated shelf life.
- C. Protect roof insulation materials from physical damage and from deterioration by sunlight, moisture, soiling, and other sources. Store in a dry location. Comply with insulation manufacturer's written instructions for handling, storing, and protecting during installation.
- D. Handle and store roofing materials and place equipment in a manner to avoid permanent deflection of deck.

1.9 PROJECT CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed according to manufacturer's written instructions and warranty requirements.

1.10 WARRANTY

- A. Special Warranty: Manufacturer's standard or customized form, without monetary limitation, in which manufacturer agrees to repair or replace components of membrane roofing system that fail in materials or workmanship within specified warranty period.
 - 1. Special warranty includes membrane roofing, base flashings, roof insulation, fasteners, cover boards, substrate board, roofing accessories, and other components of membrane roofing system.
 - 2. Warranty Period: 20 years from date of Substantial Completion.
- B. Special Project Warranty: Submit roofing Installer's warranty, on warranty form at end of this Section, signed by Installer, covering the Work of this Section, including all components of roofing system such as roofing, base flashing, roof insulation, fasteners, cover boards, substrate boards, vapor retarders, roof pavers, and walkway products, for the following warranty period:
 - 1. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 TPO MEMBRANE ROOFING

- A. Fabric-Reinforced Thermoplastic Polyolefin Sheet: ASTM D 6878, internally fabric or scrim reinforced, uniform, flexible TPO sheet.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Firestone Building Products Company
 - b. Carlisle SynTec Incorporated
 - c. GAF Materials Corporation
 - d. Johns Manville
 2. Thickness: 60 mils, nominal.
 3. Exposed Face Color: White.
 - a. Complying with Solar Reflectance Index (SRI) performance requirements as specified within this Section.

2.2 AUXILIARY MEMBRANE ROOFING MATERIALS

- A. General: Auxiliary membrane roofing materials recommended by roofing system manufacturer for intended use, and compatible with membrane roofing.
1. Liquid-type auxiliary materials shall comply with VOC limits of authorities having jurisdiction.
 2. Adhesives and sealants that are not on the exterior side of weather barrier shall comply with the following limits for VOC content when calculated according to 40 CFR 59, Subpart D (EPA Method 24):
 - a. Plastic Foam Adhesives: 50 g/L.
 - b. Gypsum Board and Panel Adhesives: 50 g/L.
 - c. Multipurpose Construction Adhesives: 70 g/L.
 - d. Fiberglass Adhesives: 80 g/L.
 - e. Single-Ply Roof Membrane Adhesives: 250 g/L.
 - f. Other Adhesives: 250 g/L.
 - g. Single-Ply Roof Membrane Sealants: 450 g/L.
 - h. Nonmembrane Roof Sealants: 300 g/L.
 - i. Sealant Primers for Nonporous Substrates: 250 g/L.
 - j. Sealant Primers for Porous Substrates: 775 g/L.
- B. Sheet Flashing: Manufacturer's standard unreinforced thermoplastic polyolefin sheet flashing, 55 mils thick, minimum, of same color as sheet membrane.
- C. Bonding Adhesive: Manufacturer's standard solvent-based bonding adhesive for membrane, and solvent-based bonding adhesive for base flashings.

- D. Metal Termination Bars: Manufacturer's standard, predrilled stainless-steel or aluminum bars, approximately 1 by 1/8 inch thick; with anchors.
- E. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Approvals 4470, designed for fastening membrane to substrate, and acceptable to membrane roofing system manufacturer.
- F. Miscellaneous Accessories: Provide pourable sealers, preformed cone and vent sheet flashings, preformed inside and outside corner sheet flashings, T-joint covers, lap sealants, termination reglets, and other accessories.
 - 1. Stucco Reglet and Counterflashing: Refer to Division 07 Section "Roof Specialties" for prefabricated reglet and counterflashing.

2.3 ROOF INSULATION

- A. General: Preformed roof insulation boards manufactured or approved by TPO membrane roofing manufacturer, selected from manufacturer's standard sizes suitable for application, of thicknesses indicated and that produce FM Approvals-approved roof insulation.
- B. Polyisocyanurate Board Insulation: ASTM C 1289, Type II, Class 1, Grade 2, felt or glass-fiber mat facer on both major surfaces.
- C. Tapered Insulation: Provide factory-tapered insulation boards fabricated to slope of 1/4 inch per 12 inches unless otherwise indicated.
- D. Provide preformed saddles, crickets, tapered edge strips, and other insulation shapes where indicated for sloping to drain. Fabricate to slopes indicated.

2.4 INSULATION ACCESSORIES

- A. General: Furnish roof insulation accessories recommended by insulation manufacturer for intended use and compatibility with membrane roofing.
- B. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Approvals 4470, designed for fastening roof insulation to substrate, and acceptable to roofing system manufacturer.
- C. Cover Board: ASTM C 1177/C 1177M, glass-mat, water-resistant gypsum substrate, 1/2 inch thick.
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Georgia-Pacific Corporation.
 - b. United States Gypsum Co.
 - 2. Prime cover board as recommended by roof membrane manufacturer.

2.5 WALKWAYS

- A. Flexible Walkways: Factory-formed, nonporous, heavy-duty, slip-resisting, surface-textured walkway pads or rolls, approximately 3/16 inch thick, and acceptable to membrane roofing system manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with the following requirements and other conditions affecting performance of roofing system:
 - 1. Verify that roof openings and penetrations are in place and curbs are set and braced and that roof drain bodies are securely clamped in place.
 - 2. Verify that wood blocking, curbs, and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thicknesses of insulation.
 - a. The wood shall be attached in a manner that will resist a minimum force of 200 lbs./ft. in any direction.
 - 3. Verify that surface plane flatness and fastening of steel roof deck complies with requirements in Division 05 Section "Steel Decking."
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean substrate of dust, debris, moisture, and other substances detrimental to roofing installation according to roofing system manufacturer's written instructions. Remove sharp projections.
- B. Prevent materials from entering and clogging roof drains and conductors and from spilling or migrating onto surfaces of other construction. Remove roof-drain plugs when no work is taking place or when rain is forecast.
- C. Complete terminations and base flashings and provide temporary seals to prevent water from entering completed sections of roofing system at the end of the workday or when rain is forecast. Remove and discard temporary seals before beginning work on adjoining roofing.

3.3 INSULATION INSTALLATION

- A. Coordinate installing membrane roofing system components so insulation is not exposed to precipitation or left exposed at the end of the workday.
- B. Comply with membrane roofing system and insulation manufacturer's written instructions for installing roof insulation.
- C. Install tapered insulation under area of roofing to conform to slopes indicated.

- D. Install insulation under area of roofing to achieve required thickness. Where overall insulation thickness is 2.7 inches or greater, install two or more layers with joints of each succeeding layer staggered from joints of previous layer a minimum of 6 inches in each direction.
- E. Trim surface of insulation where necessary at roof drains so completed surface is flush and does not restrict flow of water.
- F. Install insulation with long joints of insulation in a continuous straight line with end joints staggered between rows, abutting edges and ends between boards. Fill gaps exceeding 1/4 inch with insulation.
 - 1. Cut and fit insulation within 1/4 inch of nailers, projections, and penetrations.
- G. Loosely Laid Insulation: Loosely lay insulation units over substrate.
- H. Install cover boards over insulation with long joints in continuous straight lines with end joints staggered between rows. Offset joints of insulation below a minimum of 6 inches in each direction. Loosely butt cover boards together and fasten to roof deck.
 - 1. Fasten cover boards according to requirements in FM Approvals' "RoofNav" for specified Windstorm Resistance Classification.

3.4 ADHERED MEMBRANE ROOFING INSTALLATION

- A. Adhere membrane roofing over area to receive roofing and install according to membrane roofing system manufacturer's written instructions.
- B. Start installation of membrane roofing in presence of membrane roofing system manufacturer's technical personnel.
- C. Accurately align membrane roofing and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps.
- D. Bonding Adhesive: Apply to substrate and underside of membrane roofing at rate required by manufacturer and allow to partially dry before installing membrane roofing. Do not apply to splice area of membrane roofing.
- E. In addition to adhering, mechanically fasten membrane roofing securely at terminations, penetrations, and perimeter of roofing.
- F. Apply membrane roofing with side laps shingled with slope of roof deck where possible.
- G. Seams: Clean seam areas, overlap membrane roofing, and hot-air weld side and end laps of membrane roofing and sheet flashings according to manufacturer's written instructions to ensure a watertight seam installation.
 - 1. Test lap edges with probe to verify seam weld continuity. Apply lap sealant to seal cut edges of sheet membrane.
 - 2. Verify field strength of seams a minimum of twice daily and repair seam sample areas.
 - 3. Repair tears, voids, and lapped seams in roofing that does not comply with requirements.

- H. Spread sealant bed over deck drain flange at roof drains and securely seal membrane roofing in place with clamping ring.

3.5 BASE FLASHING INSTALLATION

- A. Install sheet flashings and preformed flashing accessories and adhere to substrates according to membrane roofing system manufacturer's written instructions.
- B. Apply bonding adhesive to substrate and underside of sheet flashing at required rate and allow to partially dry. Do not apply to seam area of flashing.
- C. Flash penetrations and field-formed inside and outside corners with cured or uncured sheet flashing.
- D. Clean seam areas, overlap, and firmly roll sheet flashings into the adhesive. Hot-air weld side and end laps to ensure a watertight seam installation.
- E. Terminate and seal top of sheet flashings and mechanically anchor to substrate through termination bars.

3.6 WALKWAY INSTALLATION

- A. Prior to installation, the manufacturer's technical inspector must inspect all field seams of the roofing membrane. Any defects, found in the field membrane, must be repaired.
 - 1. Roofing membrane to receive walkway shall be clean and dry.
 - 2. Recheck all existing deck membrane seams that are to be covered by Walkway with rounded screwdriver and re-weld any inconsistencies before walkway installation.
 - 3. Place chalk lines on deck sheet to indicate location of walkway.
 - 4. Layout to be reviewed and approved by Owner and Architect prior to installation.
 - 5. Apply a continuous coat of contact adhesive to the deck sheet and the back of walkway in accordance with roofing manufacturer's technical requirements.
 - 6. Press walkway into place with a water-filled, foam-covered lawn roller.
 - 7. Clean the deck membrane in areas to be welded. Hot-air weld the entire perimeters of the walkway to the roofing deck sheet.
 - 8. Check all welds of the walkway with a rounded screwdriver. Re-weld any inconsistencies.
- B. Flexible Walkways: Install walkway products in locations indicated. Heat weld to substrate or adhere walkway products to substrate with compatible adhesive according to roofing system manufacturer's written instructions.

3.7 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to inspect substrate conditions, surface preparation, membrane application, flashings, protection, and drainage components, and to furnish reports to Architect.
- B. Adhesion Testing: Test roof membrane for adhesion according to industry standard testing methods.

1. Provide one test for each 500 square feet.
- C. Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion.
 1. Notify Owner and Architect 48 hours in advance of date and time of inspection.
- D. Repair or remove and replace components of membrane roofing system where inspections indicate that they do not comply with specified requirements.
- E. Additional inspections, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

3.8 PROTECTING AND CLEANING

- A. Protect membrane roofing system from damage and wear during remainder of construction period. When remaining construction will not affect or endanger roofing, inspect roofing for deterioration and damage, describing its nature and extent in a written report, with copies to Architect and Owner.
- B. Correct deficiencies in or remove membrane roofing system that does not comply with requirements; repair substrates; and repair or reinstall membrane roofing system to a condition free of damage and deterioration at time of Substantial Completion and according to warranty requirements.
- C. Clean overspray and spillage from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

3.9 ROOFING INSTALLER'S WARRANTY

- A. WHEREAS _____ of _____, herein called the "Roofing Installer," has performed roofing and associated work ("work") on the following project:
 1. Owner: Bank of America.
 2. Owner's Representative: JLL
 - a. Address: 800 5th Avenue, 17th Floor Seattle, WA 98104
 3. Building Name/Type: BAC Centerville / Retail Bank Branch
 4. Address: 782 West Parrish Lane Centerville, UT 84014
 5. Area of Work: Conditioned Building Roof and ATM Canopy Roof
 6. Acceptance Date: _____.
 7. Warranty Period: 2 years.
 8. Expiration Date: _____.
- B. AND WHEREAS Roofing Installer has contracted (either directly with Owner or indirectly as a subcontractor) to warrant said work against leaks and faulty or defective materials and workmanship for designated Warranty Period,

- C. NOW THEREFORE Roofing Installer hereby warrants, subject to terms and conditions herein set forth, that during Warranty Period he will, at his own cost and expense, make or cause to be made such repairs to or replacements of said work as are necessary to correct faulty and defective work and as are necessary to maintain said work in a watertight condition.
- D. This Warranty is made subject to the following terms and conditions:
1. Specifically excluded from this Warranty are damages to work and other parts of the building, and to building contents, caused by:
 - a. lightning;
 - b. peak gust wind speed exceeding 74 mph.
 - c. fire;
 - d. failure of roofing system substrate, including cracking, settlement, excessive deflection, deterioration, and decomposition;
 - e. faulty construction of parapet walls, copings, chimneys, skylights, vents, equipment supports, and other edge conditions and penetrations of the work;
 - f. vapor condensation on bottom of roofing; and
 - g. activity on roofing by others, including construction contractors, maintenance personnel, other persons, and animals, whether authorized or unauthorized by Owner.
 2. When work has been damaged by any of foregoing causes, Warranty shall be null and void until such damage has been repaired by Roofing Installer and until cost and expense thereof have been paid by Owner or by another responsible party so designated.
 3. Roofing Installer is responsible for damage to work covered by this Warranty but is not liable for consequential damages to building or building contents resulting from leaks or faults or defects of work.
 4. During Warranty Period, if Owner allows alteration of work by anyone other than Roofing Installer, including cutting, patching, and maintenance in connection with penetrations, attachment of other work, and positioning of anything on roof, this Warranty shall become null and void on date of said alterations, but only to the extent said alterations affect work covered by this Warranty. If Owner engages Roofing Installer to perform said alterations, Warranty shall not become null and void unless Roofing Installer, before starting said work, shall have notified Owner in writing, showing reasonable cause for claim, that said alterations would likely damage or deteriorate work, thereby reasonably justifying a limitation or termination of this Warranty.
 5. During Warranty Period, if original use of roof is changed and it becomes used for, but was not originally specified for, a promenade, work deck, spray-cooled surface, flooded basin, or other use or service more severe than originally specified, this Warranty shall become null and void on date of said change, but only to the extent said change affects work covered by this Warranty.
 6. Owner shall promptly notify Roofing Installer of observed, known, or suspected leaks, defects, or deterioration and shall afford reasonable opportunity for Roofing Installer to inspect work and to examine evidence of such leaks, defects, or deterioration.
 7. This Warranty is recognized to be the only warranty of Roofing Installer on said work and shall not operate to restrict or cut off Owner from other remedies and resources lawfully available to Owner in cases of roofing failure. Specifically, this Warranty shall not operate to relieve Roofing Installer of responsibility for performance of original work

according to requirements of the Contract Documents, regardless of whether Contract was a contract directly with Owner or a subcontract with Owner's General Contractor.

E. IN WITNESS THEREOF, this instrument has been duly executed this _____ day of _____, _____.

1. Authorized Signature: _____.
2. Name: _____.
3. Title: _____.

END OF SECTION 07 54 23

SECTION 07 62 00 - SHEET METAL FLASHING AND TRIM

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Formed low-slope roof sheet metal fabrications.
2. Formed wall sheet metal fabrications.
3. Formed equipment support flashing.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 COORDINATION

- A. Coordinate sheet metal flashing and trim layout and seams with sizes and locations of penetrations to be flashed, and joints and seams in adjacent materials.
- B. Coordinate sheet metal flashing and trim installation with adjoining roofing and wall materials, joints, and seams to provide leakproof, secure, and noncorrosive installation.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review construction schedule. Verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
2. Review special roof details, roof-penetration flashing, equipment curbs, and condition of other construction that affect sheet metal flashing and trim.
3. Review requirements for insurance and certificates if applicable.
4. Review sheet metal flashing observation and repair procedures after flashing installation.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each manufactured product and accessory.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.

- c. Regional Materials Information.
- d. LEED Materials and Resources Calculator.

C. Shop Drawings: For sheet metal flashing and trim.

- 1. Include plans, elevations, sections, and attachment details.
- 2. Detail fabrication and installation layouts, expansion-joint locations, and keyed details. Distinguish between shop- and field-assembled work.
- 3. Include identification of material, thickness, weight, and finish for each item and location in Project.
- 4. Include details for forming, including profiles, shapes, seams, and dimensions.
- 5. Include details for joining, supporting, and securing, including layout and spacing of fasteners, cleats, clips, and other attachments. Include pattern of seams.
- 6. Include details of termination points and assemblies.
- 7. Include details of expansion joints and expansion-joint covers, including showing direction of expansion and contraction from fixed points.
- 8. Include details of roof-penetration flashing.
- 9. Include details of edge conditions, including eaves, ridges, valleys, rakes, crickets, and counterflashings as applicable.
- 10. Include details of special conditions.
- 11. Include details of connections to adjoining work.
- 12. Detail formed flashing and trim at scale of not less than 3 inches per 12 inches.

D. Samples for Verification: For each type of exposed finish.

- 1. Sheet Metal Flashing: 12 inches long by actual width of unit, including finished seam and in required profile. Include fasteners, cleats, clips, closures, and other attachments.
- 2. Trim, Metal Closures, Expansion Joints, Joint Intersections, and Miscellaneous Fabrications: 12 inches long and in required profile. Include fasteners and other exposed accessories.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For fabricator.
- B. Product Certificates: For each type of coping and roof edge flashing that is FM Approvals approved.
- C. Product Test Reports: For each product, for tests performed by a qualified testing agency.
- D. Sample Warranty: For special warranty.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For sheet metal flashing and trim, and its accessories, to include in maintenance manuals.

1.7 QUALITY ASSURANCE

- A. Fabricator Qualifications: Employs skilled workers who custom fabricate sheet metal flashing and trim similar to that required for this Project and whose products have a record of successful in-service performance.
- B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for fabrication and installation.
 - 1. Build mockup of typical roof edge, approximately 10 feet long, including supporting construction cleats, seams, attachments, underlayment,] and accessories.
 - 2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 - 3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Do not store sheet metal flashing and trim materials in contact with other materials that might cause staining, denting, or other surface damage. Store sheet metal flashing and trim materials away from uncured concrete and masonry.
- B. Protect strippable protective covering on sheet metal flashing and trim from exposure to sunlight and high humidity, except to extent necessary for period of sheet metal flashing and trim installation.

1.9 WARRANTY

- A. Special Warranty on Finishes: Manufacturer agrees to repair finish or replace sheet metal flashing and trim that shows evidence of deterioration of factory-applied finishes within specified warranty period.
 - 1. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:
 - a. Color fading more than 5 Hunter units when tested according to ASTM D 2244.
 - b. Chalking in excess of a No. 8 rating when tested according to ASTM D 4214.
 - c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.
 - 2. Finish Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. General: Sheet metal flashing and trim assemblies shall withstand wind loads, structural movement, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Completed sheet metal flashing and trim shall not rattle, leak, or loosen, and shall remain watertight.

- B. Sheet Metal Standard for Flashing and Trim: Comply with SMACNA's "Architectural Sheet Metal Manual" requirements for dimensions and profiles shown unless more stringent requirements are indicated.
- C. Recycled Content of Steel-Sheet Flashing and Trim: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes to prevent buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 - 1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces

2.2 SHEET METALS

- A. General: Protect mechanical and other finishes on exposed surfaces from damage by applying strippable, temporary protective film before shipping.
- B. Aluminum Sheet: ASTM B 209, alloy as standard with manufacturer for finish required, with temper as required to suit forming operations and performance required; with smooth, flat surface.
 - 1. Exposed Coil-Coated Finish:
 - a. Two-Coat Fluoropolymer: AAMA 620. Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.
 - 2. Color: Refer to "Finish Schedule" located on Drawings.
 - 3. Concealed Finish: Pretreat with manufacturer's standard white or light-colored acrylic or polyester backer finish, consisting of prime coat and wash coat with minimum total dry film thickness of 0.5 mil.
- C. Stainless-Steel Sheet: ASTM A 240/A 240M, Type 304, dead soft, fully annealed; with smooth, flat surface.
 - 1. Finish: 2D (dull, cold rolled).

2.3 UNDERLAYMENT MATERIALS

- A. Self-Adhering, High-Temperature Sheet: Minimum 30 mils thick, consisting of a slip-resistant polyethylene- or polypropylene-film top surface laminated to a layer of butyl- or SBS-modified asphalt adhesive, with release-paper backing; specifically designed to withstand high metal temperatures beneath metal roofing. Provide primer according to written recommendations of underlayment manufacturer.
 - 1. Thermal Stability: ASTM D 1970; stable after testing at 240 deg F or higher.

2. Low-Temperature Flexibility: ASTM D 1970; passes after testing at minus 20 deg F or lower.

2.4 MISCELLANEOUS MATERIALS

- A. General: Provide materials and types of fasteners, solder, protective coatings, sealants, and other miscellaneous items as required for complete sheet metal flashing and trim installation and as recommended by manufacturer of primary sheet metal unless otherwise indicated.
- B. Fasteners: Wood screws, annular threaded nails, self-tapping screws, self-locking rivets and bolts, and other suitable fasteners designed to withstand design loads and recommended by manufacturer of primary sheet metal.
 1. General: Blind fasteners or self-drilling screws, gasketed, with hex-washer head.
 - a. Exposed Fasteners: Heads matching color of sheet metal using plastic caps or factory-applied coating. Provide metal-backed EPDM or PVC sealing washers under heads of exposed fasteners bearing on weather side of metal.
 - b. Blind Fasteners: High-strength aluminum or stainless-steel rivets suitable for metal being fastened.
 - c. Spikes and Ferrules: Same material as gutter; with spike with ferrule matching internal gutter width.
 2. Fasteners for Aluminum Sheet: Aluminum or Series 300 stainless steel.
 3. Fasteners for Stainless-Steel Sheet: Series 300 stainless steel.
- C. Solder:
 1. For Stainless Steel: ASTM B 32, Grade Sn60, with acid flux of type recommended by stainless-steel sheet manufacturer.
- D. Sealant Tape: Pressure-sensitive, 100 percent solids, polyisobutylene compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape 1/2 inch wide and 1/8 inch thick.
- E. Elastomeric Sealant: ASTM C 920, elastomeric polyurethane or silicone polymer sealant; of type, grade, class, and use classifications required to seal joints in sheet metal flashing and trim and remain watertight.
- F. Butyl Sealant: ASTM C 1311, single-component, solvent-release butyl rubber sealant; polyisobutylene plasticized; heavy bodied for hooked-type expansion joints with limited movement.
- G. Bituminous Coating: Cold-applied asphalt emulsion according to ASTM D 1187.
- H. Asphalt Roofing Cement: ASTM D 4586, asbestos free, of consistency required for application.

2.5 FABRICATION, GENERAL

- A. General: Custom fabricate sheet metal flashing and trim to comply with details shown and recommendations in cited sheet metal standard that apply to design, dimensions, geometry, metal thickness, and other characteristics of item required. Fabricate sheet metal flashing and trim in shop to greatest extent possible.
 - 1. Fabricate sheet metal flashing and trim in thickness or weight needed to comply with performance requirements, but not less than that specified for each application and metal.
 - 2. Obtain field measurements for accurate fit before shop fabrication.
 - 3. Form sheet metal flashing and trim to fit substrates without excessive oil canning, buckling, and tool marks; true to line, levels, and slopes; and with exposed edges folded back to form hems.
 - 4. Conceal fasteners and expansion provisions where possible. Do not use exposed fasteners on faces exposed to view.
- B. Fabrication Tolerances: Fabricate sheet metal flashing and trim that is capable of installation to a tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.
- C. Expansion Provisions: Form metal for thermal expansion of exposed flashing and trim.
 - 1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with butyl sealant concealed within joints.
 - 2. Use lapped expansion joints only where indicated on Drawings.
- D. Sealant Joints: Where movable, nonexpansion-type joints are required, form metal to provide for proper installation of elastomeric sealant according to cited sheet metal standard.
- E. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal.
- F. Fabricate cleats and attachment devices of sizes as recommended by cited sheet metal standard and by FM Global Property Loss Prevention Data Sheet 1-49 for application, but not less than thickness of metal being secured.
- G. Seams: Fabricate nonmoving seams with flat-lock seams. Tin edges to be seamed, form seams, and solder.
- H. Do not use graphite pencils to mark metal surfaces.

2.6 LOW-SLOPE ROOF SHEET METAL FABRICATIONS

- A. Custom Copings: Fabricate in minimum 96-inch- long, but not exceeding 12-foot- long, sections. Fabricate joint plates of same thickness as copings. Furnish with continuous cleats to support edge of external leg and interior leg. Miter corners, fasten and seal watertight. Shop fabricate interior and exterior corners.
 - 1. Custom Coping Profile: Refer to Drawings for custom coping at canopy.
 - 2. Joint Style: Butted with expansion space and 6-inch- wide, concealed backup plate.

3. Fabricate from the Following Materials:

- a. Aluminum: 0.050 inch thick.
- b. Color: Refer to "Finish Schedule" located on Drawings for custom color selection.

B. Roof-to-Wall Transition Expansion-Joint Cover: Fabricate from the following materials:

- 1. Stainless Steel: 0.025 inch thick.

C. Base Flashing: Fabricate from the following materials:

- 1. Stainless Steel: 0.019 inch thick.

D. Counterflashing: Fabricate from the following materials:

- 1. Stainless Steel: 0.019 inch thick.

E. Flashing Receivers: Fabricate from the following materials:

- 1. Stainless Steel: 0.016 inch thick.

F. Roof-Penetration Flashing: Fabricate from the following materials:

- 1. Stainless Steel: 0.019 inch thick.

G. Roof-Drain Flashing: Fabricate from the following materials:

- 1. Stainless Steel: 0.016 inch thick.

2.7 WALL SHEET METAL FABRICATIONS

A. Through-Wall Flashing: Fabricate continuous flashings in minimum 96-inch- long, but not exceeding 12-foot- long, sections, under copings, and at shelf angles. Fabricate discontinuous lintel, sill, and similar flashings to extend 6 inches beyond each side of wall openings; and form with 2-inch- high, end dams. Fabricate from the following materials:

- 1. Stainless Steel: 0.016 inch thick.

B. Opening Flashings in Frame Construction: Fabricate head, sill, jamb, and similar flashings to extend 4 inches beyond wall openings. Form head and sill flashing with 2-inch- high, end dams. Fabricate from the following materials:

- 1. Stainless Steel: 0.016 inch thick.

2.8 MISCELLANEOUS SHEET METAL FABRICATIONS

A. Equipment Support Flashing: Fabricate from the following materials:

- 1. Stainless Steel: 0.019 inch thick.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, substrate, and other conditions affecting performance of the Work.
 - 1. Verify compliance with requirements for installation tolerances of substrates.
 - 2. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.
 - 3. Verify that air- or water-resistant barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 UNDERLAYMENT INSTALLATION

- A. Self-Adhering Sheet Underlayment: Install self-adhering sheet underlayment, wrinkle free. Prime substrate if recommended by underlayment manufacturer. Comply with temperature restrictions of underlayment manufacturer for installation; use primer for installing underlayment at low temperatures. Apply in shingle fashion to shed water, with end laps of not less than 6 inches staggered 24 inches between courses. Overlap side edges not less than 3-1/2 inches. Roll laps and edges with roller. Cover underlayment within 14 days.

3.3 INSTALLATION, GENERAL

- A. General: Anchor sheet metal flashing and trim and other components of the Work securely in place, with provisions for thermal and structural movement. Use fasteners[, **solder**], protective coatings, separators, sealants, and other miscellaneous items as required to complete sheet metal flashing and trim system.
 - 1. Install sheet metal flashing and trim true to line, levels, and slopes. Provide uniform, neat seams with minimum exposure of solder, welds, and sealant.
 - 2. Install sheet metal flashing and trim to fit substrates and to result in watertight performance. Verify shapes and dimensions of surfaces to be covered before fabricating sheet metal.
 - 3. Space cleats not more than 12 inches apart. Attach each cleat with at least two fasteners. Bend tabs over fasteners.
 - 4. Install exposed sheet metal flashing and trim with limited oil canning, and free of buckling and tool marks.
 - 5. Torch cutting of sheet metal flashing and trim is not permitted.
 - 6. Do not use graphite pencils to mark metal surfaces.
- B. Metal Protection: Where dissimilar metals contact each other, or where metal contacts pressure-treated wood or other corrosive substrates, protect against galvanic action or corrosion by painting contact surfaces with bituminous coating or by other permanent separation as recommended by sheet metal manufacturer or cited sheet metal standard.

1. Coat concealed side of uncoated-aluminum and stainless-steel sheet metal flashing and trim with bituminous coating where flashing and trim contact wood, ferrous metal, or cementitious construction.
 2. Underlayment: Where installing sheet metal flashing and trim directly on cementitious or wood substrates, install underlayment and cover with slip sheet.
- C. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at maximum of 10 feet with no joints within 24 inches of corner or intersection.
1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with sealant concealed within joints.
 2. Use lapped expansion joints only where indicated on Drawings.
- D. Fasteners: Use fastener sizes that penetrate substrate not less than recommended by fastener manufacturer to achieve maximum pull-out resistance.
- E. Conceal fasteners and expansion provisions where possible in exposed work and locate to minimize possibility of leakage. Cover and seal fasteners and anchors as required for a tight installation.
- F. Seal joints as required for watertight construction.
1. Use sealant-filled joints unless otherwise indicated. Embed hooked flanges of joint members not less than 1 inch into sealant. Form joints to completely conceal sealant. When ambient temperature at time of installation is between 40 and 70 deg F, set joint members for 50 percent movement each way. Adjust setting proportionately for installation at higher ambient temperatures. Do not install sealant-type joints at temperatures below 40 deg F.
 2. Prepare joints and apply sealants to comply with requirements in Section 079200 "Joint Sealants."
- G. Soldered Joints: Clean surfaces to be soldered, removing oils and foreign matter. Pre-tin edges of sheets with solder to width of 1-1/2 inches; however, reduce pre-tinning where pre-tinned surface would show in completed Work.
1. Do not solder aluminum sheet.
 2. Do not use torches for soldering.
 3. Heat surfaces to receive solder, and flow solder into joint. Fill joint completely. Completely remove flux and spatter from exposed surfaces.
 4. Stainless-Steel Soldering: Tin edges of uncoated sheets, using solder for stainless steel and acid flux. Promptly remove acid flux residue from metal after tinning and soldering. Comply with solder manufacturer's recommended methods for cleaning and neutralization.
- H. Rivets: Rivet joints in uncoated aluminum where necessary for strength.

3.4 ROOF FLASHING INSTALLATION

- A. General: Install sheet metal flashing and trim to comply with performance requirements, sheet metal manufacturer's written installation instructions, and cited sheet metal standard. Provide concealed fasteners where possible, and set units true to line, levels, and slopes. Install work with laps, joints, and seams that are permanently watertight and weather resistant.
- B. Copings: Anchor to resist uplift and outward forces according to recommendations in FM Global Property Loss Prevention Data Sheet 1-49 for specified FM Approvals' listing for required windstorm classification.
- C. Pipe or Post Counterflashing: Install counterflashing umbrella with close-fitting collar with top edge flared for elastomeric sealant, extending minimum of 4 inches over base flashing. Install stainless-steel draw band and tighten.
- D. Counterflashing: Coordinate installation of counterflashing with installation of base flashing. Insert counterflashing in reglets or receivers and fit tightly to base flashing. Extend counterflashing 4 inches over base flashing. Lap counterflashing joints minimum of 4 inches. Secure in waterproof manner by means of interlocking folded seam or blind rivets and sealant unless otherwise indicated.
- E. Roof-Penetration Flashing: Coordinate installation of roof-penetration flashing with installation of roofing and other items penetrating roof. Seal with elastomeric sealant and clamp flashing to pipes that penetrate roof.

3.5 WALL FLASHING INSTALLATION

- A. General: Install sheet metal wall flashing to intercept and exclude penetrating moisture according to cited sheet metal standard unless otherwise indicated. Coordinate installation of wall flashing with installation of wall-opening components such as windows, doors, and louvers.
- B. Through-Wall Flashing: Installation of through-wall flashing is specified in Section 042000 "Unit Masonry."
- C. Reglets: Installation of reglets is specified in Section 042000 "Unit Masonry."
- D. Opening Flashings in Frame Construction: Install continuous head, sill, jamb, and similar flashings to extend 4 inches beyond wall openings.

3.6 MISCELLANEOUS FLASHING INSTALLATION

- A. Equipment Support Flashing: Coordinate installation of equipment support flashing with installation of roofing and equipment. Weld or seal flashing with elastomeric sealant to equipment support member.

3.7 ERECTION TOLERANCES

- A. Installation Tolerances: Shim and align sheet metal flashing and trim within installed tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.

3.8 CLEANING AND PROTECTION

- A. Clean exposed metal surfaces of substances that interfere with uniform oxidation and weathering.
- B. Clean and neutralize flux materials. Clean off excess solder.
- C. Clean off excess sealants.
- D. Remove temporary protective coverings and strippable films as sheet metal flashing and trim are installed unless otherwise indicated in manufacturer's written installation instructions. On completion of sheet metal flashing and trim installation, remove unused materials and clean finished surfaces as recommended by sheet metal flashing and trim manufacturer. Maintain sheet metal flashing and trim in clean condition during construction.
- E. Replace sheet metal flashing and trim that have been damaged or that have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION 07 62 00

SECTION 07 71 00 - ROOF SPECIALTIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Copings.
2. Reglets and counterflashings.

1.2 PERFORMANCE REQUIREMENTS

- A. General Performance: Roof specialties shall withstand exposure to weather and resist thermally induced movement without failure, rattling, leaking, or fastener disengagement due to defective manufacture, fabrication, installation, or other defects in construction.
- B. FM Approvals' Listing: Manufacture and install copings that are listed in FM Approvals' "RoofNav" and approved for windstorm classification, Class 1-90. Identify materials with FM Approvals' markings.
- C. SPRI Wind Design Standard: Manufacture and install copings tested according to SPRI ES-1 and capable of resisting the following design pressures:
1. Design Pressure: As indicated on Drawings.
- D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes to prevent buckling, opening of joints, hole elongation, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Provide clips that resist rotation and avoid shear stress as a result of thermal movements. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
- B. Shop Drawings: For roof specialties. Include plans, elevations, expansion-joint locations, keyed details, and attachments to other work. Distinguish between plant- and field-assembled work. Include the following:
1. Details for expansion and contraction; locations of expansion joints, including direction of expansion and contraction.
 2. Pattern of seams and layout of fasteners, cleats, clips, and other attachments.
 3. Details of termination points and assemblies, including fixed points.
 4. Details of special conditions.

- C. Samples for Verification: For copings, reglets and counterflashings made from 12-inch lengths of full-size components including fasteners, cover joints, accessories, and attachments.

1.4 INFORMATIONAL SUBMITTALS

- A. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for copings.
- B. Warranty: Sample of special warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For roofing specialties to include in maintenance manuals.

1.6 QUALITY ASSURANCE

- A. Preinstallation Conference: Conduct conference at Project site.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Do not store roof specialties in contact with other materials that might cause staining, denting, or other surface damage. Store roof specialties away from uncured concrete and masonry.
- B. Protect strippable protective covering on roof specialties from exposure to sunlight and high humidity, except to extent necessary for the period of roof specialties installation.

1.8 WARRANTY

- A. Special Warranty on Painted Finishes: Manufacturer's standard form in which manufacturer agrees to repair finish or replace roof specialties that show evidence of deterioration of factory-applied finishes within specified warranty period.
 - 1. Fluoropolymer Finish: Deterioration includes, but is not limited to, the following:
 - a. Color fading more than 5 Hunter units when tested according to ASTM D 2244.
 - b. Chalking in excess of a No. 8 rating when tested according to ASTM D 4214.
 - c. Cracking, checking, peeling, or failure of paint to adhere to bare metal.
 - 2. Finish Warranty Period: 20 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 EXPOSED METALS

- A. Aluminum Sheet: ASTM B 209, alloy as standard with manufacturer for finish required, with temper to suit forming operations and performance required.
 - 1. Surface: Smooth, flat finish.
 - 2. Exposed Coil-Coated Finishes: Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' written instructions.

- a. Two-Coat Fluoropolymer: AAMA 620. System consisting of primer and fluoropolymer color topcoat containing not less than 70 percent PVDF resin by weight.
 - b. Concealed Surface: Pretreat with manufacturer's standard white or light-colored acrylic or polyester backer finish, consisting of prime coat and wash coat with a minimum total dry film thickness of 0.5 mil.
- B. Stainless-Steel Sheet: ASTM A 240/A 240M or ASTM A 666, Type 304, dead soft, fully annealed; with smooth, flat surface.
- 1. Finish: 2D (dull, cold rolled).

2.2 CONCEALED METALS

- A. Stainless-Steel Sheet: ASTM A 240/A 240M or ASTM A 666, Type 304.
- B. Zinc-Coated (Galvanized) Steel Sheet: ASTM A 653/A 653M, G90 coating designation.

2.3 UNDERLAYMENT MATERIALS

- A. Self-Adhering, High-Temperature Sheet: Minimum 30 to 40 mils thick, consisting of slip-resisting polyethylene-film top surface laminated to layer of butyl or SBS-modified asphalt adhesive, with release-paper backing; cold applied. Provide primer when recommended by underlayment manufacturer.
- 1. Thermal Stability: ASTM D 1970; stable after testing at 240 deg F.
 - 2. Low-Temperature Flexibility: ASTM D 1970; passes after testing at minus 20 deg F.

2.4 MISCELLANEOUS MATERIALS

- A. General: Provide materials and types of fasteners, protective coatings, sealants, and other miscellaneous items required by manufacturer for a complete installation.
- B. Fasteners: Manufacturer's recommended fasteners, suitable for application and designed to meet performance requirements. Furnish the following unless otherwise indicated:
 - 1. Exposed Penetrating Fasteners: Gasketed screws with hex washer heads matching color of sheet metal.
 - 2. Fasteners for Aluminum: Aluminum or Series 300 stainless steel.
 - 3. Fasteners for Zinc-Coated (Galvanized) Steel Sheet: Series 300 stainless steel or hot-dip zinc-coated steel according to ASTM A 153/A 153M or ASTM F 2329.
- C. Elastomeric Sealant: ASTM C 920, elastomeric silicone polymer sealant of type, grade, class, and use classifications required by roofing-specialty manufacturer for each application.
- D. Butyl Sealant: ASTM C 1311, single-component, solvent-release butyl rubber sealant; polyisobutylene plasticized; heavy bodied for hooked-type expansion joints with limited movement.
- E. Bituminous Coating: Cold-applied asphalt emulsion complying with ASTM D 1187.

2.5 COPINGS

- A. Copings: Manufactured coping system consisting of formed-metal coping cap in section lengths not exceeding 12 feet, concealed anchorage; corner units, end cap units, and concealed splice plates with same finish as coping caps.
 - 1. Coping-Cap Material: Formed aluminum, 0.050 inch thick, unless otherwise indicated.
 - a. Finish: Two-coat fluoropolymer.
 - b. Color: Refer to "Finish Schedule" located on Drawings for custom color selection.
 - 2. Corners: Factory mitered and mechanically clinched and sealed watertight.
 - 3. Coping-Cap Attachment Method: Snap-on, fabricated from coping-cap material.
 - 4. Snap-on-Coping Anchor Plates: Concealed, galvanized-steel sheet, 12 inches wide, with integral cleats.

2.6 REGLETS AND COUNTERFLASHINGS

- A. Reglets: Manufactured units formed to provide secure interlocking of separate reglet and counterflashing pieces, from the following exposed metal:
 - 1. Stainless Steel: 0.020 inch thick.
 - 2. Corners: Factory mitered and continuously welded.
 - 3. Stucco Type, Embedded: Provide reglets with upturned fastening flange and extension leg of length to match thickness of applied finish materials.
- B. Counterflashings: Manufactured units of heights to overlap top edges of base flashings by 4 inches and in lengths not exceeding 12 feet designed to snap into reglets and compress against base flashings with joints lapped, from the following exposed metal:
 - 1. Stainless Steel: 0.020 inch thick.
- C. Accessories:
 - 1. Flexible-Flashing Retainer: Provide resilient plastic or rubber accessory to secure flexible flashing in reglet where clearance does not permit use of standard metal counterflashing or where reglet is provided separate from metal counterflashing.
 - 2. Counterflashing Wind-Restraint Clips: Provide clips to be installed before counterflashing to prevent wind uplift of counterflashing lower edge.

2.7 ACCESSORIES

- A. Concealed Fasteners: Same metal as item fastened or other noncorrosive metal as recommended by manufacturer.
- B. Adhesives: Type recommended by manufacturer for substrate and Project conditions, and formulated to withstand minimum 60 lbf/sq. ft. wind-uplift force.

2.8 GENERAL FINISH REQUIREMENTS

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Protect mechanical and painted finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, to verify actual locations, dimensions, and other conditions affecting performance of the Work.
- B. Examine walls, roof edges, and parapets for suitable conditions for roof specialties.
- C. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 UNDERLAYMENT INSTALLATION

- A. Self-Adhering Sheet Underlayment: Install wrinkle free. Apply primer if required by underlayment manufacturer. Comply with temperature restrictions of underlayment manufacturer for installation; use primer rather than nails for installing underlayment at low temperatures. Apply in shingle fashion to shed water. Overlap edges not less than 3-1/2 inches. Roll laps with roller. Cover underlayment within 14 days.

3.3 INSTALLATION, GENERAL

- A. General: Install roof specialties according to manufacturer's written instructions. Anchor roof specialties securely in place, with provisions for thermal and structural movement. Use fasteners, solder, protective coatings, separators, sealants, and other miscellaneous items as required to complete roof-specialty systems.
 - 1. Install roof specialties level, plumb, true to line and elevation; with limited oil-canning and without warping, jogs in alignment, buckling, or tool marks.
 - 2. Provide uniform, neat seams with minimum exposure of solder and sealant.
 - 3. Install roof specialties to fit substrates and to result in watertight performance. Verify shapes and dimensions of surfaces to be covered before manufacture.
 - 4. Torch cutting of roof specialties is not permitted.
 - 5. Do not use graphite pencils to mark metal surfaces.

- B. **Metal Protection:** Protect metals against galvanic action by separating dissimilar metals from contact with each other or with corrosive substrates by painting contact surfaces with bituminous coating or by other permanent separation as recommended by manufacturer.
 - 1. Coat concealed side of uncoated aluminum roof specialties with bituminous coating where in contact with wood, ferrous metal, or cementitious construction.
 - 2. Underlayment: Where installing metal flashing directly on cementitious or wood substrates, install a course of self-adhering, high-temperature sheet underlayment.
 - 3. Bed flanges in thick coat of asphalt roofing cement where required by manufacturers of roof specialties for waterproof performance.
- C. **Expansion Provisions:** Allow for thermal expansion of exposed roof specialties.
 - 1. Space movement joints at a maximum of 12 feet with no joints within 18 inches of corners or intersections unless otherwise shown on Drawings.
 - 2. When ambient temperature at time of installation is between 40 and 70 deg F, set joint members for 50 percent movement each way. Adjust setting proportionately for installation at higher ambient temperatures.
- D. **Fastener Sizes:** Use fasteners of sizes that will penetrate wood blocking or sheathing not less than 1-1/4 inches for nails and not less than 3/4 inch for wood screws.
- E. Seal joints with elastomeric sealant as required by roofing-specialty manufacturer.
- F. Seal joints as required for watertight construction. Place sealant to be completely concealed in joint. Do not install sealants at temperatures below 40 deg F.

3.4 COPING INSTALLATION

- A. Install cleats, anchor plates, and other anchoring and attachment accessories and devices with concealed fasteners.
- B. Anchor copings to meet performance requirements.
 - 1. Interlock face and back leg drip edges of snap-on coping cap into cleated anchor plates anchored to substrate at manufacturer's required spacing that meets performance requirements.

3.5 REGLET AND COUNTERFLASHING INSTALLATION

- A. **General:** Coordinate installation of reglets and counterflashings with installation of base flashings.
- B. **Embedded Reglets:** Install reglets complying with manufacturers written instructions to receive flashings. Install at height so that inserted counterflashings overlap 4 inches over top edge of base flashings.
- C. **Counterflashings:** Insert counterflashings into reglets or other indicated receivers; ensure that counterflashings overlap 4 inches over top edge of base flashings. Lap counterflashing joints a minimum of 4 inches and bed with butyl sealant. Fit counterflashings tightly to base flashings.

3.6 CLEANING AND PROTECTION

- A. Clean exposed metal surfaces of substances that interfere with uniform oxidation and weathering.
- B. Clean and neutralize flux materials. Clean off excess solder and sealants.
- C. Remove temporary protective coverings and strippable films as roof specialties are installed. On completion of installation, clean finished surfaces including removing unused fasteners, metal filings, pop rivet stems, and pieces of flashing. Maintain roof specialties in a clean condition during construction.
- D. Replace roof specialties that have been damaged or that cannot be successfully repaired by finish touchup or similar minor repair procedures.

END OF SECTION 07 71 00

SECTION 07 72 00 - ROOF ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Roof hatches.

1.2 PERFORMANCE REQUIREMENTS

- A. General Performance: Roof accessories shall withstand exposure to weather and resist thermally induced movement without failure, rattling, leaking, or fastener disengagement due to defective manufacture, fabrication, installation, or other defects in construction.

1. Roof hatches shall be approved in accordance with Miami Dade County Test Protocols.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of roof accessory indicated. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.

1. Notice of Acceptance Letter: Provide roof hatch manufacturer's notice of acceptance letter certifying compliance with Miami Dade County testing standards.

- B. Shop Drawings: For roof accessories. Include plans, elevations, keyed details, and attachments to other work. Indicate dimensions, loadings, and special conditions. Distinguish between plant- and field-assembled work.

- C. Samples: For each exposed product and for each color and texture specified, prepared on Samples of size to adequately show color.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Roof plans, drawn to scale, and coordinating penetrations and roof-mounted items. Show the following:

1. Size and location of roof accessories specified in this Section.
2. Method of attaching roof accessories to roof or building structure.
3. Other roof-mounted items including mechanical and electrical equipment, ductwork, piping, and conduit.
4. Required clearances.

- B. Warranty: Sample of special warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For roof accessories to include in operation and maintenance manuals.

1.6 COORDINATION

- A. Coordinate layout and installation of roof accessories with roofing membrane and base flashing and interfacing and adjoining construction to provide a leakproof, weathertight, secure, and noncorrosive installation.
- B. Coordinate dimensions with rough-in information or Shop Drawings of equipment to be supported.

PART 2 - PRODUCTS

2.1 METAL MATERIALS

- A. Zinc-Coated (Galvanized) Steel Sheet: ASTM A 653/A 653M, G90 coating designation.
 - 1. Factory Prime Coating: Where field painting is indicated, apply pretreatment and factory-applied, alkyd base red oxide primer coat, with a minimum dry film thickness of 0.2 mil.
- B. Steel Shapes: ASTM A 36/A 36M, hot-dip galvanized according to ASTM A 123/A 123M unless otherwise indicated.
- C. Steel Tube: ASTM A 500, round tube.

2.2 MISCELLANEOUS MATERIALS

- A. General: Provide materials and types of fasteners, protective coatings, sealants, and other miscellaneous items required by manufacturer for a complete installation.
- B. Glass-Fiber Board Insulation: ASTM C 726, thickness as indicated.
- C. Wood Nailers: Softwood lumber, pressure treated with waterborne preservatives for aboveground use, acceptable to authorities having jurisdiction, containing no arsenic or chromium, and complying with AWPA C2; not less than 1-1/2 inches thick.
- D. Bituminous Coating: Cold-applied asphalt emulsion complying with ASTM D 1187.
- E. Underlayment:
 - 1. Felt: ASTM D 226, Type II (No. 30), asphalt-saturated organic felt, nonperforated.
 - 2. Polyethylene Sheet: 6-mil- thick polyethylene sheet complying with ASTM D 4397.
 - 3. Slip Sheet: Building paper, 3-lb/100 sq. ft. minimum, rosin sized.
- F. Fasteners: Roof accessory manufacturer's recommended fasteners suitable for application and metals being fastened. Match finish of exposed fasteners with finish of material being fastened.

Provide nonremovable fastener heads to exterior exposed fasteners. Furnish the following unless otherwise indicated:

1. Fasteners for Zinc-Coated or Aluminum-Zinc Alloy-Coated Steel: Series 300 stainless steel or hot-dip zinc-coated steel according to ASTM A 153/A 153M or ASTM F 2329.
- G. Gaskets: Manufacturer's standard tubular or fingered design of neoprene, EPDM, PVC, or silicone or a flat design of foam rubber, sponge neoprene, or cork.
- H. Elastomeric Sealant: ASTM C 920, elastomeric silicone polymer sealant as recommended by roof accessory manufacturer for installation indicated; low modulus; of type, grade, class, and use classifications required to seal joints and remain watertight.
- I. Asphalt Roofing Cement: ASTM D 4586, asbestos free, of consistency required for application.

2.3 ROOF HATCH

- A. Roof Hatches: Metal roof-hatch units with lids and insulated single-walled curbs, welded or mechanically fastened and sealed corner joints, continuous lid-to-curb counterflashing and weathertight perimeter gasketing, and integrally formed deck-mounting flange at perimeter bottom.
 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Babcock-Davis Hatchways, Inc.
 - b. Bilco Company
 - c. Dur-Red Products, Inc.
 - d. J. L. Industries, Inc.
 - e. Milcor, Inc.
 - f. Nystrom Products Co.
- B. Type and Size: Single-leaf lid, 30 by 36 inches.
- C. Loads: Minimum 40-lbf/sq. ft. external live load and 20-lbf/sq. ft. internal uplift load.
- D. Hatch Material: Zinc-coated (galvanized) steel sheet, 0.075 (14 gauge) inch thick.
 1. Finish: Factory prime coating.
- E. Construction:
 1. Insulation: Glass-fiber board.
 2. Hatch Lid: Opaque, insulated, and double walled, with manufacturer's standard metal liner of same material and finish as outer metal lid.
 3. Curb Liner: Manufacturer's standard, of same material and finish as metal curb.
 - a. Steel Sheet Thickness: 0.0299 inch (22 gauge) thick.

4. On ribbed or fluted metal roofs, form flange at perimeter bottom to conform to roof profile.
 5. Fabricate curbs of same material and finish as metal hatch lid and at a minimum height of 12 inches unless otherwise indicated.
 6. Sloping Roofs: Where slope or roof deck exceeds 1:48, fabricate curb with perimeter curb height that is tapered to accommodate roof slope so that top surfaces of perimeter curb are level. Equip hatch with water diverter or cricket on side that obstructs water flow.
- F. Hardware: Stainless-steel spring latch with turn handles, heavy-duty butt- or pintle-type hinge system, hold-open arms with a 1 inch diameter red vinyl grip handle and padlock hasps inside and outside.
1. Provide two-point latch on lids larger than 84 inches.
- G. Ladders: Refer to Division 05 Section "Metal Fabrications" for metal ladders.
- H. Ladder-Assist Post: Roof-hatch manufacturer's standard device for attachment to roof-access ladder.
1. Operation: Post locks in place on full extension; release mechanism returns post to closed position.
 2. Height: 42 inches above finished roof deck.
 3. Material: High strength steel tube.
 4. Post: Square tubing.
 5. Finish: Manufacturer's standard baked enamel or powder coat.
 - a. Color: Yellow, unless otherwise indicated.

2.4 GENERAL FINISH REQUIREMENTS

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, to verify actual locations, dimensions, and other conditions affecting performance of the Work.
- B. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.
- C. Verify dimensions of roof openings for roof accessories.

- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. General: Install roof accessories according to manufacturer's written instructions.
 - 1. Install roof accessories level, plumb, true to line and elevation, and without warping, jogs in alignment, excessive oil canning, buckling, or tool marks.
 - 2. Anchor roof accessories securely in place so they are capable of resisting indicated loads.
 - 3. Use fasteners, separators, sealants, and other miscellaneous items as required to complete installation of roof accessories and fit them to substrates.
 - 4. Install roof accessories to resist exposure to weather without failing, rattling, leaking, or loosening of fasteners and seals.
- B. Metal Protection: Protect metals against galvanic action by separating dissimilar metals from contact with each other or with corrosive substrates by painting contact surfaces with bituminous coating or by other permanent separation as recommended by manufacturer.
 - 1. Coat concealed side of roof accessories with bituminous coating where in contact with wood, ferrous metal, or cementitious construction.
 - 2. Underlayment: Where installing roof accessories directly on cementitious or wood substrates, install a course of felt underlayment and cover with a slip sheet, or install a course of polyethylene sheet.
 - 3. Bed flanges in thick coat of asphalt roofing cement where required by manufacturers of roof accessories for waterproof performance.
- C. Roof-Hatch Installation:
 - 1. Install roof hatch so top surface of hatch curb is level.
 - 2. Verify that roof hatch operates properly. Clean, lubricate, and adjust operating mechanism and hardware.
 - 3. Attach ladder-assist post according to manufacturer's written instructions.
- D. Preformed Flashing-Sleeve Installation: Secure flashing sleeve to roof membrane according to flashing-sleeve manufacturer's written instructions.
- E. Seal joints with elastomeric sealant as required by roof accessory manufacturer.

3.3 REPAIR AND CLEANING

- A. Touch up factory-primed surfaces with compatible primer ready for field painting according to Division 09 Section "Exterior Painting."
- B. Clean exposed surfaces according to manufacturer's written instructions.
- C. Clean off excess sealants.
- D. Replace roof accessories that have been damaged or that cannot be successfully repaired by finish touchup or similar minor repair procedures.

Gensler

057.7202.950

Bank of America / BAC Performance / Bulletin #02-2017 / 06-26-17

January 22, 2021
Issue for Construction

Bank of America
BAC Centerville GU
Centerville, UT

END OF SECTION 07 72 00

SECTION 07 92 00 - JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Silicone joint sealants.
2. Urethane joint sealants.
3. Latex joint sealants.
4. Preformed joint sealants.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each joint-sealant product indicated.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.

C. Samples for Initial Selection: Manufacturer's color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.

D. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch- wide joints formed between two 6-inch- long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.

E. Joint-Sealant Schedule: Include the following information:

1. Joint-sealant application, joint location, and designation.
2. Joint-sealant manufacturer and product name.
3. Joint-sealant formulation.
4. Joint-sealant color.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For qualified Installer.

B. Product Certificates: For each kind of joint sealant and accessory, from manufacturer.

- C. Sealant, Waterproofing, and Restoration Institute (SWRI) Validation Certificate: For each sealant specified to be validated by SWRI's Sealant Validation Program.
- D. Warranties: Sample of special warranties.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.
- B. Source Limitations: Obtain each kind of joint sealant from single source from single manufacturer.

1.5 PROJECT CONDITIONS

- A. Do not proceed with installation of joint sealants under the following conditions:
 - 1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
 - 2. When joint substrates are wet.
 - 3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
 - 4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

1.6 WARRANTY

- A. Special Installer's Warranty: Manufacturer's standard form in which Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
 - 1. Warranty Period: Two years from date of Substantial Completion.
- B. Special Manufacturer's Warranty: Manufacturer's standard form in which joint-sealant manufacturer agrees to furnish joint sealants to repair or replace those that do not comply with performance and other requirements specified in this Section within specified warranty period.
 - 1. Warranty Period: Five years from date of Substantial Completion.
- C. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:
 - 1. Movement of the structure caused by structural settlement or errors attributable to design or construction resulting in stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
 - 2. Disintegration of joint substrates from natural causes exceeding design specifications.
 - 3. Mechanical damage caused by individuals, tools, or other outside agents.
 - 4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

PART 2 - PRODUCTS

2.1 MATERIALS, GENERAL

- A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.
- B. VOC Content of Interior Sealants: Sealants and sealant primers used inside the weatherproofing system shall comply with the following limits for VOC content when calculated according to 40 CFR 59, Subpart D (EPA Method 24):
 - 1. Architectural Sealants: 250 g/L.
 - 2. Sealant Primers for Nonporous Substrates: 250 g/L.
 - 3. Sealant Primers for Porous Substrates: 775 g/L.
- C. Liquid-Applied Joint Sealants: Comply with ASTM C 920 and other requirements indicated for each liquid-applied joint sealant specified, including those referencing ASTM C 920 classifications for type, grade, class, and uses related to exposure and joint substrates.
- D. Stain-Test-Response Characteristics: Where sealants are specified to be nonstaining to porous substrates, provide products that have undergone testing according to ASTM C 1248 and have not stained porous joint substrates indicated for Project.
- E. Colors of Exposed Joint Sealants: Match Architect's samples.

2.2 SILICONE JOINT SEALANTS

- A. Single-Component, Nonsag, Neutral-Curing Silicone Joint Sealant: ASTM C 920, Type S, Grade NS, Class 50, for Use NT.
 - 1. For Horizontal and Vertical Applications:
 - a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - 1) Dow Corning Corporation; 756 SMS.
 - 2) GE Advanced Materials - Silicones; SilPruf SCS9000.
 - 3) Tremco Incorporated; Spectrem 3.
- B. Mildew-Resistant, Single-Component, Nonsag, Neutral-Curing Silicone Joint Sealant: ASTM C 920, Type S, Grade NS, Class 25, for Use NT.
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Dow Corning; 786 Mildew Resistant Silicone Sealant.
 - b. GE Advanced Materials - Silicones; Sanitary SCS 1700.
 - c. Tremco, an RPM Co.; Tremsil 200 Sanitary.

2.3 URETHANE JOINT SEALANTS

- A. Multicomponent, Nonsag, Urethane Joint Sealant: ASTM C 920, Type M, Grade NS, Class 50, for Use NT.
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Pecora Corporation; Dynatrol II.
 - b. Polymeric Systems, Inc.; PSI-270.
 - c. Tremco Incorporated; Dymeric 240.
- B. Immersible Multicomponent, Pourable, Traffic-Grade, Urethane Joint Sealant: ASTM C 920, Type M, Grade P, Class 25, for Use T and I.
 - 1. For Horizontal Applications with Slopes not Exceeding 5% (Self Leveling):
 - a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - 1) BASF Building Systems; Sonolastic SL 2.
 - 2) Pecora Corporation; Urexpan NR-200.
 - 3) Tremco Incorporated; THC 900.
 - 2. For Horizontal Applications with Slopes Exceeding 5%:
 - a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - 1) BASF Building Systems; Sonolastic SL 2.
 - 2) Tremco Incorporated; THC 901.

2.4 LATEX JOINT SEALANTS

- A. Latex Joint Sealant: Acrylic latex or siliconized acrylic latex, ASTM C 834, Type OP, Grade NF.
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. BASF Building Systems; Sonolac.
 - b. Pecora Corporation; AC-20+.
 - c. Tremco Incorporated; Tremflex 834.

2.5 PREFORMED JOINT SEALANTS

- A. Preformed Silicone Joint Sealants: Manufacturer's standard sealant consisting of precured low-modulus silicone extrusion, in sizes to fit joint widths indicated, combined with a neutral-curing silicone sealant for bonding extrusions to substrates.
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Dow Corning Corporation; 123 Silicone Seal.
 - b. GE Advanced Materials - Silicones; UltraSpan US1100.
 - c. Pecora Corporation; Sil-Span.
- B. Preformed Foam Joint Sealant: Manufacturer's standard preformed, precompressed, open-cell foam sealant manufactured from urethane foam with minimum density of 10 lb/cu. ft. and impregnated with a nondrying, water-repellent agent. Factory produce in precompressed sizes in roll or stick form to fit joint widths indicated; coated on one side with a pressure-sensitive adhesive and covered with protective wrapping.
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Dayton Superior Specialty Chemicals; Polytite Standard.
 - b. EMSEAL Joint Systems, Ltd.; Emseal 25V.
 - c. Willseal USA, LLC; Willseal 600.

2.6 JOINT SEALANT BACKING

- A. General: Provide sealant backings of material that are nonstaining; are compatible with joint substrates, sealants, primers, and other joint fillers; and are approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
- B. Cylindrical Sealant Backings: ASTM C 1330, Type C (closed-cell material with a surface skin), Type B (bicellular material with a surface skin) or any of the preceding types, as approved in writing by joint-sealant manufacturer for joint application indicated, and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Type C: (Closed-cell material with a surface skin.)
 - 1) HBR Closed Cell Backer Rod; Nomaco, Inc.
 - 2) Sonneborn Closed-Cell Backer-Rod; BASF.
 - b. Type B: (Bicellular material with a surface skin.)

- 1) SOFROD; Nomaco, Inc.
- 2) Sonneborn Sonolastic Soft Backer-Rod; BASF.

- C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

2.7 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.
- C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:
1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
 2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:
 - a. Concrete.
 - b. Masonry.
 - c. Unglazed surfaces of ceramic tile.

3. Remove laitance and form-release agents from concrete.
4. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:

- a. Metal.
- b. Glass.

- B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.
- C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

- A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.
- B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- C. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
 1. Do not leave gaps between ends of sealant backings.
 2. Do not stretch, twist, puncture, or tear sealant backings.
 3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.
- D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.
- E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:
 1. Place sealants so they directly contact and fully wet joint substrates.
 2. Completely fill recesses in each joint configuration.
 3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.

1. Remove excess sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
3. Provide concave joint profile per Figure 8A in ASTM C 1193, unless otherwise indicated.

G. Installation of Preformed Silicone-Sealant System: Comply with the following requirements:

1. Apply masking tape to each side of joint, outside of area to be covered by sealant system.
2. Apply silicone sealant to each side of joint to produce a bead of size complying with preformed silicone-sealant system manufacturer's written instructions and covering a bonding area of not less than 3/8 inch. Hold edge of sealant bead 1/4 inch inside masking tape.
3. Within 10 minutes of sealant application, press silicone extrusion into sealant to wet extrusion and substrate. Use a roller to apply consistent pressure and ensure uniform contact between sealant and both extrusion and substrate.
4. Complete installation of sealant system in horizontal joints before installing in vertical joints. Lap vertical joints over horizontal joints. At ends of joints, cut silicone extrusion with a razor knife.

H. Installation of Preformed Foam Sealants: Install each length of sealant immediately after removing protective wrapping. Do not pull or stretch material. Produce seal continuity at ends, turns, and intersections of joints. For applications at low ambient temperatures, apply heat to sealant in compliance with sealant manufacturer's written instructions.

3.4 CLEANING

- A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.5 PROTECTION

- A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

3.6 JOINT-SEALANT SCHEDULE

- A. Joint-Sealant Application: Exterior joints in horizontal traffic surfaces subject to water immersion.
1. Joint Locations:
 - a. Joints between paving.
 - b. Other joints as indicated.
 2. Urethane Joint Sealant: Immersible, multicomponent, pourable, traffic grade.
 3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

B. Joint-Sealant Application: Exterior joints in vertical surfaces and horizontal nontraffic surfaces.

1. Joint Locations:
 - a. Construction joints in cast-in-place concrete.
 - b. Joints between metal panels.
 - c. Joints between different materials listed above.
 - d. Perimeter joints between materials listed above and frames of doors, windows and louvers.
 - e. Control and expansion joints in ceilings and other overhead surfaces.
 - f. Other joints as indicated.
2. Silicone Joint Sealant: Single component, nonsag, neutral curing, Class 50.
3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

C. Joint-Sealant Application: Exterior joints in vertical surfaces.

1. Joint Locations:
 - a. Joints between different materials as directed by Architect.
 - b. Other joints as indicated.
2. Urethane Joint Sealant: Multicomponent, nonsag,, Class 50.
3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

D. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces.

1. Joint Locations:
 - a. Control and expansion joints on exposed interior surfaces of exterior walls.
 - b. Perimeter joints of exterior openings where indicated.
 - c. Vertical joints on exposed surfaces of walls and partitions.
 - d. Perimeter joints between interior wall surfaces and frames of interior doors windows and elevator entrances.
 - e. Other joints as indicated.
2. Joint Sealant: Latex.
3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.

E. Joint-Sealant Application: Mildew-resistant interior joints in vertical surfaces and horizontal nontraffic surfaces.

1. Joint Sealant Location:
 - a. Joints between plumbing fixtures and adjoining walls, floors, counters, vanities, and at janitor closet mop receptor to wall transition
 - b. Tile control and expansion joints where indicated.
 - c. Other joints as indicated.
2. Joint Sealant: Mildew resistant, single component, nonsag, neutral curing, Silicone.
3. Joint Sealant Color: As selected by Architect from manufacturer's full range of colors.

Gensler

057.7202.950

Bank of America / BAC Performance / Specification Update / 01-27-14

January 22, 2021
Issue for Construction

Bank of America
BAC Centerville GU
Centerville, UT

END OF SECTION 07 92 00

SECTION 08 11 13 - HOLLOW METAL DOORS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Hollow-metal work.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 DEFINITIONS

- A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or SDI A250.8.

1.3 COORDINATION

- A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.

1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1. Include construction details, material descriptions, core descriptions, and finishes.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.
 - d. LEED Materials and Resources Calculator.

C. Shop Drawings: Include the following:

1. Elevations of each door type.
2. Details of doors, including vertical- and horizontal-edge details and metal thicknesses.

3. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
4. Locations of reinforcement and preparations for hardware.
5. Details of each different wall opening condition.
6. Details of anchorages, joints, field splices, and connections.
7. Details of accessories.
8. Details of moldings, removable stops, and glazing.

D. Samples for Initial Selection: For units with factory-applied color finishes.

E. Samples for Verification:

1. For each type of exposed finish required, prepared on Samples of not less than 3 by 5 inches.
2. For "Doors" and "Frames" subparagraphs below, prepare Samples approximately 12 by 12 inches to demonstrate compliance with requirements for quality of materials and construction:
 - a. Doors: Show vertical-edge, top, and bottom construction; core construction; and hinge and other applied hardware reinforcement. Include separate section showing glazing if applicable.
 - b. Frames: Show profile, corner joint, floor and wall anchors, and silencers. Include separate section showing fixed hollow-metal panels and glazing if applicable.

F. Schedule: Provide a schedule of hollow-metal work prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final Door Hardware Schedule.

1.6 QUALITY ASSURANCE

A. Source Limitations: Obtain hollow-metal work from single source from single manufacturer.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Deliver hollow-metal work palletized, packaged, or crated to provide protection during transit and Project-site storage. Do not use nonvented plastic.

1. Provide additional protection to prevent damage to factory-finished units.

B. Store hollow-metal work vertically under cover at Project site with head up. Place on minimum 4-inch- high wood blocking. Provide minimum 1/4-inch space between each stacked door to permit air circulation.

PART 2 - PRODUCTS

2.1 INTERIOR DOORS AND FRAMES

A. Construct interior doors and frames to comply with the standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.

B. Hollow-Metal Doors and Frames: NAAMM-HMMA 860. At locations indicated in the Door and Frame Schedule.

1. Physical Performance: Level A according to SDI A250.4.
2. Frames:
 - a. Products: Subject to compliance with requirements, provide one of the following:
 - 1) Ceco Door Products; an Assa Abloy Group company; "S - Series"
 - 2) Curries Company; an Assa Abloy Group company; "CM-Series"
 - 3) Steelcraft; an Ingersoll-Rand company; "F-Series"
 - b. Materials: Uncoated steel sheet, minimum thickness of 0.053 inch.
 - c. Construction: Full profile welded.
3. Exposed Finish: Prime.

2.2 EXTERIOR HOLLOW-METAL DOORS AND FRAMES

A. Construct exterior doors and frames to comply with the standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.

B. Commercial Doors and Frames: NAAMM-HMMA 861. At locations indicated in the Door and Frame Schedule.

1. Physical Performance: Level A according to SDI A250.4.
2. Doors:
 - a. Products: Subject to compliance with requirements, provide one of the following:
 - 1) Ceco Door Products; an Assa Abloy Group company; "Trio - HE"
 - 2) Curries Company; an Assa Abloy Group company; "747 Series – Steel Stiffened"
 - 3) Steelcraft; an Ingersoll-Rand company; "B - Series"
 - b. Type: As indicated in the Door and Frame Schedule.
 - c. Thickness: 1-3/4 inches
 - d. Face: Metallic-coated steel sheet, minimum thickness of 0.053 inch, with minimum G60A60 coating.
 - e. Edge Construction: Continuously welded with no visible seam.
 - f. Core: Steel stiffened.
 - 1) Thermal-Rated Doors: Provide doors fabricated with thermal-resistance value (R-value) of not less than 2.1 deg F x h x sq. ft./Btu when tested according to ASTM C 1363.
3. Frames:

- a. Products: Subject to compliance with requirements, provide one of the following:
 - 1) Ceco Door Products; an Assa Abloy Group company; "S - Series"
 - 2) Curries Company; an Assa Abloy Group company; "M14"
 - 3) Steelcraft; an Ingersoll-Rand company; "F - Series"
 - b. Materials: Metallic-coated steel sheet, minimum thickness of 0.067 inch, with minimum G60A60 coating.
 - c. Construction: Full profile welded.
4. Exposed Finish: Prime.

2.3 FRAME ANCHORS

- A. Jamb Anchors:
 - 1. Stud-Wall Type: Designed to engage stud, welded to back of frames; not less than 0.042 inch thick.
 - 2. Compression Type for Drywall Slip-on Frames: Adjustable compression anchors.
- B. Floor Anchors: Formed from same material as frames, minimum thickness of 0.042 inch, and as follows:
 - 1. Monolithic Concrete Slabs: Clip-type anchors, with two holes to receive fasteners.
 - 2. Separate Topping Concrete Slabs: Adjustable-type anchors with extension clips, allowing not less than 2-inch height adjustment. Terminate bottom of frames at finish floor surface.

2.4 MATERIALS

- A. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B; suitable for exposed applications.
- B. Hot-Rolled Steel Sheet: ASTM A 1011/A 1011M, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.
- C. Metallic-Coated Steel Sheet: ASTM A 653/A 653M, Commercial Steel (CS), Type B.
- D. Frame Anchors: ASTM A 879/A 879M, Commercial Steel (CS), 04Z coating designation; mill phosphatized.
 - 1. For anchors built into exterior walls, steel sheet complying with ASTM A 1008/A 1008M or ASTM A 1011/A 1011M, hot-dip galvanized according to ASTM A 153/A 153M, Class B.
- E. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A 153/A 153M.
- F. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow-metal frames of type indicated.

- G. Grout: ASTM C 476, except with a maximum slump of 4 inches, as measured according to ASTM C 143/C 143M.
- H. Mineral-Fiber Insulation: ASTM C 665, Type I (blankets without membrane facing); consisting of fibers manufactured from slag or rock wool; with maximum flame-spread and smoke-developed indexes of 25 and 50, respectively; passing ASTM E 136 for combustion characteristics.
- I. Bituminous Coating: Cold-applied asphalt mastic, compounded for 15-mil dry film thickness per coat. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.

2.5 FABRICATION

- A. Fabricate hollow-metal work to be rigid and free of defects, warp, or buckle. Accurately form metal to required sizes and profiles, with minimum radius for metal thickness. Where practical, fit and assemble units in manufacturer's plant. To ensure proper assembly at Project site, clearly identify work that cannot be permanently factory assembled before shipment.
- B. Hollow-Metal Doors:
 - 1. Steel-Stiffened Door Cores: Provide minimum thickness 0.026 inch, steel vertical stiffeners of same material as face sheets extending full-door height, with vertical webs spaced not more than 6 inches apart. Spot weld to face sheets no more than 5 inches o.c. Fill spaces between stiffeners with glass- or mineral-fiber insulation.
 - 2. Vertical Edges for Single-Acting Doors: Bevel edges 1/8 inch in 2 inches.
 - 3. Top Edge Closures: Close top edges of doors with inverted closures of same material as face sheets.
 - 4. Bottom Edge Closures: Close bottom edges of doors with end closures or channels of same material as face sheets.
 - 5. Exterior Doors: Provide weep-hole openings in bottoms of exterior doors to permit moisture to escape. Seal joints in top edges of doors against water penetration.
- C. Hollow-Metal Frames: Where frames are fabricated in sections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of same thickness metal as frames.
 - 1. Frames: Provide closed tubular members with no visible face seams or joints, fabricated from same material as door frame. Fasten members at crossings and to jambs by butt welding.
 - 2. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
 - 3. Grout Guards: Weld guards to frame at back of hardware mortises in frames to be grouted.
 - 4. Floor Anchors: Weld anchors to bottoms of jambs with at least four spot welds per anchor; however, for slip-on drywall frames, provide anchor clips or countersunk holes at bottoms of jambs.
 - 5. Jamb Anchors: Provide number and spacing of anchors as follows:

- a. Stud-Wall Type: Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:
 - 1) Three anchors per jamb up to 60 inches high.
 - 2) Four anchors per jamb from 60 to 90 inches high.
 - 3) Five anchors per jamb from 90 to 96 inches high.
 - 4) Five anchors per jamb plus one additional anchor per jamb for each 24 inches or fraction thereof above 96 inches high.
 - b. Compression Type: Not less than two anchors in each frame.
6. Door Silencers: Drill stops to receive door silencers as follows. Keep holes clear during construction.
- a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
 - b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.
- D. Fabricate concealed stiffeners and edge channels from either cold- or hot-rolled steel sheet.
- E. Hardware Preparation: Factory prepare hollow-metal work to receive templated mortised hardware; include cutouts, reinforcement, mortising, drilling, and tapping according to SDI A250.6, the Door Hardware Schedule, and templates.
- 1. Reinforce doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.
 - 2. Comply with applicable requirements in SDI A250.6 and BHMA A156.115 for preparation of hollow-metal work for hardware.
- 2.6 STEEL FINISHES
- A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.
- 1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in for embedded and built-in anchors to verify actual locations before frame installation.
- C. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.

- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces.
- B. Drill and tap doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.

3.3 INSTALLATION

- A. General: Install hollow-metal work plumb, rigid, properly aligned, and securely fastened in place. Comply with Drawings and manufacturer's written instructions.
- B. Hollow-Metal Frames: Install hollow-metal frames of size and profile indicated. Comply with NAAMM-HMMA 840 as required by standards specified.
 - 1. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces, leaving surfaces smooth and undamaged.
 - a. Where frames are fabricated in sections because of shipping or handling limitations, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces.
 - b. Install door silencers in frames before grouting.
 - c. Remove temporary braces necessary for installation only after frames have been properly set and secured.
 - d. Check plumb, square, and twist of frames as walls are constructed. Shim as necessary to comply with installation tolerances.
 - e. Field apply bituminous coating to backs of frames that will be filled with grout containing antifreezing agents.
 - 2. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor, and secure with postinstalled expansion anchors.
 - a. Floor anchors may be set with power-actuated fasteners instead of postinstalled expansion anchors if so indicated and approved on Shop Drawings.
 - 3. Metal-Stud Partitions: Solidly pack mineral-fiber insulation inside frames.
 - 4. In-Place Metal or Wood-Stud Partitions: Secure slip-on drywall frames in place according to manufacturer's written instructions.
 - 5. Installation Tolerances: Adjust hollow-metal door frames for squareness, alignment, twist, and plumb to the following tolerances:
 - a. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
 - b. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.

- c. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
 - d. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.
- C. Hollow-Metal Doors: Fit hollow-metal doors accurately in frames, within clearances specified below. Shim as necessary.
 - 1. Non-Fire-Rated Steel Doors:
 - a. Between Door and Frame Jambs and Head: 3/32 inch.
 - b. Between Edges of Pairs of Doors: 1/8 inch to 1/4 inch plus or minus 1/32 inch.
 - c. At Bottom of Door: 3/8 inch, if no threshold or carpet.
 - d. At Bottom of Door: 1/8 inch, at threshold or carpet.
 - e. Between Door Face and Stop: 1/16 inch to 1/8 inch plus or minus 1/32 inch.

3.4 ADJUSTING AND CLEANING

- A. Final Adjustments: Check and readjust operating hardware items immediately before final inspection. Leave work in complete and proper operating condition. Remove and replace defective work, including hollow-metal work that is warped, bowed, or otherwise unacceptable.
- B. Remove grout and other bonding material from hollow-metal work immediately after installation.
- C. Metallic-Coated Surface Touchup: Clean abraded areas and repair with galvanizing repair paint according to manufacturer's written instructions.
- D. Touchup Painting: Cleaning and touchup painting of abraded areas of paint are specified in painting Sections.

END OF SECTION 08 11 13

SECTION 08 14 16 - FLUSH WOOD DOORS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Solid-core doors with opaque finish.
2. Shop priming flush wood doors.
3. Factory fitting flush wood doors to frames and factory machining for hardware.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of door. Include details of core and edge construction and trim for openings.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. FSC Certified Wood Information.
 - c. FSC Chain of Custody Certificates.
 - d. Recycled Content Information.
 - e. Regional Materials Information.
 - f. Low Emitting Materials Information.
 - g. LEED Materials and Resources Calculator.

- C. Shop Drawings: Indicate location, size, and hand of each door; elevation of each kind of door; construction details not covered in Product Data; and the following:

1. Dimensions and locations of blocking.
2. Dimensions and locations of mortises and holes for hardware.
3. Dimensions and locations of cutouts.
4. Undercuts.
5. Fire-protection ratings for fire-rated doors.

D. Samples for Verification:

1. Corner sections of doors, approximately 8 by 10 inches, with door faces and edges representing actual materials to be used.

- a. Provide Samples for each species of veneer and solid lumber required.

1.4 INFORMATIONAL SUBMITTALS

- A. Sample Warranty: For special warranty.
- B. Quality Standard Compliance Certificates: AWI Quality Certification Program certificates.

1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A qualified manufacturer that is certified for chain of custody by an FSC-accredited certification body.
- B. Vendor Qualifications: A vendor that is certified for chain of custody by an FSC-accredited certification body.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Comply with requirements of referenced standard and manufacturer's written instructions.
- B. Mark each door on top and bottom rail with opening number used on Shop Drawings.

1.7 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install doors until spaces are enclosed and weathertight, wet work in spaces is complete and dry, and HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during remainder of construction period.

1.8 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace doors that fail in materials or workmanship within specified warranty period.
 1. Failures include, but are not limited to, the following:
 - a. Warping (bow, cup, or twist) more than 1/4 inch in a 42-by-84-inch section.
 - b. Telegraphing of core construction in face veneers exceeding 0.01 inch in a 3-inch span.
 2. Warranty shall also include installation and finishing that may be required due to repair or replacement of defective doors.
 3. Warranty Period for Solid-Core Interior Doors: Life of installation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Products: Subject to compliance with requirements, provide products by one of the following:

1. Factory Primed, Non-Fire Rated Door:

- a. Masonite Architectural; "Cendura Series" Factory primed, NAUF, 5-Ply Particleboard Core Doors.
- b. VT Industries, Inc.; "Heritage Collection, PC5" Factory primed, 5-Ply Particleboard Core Non-Rated (PB) Architectural Wood Doors with no added Urea Formaldehyde Resin.

B. Source Limitations: Obtain flush wood doors from single manufacturer.

2.2 FLUSH WOOD DOORS, GENERAL

A. Quality Standard: In addition to requirements specified, comply with AWI's "Architectural Woodwork Standards."

1. Provide AWI Quality Certification Labels indicating that doors comply with requirements of grades specified.

B. Certified Wood: Flush wood doors shall be certified as "FSC Pure" according to FSC STD-01-001, "FSC Principles and Criteria for Forest Stewardship," and to FSC STD-40-004, "FSC Standard for Chain of Custody Certification."

C. Low-Emitting Materials: Fabricate doors with adhesives and composite wood products that do not contain urea formaldehyde.

D. Fire-Rated Wood Doors: Doors complying with NFPA 80 that are listed and labeled by a qualified testing agency, for fire-protection ratings indicated, based on testing at positive pressure according to NFPA 252.

1. Oversize Fire-Rated Door Assemblies: For units exceeding sizes of tested assemblies, provide certification by a qualified testing agency that doors comply with standard construction requirements for tested and labeled fire-rated door assemblies except for size.
2. Temperature-Rise Limit: Where indicated, provide doors that have a maximum transmitted temperature end point of not more than 450 deg F above ambient after 30 minutes of standard fire-test exposure.
3. Cores: Provide core specified or mineral core as needed to provide fire-protection rating indicated.
4. Edge Construction: Provide edge construction with intumescent seals concealed by outer stile. Comply with specified requirements for exposed edges.
5. Pairs: Provide fire-retardant stiles that are listed and labeled for applications indicated without formed-steel edges and astragals. Provide stiles with concealed intumescent seals. Comply with specified requirements for exposed edges.

E. Particleboard-Core Doors:

1. Particleboard: ANSI A208.1, Grade LD-1 or Grade LD-2, made with binder containing no urea-formaldehyde.
2. Blocking: Provide wood blocking in particleboard-core doors as follows:
 - a. 5-inch top-rail blocking, in doors indicated to have closers.
 - b. 5-inch bottom-rail blocking, in exterior doors and doors indicated to have kick, mop, or armor plates.
3. Provide doors with glued-wood-stave or structural-composite-lumber cores instead of particleboard cores for doors indicated to receive exit devices.

2.3 DOORS FOR OPAQUE FINISH

A. Interior Solid-Core Doors:

1. Grade: Custom.
2. Faces: Any closed-grain hardwood of mill option.
3. Exposed Vertical and Top Edges: Any closed-grain hardwood.
4. Core: Particleboard.
5. Construction: Five plies. Stiles and rails are bonded to core, then entire unit is abrasive planed before veneering. Faces are bonded to core using a hot press.

2.4 FABRICATION

- A. Factory fit doors to suit frame-opening sizes indicated. Comply with clearance requirements of referenced quality standard for fitting unless otherwise indicated.
- B. Factory machine doors for hardware that is not surface applied. Locate hardware to comply with DHI-WDHS-3. Comply with final hardware schedules, door frame Shop Drawings, BHMA-156.115-W, and hardware templates.
 1. Coordinate with hardware mortises in metal frames to verify dimensions and alignment before factory machining.

2.5 SHOP PRIMING

- A. Doors for Opaque Finish: Shop prime faces, all four edges, edges of cutouts, and mortises with one coat of wood primer specified in Division 01 Section "Interior Painting."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine doors and installed door frames, with Installer present, before hanging doors.
 1. Verify that installed frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.

2. Reject doors with defects.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. Hardware: For installation, refer to Division 08 Section "Door Hardware."

B. Installation Instructions: Install doors to comply with manufacturer's written instructions and referenced quality standard, and as indicated.

C. Factory-Fitted Doors: Align in frames for uniform clearance at each edge.

3.3 ADJUSTING

A. Operation: Rehang or replace doors that do not swing or operate freely.

END OF SECTION 08 14 16

SECTION 08 31 13 - ACCESS DOORS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Access doors and frames for walls and ceilings.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details materials, individual components and profiles, and finishes.
- B. Shop Drawings:
 - 1. Include plans, elevations, sections, details, and attachments to other work.
 - 2. Detail fabrication and installation of access doors and frames for each type of substrate.
- C. Samples: For each door face material, at least 3 by 5 inches in size, in specified finish.
- D. Product Schedule: Provide complete access door and frame schedule, including types, locations, sizes, latching or locking provisions, and other data pertinent to installation.

PART 2 - PRODUCTS

2.1 ACCESS DOORS AND FRAMES FOR WALLS AND CEILINGS

- A. Source Limitations: Obtain each type of access door and frame from single source from single manufacturer.
- B. Flush Access Doors with Concealed Flanges:
 - 1. Assembly Description: Fabricate door to fit flush to frame. Provide frame with gypsum board beads for concealed flange installation.
 - 2. Locations: Wall and ceiling.
 - 3. Door Size: 24 by 24 inches, unless otherwise indicated.
 - 4. Uncoated Steel Sheet for Door: Nominal 0.064 inch, 16 gage.
 - a. Finish: Factory prime.
 - 5. Frame Material: Same material and thickness as door.
 - 6. Hinges: Concealed continuous piano hinge.
 - 7. Hardware: Provide each type of hardware in the following locations:
 - a. ATM Vestibule: Lock and latch.
 - b. All Other Interior Spaces: Latch, unless otherwise indicated.

C. Hardware:

1. Lock: Key operated cam lock with mortise cylinder to match cylinders used throughout the Project.
 - a. Finish: US26D - Satin Chromium plated, unless otherwise indicated.
 - b. Lock Preparation: Prepare door panel to accept a 1-1/8 inch diameter mortise cylinder.
2. Latch: Flush, screwdriver-operated cam latch of number required to hold door in flush, smooth plane when closed.
 - a. Provide not less than two latches for each access door panel. Locate latches at corners of door panel.

2.2 MATERIALS

- A. Steel Sheet: Uncoated or electrolytic zinc coated, ASTM A 879/A 879M, with cold-rolled steel sheet substrate complying with ASTM A 1008/A 1008M, Commercial Steel (CS), exposed.
- B. Frame Anchors: Same type as door face.
- C. Inserts, Bolts, and Anchor Fasteners: Hot-dip galvanized steel according to ASTM A 153/A 153M or ASTM F 2329.

2.3 FABRICATION

- A. General: Provide access door and frame assemblies manufactured as integral units ready for installation.
- B. Metal Surfaces: For metal surfaces exposed to view in the completed Work, provide materials with smooth, flat surfaces without blemishes. Do not use materials with exposed pitting, seam marks, roller marks, rolled trade names, or roughness.
- C. Doors and Frames: Grind exposed welds smooth and flush with adjacent surfaces. Furnish attachment devices and fasteners of type required to secure access doors to types of supports indicated.
 1. For concealed flanges with drywall bead, provide edge trim for gypsum board and gypsum base securely attached to perimeter of frames.
 2. Provide mounting holes in frames for attachment of units to metal or wood framing.
 3. Provide mounting holes in frame for attachment of masonry anchors.
- D. Latching Mechanisms: Furnish number required to hold doors in flush, smooth plane when closed.
 1. For cylinder locks, furnish two keys per lock and key all locks alike.

2.4 FINISHES

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.
- D. Steel Finishes:
 - 1. Factory Prime: Apply manufacturer's standard, fast-curing, lead- and chromate-free, universal primer immediately after surface preparation and pretreatment.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Comply with manufacturer's written instructions for installing access doors and frames.
- B. Install doors flush with adjacent finish surfaces or recessed to receive finish material.

3.3 ADJUSTING

- A. Adjust doors and hardware, after installation, for proper operation.
- B. Remove and replace doors and frames that are warped, bowed, or otherwise damaged.

END OF SECTION 08 31 13

SECTION 08 41 13 - ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Exterior and interior, storefront and framing.
2. Exterior and interior, manual-swing entrance doors and door-frame units.
3. Exterior storefront framing for punched openings.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 REFERENCES

- A. ADA/ABA Accessibility Guidelines: U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disability Act (ADA) and Architectural Barriers Act (ABA) Accessibility Guidelines for Buildings and Facilities."

1.3 PERFORMANCE REQUIREMENTS

- A. General Performance: Aluminum-framed systems shall withstand the effects of the following performance requirements without exceeding performance criteria or failure due to defective manufacture, fabrication, installation, or other defects in construction:

1. Movements of supporting structure indicated on Drawings including, but not limited to, story drift and deflection from uniformly distributed and concentrated live loads.
2. Dimensional tolerances of building frame and other adjacent construction.
3. Failure includes the following:
 - a. Deflection exceeding specified limits.
 - b. Thermal stresses transferring to building structure.
 - c. Framing members transferring stresses, including those caused by thermal and structural movements to glazing.
 - d. Noise or vibration created by wind and by thermal and structural movements.
 - e. Loosening or weakening of fasteners, attachments, and other components.
 - f. Sealant failure.
 - g. Failure of operating units.

- B. Delegated Design: Design aluminum-framed systems, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

C. Structural Performance: Exterior aluminum-framed entrances and storefront assemblies shall withstand the effects of gravity loads and wind loads and stresses within limits and under conditions indicated

1. Wind Loads: As indicated on Drawings.
2. Deflection Limitations:
 - a. Deflections: Base calculations for the following deflections upon the combination of maximum direct wind loads, building deflections, thermal stresses, and erection tolerances.
 - 1) The deflection of any framing member in a direction normal to the plane of the wall when subjected to the full code required wind loads specified above shall not exceed 1/175 of its clear span or 3/4 inch whichever is less, except limit deflection of glass to 1 inch.
 - 2) Glass, sealants and interior finishes shall not be included to contribute to framing member strength, stiffness or lateral stability.
 - b. Do not permit any permanent deformation (set) in the metal framing work. Permanent deformation, fastener, weld, or gasket failure, component breakage or disengagement shall not occur under wind loading equal to 1.5 times the wind loads (positive or negative). Permanent deformation shall be taken as deflection without recovery exceeding 1/1000 times span.
3. Dead Loads:
 - a. Maximum full deadload deflections, parallel (in-plane) to wall plane, of framing members shall not reduce glass bite or glass coverage, to less than 75 percent of the design dimension, and shall not reduce edge clearance to less than 25 percent of design dimension or 1/8 inch whichever is greater.
 - b. Limit deflections of metal members spanning door openings to 1/300. The clearance between the member and an operable door shall be no less than 1/16 inch.
 - c. Twisting (rotation) of the horizontals due to the weight of the glass shall not exceed 1 degree, measured between ends and center of each span.
4. Uniform Structural Loads: Satisfactory uniform wind loading tests of each aluminum entrance and storefront assembly (each swinging door) shall have been conducted in accordance with the requirements of ASTM E330. Each assembly shall have been subjected to inward and outward acting uniform loads equal to 1.5 times the inward and outward acting design wind loads specified above under paragraph 'wind loads'. Satisfactory performance at these loads shall mean no glass or other component breakage, component disengagement, and no permanent deformation of main framing members in excess of the permanent deformation criteria specified above.
5. Operational (Traffic) Loads: Design and fabricate aluminum entrances to withstand the operating loads which result from heavy traffic conditions using the specified hardware, without measurable permanent deflection. Limit elastic deflections so as to provide the normal degree of rigidity required to avoid glass breakage, air leaks and other objectionable results of excessive flexibility. Provide weatherstripping at stiles, sill and head rails of door leaves, to minimize air, water and sound leaks.

- D. **Air Leakage:** Air leakage through each aluminum entrance and storefront assembly shall not have exceeded 0.06 cfm/sq. ft. of fixed wall area when tested in accordance with ASTM E 283 at a static-air-pressure difference of 6.24 lbf/sq. ft.
- E. **Water Penetration:**
 - 1. Water penetration in this specification is defined as the appearance of uncontrolled water, other than condensation, on any indoor face of any part of the wall.
 - 2. Provision shall be made to drain to the exterior face of the wall any water entering the system.
 - 3. No uncontrolled water penetration shall have occurred when each entrance and storefront assembly (each entrance and storefront wall) was tested in accordance with the ASTM E331 for one 15 minute cycle at a static pressure difference of 12 lbf/sq. ft. minimum.
- F. **Thermal Movements:** Fabricate the entrance and storefront work to accommodate for such expansion and contraction of component materials, and supporting elements, as will be caused by surface temperatures ranging from -5 deg F to 180 deg F, without causing buckling, glass breakage, failure of joint sealants, undue stress on metal members and fasteners, failure of doors or other operating units to function properly, reduction of performance, and other detrimental effects.
 - 1. Dimensions shown on Drawings are based on an assumed design temperature of 70 deg F. Fabrication and erection procedures shall take into account the ambient temperature range at the time of the respective operations.
- G. **Building Frame Movement:** Design, fabricate and install aluminum entrances and storefronts to withstand building movements including thermal movements, loading deflections, shrinkage, creep and similar movements. Thermal movements shall be as specified above. Building frame deflections, shrinkage, creep and other movements are available from the structural engineer.
- H. **Condensation Resistance:** Provide storefront systems with condensation resistance factor (CRF) of not less than 45 when tested according to AAMA 1503.1.
- I. **Average Thermal Conductance:** Provide storefront systems with average U-values not exceeding those listed in drawings and COM Check compliance report for storefront and entrance door performance.
- J. **Design Modifications:**
 - 1. Submit design modifications necessary to meet the performance requirements and field coordination.
 - 2. Variations in details or materials shall not adversely affect the appearance, durability or strength of components.
 - 3. Maintain the general design concept without altering size of members, profiles and alignment.

1.4 ACTION SUBMITTALS

- A. **Product Data:** For each type of product

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.
 - d. Low Emitting Materials Information.
 - e. LEED Materials and Resources Calculator.

- C. **Shop Drawings:** Submit shop drawings showing scaled elevations, plans, and sections of the aluminum entrance and storefront work. Full-scale sections shall be prepared and submitted for details of the assemblies that cannot be shown in the elevations or sections. Include with shop drawings metal thickness of all metal components, glass thicknesses, metal finishes, and all other pertinent information as necessary or requested by the Architect to indicate compliance with the Contract Documents. Details of field connections, anchorage, and their relationship to the work of others shall be clearly indicated for the coordination of the work by other building trades. Details of fastening and sealing methods and product joinery shall be shown to ensure proper performance of the field installation. No work shall be fabricated until shop drawings for that work have been approved by Architect for fabrication.

- D. **Samples for Verification:** For each type of exposed finish required, in manufacturer's standard sizes.

- E. **Delegated-Design Submittal:** For aluminum-framed systems indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1. Detail fabrication and assembly of aluminum-framed systems.
2. Include design calculations.

1.5 INFORMATIONAL SUBMITTALS

- A. **Qualification Data:** For qualified Installer.
- B. **Structural Calculations:** Submit, for information only, copies of structural calculations indicating complete compliance with the specified performance requirements. Calculations shall be prepared, signed and sealed by a Professional Engineer registered in the state wherein the work is to be erected.
- C. **Product Test Reports:** Based on evaluation of comprehensive tests performed by a qualified testing agency, for aluminum-framed systems, indicating compliance with performance requirements.
- D. **Source quality-control reports.**
- E. **Field quality-control reports.**
- F. **Warranties:** Sample of special warranties.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Instructions: Submit copies of manufacturer's written instructions for adjustment, operation and maintenance of doors.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.
- B. Testing Agency Qualifications: Qualified according to ASTM E 699 for testing indicated.
- C. Engineering Responsibility: Prepare data for aluminum-framed systems, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in systems similar to those indicated for this Project.
- D. Standards: Comply with the applicable provisions and recommendations of the following standards below, where standards conflict the more stringent shall apply:
 - 1. Aluminum Association (AA):
 - a. No. 1 "Aluminum Standards and Data."
 - b. "The Aluminum Design Manual."
 - 2. American Architectural Manufacturers Association (AAMA):
 - a. AAMA "Aluminum Curtain Wall Design Guide Manual," Volumes 1-9.
 - b. AAMA "Aluminum Store Front and Entrance Design Guide Manual."
 - c. AAMA 611 "Anodized Architectural Aluminum."
 - 3. American Institute of Steel Construction (AISC), "Steel Construction Manual," Current Edition.
 - 4. Steel Structures Painting Council (SSPC): "Steel Structures Painting Manual, Vol. 2, Systems and Specifications."
 - 5. Federal Standard 16 CFR 1201, Consumer Product Safety Commission (CPSC): "Safety Standard for Architectural Glazing Materials," as published in the Code of Federal Regulations (CFR). Comply with the applicable requirements of the laws, codes, ordinances and regulations of Federal and Municipal authorities having jurisdiction, wherever requirements conflict the more stringent shall be required. Obtain approvals from all such authorities. As a minimum provide safety glazing complying with ANSI Z97.1 and testing requirements of 16 CFR Part 1201 for Category II materials.
 - 6. Accessible Entrances: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines and ICC/ANSI A117.1.
- E. Source Limitations for Aluminum-Framed Systems: Obtain from single source from single manufacturer.

1.8 IDENTIFICATION, DELIVERY, STORAGE, AND HANDLING

- A. General: Comply with the applicable provisions of AAMA "Curtain Wall Manual #10" for the care and handling of aluminum entrance and storefront work from shop to site.
- B. All components of the aluminum entrance and storefront work shall be identified after fabrication by marks clearly indicating their location in the building. Packaging of components shall be so selected to protect the components from damage during shipping and handling.
- C. Storage on Site:
 - 1. Store aluminum entrance and storefront components in a location and in a manner to avoid damage to the components. Stacking shall be done in a way which will prevent bending, excessive pressure, abrasion or other permanent damage of the component and its finished surfaces.
 - 2. Store aluminum entrance and storefront components and materials in a clean, dry location, away from uncured concrete, masonry work, sprayed on fireproofing work, and other construction activities. Cover with non-staining waterproof paper, tarpaulin, or polyethylene sheeting in a manner that will permit circulation of air inside the covering.
- D. Keep handling on site to a minimum. Exercise particular care to avoid damage to finishes of metals.

1.9 PROJECT CONDITIONS

- A. Field Measurements: Verify dimensions of supporting structure by field measurements before fabrication so that the entrance and storefront work will be accurately designed, fabricated and fitted to the structure. Indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work. Use Contractor's lines and benchmarks as a basis for measurements.
- B. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabricating entrance and storefront work without field measurements. Coordinate supporting structure construction to ensure actual dimensions correspond to established dimensions.

1.10 WARRANTY

- A. General Warranty: The special warranty specified in this Article shall not deprive the Owner of other rights the Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by the Contractor under requirements of the Contract Documents.
- B. Special Warranty: Submit a 2 year written warranty, beginning from date of substantial completion, and executed by the Contractor, manufacturer and the aluminum entrance and storefront installer agreeing to repair or replace components of entrance and storefront systems that develop defects in materials or workmanship within the specified warranty period. Defects include, structural failures, sealant failures, deterioration of metals, metal finishes, and other materials beyond normal weathering, failure of operating components to function properly,

uncontrolled water leakage, uncontrolled air leakage, and any other evidence of failure or deterioration of the aluminum entrance and storefront work to meet performance requirements.

- C. Warranty; Anodized Coatings: Submit a warranty for a period of 3 years, warranting that the anodized aluminum will not develop excessive fading or excessive non-uniformity of color or shade, and will not crack, peel, pit, or corrode; all within the limits defined as follows:
1. "Excessive Fading" means a change in appearance which is perceptible and objectionable as determined by the Architect when viewed visually in comparison with the original color range samples.
 2. "Excessive Non-Uniformity" means non-uniform fading during the period of the warranty to the extent that adjacent panels have a color difference greater than the original acceptable range of color.
 3. "Will Not Pit or Otherwise Corrode" means there shall be no pitting or other type of corrosion discernable from a distance of 10 feet, resulting from the natural elements in the atmosphere at the project site.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Basis-of-Design Products: Subject to compliance with requirements, provide "TriFab VG 451T Front" for exterior framing, and "TriFab VG 451 Center" for interior framing as manufactured by Kawneer North America; an Alcoa company_or comparable products by one of the following:
1. Oldcastle Building Envelope:
 - a. Exterior Framing Product: "Series 3000 Thermal MultiPlane."
 - 1) Construction: Thermally broken.
 - 2) Glazing Plane: Front.
 - b. Interior Framing Product: "FG-3000 CS."
 - 1) Construction: Non-thermally broken.
 - 2) Glazing Plane: Center.
 2. United States Aluminum; A Division of CR Laurence Co., Inc:
 - a. Exterior Framing Product: "Series IT451."
 - 1) Construction: Thermally broken.
 - 2) Glazing Plane: Front.
 - b. Interior Framing Product: "Series 451."
 - 1) Construction: Non-thermally broken.
 - 2) Glazing Plane: Center.
 3. YKK AP America Inc.:

- a. Exterior Framing Product: "YES 45 TU."
 - 1) Construction: Thermally broken.
 - 2) Glazing Plane: Front.
- b. Interior Framing Product: " YES 45 FI."
 - 1) Construction: Non-thermally broken.
 - 2) Glazing Plane: Center.

2.2 MATERIALS

- A. Aluminum: Alloy and temper recommended by manufacturer for type of use and finish indicated.
 - 1. Sheet and Plate: ASTM B 209.
 - 2. Extruded Bars, Rods, Profiles, and Tubes: ASTM B 221.
 - 3. Extruded Structural Pipe and Tubes: ASTM B 429.
 - 4. Structural Profiles: ASTM B 308/B 308M.
 - 5. Welding Rods and Bare Electrodes: AWS A5.10/A5.10M.
- B. Steel Reinforcement: Manufacturer's standard zinc-rich, corrosion-resistant primer, complying with SSPC-PS Guide No. 12.00; applied immediately after surface preparation and pretreatment. Select surface preparation methods according to recommendations in SSPC-SP COM and prepare surfaces according to applicable SSPC standard.
 - 1. Structural Shapes, Plates, and Bars: ASTM A 36/A 36M.
 - 2. Cold-Rolled Sheet and Strip: ASTM A 1008/A 1008M.
 - 3. Hot-Rolled Sheet and Strip: ASTM A 1011/A 1011M.

2.3 FRAMING SYSTEMS

- A. Framing Members: Manufacturer's standard extruded-aluminum framing members of thickness required and reinforced as required to support imposed loads.
 - 1. Construction: Provide thermally broken for exterior framing assemblies and non-thermal for interior framing assemblies.
 - a. Framing Member Size: 2 inch width by 4-1/2 inch depth.
 - 2. Glazing System: Retained mechanically with gaskets on four sides.
 - 3. Glazing Plane: Center, unless otherwise indicated.
- B. Brackets and Reinforcements: Manufacturer's standard high-strength aluminum with nonstaining, nonferrous shims for aligning system components.
- C. Fasteners and Accessories: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding fasteners and accessories compatible with adjacent materials.

1. Use self-locking devices where fasteners are subject to loosening or turning out from thermal and structural movements, wind loads, or vibration.
 2. Reinforce members as required to receive fastener threads.
 3. Do not use exposed anchors and fasteners, except for hardware application. For hardware application, use countersunk Phillips flat-head machine screws finished to match framing members or hardware being fastened, unless otherwise indicated.
- D. Concrete and Masonry Inserts: Hot-dip galvanized cast-iron, malleable-iron, or steel inserts, complying with ASTM A 123/A 123M or ASTM A 153/A 153M.
- E. Concealed Flashing: Dead-soft, 0.018-inch-thick stainless steel, ASTM A 240/A 240M of type recommended by manufacturer.
- F. Framing System Gaskets and Sealants: Manufacturer's standard, recommended by manufacturer for joint type.
1. Sealants used inside the weatherproofing system shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

2.4 GLAZING SYSTEMS

- A. Glazing: As specified in Division 08 Section "Glazing."
- B. Glazing Gaskets: Manufacturer's standard compression types; replaceable, molded or extruded, of profile and hardness required to maintain watertight seal.
- C. Spacers and Setting Blocks: Manufacturer's standard elastomeric type.

2.5 ENTRANCE DOOR SYSTEMS

- A. Entrance Doors: Manufacturer's standard glazed entrance doors for manual-swing operation.
1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. Kawneer North America; an Alcoa company; "500T Insulpour."
 - b. Oldcastle Building Envelope; "Series 500 - Wide Stile, Rugged Entrance."
 - c. United States Aluminum; A Division of CR Laurence Co., Inc; "Series 850, Durafront Doors."
 - d. YKK AP America Inc.; "50M, Monumental Entrance."
 2. Door Construction: 2-inch overall thickness with minimum 0.125-inch-thick, extruded-aluminum tubular rail and stile members. Mechanically fasten corners with reinforcing brackets that are deeply penetrated and fillet welded or that incorporate concealed tie rods.
 3. Door Design: Door Design: Wide stile.
 - a. Accessible Doors: Smooth surfaced for width of door in area within 10 inches above floor or ground plane.

4. Glazing Stops and Gaskets: Square, snap-on, extruded-aluminum stops and preformed gaskets, unless otherwise indicated.

- a. Provide nonremovable glazing stops on outside of door.

- B. Entrance Door Hardware: As specified in Division 08 Section "Door Hardware."

2.6 ACCESSORY MATERIALS

- A. Joint Sealants: For installation at perimeter of aluminum-framed systems, as specified in Division 07 Section "Joint Sealants."

1. Provide sealants for use inside of the weatherproofing system that have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

2.7 SEALING MATERIALS

- A. Concealed Sealing Materials: All sealing materials concealed within the entrances and storefronts shall be silicone, compatible with and adherent to each material it will be in contact with, as recommended by the manufacturer to fulfill performance requirements.
- B. Exposed Sealing Materials: All sealing materials exposed at entrance and storefront perimeter joints in contact with adjacent cladding materials: 2 component silicone, refer to Division 07 Section "Joint Sealants."

2.8 FABRICATION

- A. General: Fabricate the entrances and storefronts to the designs, shapes, and sizes shown using the materials specified and shown to produce assemblies that meet or exceed the performance requirements. To the greatest extent possible complete fabrication, assembly, finishing, hardware applications and other work before shipment to Project site.
 1. Metal Wall Thickness: Provide shapes as shown and as required to suit the performance requirements but with wall thickness of not less than 1/8 inch.
 2. Doors and frames shall be cut, reinforced, drilled and tapped in strict accordance with the printed door hardware manufacturer's templates and instructions. Provide solid stainless steel hardware reinforcements, securely fastened to doors and frames where door hardware is to be attached.
 - a. Security system components may be incorporated into the door and frame openings of all entrance doors and frames. Provide all cutouts required by the Owner's security system vendor and all prewiring for vendor provided security system devices. Wherever storefront and entrance framing components are to receive wiring provide unobstructed clear paths free of burrs and sharp objects with pull strings to facilitate wiring.
 3. Joints in Metal Work: All exposed work shall be carefully fitted and matched to produce continuity of line and design, with all joints, being accurately fitted for hairline contact and rigidly secured. Where additional rigidity or strength is required to satisfy the

performance requirements reinforce entrance components with aluminum or carbon steel shapes, bars, and plates.

- B. Form or extrude aluminum shapes before finishing.
- C. Framing Members, General: Fabricate components that, when assembled, have the following characteristics:
 - 1. Profiles that are sharp, straight, and free of defects or deformations.
 - 2. Accurately fitted joints with ends coped or mitered.
 - 3. Means to drain water passing joints, condensation within framing members, and moisture migrating within the system to exterior.
 - 4. Physical and thermal isolation of glazing from framing members.
 - 5. Accommodations for thermal and mechanical movements of glazing and framing to maintain required glazing edge clearances.
 - 6. Provisions for field replacement of glazing from interior.
 - 7. Fasteners, anchors, and connection devices that are concealed from view to greatest extent possible.
- D. Mechanically Glazed Framing Members: Fabricate for flush glazing without projecting stops.
- E. Storefront Framing: Fabricate components for assembly using shear-block system, unless otherwise indicated.
- F. Entrance Door Frames: Reinforce as required to support loads imposed by door operation and for installing entrance door hardware.
 - 1. At exterior doors, provide compression weather stripping at fixed stops.
- G. Entrance Doors: Reinforce doors as required for installing entrance door hardware.
 - 1. At pairs of exterior doors, provide sliding-type weather stripping retained in adjustable strip and mortised into door edge.
 - 2. At exterior doors, provide weather sweeps applied to door bottoms.
- H. Entrance Door Hardware Installation: Factory install entrance door hardware to the greatest extent possible. Cut, drill, and tap for factory-installed entrance door hardware before applying finishes.
- I. After fabrication, clearly mark components to identify their locations in Project according to Shop Drawings.
- J. Shop Assembly: As far as practicable, all fitting and assembly work shall be done in a fabrication shop.
 - 1. For exterior entrances, provide weepholes and internal water passages in the glazing framing recesses as recommended by the respective glass and framing manufacturers to conduct infiltrating water to the exterior. Provide weep baffles secured to inside of frame behind weepholes.

- K. Exposed Fasteners: Not permitted.
- L. Protection of Metals: Wherever dissimilar metals are in contact, except in the case of aluminum in contact with galvanized steel, zinc, separate such surfaces with a coating of zinc rich primer, bituminous paint, or separation gaskets as the condition requires. Wherever aluminum comes in contact with concrete surfaces separate such surfaces with a coating of zinc rich primer, bituminous paint, or separation gaskets as the condition requires.

2.9 ALUMINUM FINISHES

- A. General: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations relative to applying and designating finishes.
- B. Finish Application: Apply anodized coatings to all exposed surfaces of storefront and entrance components.
- C. Appearance of Finished Work: During production, maintain large size color range samples for use in comparing against production material. Variations in appearance of abutting or adjacent pieces are acceptable if they are within the range of approved samples. Noticeable variations in the same piece are not acceptable.
- D. Finish designations prefixed by AA conform to the system established by the Aluminum Association for designating aluminum finishes.
- E. Class I, Clear Anodic Finish for Exterior Locations: Complying with AA-M10C22A41 for an Architectural Class I finish and the following:
 - 1. Metal Preparation and Pretreatment: Remove die markings prior to finishing operations. Perform this work in addition to the finish specified. Scratches, abrasions, dents and similar defects are unacceptable.
 - 2. Thickness: 0.018 mm or thicker.
 - 3. Performance Criteria: Meets or exceeding AAMA 611.
 - 4. Color: Medium matte finished, clear natural anodized.
 - 5. Post Anodizing Finish (Sealing): Anodized finishes shall be fully sealed by the manufacturer or processor according to procedures recommended by the licensor of the process. Maximum weight loss shall be 2.6 mg/ sq. in.

2.10 COATINGS FOR CONCEALED METAL SURFACES

- A. General: The following protective coatings shall be applied to surfaces of metals which are to be concealed in the construction:
 - 1. Coating for Steel: Hot dip galvanized, complying with ASTM A123.
 - 2. Coating for Aluminum, and Steel: Where aluminum or carbon steel surfaces are to be in contact with each other or in contact with dissimilar materials such as masonry or concrete, and where hot dip galvanizing of carbon steel is incompatible with component parts because of galvanic action or component fabrication tolerances provide one of the following:

- a. Bituminous Paint: Cold-applied, non-sagging, asphalt-mastic paint complying with SSPC-Paint 12 requirements, except containing no asbestos. Apply in two coats for an overall minimum dry film thickness of 25 mils.
- b. Zinc Rich Primer: Organic zinc-rich primer, complying with SSPC-Paint 20.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Coordinate entrance and storefront work with the work of other Sections and provide items to be placed during the installation of other work at the proper time to avoid delays in the work.
- B. Templates and Diagrams: Furnish templates, diagrams, and other data to fabricators and installers of related work, as necessary for coordinating entrance and storefront installation.
- C. Place such items, including concealed overhead framing, accurately in relation to the final location of entrance and storefront components.

3.2 EXAMINATION

- A. Examine the substrates, adjoining construction, and conditions under which the Work is to be installed. Proceed with installation only after unsatisfactory conditions have been corrected.
 1. Before beginning installation of the entrance and storefront work examine all parts of the existing building structural frame and the existing building cladding indicated to support the entrance and storefront work. Ensure that the existing swing door thresholds, existing swing doors, swing door framing and subframes have been completely removed with all projecting anchors cut off flush. Notify Contractor in writing, of any dimensions, or conditions, found which will prevent the proper execution of the entrance and storefront work, including specified tolerances. Use Contractor's offset lines and bench marks as basis of measurements.

3.3 INSTALLATION

- A. General: Comply with manufacturer's written instructions for protecting, handling, and installing entrance and storefront systems. Do not install damaged components. Fit frame joints to produce hairline joints free of burrs and distortion. Rigidly secure nonmovement joints. Seal joints watertight. Clean excess joint sealants from finished surfaces.
 1. Cut and trim component parts of the entrance and storefront work during erection only with the approval of the manufacturer or fabricator, and in accordance with his recommendations. Restore finish completely to protect material and remove all evidence of cutting and trimming. Remove and replace members where cutting and trimming has impaired strength or appearance, as directed by Architect.
 2. Set components within the erection tolerances with uniform joints. Place components on shims and fasten to supporting substrates using bolts and similar fasteners. Use stainless steel shims at structural connections only. U shaped shims at structural connections are not permitted. Use aluminum, stainless steel, or high impact polystyrene shims at other connections.

3. Do not erect components that are warped, deformed, bowed, dented, defaced or otherwise damaged as to impair its strength or appearance. Remove and replace members damaged in the process of erection.
 4. Coat concealed surfaces of dissimilar materials, and any ferrous metal components, with a heavy coating of bituminous paint, zinc rich primer or other separation in accordance with manufacturer's recommendations. Where aluminum components will contact concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint.
 5. No holes or slots shall be burned, cut into, or field drilled in any building framing member without the written acceptance of the structural engineer.
- B. Entrance and Storefront Framing: Install framing components plumb and true in alignment with established lines and grades without warp or rack of framing members.
- C. Entrance Doors: Doors shall be securely anchored in place to a straight, plumb and level condition, without distortion. Adjust doors to provide a tight fit at contact points for weathertight closure and to operate smoothly, without binding, with hardware functioning properly. Weatherstripping contact, and hardware movement, shall be field tested and final adjustment, and lubrication, made for proper operation and performance of doors.
1. Door Hardware: Refer to Division 08 Section "Door Hardware."
 2. Set sill members in a bed of silicone sealant to provide weathertight construction. Comply with requirements of Division 07 Section "Joint Sealants."
- D. Install glazing to comply with requirements of Division 08 Section "Glazing," unless otherwise indicated.
- E. Install metal-faced composite wall panels to comply with wall panel manufactures and aluminum entrance and storefront manufacturers written instructions and recommendations.
- F. Install perimeter sealant to comply with requirements of Division 07 Section "Joint Sealants," unless otherwise indicated.
- G. Concealed Sealing Components: Apply sealant and gasket components that are integral to the entrance and storefront systems in strict accordance with the each component manufacturer's printed instructions. Before applying components remove all mortar, dust, dirt, moisture, and other foreign matter that will be deleterious to the intended performance of the component. Mask adjoining exposed surfaces to avoid spilling, dripping, dropping or other unintended contact of the sealing components onto adjacent exposed surfaces.

3.4 ERECTION TOLERANCES

- A. The entrance and storefront systems shall be fabricated and erected to accommodate the dimensional tolerances of the structural frame and surrounding cladding while providing the following as installed tolerances.
1. Variation from theoretical calculated position as located in plan or elevation in relation to established floors lines, column lines and other fixed elements of the structure, including variations from plumb, level, straight and member size: +/- 1/4 inch max in any 20'-0" run, column-to-column bay, or floor-to-floor height.

2. Alignment: Where surfaces abut in line, and where they meet at corners, limit offset from true alignment to 1/32 inch.
3. Variation from angle, or plumb, shown: +/- 1/8 inch max in any 10'-0" run or story height, non-cumulative.
4. Variation from slope, or level, shown: +/- 1/8 inch max in any 20'-0" run or column-to-column bay, non-cumulative.

3.5 ANCHORAGE

- A. Anchorage of the entrance and storefront work to the structure and surrounding cladding shall be in accordance with the accepted shop drawings.

3.6 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified independent testing agency to perform field quality-control testing indicated. Conduct tests of each specified sample installation under the direction of the testing agency in the presence of the Owner, Architect, the Contractor, various component manufacturers and fabricators and the Installer for each system incorporated in the sample installation.
- B. Water Spray Without Air Pressure Difference Test: After completing the installation of test areas indicated, but before the installation of interior finishes has begun, test storefront system for water penetration according to AAMA 501.2 requirements.
- C. Repair or remove and replace Work that does not meet requirements or that is damaged by testing; replace to conform to specified requirements.

3.7 REMOVAL OF DEBRIS

- A. All debris caused by, or incidental to, the erection of the entrance and storefront work shall be removed from the site and disposed of legally.

3.8 CLEANING

- A. Clean metal surfaces promptly after installation, exercising care to avoid damage to factory finished exposed surfaces.
- B. Wash glass on both faces not more than 4 days prior to date scheduled for inspections that establish date of Substantial Completion. Wash glass as recommended by glass manufacturer. Remove excess glazing and sealant compounds, dirt, and other substances.
- C. Immediately remove any deleterious material from surfaces of aluminum.

3.9 PROTECTION

- A. Institute protective measures required throughout the remainder of the construction period to ensure that entrance and storefront work will be without damage or deterioration, other than normal weathering, at time of acceptance.

Gensler

057.7202.950

Bank of America / BAC Prescriptive / Bulletin 01-2020 / 03-16-20

January 22, 2021
Issue for Construction

Bank of America
BAC Centerville GU
Centerville, UT

END OF SECTION 08 41 13

SECTION 08 41 26 - ALL-GLASS ENTRANCES AND STOREFRONTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior all-glass airlock system consisting of manual-swinging all-glass entrance doors and storefront.

1.2 DEFINITIONS

- A. ADA/ABA Accessibility Guidelines: U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disability Act (ADA) and Architectural Barriers Act (ABA) Accessibility Guidelines for Buildings and Facilities."
- B. Airlock System: When used "Airlock" or "Airlock System" shall refer to industry standard all-glass entrance and storefront assemblies.

1.3 PERFORMANCE REQUIREMENTS

- A. General Performance: All-glass systems shall withstand the effects of the following performance requirements without exceeding performance criteria or failure due to defective manufacture, fabrication, installation, or other defects in construction.
 1. Movements of supporting structure indicated on Drawings including, but not limited to, deflection from uniformly distributed and concentrated live loads.
 2. Dimensional tolerances of building frame and other adjacent construction.
 3. Failure includes the following:
 - a. Deflection exceeding specified limits.
 - b. Thermal stresses transferring to building structure.
 - c. Framing members transferring stresses, including those caused by thermal and structural movements to glazing.
 - d. Noise or vibration created by thermal and structural movements.
 - e. Loosening or weakening of fasteners, attachments, and other components.
 - f. Failure of operating units.
- B. Structural Performance: All-glass systems shall withstand the effects of gravity loads and the following loads and stresses within limits and under conditions indicated according to SEI/ASCE 7.
 1. Seismic Loads: As indicated on Structural Drawings.
 2. Deflection Limits:

- a. Deflection normal to glazing plane is limited to 1/2 inch for an entrance and storefront assembly height of 10'-6" with use of two mall clamps at each butt joint to achieve minimum deflection.
 - b. Deflection of any framing member in a direction normal to the plane of the wall when subjected to the full code required wind loads specified above shall not exceed 1/175 of its clear span or 3/4 inch whichever is less, except limit deflection of glass to 1 inch.
- C. Delegated Design: Design all-glass systems, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.
- D. Thermal Movements: Allow for thermal movements resulting from the following ambient and surface temperature changes.
1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for all-glass system.
- B. Shop Drawings: Show fabrication and installation details, including the following:
1. Plans, elevations, and sections.
 2. Details of fittings and glazing, including isometric drawings of patch and rail fittings.
 3. Details of aluminum entrance and storefront work, including field connections, anchorage, and their relationship to the work.
 4. Door hardware locations, mounting heights, and installation requirements.
- C. Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below.
1. Metal Finishes: 6-inch- long sections of patch and rail fittings, accessory fittings, and other items.
 2. Glass: 6 inches square, showing exposed-edge finish.
 3. Door Hardware: For exposed door hardware of each type, in specified finish, full size.
 4. Preformed Glazing Joint Strips: 6-inch- long sections of each type of preformed joint strips.
- D. Other Action Submittals:
1. Entrance Door Hardware Schedule: Prepared by or under the supervision of supplier, detailing fabrication and assembly of entrance door hardware, as well as procedures and diagrams. Coordinate final entrance door hardware schedule with doors, sidelights, transoms, and related work to ensure proper size, thickness, hand, function, and finish of entrance door hardware.

- E. Delegated-Design Submittal: For all-glass systems indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

- 1. Detail fabrication and assembly of all-glass systems.
- 2. Detail fabrication and assembly of aluminum-framed systems.
- 3. Include design calculations.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer.
- B. Seismic Qualification Certificates: For all-glass systems, accessories, and components, from manufacturer.
- C. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for all-glass systems.
- D. Warranty: Sample of special warranty.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For all-glass systems to include in maintenance manuals.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.
- B. Engineering Responsibility: Prepare data for all-glass systems, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in systems similar to those indicated for this Project.
- C. Source Limitations: Obtain all-glass systems from single source from single manufacturer.
- D. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for fabrication and installation.
 - 1. Build mockups for all-glass systems including entrance door hardware, patch and rail fittings, and accessory fittings.
 - a. Size: As directed by Architect.
 - 2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 - 3. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.
- E. Accessible All-Glass Entrance Doors: Comply with applicable provisions in ICC/ANSI A117.1.

- F. Preinstallation Conference: Conduct conference at Project site.

1.8 PROJECT CONDITIONS

- A. Field Measurements: Verify actual locations of walls and other construction contiguous with all-glass systems by field measurements before fabrication and indicate measurements on Shop Drawings.

1.9 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of all-glass systems that do not comply with requirements or that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:
 - a. Structural failures including excessive deflection.
 - b. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
 - c. Failure of operating components.
2. Warranty Period: Two years from date of Substantial Completion, except as follows:
 - a. Concealed Floor Closers: 25 years from date of Substantial Completion.

1.10 MAINTENANCE SERVICE

- A. Initial Maintenance Service: Beginning at Substantial Completion, provide 12 months' full maintenance by skilled employees of all-glass system Installer. Include quarterly preventive maintenance, repair, or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper all-glass system operation. Provide parts and supplies the same as those used in the manufacture and installation of original equipment.
- B. Continuing Maintenance Proposal: From Installer to Owner, in the form of a standard yearly (or other period) maintenance agreement, starting on date initial maintenance service is concluded. State services, obligations, conditions, and terms for agreement period and for future renewal options.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Glass: Refer to Division 08 Section "Glazing" for monolithic glazing.
1. Exposed Edges: Machine ground and flat polished.
 2. Butt Edges: Flat polished.
 3. Corner Edges: Lap-joint corners with exposed edges polished.
- B. Aluminum Extrusions: ASTM B 221, with strength and durability characteristics of not less than Alloy 6063-T5.

- C. Stainless Steel Sheet, Strip, Plate, and Flat Bar: ASTM A 666, Type 304.
- D. Single-Component, Nonsag, Acid-Curing Silicone Joint Sealant: ASTM C 920, Type S, Grade NS, Class 25, for Uses NT, G, and A.
 - 1. Sealants used inside the weatherproofing system shall have a VOC content of 250 g/L.

2.2 METAL COMPONENTS

- A. Fitting Configuration:
 - 1. Vestibule:
 - a. Manual-Swinging, All-Glass Doors: Continuous top and bottom rail fittings.

2.3 ENTRANCE DOOR HARDWARE

- A. General: Heavy-duty entrance door hardware units in sizes, quantities, and types recommended by manufacturer for all-glass entrance systems indicated. For exposed parts, match metal and finish of patch and rail fittings.
 - 1. Refer to Division 08 Section "Door Hardware."

2.4 FABRICATION

- A. Provide holes and cutouts in glass to receive hardware, fittings, and accessory fittings before tempering glass. Do not cut, drill, or make other alterations to glass after tempering.
 - 1. Fully temper glass using horizontal (roller-hearth) process, and fabricate so that when glass is installed, roll-wave distortion is parallel with bottom edge of door or lite.
- B. Factory assemble components and factory install hardware and fittings to greatest extent possible.

2.5 ALUMINUM FINISHES

- A. Clear Anodic Finish: AAMA 611, AA-M12C22A31, Class II, 0.010 mm or thicker.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Coordinate entrance and storefront work with the work of other Sections and provide items to be placed during the installation of other work at the proper time to avoid delays in the work.
- B. Templates and Diagrams: Furnish templates, diagrams, and other data to fabricators and installers of related work, as necessary for coordinating entrance and storefront installation.
- C. Place such items, including concealed overhead framing, accurately in relation to the final location of entrance and storefront components.

3.2 EXAMINATION

- A. Examine areas and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.3 INSTALLATION

- A. Install all-glass systems and associated components according to manufacturer's written instructions.
- B. Adjust all-glass entrance doors and hardware to produce smooth operation and tight fit at contact points and weather stripping.
 - 1. For all-glass entrance doors accessible to people with disabilities, adjust closers to provide a 3-second closer sweep period for doors to move from a 70-degree open position to 3 inches from the latch measured to the leading door edge.
- C. Remove excess sealant and glazing compounds and dirt from surfaces.

END OF SECTION 08 41 26

SECTION 08 71 00 – DOOR HARDWARE

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes door hardware.

1.2 PREINSTALLATION MEETINGS

- A. Keying Conference: Conduct conference at Project site to comply with requirements in Division 01 Section "Project Management and Coordination." Incorporate keying conference decisions into final keying schedule after reviewing door hardware keying system including, but not limited to, the following:
 - 1. Function of building, flow of traffic, purpose of each area, degree of security required, and plans for future expansion.
 - 2. Preliminary key system schematic diagram.
 - 3. Requirements for key control system.
 - 4. Address for delivery of keys.
- B. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01 Section "Project Management and Coordination."
- C. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01 Section "Project Management and Coordination." Review methods and procedures related to electrified door hardware including, but not limited to, the following:
 - 1. Inspect and discuss electrical roughing-in and other preparatory work performed by other trades.
 - 2. Review sequence of operation for each type of electrified door hardware.
 - 3. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
 - 4. Review required testing, inspecting, and certifying procedures.

1.3 ACTION SUBMITTALS

- A. Product Data: Submit product data including installation details, material descriptions, dimensions of individual components and profiles, and finishes.
- B. Shop Drawings: Submit shop drawings with details of electrified door hardware, indicating the following:
 - 1. Wiring Diagrams: Detail wiring for power, signal, and control systems and differentiate between manufacturer-installed and field-installed wiring. Include the following:
 - a. System schematic.
 - b. Point-to-point wiring diagram.

- c. Riser diagram.
 - d. Elevation of each door controlled by electrified hardware.
 - 2. Detail interface between electrified door hardware and fire alarm, access control, security, and building control system.
- C. Samples: Submit samples of exposed door hardware for each type indicated below, in specified finish. Tag with full description for coordination with the Door Hardware Schedule.
 - 1. Door Hardware: As follows:
 - a. Locks and latches.
 - b. Operating trim.
 - c. Wall stops.
 - d. Floor stops.
 - e. Hinge pin door stops.
 - f. Coat hooks.
 - 2. Samples will be returned to Contractor. Units that are acceptable and remain undamaged through submittal, review, and field comparison process may, after final check of operation, be incorporated into the Work, within limitations of keying requirements.
- D. Door Hardware Schedule: Submit door hardware schedule prepared by or under the supervision of door hardware supplier. Coordinate the final Door Hardware Schedule with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of door hardware. The Architect's review of schedule shall neither be construed as a complete check nor shall it relieve the Contractor of responsibility for errors, deviations, or omissions from the specified requirements to provide complete door hardware for the project.
 - 1. Organization: Organize the Door Hardware Schedule into door hardware sets indicating complete designations of every item required for each door or opening.
 - a. Organize door hardware sets in same order as in the Door Hardware Schedule at the end of Part 3.
 - 2. Content: Include the following information:
 - a. Type, style, function, size, label, hand, and finish of each door hardware item.
 - b. Manufacturer of each item.
 - c. Fastenings and other pertinent information.
 - d. Location of each door hardware set, cross-referenced to Drawings, both on floor plans and in door and frame schedule.
 - e. Explanation of abbreviations, symbols, and codes contained in schedule.
 - f. Mounting locations for door hardware. Supply templates to door and frame manufacturer(s) to enable proper and accurate sizing and locations of cutouts for hardware. Detail conditions requiring custom extended lip strikes, or other special or custom conditions.
 - g. Door and frame sizes and materials.
 - h. Description of each electrified door hardware function, including location, sequence of operation, and interface with other building control systems.

- 1) Sequence of Operation: Include description of component functions that occur in the following situations: authorized person wants to enter; authorized person wants to exit; unauthorized person wants to enter; unauthorized person wants to exit.

- E. Keying Schedule: Submit keying schedule prepared by or under the supervision of supplier, detailing Owner's final keying instructions for locks. Include schematic keying diagram and index each key set to unique door designations.

1.4 INFORMATIONAL SUBMITTALS

- A. Product Test Reports: Submit a written record of each fire door assembly to the Owner to be made available to the Authority Having Jurisdiction (AHJ) for future building inspections.
- B. Warranties: Submit special warranties specified in this Section.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For each type of door hardware. Include final hardware and keying schedule.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Maintenance Tools: Furnish a complete set of specialized tools for Owner's continued adjustment, maintenance, removal, and replacement of door hardware.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who has completed door hardware similar in material, design, and extent to that indicated for this Project and whose work has resulted in construction with a record of successful in-service performance.
- B. Supplier Qualifications: Door hardware supplier, who has completed a minimum of three (3) projects over the last 5 years which were similar in material, design and extent to that indicated for the Project – as determined by the Architect – and which have resulted in construction with a record of successful in service performance, and who is or employs a qualified Architectural Hardware Consultant, available during the course of the Work to consult with Contractor, Architect, and Owner about door hardware and keying.
 1. Electrified Door Hardware Supplier Qualifications: An experienced door hardware supplier who has completed projects with electrified door hardware similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance, and who is acceptable to manufacturer of primary materials.
 - a. Engineering Responsibility: Prepare data for electrified door hardware, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project.
 2. Scheduling Responsibility: Preparation of door hardware and keying schedules.

- C. Architectural Hardware Consultant Qualifications: A person who is currently certified by the Door and Hardware Institute as an Architectural Hardware Consultant and who is experienced in providing consulting services for door hardware installations that are comparable in material, design, and extent to that indicated for this Project.
 - 1. Electrified Door Hardware Qualifications: Experienced in providing consulting services for electrified door hardware installations.
- D. Source Limitations: Obtain each type of door hardware from a single manufacturer, unless otherwise indicated.
- E. Regulatory Requirements: Comply with the following:
 - 1. Provide hardware items complying with the applicable provisions for accessibility and usability by the disabled and handicapped in compliance with Americans with Disabilities Act (ADA), "Accessibility Guidelines for Buildings and Facilities (ADAAG), ANSI A117.1.
 - 2. NFPA 101: Comply with applicable provisions for means of egress doors.
 - 3. Electrified Door Hardware: Listed and classified by Underwriters Laboratories, Inc. or by a testing agency acceptable to authorities having jurisdiction, as suitable for the purpose indicated.
- F. Fire-Rated Door Assemblies: Provide door hardware for assemblies complying with NFPA 80 that are listed and labeled by Underwriters Laboratories, Inc. for fire ratings indicated, based on testing according to NFPA 252. Provide only door hardware items that are identical to items tested by UL for the types and sizes of doors required. In case of conflict between type of hardware specified and type required for accessibility or fire protection, furnish type required by NFPA and UL. Doors indicated in fire rated partitions and walls shall be positive latching and self-closing, with smoke gaskets where required by applicable codes.
 - 1. Wherever exit device hardware is required on doors, comply with UL 305. Furnish hardware to door manufacturer for installation at factory. Provide supplementary label, "Fire Exit Hardware," on each exit device to certify that panic hardware has been panic load tested with door.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Inventory door hardware on receipt and provide secure lock-up for door hardware delivered to Project site.
- B. Tag each item or package separately with identification related to the final Door Hardware Schedule, and include basic installation instructions with each item or package.

1.9 COORDINATION

- A. Coordinate layout and installation of recessed pivots and closers with floor construction. Cast anchoring inserts into concrete. Concrete, reinforcement, and formwork requirements are specified in Division 03 Section "Cast-in-Place Concrete."

- B. Templates: Furnish templates and door hardware schedules, coordinated for the application of door hardware items with door and frame details, to door opening fabricators and trades performing door opening work to permit the preparation of doors and frames to receive the specified door hardware. Where the door hardware item scheduled is not adaptable to the finished size of door opening members requiring door hardware, submit an item having a similar operation and quality to the Architect for review. Each door hardware item shall be fabricated to templates.
- C. Electrical System Roughing-in: Coordinate layout and installation of electrified door hardware with connections to, power supplies, fire alarm system and detection devices, access control system, security system, building control system.

1.10 WARRANTY

- A. Special Warranty: Written warranty, executed by manufacturer agreeing to repair or replace components of door hardware that fail in materials or workmanship within specified warranty period. Failures include, but are not limited to, the following:
 - 1. Faulty operation of door hardware.
 - 2. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
- B. Warranty Period for Manual Closers: Ten years from date of Substantial Completion.
- C. Warranty Period for Exit Devices: Five years from date of Substantial Completion.
- D. Warranty Period for Other Hardware: Two years from date of Substantial Completion.
- E. Warranty for Mortised Mechanical Lock and Latchsets: Ten years from date of Substantial Completion.
- F. Warranty for Heavy Duty Cylindrical Mechanical Lock and Latchsets: Seven years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SCHEDULED DOOR HARDWARE

- A. General: Provide door hardware for each door to comply with requirements in this Section, door hardware sets are keyed to each scheduled door in the door and frame schedule, and the Door Hardware Schedule at the end of Part 3.
 - 1. Door Hardware Sets: Provide quantity, item, size, finish or color indicated, and named manufacturer's products.
 - 2. Sequence of Operation: Provide electrified door hardware function, sequence of operation, and interface with other building control systems indicated.
 - 3. The hardware supplier shall review each hardware set and compare it with the door types, details, and sizes as shown and verify each hardware item for function, hand, backset, and method of fastening through shop drawing submittals.

2.2 HINGES AND PIVOTS

A. Butt Hinge Products and Manufacturers:

1. Standard Weight, Ball Bearing, 5 Knuckle, Steel: Complying with BHMA A156.1 A8112.
 - a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - 1) BB5000; Bommer Industries, Inc., Landrum, SC (BI).
 - 2) BB1279; Hager Companies (HAG).
 - 3) TA2714; McKinney Products Company (MCK).
 - 4) FBB179; Stanley Commercial Hardware (STH).
2. Heavy Weight, Ball Bearing, 5 Knuckle, Steel: Complying with BHMA A156.1 A8111.
 - a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - 1) BB5004; Bommer Industries, Inc., Landrum, SC (BI).
 - 2) BB1168; Hager Companies (HAG).
 - 3) T4A3786; McKinney Products Company (MCK).
 - 4) FBB168; Stanley Commercial Hardware (STH).
3. Heavy Weight, Ball Bearing, 5 Knuckle, Stainless Steel: Complying with BHMA A156.1 A5111.
 - a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - 1) BB5006; Bommer Industries, Inc., Landrum, SC (BI).
 - 2) BB1199; Hager Companies (HAG).
 - 3) T4A3386-32D; McKinney Products Company (MCK).
 - 4) FBB199 (US32D); Stanley Commercial Hardware (STH).

B. Pivot and Pivot Hinge Products and Manufacturers:

1. Center Pivots: Mortised mounted, non-handed, center pivot set with sealed bearings for protection against weather and debris and composed of a head mounted top pivot and floor mounted bottom pivot. Furnish with extended spindles. Complying with BHMA A156.4 C07032.
 - a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"

- 1) Model 370 Center Hung Pivot Set; Rixson-Firemark, Inc. (RIX).
- 2) 7255 Pivot Set; H. B. Ives (IVS).
- 3) 0370 Center Hung Pivot Set; Architectural Builders Hardware Mfg., Inc. (ABH).

- C. General Hinge and Pivot Characteristics: Where door jamb or trim projects to such an extent that the width of leaf specified will not allow the door to clear such frame or trim, furnish hinges and pivots with leaves of sufficient width to clear. Hinges and pivots shall be template hinges conforming to BHMA A156.1 and in accordance with door and frame material requirements.
- D. Butt Hinge and Offset Pivot Hinge Quantity: Provide the following, unless otherwise indicated:
1. Two Hinges: For doors with heights up to and including 60 inches.
 2. Three Hinges: For doors with heights of greater than 60 inches to and including 90 inches.
 3. Four Hinges: For doors with heights greater than 90 inches to and including 120 inches.
 4. Provide 4 hinges, plus 1 hinge for every 30 inches of door height greater than 120 inches.
- E. Butt Hinge Sizes: 4-1/2 inches high by 4 inches or 4-1/2 inches wide for doors up to and including 36 inches in width; 5 inches high by 4 inches or 4-1/2 inches wide for doors greater than 36 inches in width.
- F. Hinge Characteristics: Full mortise type with square corners. All butt hinges are to have non-rising pins for interior hinges and all exterior butt hinges are to be made of non-ferrous base metal and have non-removable pins (NRP). Provide only steel bodied butt and pivot hinges at labeled doors. All butt hinges shall be furnished with button tips. Provide heavy weight, ball bearing, hinges at doors 40 inches and greater in width.
- G. Electrified Functions for Hinges and Pivots: Furnish fully concealed circuit, tamper resistant, wired hinges and pivots at doors requiring power transfer or door monitoring from jamb to door. All electrified hinges and pivots shall be rated for the in-rush amperage of the door mounted device being electrified.
- H. Fasteners: Package all hinges and pivots with machine and wood screws as required by door and frame construction.

2.3 LOCKS AND LATCHES

- A. Bored Lock and Latch Sets: Extra heavy duty, commercial, cylindrical bodies complying with BHMA A156.2 Series 4000, Grade 1. Furnish cylindrical type, field reversible, lock and latch sets with deadlocking brass or stainless steel latch bolts having a minimum 1/2 inch throw together with guard (auxiliary) latch added to bolt, 2-3/4 inches backset, and UL listed for 3 hour single doors. Furnish latch bolts having a minimum 3/4 inch throw together with guard (auxiliary) latch added to bolt, and UL listed for labeled pairs of fire doors. All lock and latch sets, to be furnished complete with heavy gage steel zinc dichromate coated cylindrical bodies, trim, 2-1/4 inches by 1-1/8 inches beveled square cornered fronts, and 6 pin tumbler key in lever core. Provide wrought steel, aluminum, or black plastic, box strikes for each lock and latch set with curved lips of sufficient length to protect frames. Provide plated cast zinc levers with plated wrought brass or bronze roses. Where electro-mechanical locksets are scheduled provide

transformers properly sized for conversion of power supply to the power characteristics of the electromechanical locksets. Where electro-mechanical locksets are scheduled provide request to exit (REX) monitoring feature.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Schlage ND-Series, Sparta SPA; Schlage Lock Company (SCH). Where electro-mechanical locksets are scheduled provide ND Series Electrified Locks with trim matching mechanical locksets.
 - b. Dorma CL800 Series, LC Trim; Dorma Architectural Hardware (DOR). Where electro-mechanical locksets are scheduled provide Series Electrified Locks with trim matching mechanical locksets.
 - c. Sargent 10 Line, LP Design; Sargent Manufacturing Company (SGT). Where electro-mechanical locksets are scheduled provide 10G70 Series with trim matching mechanical locksets.
- B. Mortise Lock and Latch Sets: Heavy duty, commercial, mortise bodies complying with BHMA A156.13 Series 1000, Grade 1, with throughbolted lever trim. Furnish mortise type, field reversible without disassembly, field multifunctional without opening lock cases, lock and latch sets with 1 or 2 piece anti-friction deadlocking stainless steel latchbolts having a minimum 3/4 inch throw, 2-3/4 inches backset, and UL listed for 3 hour doors. All lock and latch sets, to be furnished complete with heavy 0.109 inch (12 gage) wrought steel zinc dichromate or chrome plated case, trim, adjustable beveled square cornered armored fronts, cold forged steel or stainless steel hubs, and 6 pin cylinders. Conceal fastenings, washers and bushings. Provide wrought, or black plastic, box strikes for each lock and latch set. Provide brass, bronze or stainless steel strikes with curved lips of sufficient length to protect frames. Provide solid forged or cast levers with wrought roses. Where lock functions are scheduled provide non-handed guard bolt and stainless steel deadbolt with a minimum 1 inch throw. Where electro-mechanical locksets are scheduled provide transformers properly sized for conversion of power supply to the power characteristics of the electromechanical locksets. Where electro-mechanical locksets are scheduled provide request to exit (REX) monitoring feature.
 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Schlage L9000 Series, 17 Design x A Rose; Schlage Lock Company (SCH). Provide handed ANSI 4-7/8 inch curved lip strikes die punched to match bolts provided with latchset functions only (Part No. XL11-820/XL11-821), provide non-handed standard curve lip strikes for all other functions 10-072. Where electro-mechanical locksets are scheduled provide L9000EL Series with trim matching mechanical locksets.
 - b. Dorma ML9000 Series, LCA Design, Dorma Architectural Hardware (DOR). Provide handed ANSI 4-7/8 inch curved lip strikes die punched to match bolts provided with latchset functions only, provide non-handed standard curve lip strikes for all other functions. Where electro-mechanical locksets are scheduled provide with trim matching mechanical locksets.
 - c. Sargent 8200 Series, LNP Design; Sargent Manufacturing Company (SGT). Provide handed ANSI 4-7/8 inch curved lip strikes die punched to match bolts provided with latchset functions only, provide non-handed standard curve lip strikes 82-0110 for

all other functions. Where electro-mechanical locksets are scheduled provide 8270 Series with trim matching mechanical locksets.

C. Push-Button Combination Locks:

1. Bored Lock Set Combination Locks:

- a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"

1) 5000 Series; Kaba Ilco Corp.

D. Padlocks: Minimum 11/32 inch diameter hardened steel shackle with multiple plating for wear and corrosion resistance, case shall be machined from solid extruded brass, height of opening shall be minimum 2-9/16 inch. Housing shall be machined for 6 pin core.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"

- a. 758-2; Sargent Manufacturing Company (SGT).
b. PL5000 Series; Corbin Russwin Architectural Hardware (CR).

E. Rabbeted Doors: Provide special rabbeted front and strike on locksets for rabbeted meeting stiles.

2.4 DOOR BOLTS

A. Manual Flush Bolts: Provide flush bolts, with 1 inch wide fronts, in paired sets (top and bottom), with 1/2 inch diameter flattened bolt tip for both wood and metal doors and standard 12 inch rod at flushbolts for metal doors. Flush bolts shall fit ANSI A115.4 door and frame preparation. Flush bolts in wood and metal fire doors shall be A Label UL Listed. Bolts for fire doors to comply with BHMA A156.16, Type L14081, L14251, L04261 or L24081. Furnish rods of proper length to afford easy reach from the floor. Furnish manufacturer's standard top strikes for top bolts.

1. Manual Flushbolts for Fire Rated Wood Doors: One of the following:

- a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"

- 1) No. 790F; Door Controls International (DCI).
2) FB358; H. B. Ives (IVS).
3) 3913; Triangle Brass Manufacturing Company, Inc. (TBM).
4) 557; Rockwood Manufacturing Company (RM).

2. Manual Flushbolts for Fire Rated Metal Doors: One of the following:

- a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"

- 1) No. 780F; Door Controls International (DCI).
- 2) FB458; H. B. Ives (IVS).
- 3) 3917; Triangle Brass Manufacturing Company, Inc. (TBM).
- 4) 555; Rockwood Manufacturing Company (RM).

2.5 EXIT DEVICES

- A. Exit Devices: Exit devices and exit device accessories shall conform to BHMA A156.3, Grade 1. Trim shall be wrought construction and commercial plain design with straight, beveled or smoothly rounded sides, corners and edges. Keyed devices shall be furnished less cylinders. Cylinders shall be as herein specified keyed to building system.
- B. Push Pad Style Exit Devices: One of the following:
 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. 98 Series, function and trim as scheduled; Von Duprin (VD).
 - b. 9000 Series, function and trim as scheduled; Dorma Architectural Hardware (DOR).
 - c. 19-80 Series, function and trim as scheduled; Sargent Manufacturing Company (SGT).
- C. Ornamental Exit Devices and Exterior Pulls: UL listed devices that have been panic load tested for use on all-glass entrance doors and fabricated principally from 1-1/4 inch diameter satin finished stainless steel tubing. Operation: The top latch bolt of the panic device shall be retracted by pushing the interior "L" shaped crash bar. In addition a built-in dogging device shall be provided which keeps the latch bolt in the retracted position and the crash bar becomes fixed. An exterior key cylinder for entry shall also be provided with each device.
 1. Products: Subject to compliance with requirements, provide one of the following products:
 - a. PA-100F; Blumcraft Div. of C. R. Laurence (CRL).
 - b. DG1000-PA; Dorma Architectural Hardware (DOR).
- D. Panic Exit Devices: Listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for panic protection, based on testing according to UL 305.
- E. Fire Exit Devices: Complying with NFPA 80 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire and panic protection, based on testing according to UL 305 and NFPA 252.
- F. Outside Trim: Match design for locksets and latchsets, unless otherwise indicated.

2.6 CYLINDERS AND KEYING

- A. Cores for Bored Cylindrical Locksets: Provide key-in lever 6 pin cores for all bored cylindrical locksets, keyed into building system, as manufactured by the bored lockset manufacturer.
- B. Cylinders: Full faced cylinders with square shouldered (not tapered) compression rings, 7 pin cylinders, standard threaded, keyed into building system, with cams to suit lock functions. Provide cylinders for installation into all locks.
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. 80-301 Mortised cylinder; Schlage Lock Company (SCH).
 - b. 96B10 Mortise Cylinder; Dorma Architectural Hardware (DOR).
 - c. Series 73-43 Mortise Cylinder; Sargent Manufacturing Company (SGT).
- C. Key Control Systems:
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Model 1205-C; Lund Equipment Co., Inc.
 - b. Aristocrat AWC 450-S; Telkee, Inc.
- D. Keying System: Final keying to determine lock cylinders, keyed alike sets, level of keying, master key groups, grandmaster keying system shall be as directed by the Owner. Supplier and Contractor shall meet with the Owner and obtain final instructions in writing. Provide 2 nickel silver keys for each lock, and 6 keys for each grandmaster and masterkey system. Provide 2 blank keys for each lock for the Owner's convenience in making additional keys.
 - 1. Construction Keyed Cylinders: Provide construction keyed cylinders in locks during construction and as may be necessary for security or as may be requested by the Owner. Upon completion of the construction phase, construction keyed cylinders shall be voided mechanically without the removal of the cylinders from the locks. All construction keyed cylinders shall be individually keyed as required and subject to a single master key.
 - 2. Permanent Cores: Provide and install keyed permanent cores at the end of the project with all permanent keys and control keys turned over directly to the owner.
- E. Key Control System: Furnish a key control system of the type specified. Furnish complete accessories including key gathering envelopes, labels, reserve pattern key tags with self-locking key clips, key receipt forms, key receipt holders, 3 way visible card index, temporary key markers and permanent key markers.

2.7 STRIKES

- A. Strikes for Locks and Latches: All strikes for locks and latches shall be provided by the lock and latch manufacturer unless otherwise specified or scheduled, refer to Article 'Locks and Latches'.

B. Dustproof Floor Strikes: Complying with BHMA A156.16, Type L04251, L04021 or L14021.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"

- a. No. 80; Door Controls International.
- b. DP2; H.B. Ives.
- c. 3910; Triangle Brass Manufacturing Company, Inc. (TBM).
- d. 570; Rockwood Manufacturing Company (RM).

C. Electric Strikes: Complying with BHMA A156.5, Grade 1. Mortised type for devices mounted in hollow metal frames. Unless otherwise required to interphase with the security access system furnish in 24 volt DC continuous voltage for silent operation. Provide each strike with extended lips as required to suit jamb conditions and fail secure function. Remote electrical control from card reader or control panel will unlock strike jaw, releasing latchbolt of the deadlatch, so door can be opened without operating latch by key cylinders from outside of secured room. Electric strikes shall be UL listed for up to 3 hour fire door assemblies.

1. Jamb Mounted Electric Strikes:

- a. Products: Subject to compliance with requirements, provide one of the following products.

- 1) 7400 (Fail-Secure); Adams Rite (ADR)
- 2) 5100; Von Duprin (VD)
- 3) 5200 Series; HES.

2. Overhead Mounted, Double Door Electric Strikes:

- a. Products: Subject to compliance with requirements, provide one of the following:

- 1) ESK-2; C. R. Laurence (CRL).
- 2) 310-4; Folger Adams (FA).

D. Door Pin Grommet:

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"

- a. Don-Jo, TS-100: Thimble Strike, Finish: BP- Brass Plated.

2.8 OPERATING TRIM (PUSHES AND PULLS)

- A. Fabricate straight push pulls for back to back mounting from 1-1/4 inch diameter stainless steel bar stock in finish as scheduled. Custom fabricate pulls with minimum 2-3/4 inch projection, 1-1/2 inch clearance, 10 inch center to center of bases with center line of pull centered on door stiles. Furnish spanner turning washer and stud assemblies threaded to accept concealed throughbolt attachment including provision for spanner tightening of bolts of push/pull assembly. Do not provide baseplates at stile to pull interface.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"

- a. 1161; Trimco (TRI).
- b. RM2110; Rockwood Manufacturing Company (RM).

2.9 CLOSERS

- A. Surface-Mounted Closers: Closers shall be certified by ETL laboratories and the manufacturer to a minimum of 8,000,000 cycles and meet BHMA A156.4, Grade 1. Closers used in conjunction with overhead stops and holders shall be templated and coordinated to function properly. Properly detail closers to meet application requirements by providing drop plates, brackets, etc. to meet application and installation requirements as indicated. Comply with manufacturer's recommendations for size of door closer depending on size of door, stack pressure conditions, exposure to weather, and anticipated frequency of use. Closers shall have adjustable spring power, full rack and pinion, independent closing speed and latch regulating V-slotted valves, fully hydraulic with a high strength cast iron cylinder and solid forged steel arms, bore diameter of 1-1/2 inches, pinion shaft diameter of 5/8 inches, adjustable back check, cushion and built-in stop feature where scheduled, hold open arms where scheduled, delayed action where scheduled, arm finish to match closer cover finish scheduled. Provide metal covers of clean line design with plated or primed for paint finish as scheduled and that require removal in order to make adjustments to closer.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"

- a. 4110/4010; LCN Closers (LCN).
- b. 281; Sargent Manufacturing Company (SGT).
- c. 8916; Dorma Architectural Hardware (DOR).

- B. Concealed Closers: BHMA A156.4; rack-and-pinion hydraulic type with adjustable sweep and latch speeds controlled by key-operated valves. Comply with manufacturer's written recommendations for size of door closers depending on size of door, exposure to weather, and anticipated frequency of use. Provide factory-sized closers, adjustable to meet field conditions and requirements for opening force.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"

- a. RTS88 BFI 90° HO; Dorma Architectural Hardware (DOR).

2.10 PROTECTIVE TRIM UNITS

- A. Kick Plates: Fabricate protection plates from minimum 0.050 inch thick stainless steel, beveled top and 2 sides (B3E), square corners, complying with BHMA A156.6, and fastened with oval head Phillips fasteners countersunk into plate surface.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Series 8400; H. B. Ives (IVS).
 - b. K1050 Doorplate Series; Rockwood Manufacturing Company (RM).
 - c. K0050 for Kickplates; Trimco, Triangle Brass Manufacturing Company, Inc. (TBM).
- B. Size: Furnish kick and armor plates sized 2 inches less than door width. Furnish kickplates 10 inches high, unless otherwise indicated. Mount protective plates flush with bottom of door.

2.11 STOPS AND HOLDERS

- A. Roller Latches: Special roller latch complying with BHMA A156.16 Type E19101, fabricated from brass or bronze, for single doors, minimum 1 inch wide by 3-3/8 inches long base for mortising into the head door frame, adjustable nylon covered roller latch and ramp roller strike; finish as scheduled.
 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. 4030 Adjustable Roller Latch; Door Controls International (DCI).
 - b. RL30; H. B. Ives (IVS).
 - c. 590; Rockwood Manufacturing Company (RM).
 - d. 1559WA; Triangle Brass Manufacturing Company, Inc. (TBM).
 - B. Concealed Overhead Door Holders: Heavy duty, concealed mounting, full mortised, bronze bodied, slide track design, with heavy shock absorber spring providing 5 to 7 degree compression before deadstop, non-metal slide and shock blocks, 110 degree maximum opening, complying with BHMA A156.8 Type C11511 for hold open and Type C11541 for stop function. Provide stop, or hold open, functions as scheduled.
 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. 1000 Series; Architectural Builders Hardware Mfg., Inc. (ABH).
 - b. 100 Series; Glynn-Johnson (GJ).
 - c. Checkmate Heavy Duty 1 Series; Rixson-Firemark, Inc. (RIX).
 - C. Silencers for Wood Door Frames: BHMA A156.16, Type L03021; grey rubber, minimum 5/8 by 3/4 inch; fabricated for drilled-in application to frame, specifically designed to absorb shock and reduce noise of door closing. Provide 2 silencers for each pair of doors, 3 silencers for each single door.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. 9S; Door Controls International (DCI).
 - b. SR65; H. B. Ives (IVS).
 - c. 1229B; Triangle Brass Manufacturing Company, Inc. (TBM).
 - d. 609; Rockwood Manufacturing Company (RM).
- D. Silencers for Metal Door Frames: BHMA A156.16, Type L03011; grey rubber, minimum diameter 1/2 inch; fabricated for drilled-in application to frame, specifically designed to form an air pocket to absorb shock and reduce noise of door closing. Provide 2 silencers for each pair of doors, 3 silencers for each single door.
 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. 8S; Door Controls International (DCI).
 - b. SR64; H. B. Ives (IVS).
 - c. 1229A; Triangle Brass Manufacturing Company, Inc. (TBM).
 - d. 608; Rockwood Manufacturing Company (RM).
- E. Wall Stops: Cast disc type with concave rubber bumper, having an minimum 2-1/8 inch diameter base with nominal 1 inch projection and concealed attachment to substrate.
 1. For Attachment to Gypsum Wallboard: Complying with BHMA A156.16, Type L12251 or L12101.
 - a. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - 1) WS407CCV; H.B. Ives (IVS).
 - 2) 1270WV; Triangle Brass Manufacturing Company, Inc. (TBM).
 - 3) 409; Rockwood Manufacturing Company (RM).

2.12 DOOR GASKETING

- A. Self adhesive flexible silicone type, continuous gaskets for installation at all heads and jambs of doors:
 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. 5050C; National Guard Products, Inc. (NGP).
 - b. S88CL; Pemko Manufacturing Co., Inc. (PEM).
 - c. 188BK; Zero International, Inc. (ZRO).

- B. Continuous door bottom aluminum extrusion with continuous nylon brush pile sweep; sweep shall be field cut to length required to have positive contact with threshold without binding door.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. 90137CNB; Pemko.
 - b. C390MIL; Sealeze.

2.13 THRESHOLDS

- A. 1/2 inch high by 5 inch wide extruded aluminum panic threshold with resilient bumper gasket.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. 477S; Hager Companies (HAG).
 - b. 950; National Guard Products, Inc. (NGP).
 - c. S257AV; Reese Enterprises, Inc. (RE).
 - d. 566A; Zero International, Inc. (ZRO).

2.14 MISCELLANEOUS DOOR HARDWARE

- A. Boxed Power Supplies: Provide modular units complying with NEMA ICS 6, electrified for enclosure; filtered and regulated; voltage rating and type matching requirements of door hardware served; and listed and labeled for use with fire alarm systems.

1. Products: Subject to compliance with requirements, provide one of the following products:
 - a. PS914-2RS; Von Duprin (VD).
 - b. 3521; Sargent Manufacturing Company (SGT).

- B. PS610RF; Dorma Architectural Hardware (DOR).Palm Button Release Device: Provide a "request to exit" palm button release device for use with alarm and signaling systems. Button shall be a minimum of 1-1/4 inches in diameter and be mounted to a maximum 1-3/4 inch wide by 4-1/2 inches high brushed stainless steel mounting plate designed to mount into metal door frames as narrow as 1-3/4 inches. Provide each red button with 24 volt indicator lamp. Provide each button with an engraved white plastic laminate sign to be applied adjacent to the button instructing the user as to the operation and function of the button.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. 623RD-EX-DA; Schlage Electronics (SCH).
 - b. 430N-R-U-LED; Security Door Controls (SDC).
 - c. PB3N; Securitron (SEC).

- C. Door Peep Scope: Door Viewer Warnock Hersey rated to 20 minutes.
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. DS/2000-ALS (color: Silver); Du Seung Trading Corp., 1635 Lakes Parkway, Suite B, Lawrenceville, Georgia 30043, (800)274-SCOPE(7267).
- D. Exit Button:
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. PB1CL; Nutone.
- E. Card Reader System:
 - 1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. ACS-2 ATM Vestibule Card Access System; Parabit Systems.
- F. Power Transfer:
 - 1. Products: Subject to compliance with requirements, provide one of the following products:
 - a. EPT-2; Von Duprin (VD).
 - b. EPT-2; Falcon (FAL).
 - c. CEPT-10; Securitron (SEC).
- G. Key Switch:
 - 1. Products: Subject to compliance with requirements, provide one of the following products:
 - a. 653-14-NS-L2; Locknetics (SCE).
 - b. MKAN2 4"high x 1 3/4"wide; Securitron (SEC).

2.15 FABRICATION

- A. Manufacturer's Nameplate: Provide each door hardware item without exposed manufacturers' labels, names, or designs.
- B. Fasteners: Provide door hardware manufactured to comply with published templates generally prepared for machine, wood, and sheet metal screws. Provide screws according to commercially recognized industry standards for application intended. Provide Phillips oval-head screws with finished heads to match surface of door hardware item being attached. Machine screws and expansion shields shall be used for attaching hardware to concrete and masonry. Use throughbolts for renovation work only where existing door blocking and reinforcements are unknown.

1. Concealed Fasteners: All new doors and door frames have been specified with adequate blocking and reinforcement provisions to eliminate exposed throughbolting of hardware items. Doors installed with exposed throughbolts will be rejected and replaced by the Contractor at no cost to the Owner. Where through bolts are used on existing doors provide sleeves for each through bolt.

2.16 FINISHES

- A. Standard: Comply with BHMA A156.18.
- B. Appearance of Finished Work: Finishes of the same designation, that come from 2 or more sources, shall match when the items are viewed at arm's length and approximately 24 inches apart. Unless otherwise scheduled, match each hardware item in a single hardware set with the scheduled latch or lock set finish. Painting of BHMA 600 (USP) surfaces is required and is specified under Division 09 Section "Painting."
- C. Designations: The abbreviations used to schedule hardware finishes are generally BHMA (Federal Standards where indicated in parenthesis) designations. Comply with base material and finish requirements indicated by the following:
 1. BHMA 626 (US26D): Satin chromium plated.
 2. BHMA 630 (US32D): Satin stainless steel.
 3. Alum.: Aluminum.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Hardware for fire door assemblies shall be installed in accordance with NFPA 80. Hardware for smoke and draft control door assemblies shall be installed in accordance with NFPA 105. Install hardware for non-labeled and non-smoke and draft door assemblies in accordance with BHMA A156.115 for steel doors and frames, and BHMA A156.115-W series for wood doors, and hardware manufacturer's installation instructions for doors and frames fabricated from other than steel or wood.
 1. All modifications to fire doors and frame for electric and mortised hardware shall be made by the respective door and frame manufacturers.
- B. Smoke Seals at S Labeled Door Assemblies: Provide and install smoke seals at S labeled doors in accordance with door manufacturer's instructions.

3.2 INSTALLATION

- A. Mounting Heights: Mount door hardware units at the following heights, unless specifically indicated on the Drawings or required to comply with governing regulations:
 1. Locks and Latches: 38 inches to center of lever from finish floor.
 2. Door Pulls: 44 inches from finish floor to center of grip. Pull bases centered on door stiles, unless otherwise indicated.

3. Door Pulls: Pull bases centered on top and bottom door rails, and spaced from lock edge of door stile as indicated, or recommended, by the pull manufacturer.
 4. Push Plates: 44 inches from finish floor to center of plate. Coordinate with pull location.
 5. Horizontal Push/Pull Bar: 42 inches from finish floor to center of pull/pull. Push/Pull bases centered on door stiles, unless otherwise indicated.
 6. Butt Hinges: 10 inches to bottom of lowest hinge from finish floor; 5 inches to top of upper hinge from top of door; space intermediate hinges equally between lower and upper hinges.
 7. Flush Bolt Operating Mechanisms: Top bolt 66 to 72 inches from finish floor, bottom bolt 12 inches from finish floor.
 8. Exit Devices: 40 inches from finish floor to center of touch bar. 38 inches from finish floor to center of cross bar.
 9. Coat Hooks: 54 inches from finish floor to center of coat hook.
 10. Door Guards: Not more than 54 inches from finished floor to center of door guard.
 11. Door Viewers: Not more than 43 inches from finished floor to center of viewer.
- B. Install each door hardware item to comply with manufacturer's written instructions. Install overhead surface closers for maximum degree of opening obtainable. Place on room side of corridor doors, stair side of stair doors, secondary corridor side of doors between corridors. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be finished, coordinate removal, storage, and reinstallation of surface protective trim units with finishing work specified in Division 09 Sections. Do not install surface-mounted items until finishes have been completed on substrates involved.
- C. Do not install permanent key cylinders in locks until the time of preliminary acceptance by the Owner. At the time of preliminary acceptance, and in the presence of the Owner's representative, permanent key all lock cylinders. Record and file all keys in the key control system specified, and turn system over to Owner for sole possession and control.
- D. Key control storage system shall be installed where directed by the Owner.
- E. Thresholds: Thresholds shall be secured with a minimum of 3 fasteners per single door width and 6 fasteners per double door width with a maximum spacing of 12 inches. Minimum screw size shall be No. 10 length, dependent on job conditions, with a minimum of 3/4 inch thread engagement into the floor or anchoring device used. Screw heads to be countersunk and flush with face of threshold. Set thresholds for exterior and acoustical doors in full bed of sealant complying with requirements specified in Division 07 Section "Joint Sealants." Once installed thresholds shall not rock or cause noise when walked on.

3.3 FIELD QUALITY CONTROL

- A. Independent Architectural Hardware Consultant: Owner will engage a qualified independent Architectural Hardware Consultant to perform inspections and to prepare inspection reports.
1. Independent Architectural Hardware Consultant will inspect door hardware and state in each report whether installed work complies with or deviates from requirements, including whether door hardware is properly installed and adjusted.

3.4 ADJUSTING

- A. Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every hardware component. Replace hardware components that cannot be adjusted to operate as intended. Adjust door control devices to compensate for building stack pressures, final operation of forced air mechanical equipment and to comply with referenced accessibility requirements.
 - 1. Test each electrical hardware item to determine if devices are properly functioning. Wiring shall be tested for correct voltage, current carrying capacity, and proper grounding. Stray voltages in wiring shall be eliminated.
 - 2. Coordinate with electrical installation for interface and connection with life safety and security systems.
- B. Fire-Rated Door Assembly Testing: Upon completion of the installation, test each fire door assembly in the project to confirm proper operation of its closing device and that it meets all criteria of a fire door assembly as per NFPA 80 2007 Edition. The inspection of the fire doors is to be performed by individuals with knowledge and understanding of the operation components of the type of door being subjected to testing. A written record shall be maintained and transmitted to the Owner to be made available to the Authority Having Jurisdiction (AHJ). The record shall list each fire door assembly throughout the project, and include each door number, an itemized list of hardware set components at each door opening, and each door location in the facility.

3.5 CLEANING AND PROTECTION

- A. Clean adjacent surfaces soiled by door hardware installation. Clean hardware components as necessary to restore proper finish. Provide protection during the progress of the work and maintain conditions that ensure door hardware is in perfect working order and without damage or deterioration at time of Substantial Completion.

3.6 DOOR HARDWARE SCHEDULE – SCHEDULED DOORS

- A. Refer to “Door Hardware Schedule” located on drawings.

END OF SECTION 08 71 00

SECTION 08 80 00 – GLAZING

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes glazing for the following products and applications, including those specified in other Sections where glazing requirements are specified by reference to this Section:
 - 1. Windows.
 - 2. Doors.
 - 3. Glazed entrances.
 - 4. Interior borrowed lites.
 - 5. Storefront framing.
- B. Related Sections:
 - 1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 DEFINITIONS

- A. Glass Manufacturers: Firms that produce primary glass, fabricated glass, or both, as defined in referenced glazing publications.
- B. Glass Thicknesses: Indicated by thickness designations in millimeters according to ASTM C 1036.
- C. Interspace: Space between lites of an insulating-glass unit.

1.3 PERFORMANCE REQUIREMENTS

- A. General: Installed glazing systems shall withstand normal thermal movement and wind and impact loads (where applicable) without failure, including loss or glass breakage attributable to the following: defective manufacture, fabrication, or installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; or other defects in construction.
 - 1. Glass Design: Glass thicknesses and heat treatments indicated are minimum requirements. Glazing details shown are for convenience of detailing only and are to be confirmed by the Contractor relative to cited standards and final framing details.
- B. Delegated Design: Design glass, including comprehensive engineering analysis according to ASTM E 1300 by a qualified professional engineer, using the following design criteria:
 - 1. Design Wind Pressures: As indicated on Drawings.
 - 2. Vertical Glazing: For glass surfaces sloped 15 degrees or less from vertical, design glass to resist design wind pressure based on glass type factors for short-duration load.

3. Maximum Lateral Deflection: For glass supported on all four edges, limit center-of-glass deflection at design wind pressure to not more than 1/50 times the short-side length or 1 inch, whichever is less.
 4. Differential Shading: Design glass to resist thermal stresses induced by differential shading within individual glass lites.
- C. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes acting on glass framing members and glazing components.
1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

1.4 ACTION SUBMITTALS

- A. Product Data: Submit product data for each glass product and glazing material indicated.
- B. LEED Documentation Submittals:
1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. Regional Materials Information.
 - d. LEED Materials and Resources Calculator.
- C. Samples: Label samples to indicate product, characteristics, and locations in the work. Furnish samples of the following:
1. Except for clear glass, submit samples of each glass type specified, in the form of 12 inch square Samples.
 2. Submit samples of each glass type specified where production run variations, and defects are expected.
- D. Glazing Schedule: List glass types and thicknesses for each size opening and location. Use same designations indicated on Drawings.

1.5 INFORMATIONAL SUBMITTALS

- A. Glass Manufacturer's Letter: Submit a letter certifying that the glazing manufacturer has reviewed the glazing details proposed for the Project, including the use of gaskets and sealants, and that each product to be furnished is recommended for the application shown.
- B. Product Certificates: Signed by manufacturers of glass and glazing products certifying that products furnished comply with requirements.
- C. Qualification Data: For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.

- D. Product Test Reports: Submit product test reports for each type of glazing sealant and gasket indicated.
- E. Warranties: Submit special warranties specified in this Section.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who has completed glazing similar in material, design, and extent to that indicated for Project and whose work has resulted in construction with a record of successful in-service performance.
- B. Source Limitations for Glass and Glass Accessories: Obtain glass and glass accessories from one source for each product indicated below:
 - 1. Primary glass.
 - 2. Heat treated glass.
 - 3. Insulating glass.
 - 4. Glazing gaskets.
- C. Safety Glass: Comply with the applicable requirements of the laws, codes, ordinances and regulations of Federal and Municipal authorities having jurisdiction, wherever requirements conflict the more stringent shall be required. Obtain approvals from all such authorities. As a minimum provide Category II materials complying with testing requirements in 16 CFR 1201 (Consumer Product Safety Commission "Safety Standard for Architectural Glazing Materials," as published in the Code of Federal Regulations) and ANSI Z97.1.
 - 1. Subject to compliance with requirements, permanently mark safety glass with certification label of Safety Glazing Certification Council or another certification agency acceptable to authorities having jurisdiction.
- D. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below, unless more stringent requirements are indicated. Refer to these publications for glazing terms not otherwise defined in this Section or in referenced standards.
 - 1. GANA Publications: GANA's "Glazing Manual."
 - 2. IGMA Publication for Insulating Glass: SIGMA TM-3000, "North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial and Residential Use."
- E. Insulating-Glass Certification Program: Permanently marked either on spacers or on at least one component lite of units with appropriate certification label of the Insulating Glass Certification Council (IGCC).
- F. Preinstallation Conference: Conduct conference at Project site.
 - 1. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
 - 2. Review temporary protection requirements for glazing during and after installation.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Protect glazing materials according to manufacturer's written instructions and as needed to prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.
- B. For insulating-glass units that will be exposed to substantial altitude changes, comply with insulating-glass manufacturer's written recommendations for venting (using either breather or capillary tubes) and sealing.

1.8 PROJECT CONDITIONS

- A. Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.
 - 1. Do not install glazing sealants when ambient and substrate temperature conditions are outside limits permitted by sealant manufacturer or below 40 deg F.

1.9 WARRANTY

- A. General Warranty: Special warranties specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Manufacturer's Special Warranty for Coated-Glass Products: Manufacturer's standard form in which coated-glass manufacturer agrees to replace coated-glass units that deteriorate within specified warranty period. Deterioration of coated glass is defined as defects developed from normal use that are not attributed to glass breakage or to maintaining and cleaning coated glass contrary to manufacturer's written instructions. Defects include peeling, cracking, and other indications of deterioration in coating.
 - 1. Warranty Period: 10 years from date of Substantial Completion.
- C. Manufacturer's Special Warranty on Insulating Glass: Manufacturer's standard form in which insulating-glass manufacturer agrees to replace insulating-glass units that deteriorate within specified warranty period. Deterioration of insulating glass is defined as failure of hermetic seal under normal use that is not attributed to glass breakage or to maintaining and cleaning insulating glass contrary to manufacturer's written instructions. Evidence of failure is the obstruction of vision by dust, moisture, or film on interior surfaces of glass.
 - 1. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PRODUCTS AND MANUFACTURERS

- A. Refer to the drawings for the extent of glass types and locations. Glass types indicated on the drawings are keyed to the Part 3 Glass Schedule Articles at the end of this Section. The Contractor shall confirm the levels of heat treatment required for each glass type scheduled as contained in Articles Performance Requirements, Submittals and Quality Assurance.

2.2 GLASS PRODUCTS, GENERAL

- A. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass lites in thicknesses as needed to comply with requirements indicated.
- B. Strength: Where float glass is indicated, provide Kind HS heat-treated float glass, or Kind FT heat-treated float glass as needed to comply with "Performance Requirements" Article. Where heat-strengthened glass is indicated, provide Kind HS heat-treated float glass or Kind FT heat-treated float glass as needed to comply with "Performance Requirements" Article. Where fully tempered glass is indicated, provide Kind FT heat-treated float glass.
- C. Thermal and Optical Performance Properties: Provide glass with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below:
 - 1. For monolithic-glass lites, properties are based on units with lites 6.0 mm thick.
 - 2. For insulating-glass units, properties are based on units of thickness indicated for overall unit and for each lite.
 - 3. U-Factors: Center-of-glazing values, according to NFRC 100 and based on LBL's WINDOW 5.2 computer program, expressed as Btu/sq. ft. x h x deg F ($W/sq. m \times K$).
 - 4. Solar Heat-Gain Coefficient and Visible Transmittance: Center-of-glazing values, according to NFRC 200 and based on LBL's WINDOW 5.2 computer program.
 - 5. Visible Reflectance: Center-of-glazing values, according to NFRC 300.

2.3 PRIMARY FLOAT GLASS

- A. Float Glass: ASTM C 1036, Type I (transparent glass, flat), Quality q3 (glazing select); class as indicated in schedules at the end of Part 3.

2.4 HEAT-TREATED FLOAT GLASS

- A. General: Heat treat glass where the need is determined by thermal stress analyses, by wind load analyses, and where required to meet safety glazing requirements.
- B. Fabrication Process: By horizontal (roller-hearth) process with roll-wave distortion parallel to bottom edge of installed glass unit.
- C. Sizes and Cutting: Prior to heat treatment, cut glass to required sizes as determined by accurate measurement of openings to be glazed, making allowance for required edge clearances. Cut and process edges in accordance with glass manufacturer's recommendations. Do not cut or treat edges in the field.

- D. Heat-Strengthened Glass: Provide glass complying with ASTM C1048 Kind HS. Surface compression range shall be between 4,000 psi and 7,000 psi.
- E. Fully Tempered Glass: Provide glass complying with ASTM C1048 Kind FT and meeting the requirements of ANSI Z97.1. Surface compression shall be equal to or greater than 10,000 psi.
- F. Flatness Tolerances: All heat treated glass shall be fabricated to the following flatness tolerances:
 - 1. Overall Bow and Warp: Not greater than the maximum bow and warp tolerances in any direction as listed in ASTM C1048 Table 2. Localized warp limited to 1/32 inch in 12 inches.
 - 2. Roll Ripple: The deviation from flatness at any peak (peak to valley deviation) shall not exceed 0.003 inches for 6 mm thick glass.

2.5 COATED FLOAT GLASS

- A. General: Provide coated glass complying with requirements indicated in this Article and in schedules at the end of Part 3.
 - 1. Sputter-Coated Float Glass: Float glass with the coating(s) specified in schedules at the end of Part 3, deposited by magnetron sputtered vacuum deposition process after manufacture and heat treatment (if any). Pyrolytic, and wet chemical deposition, glass coatings will not be permitted.
 - 2. Coating Quality: The allowable range of defects in coatings applied to glass shall be as accepted through glass sample submissions. Installed coated glass products which are outside of the accepted sample range shall be subject to rejection by the Architect. In order to reduce the possibility of glass rejection, the supplier of coated glass products shall provide glass coating production runs for the entire project from a single coating facility. The allowable range of defects are defined as follows:
 - a. The vision glass area is defined as the field of glass which is greater than 3 inches from the glass unit edge.
 - 1) Pinholes: At an indoor viewing distance of 6 feet for low emissivity coatings, and 15 feet for reflective coatings:
 - a) Pinholes greater than 1/16 inch in dia. shall not be permitted;
 - b) Large clusters or close spacing of pinholes 1/16 inch and smaller shall not be permitted in the vision glass area; and
 - c) Large clusters or close spacing of pinholes 1/16 inch and smaller may be permitted outside of the vision glass area subject to Architect's acceptance.
 - 2) Scratches: At an indoor viewing distance of 10 feet for low emissivity coatings, and 15 feet for reflective coatings:
 - a) Scratches smaller than 3 inches long are allowed in any glass area;
 - b) Scratches from 3 inches to 5 inches long are allowed only within 3 inches of an edge; and

- c) Scratches greater than 5 inches long shall not be permitted in the vision glass area.
 - d) Concentrated scratches, scuffs, rub marks, cup marks or abraded areas shall not be permitted in any glass area.
- 3) Reflectance and Transmission Inspection: When viewed outdoors against a bright uniform opaque background at a distance of 10 feet for low emissivity coatings (15 feet for reflective coatings), color, reflectance and transmission will be permitted to have a slight variance subject to Architect's acceptance.
- a) Mottling and streaking of the coating shall not be permitted.

2.6 INSULATING GLASS

- A. Insulating-Glass Units: Preassembled units, with dehydrated entrapped air, consisting of sheets of glass hermetically sealed at all edges with a polyisobutylene primary and a silicone secondary elastomeric sealant. The lites of glass shall be separated by dessicant containing aluminum spacers. All insulating glass units shall be IGCC certified to comply with ASTM E 2190 for Class CBA units and with requirements specified in this Article and in the Insulating-Glass Schedule at the end of Part 3.
 - 1. Provide Kind HS (heat-strengthened) float glass where needed to comply with "Performance Requirements" Article. Provide Kind FT (fully tempered) where safety glass is indicated.
- B. Overall Unit Thickness and Thickness of Each Lite: Dimensions indicated in the Insulating-Glass Schedule at the end of Part 3 are nominal and the overall thicknesses of units are measured perpendicularly from outer surfaces of glass lites at unit's edge.

2.7 GLAZING SEALANTS

- A. General:
 - 1. Compatibility: Provide glazing sealants that are compatible with one another and with other materials they will contact, including glass products, seals of insulating-glass units, and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
 - 2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.
 - 3. Sealants used inside the weatherproofing system, shall have a VOC content of not more than 250 g/L when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 - 4. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range.
- B. Glazing Sealant: Neutral-curing silicone glazing sealant complying with ASTM C 920, Type S, Grade NS, Class 100/50, Use NT.

- C. Gasket, Blocking, and Spacer Wet Glazing Materials: Silicone, compatible with and adherent to each material it will be in contact with, as recommended by the manufacturer to fulfill performance requirements.

2.8 GLAZING GASKETS

- A. Lock-Strip Gaskets: Neoprene extrusions in size and shape indicated, fabricated into frames with molded corner units and zipper lock strips, complying with ASTM C 542, black.
- B. Dense Compression Gaskets:
 - 1. EPDM: Continuous extruded EPDM with cross sectional profile, physical properties, and tolerances as recommended by the window and curtain wall manufacturer, and as required, to comply with the performance requirements specified and shown all in compliance with the applicable provisions of ASTM C 864, Option II.
 - 2. Silicone: Continuous extruded silicone with cross sectional profile, physical properties, and tolerances as recommended by the window and curtain wall manufacturer, and as required, to comply with the performance requirements specified and shown all in compliance with the applicable provisions of ASTM C 1115, Type C.
 - 3. Thermoplastic Polyolefin Rubber: Continuous extruded thermoplastic polyolefin rubber with cross sectional profile, physical properties, and tolerances as recommended by the window and curtain wall manufacturer, and as required, to comply with the performance requirements specified and shown all in compliance with the applicable provisions of ASTM C 1115.
 - 4. Any material indicated above.
- C. Soft Compression Gaskets: Continuous extruded expanded foam with, cross sectional profile, physical properties, and tolerances as recommended by the window and curtain wall manufacturer, and as required, to comply with the performance requirements specified and shown all in compliance with the applicable provisions of ASTM C 509, Option II, Type II; provide the following:
 - 1. EPDM.
 - 2. Silicone.
 - 3. Thermoplastic polyolefin rubber.
 - 4. Any material indicated above.

2.9 MISCELLANEOUS GLAZING MATERIALS

- A. General: Provide products of material, size, and shape complying with referenced glazing standard, requirements of manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces, and wet glazing materials, contacted in installation.
- B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.
- C. Setting Blocks: Silicone complying with ASTM C1115 (Type C), blocks, 85 +/- 5 Shore A durometer hardness, 1/16 inch less than the channel width, and length based on the square footage of the glass unit to be supported in accordance with GANA standards and glass manufacturer recommendations but not less than 4 inches.

- D. Edge Blocks: Silicone complying with ASTM C1115 (Type C), blocks, 65 +/- 5 Shore A durometer hardness, minimum 4 inches long and sized to allow 1/8 inch clearance between edge of glass and block.

2.10 FABRICATION OF GLASS AND OTHER GLAZING PRODUCTS

- A. Fabricate glass and other glazing products in sizes required to glaze openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing standard, to comply with system performance requirements.
 - 1. Edge and Surface Conditions: Comply with the recommendations of AAMA "Structural Properties of Glass" for "clean-cut" edges, except comply with manufacturer's recommendations when they are at variance therewith.
- B. Cutting: Do not nip glass edges. Edges may be wheel cut or sawed and seamed at manufacturer's option. For glass to be cut at site, provide glass 2 inches larger than required in both dimensions, so as to facilitate cutting of clean cut edges without the necessity of seaming or nipping. Do not cut, seam, nip or abrade heat-treated glass.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine glass framing, with glazier and glass framing erector present, for compliance with the following:
 - 1. Compliance with the specified manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
 - 2. Presence and functioning of weep system.
 - 3. Minimum required face or edge clearances.
 - 4. Effective sealing between joints of glass-framing members.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean glazing stops, glazing channels, and rabbets which will be in contact with the glazing materials immediately before glazing.
 - 1. Remove coatings that might fail in adhesion or interfere with bond of sealants.
 - 2. Comply with manufacturer's instructions for final wiping of surfaces immediately before application of primers.
 - 3. Wipe metal surfaces with IPA (isopropyl alcohol) unless otherwise required by compatibility and adhesion testing results.
- B. Prime surfaces to receive glazing compounds. When priming, comply with wet glazing manufacturer's recommendations.

- C. Inspect each piece of glass immediately before installation. Do not install any pieces which are improperly sized or have damaged edges, scratches or abrasion or other evidence of damage. Remove labels from glass immediately after installation.
- D. Seal vent (breather or capillary) tubes in insulating glass units in accordance with the insulating glass manufacturer's written recommendations.

3.3 GLAZING, GENERAL

- A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.
 - 1. All glass units shall be installed in accordance with the glass manufacturer's recommendations.
- B. Glazing channel dimensions, as indicated on Drawings, provide necessary bite on glass, minimum edge and face clearances, with reasonable tolerances. Adjust as required by Project conditions during installation.
- C. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass is glass with edge damage or other imperfections that, when installed, could weaken glass and impair performance and appearance.
- D. Apply primers to surfaces indicated to receive glazing materials. Use primers as determined by preconstruction compatibility and adhesion testing.
- E. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless more stringent requirements are recommended by glass manufacturer. Place blocks to allow water passage to weep holes.
 - 1. For Glass Units Less Than 72 inches: Locate setting blocks at sill one-quarter of the width in from each end of the glass unless otherwise recommended by the glass manufacturer.
 - 2. For Glass Units 72 inches or Greater: Locate setting blocks at sill one-eighth of the width in from each end of the glass, but not less than 6 inches, unless otherwise recommended by the glass manufacturer.
- F. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.
- G. Provide edge blocking to prevent glass lites from moving sideways in glazing channel, sized and located to comply with the glass manufacturer's recommendations and the requirements in referenced glazing publications.
- H. Set glass lites with uniform pattern, draw, bow, and similar characteristics, producing the greatest possible degree of uniformity in appearance on the entire exterior wall elevation.
 - 1. Set glass units with void between edge of units and glazing channel.

2. Orient and install insulating glass units made up with one light of low emissivity coated glass with the uncoated glass light on the inboard (building) side.
3. Orient and install insulating glass units made up with one light of tinted glass with the untinted glass light on the inboard (building) side.

I. Where wedge-shaped gaskets are driven into one side of channel to pressurize gasket on opposite side, provide adequate anchorage so gasket cannot walk out when installation is subjected to movement.

J. Miter cut gaskets at corners and install gaskets in a manner recommended by gasket manufacturer to prevent corners from pulling away and join with sealant recommended by gasket manufacturer which will provide an airtight and watertight seal at the joint.

3.4 LOCK-STRIP GASKET GLAZING

A. Comply with ASTM C 716 and gasket manufacturer's written instructions. Use special tool to install and remove filler strips; lubricate in accordance with manufacturer's instructions. Provide supplementary wet seal and weep system, unless otherwise indicated.

3.5 PROTECTION AND CLEANING

A. Protect exterior glass from damage immediately after installation by attaching crossed streamers to framing held away from glass. Do not apply markers to glass surface. Remove nonpermanent labels, and clean surfaces.

B. Protect glass from contact with contaminating substances resulting from construction operations. If, despite such protection, contaminating substances do come into contact with glass, remove them immediately as recommended by glass manufacturer.

C. Remove and replace glass that is broken, chipped, cracked, abraded, or damaged in any way and from any source, including natural causes, accidents, and vandalism.

D. Wash glass on both exposed surfaces in each area of Project not more than four days before date scheduled for inspections that establish date of Substantial Completion. Wash glass as recommended by glass manufacturer.

3.6 MONOLITHIC FLOAT-GLASS SCHEDULE

A. Uncoated Clear Float Glass: Where glass as designated below is indicated, provide Type I (transparent glass, flat), Class 1 (clear) glass lites complying with the following:

1. Uncoated Clear Fully Tempered Float Glass (GL-3 & GL-4): Kind FT (fully tempered).

3.7 INSULATING-GLASS SCHEDULE

A. Low-E Insulating Glass (GL-2): Where glass of this designation is indicated, provide low-emissivity insulating-glass units complying with the following:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Guardian Industries Corporation.
 - b. PPG Industries, Inc.
 - c. Viracon Inc.
 2. Overall Unit Thickness and Thickness of Each Lite: 25 mm (1 inch) and 6 mm (1/4 inch).
 3. Interspace Content: Air.
 4. Indoor Lite: Type I (transparent glass, flat), Class 1 (clear) float glass.
 - a. Kind FT (fully tempered), Condition C (other coated glass).
 5. Outdoor Lite: Type I (transparent glass, flat) float glass.
 - a. Class 1 (clear).
 - b. Kind FT (fully tempered), Condition C (other coated glass).
 6. Low-Emissivity Coating: Sputtered on second surface.
 7. Visible Light Transmittance: 68% minimum.
 8. Solar Energy Transmittance: 31% minimum.
 9. Winter Nighttime U-Value: 0.29 or less.
 10. Summer Daytime U-Value: 0.26 or less.
 11. Solar Heat Gain Coefficient: 0.38 minimum.
- B. Low-E Insulating Glass (GL-1): Where glass of this designation is indicated, provide low-emissivity insulating-glass units complying with the following:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Guardian Industries Corporation.
 - b. PPG Industries, Inc.
 - c. Viracon Inc.
 2. Overall Unit Thickness and Thickness of Each Lite: 25 mm (1 inch) and 6 mm (1/4 inch).
 3. Interspace Content: Air.
 4. Indoor Lite: Type I (transparent glass, flat), Class 1 (clear) float glass.
 - a. Kind HS (heat strengthened), Condition A (uncoated surfaces).
 5. Outdoor Lite: Type I (transparent glass, flat) float glass.
 - a. Class 1 (clear).
 - b. Kind HS (heat strengthened), Condition A (uncoated surfaces).

6. Low-Emissivity Coating: Sputtered on second surface.
7. Visible Light Transmittance: 68% minimum.
8. Solar Energy Transmittance: 31% minimum.
9. Winter Nighttime U-Value: 0.29 or less.
10. Summer Daytime U-Value: 0.26 or less.
11. Solar Heat Gain Coefficient: 0.38 minimum.

END OF SECTION 08 80 00

SECTION 08 84 00 - PLASTIC GLAZING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Monolithic acrylic glazing.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 PERFORMANCE REQUIREMENTS

- A. Provide plastic glazing sheets and glazing materials capable of withstanding normal temperature changes, wind, and impact loads without failure, including loss or breakage of plastic sheets attributable to the following: failure of sealants or gaskets to remain watertight and airtight, deterioration of plastic sheet and glazing materials, or other defects in materials and installation.

- B. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes acting on plastic glazing and glazing framing members.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:

- a. LEED Criteria Worksheet.
- b. Low Emitting Materials Information.
- c. Regional Materials Information.
- d. LEED Materials and Resources Calculator.

- C. Plastic Glazing Samples: For each color and finish of plastic glazing indicated, 12 inches square and of same thickness indicated for final Work.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For installers.

- B. Product Certificates: For plastic glazing and glazing products, from manufacturer.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For plastic glazing to include in maintenance manuals.

1.6 QUALITY ASSURANCE

- A. Sealant Testing Agency Qualifications: An independent testing agency qualified according to ASTM C 1021 to conduct the testing indicated.
- B. Source Limitations: Obtain plastic glazing from single source from single manufacturer. Obtain sealants from single source from single manufacturer for each product and installation method.
- C. Glazing Publication: Comply with published recommendations of plastic glazing manufacturers and with GANA's "Glazing Manual" unless more stringent requirements are indicated. Refer to this publication for definitions of glazing terms not otherwise defined in this Section or in other referenced standards.
- D. Plastic Glazing Labeling: Identify plastic sheets with appropriate markings of applicable testing and inspecting agency, indicating compliance with required fire-test-response characteristics.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Protect plastic glazing materials according to manufacturer's written instructions. Prevent damage to plastic glazing and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.
- B. Maintain protective coverings on plastic glazing to avoid exposures to abrasive substances, excessive heat, and other sources of possible deterioration.

1.8 PROJECT CONDITIONS

- A. Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.
 - 1. Do not install glazing sealants when ambient and substrate temperature conditions are outside limits permitted by sealant manufacturer or below 40 deg F.

1.9 COORDINATION

- A. Coordinate dimensions of plastic glazing with dimensions of construction that receives plastic glazing to ensure that glazing channels provide adequate face and edge clearance, bite, and allowance for expansion.

PART 2 - PRODUCTS

2.1 PLASTIC GLAZING, GENERAL

- A. Sizes: Fabricate plastic glazing to sizes required for openings indicated. Allow for thermal expansion and contraction of plastic glazing without restraint and without withdrawal of edges from frames, with edge clearances and tolerances complying with plastic glazing manufacturer's written instructions.
- B. Fire-Test-Response Characteristics of Plastic Glazing: As determined by testing plastic glazing by a qualified testing agency acceptable to authorities having jurisdiction.
 - 1. Self-ignition temperature of 650 deg F or higher when tested according to ASTM D 1929 on plastic sheets in thicknesses indicated for the Work.
 - 2. Smoke-developed index of 450 or less when tested according to ASTM E 84, or smoke density of 75 or less when tested according to ASTM D 2843 on plastic sheets in thicknesses indicated for the Work.
 - 3. Burning extent of 1 inch or less when tested according to ASTM D 635 at a nominal thickness of 0.060 inch or thickness indicated for the Work.
 - 4. Burning rate of 2.5 in./min. or less when tested according to ASTM D 635 at a nominal thickness of 0.060 inch or thickness indicated for the Work.
 - 5. Flame-spread index not less than that indicated when tested according to ASTM E 84.

2.2 MONOLITHIC ACRYLIC GLAZING

- A. Plastic Glazing: Transparent acrylic sheet; ASTM D 4802, Category A-1 (cell cast), Finish 1 (smooth or polished), Type UVF (UV filtering).
 - 1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. Altuglas International, Division of Arkema Inc.; "Plexiglas G."
 - b. Cyro Industries, a subsidiary of Degussa Corporation; "Acrylite GP."
 - c. Spartech Corporation; "Polycast."
 - 2. Nominal Thickness: As indicated on Drawings.
 - 3. Color: Colorless.

2.3 GLAZING SEALANTS

- A. General:
 - 1. Compatibility: Provide glazing sealants that are compatible with one another and with other materials they will contact, including plastic glazing products and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
 - 2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.

3. Sealants used inside the weatherproofing system shall have a VOC content of not more than 250 g/L when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 4. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range.
- B. Glazing Sealant: Neutral-curing silicone glazing sealant complying with ASTM C 920, Type S, Grade NS, Class 50, Use NT.
1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. BASF Building Systems; Omniseal 50.
 - b. Dow Corning Corporation; 795.
 - c. Sika Corporation, Construction Products Division; SikaSil-C995.
 2. Applications: Apply sealants into glazing channels and grove cuts in wood casework, unless otherwise indicated.

2.4 MISCELLANEOUS GLAZING MATERIALS

- A. Compatibility: Provide products of material, size, and shape complying with requirements of manufacturers of plastic glazing and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.
- B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine plastic glazing framing, with glazing Installer present, for compliance with the following:
1. Manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
 2. Minimum required face or edge clearances.
 3. Effective sealing between joints of plastic glazing framing members.
- B. Proceed with glazing only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean glazing channels and other framing members immediately before glazing. Remove coatings not firmly bonded to substrates. Remove lacquer from metal surfaces where elastomeric sealants are indicated for use.

3.3 GLAZING, GENERAL

- A. Comply with combined written instructions of manufacturers of plastic glazing materials, sealants, and other glazing materials unless more stringent requirements are indicated, including those in referenced glazing publication.
- B. Glazing channel dimensions indicated on Drawings are designed to provide the necessary bite on plastic glazing, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances. Adjust plastic glazing lites during installation to ensure that bite is equal on all sides.
- C. Sand or scrape cut edges of plastic glazing to provide smooth edges, free of chips and hairline cracks.
- D. Remove burrs and other projections from glazing channel surfaces.
- E. Protect plastic glazing surfaces from abrasion and other damage during handling and installation, according to the following requirements:
 - 1. Retain plastic glazing manufacturer's protective covering or protect by other methods according to plastic glazing manufacturer's written instructions.
 - 2. Remove covering at border of each piece before glazing; remove remainder of covering immediately after installation where plastic glazing will be exposed to sunlight or where other conditions make later removal difficult.
 - 3. Remove damaged plastic glazing sheets from Project site and legally dispose of off-site. Damaged plastic glazing sheets are those containing imperfections that, when installed, result in weakened glazing and impaired performance and appearance.
- F. Apply primers to joint surfaces where required for adhesion of sealants, as recommended by sealant manufacturer.

3.4 SEALANT GLAZING (WET)

- A. Force sealants into glazing channels and grove cuts in wood casework, as to eliminate voids and to ensure complete wetting or bond of sealant to plastic glazing and other surfaces.
- B. Tool exposed surfaces of sealants to provide a substantial wash away from plastic glazing.

3.5 PROTECTING AND CLEANING

- A. Protect plastic glazing from contact with contaminating substances from construction operations. If, despite such protection, contaminating substances do come into contact with plastic glazing, remove immediately and wash plastic glazing according to plastic glazing manufacturer's written instructions.
- B. Remove and replace plastic glazing that is broken, chipped, cracked, abraded, or damaged in other ways during construction period, including natural causes, accidents, and vandalism.

- C. Wash plastic glazing on both faces before date scheduled for inspections intended to establish date of Substantial Completion in each area of Project. Wash plastic glazing according to plastic glazing manufacturer's written instructions.

END OF SECTION 08 84 00

SECTION 08 87 00 - GLAZING SURFACE FILMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Security protection film.
2. Decorative film.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Show location and extent of each glazing surface film type. Indicate seams and termination points.
- C. Samples for Verification: For each type of glazing surface film; 6 inches square.
- D. Product Schedule: For glazing surface films. Use same designations indicated on Drawings.

1.3 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For installers.
- B. Product Certificates: For each type of product indicated, from manufacturer.
- C. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for each type of glazing surface films.
- D. Warranties: Sample of special warranties.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer acceptable to product manufacturer who has completed successfully installations of glazing surface film similar in material, design, and extent to that indicated for Project.
- B. Source Limitations: Obtain from single source from single manufacturer for each product.
- C. Mock-up: Provide a mock-up for evaluation of surface preparation techniques and application workmanship.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Protect glazing surface film materials according to manufacturer's written instructions. Prevent damage from condensation, temperature changes, direct exposure to sun, or other causes.

1.6 PROJECT CONDITIONS

- A. Environmental Limitations: Do not proceed with glazing surface film application when ambient and substrate temperature conditions are outside limits permitted by glazing film material manufacturers and when glazing substrates are wet from rain, frost, condensation, or other causes.
1. Do not install glazing surface film when ambient and substrate temperature conditions are outside limits permitted by glazing surface film manufacturer or below 60 deg F.

1.7 WARRANTY

- A. Manufacturer's Special Warranty for Security Protection Film: Manufacturer's standard form in which glazing surface film manufacturer agrees to replace glazing film that deteriorates within specified warranty period. Deterioration is defined as defects developed from normal use that are not attributed to glass breakage or to maintaining and cleaning filmed glass contrary to manufacturer's written instructions. Defects include peeling, cracking, and other indications of deterioration in glazing film.
1. Warranty Period: Provide the following warranty period for exterior and interior applications:
 - a. Exterior: One year from date of Substantial Completion.
 - b. Interior: Ten year from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SECURITY PROTECTION FILM

- A. Anti-Graffiti Window Film (AG-4): Single-layered, abrasion-resistant film used for protecting glass surfaces from all forms of graffiti such as scratches, acid-etching and gouges in retail, and public facilities.
1. Products: Subject to compliance to the requirements, provide "GCL SR PS4" vandal protection transparent window film as manufactured by LLumar Window Film.
 - a. Thickness: 4 mils.
 - b. Roll Width: 72 inches.
 - c. Film Color: Clear.
 - d. Application Method: Wet.
 - 1) Apply on exterior side of exterior glazing.
 2. Performance Requirements:
 - a. Visible Light Transmittance: 89%
 - b. Ultraviolet Transmittance: <5%
 - c. Solar Reflectance: 9%

- B. Safety and Security Window Film (FLM-9): Multilayer, polyester film with abrasion-resistant coating used for strengthening window surfaces, and deterring break and entry (smash and grab) in retail, public facilities and any street-level glass applications.
1. Products: Subject to compliance to the requirements, provide “SCL SR PS8” safety and security window film as manufactured by LLumar Window Film.
 - a. Thickness: 8 mils.
 - b. Roll Width: As selected by Architect from film manufacturer’s standard sizes.
 - c. Film Color: Clear.
 - d. Application Method: Wet.
 - 1) Apply on interior side of exterior glazing.
 2. Performance Requirements:
 - a. Visible Light Transmittance: 88%
 - b. Ultraviolet Transmittance: 1%
 - c. Solar Reflectance: 9%
 3. Attachments System: Provide security window film manufacturers standard factory finished, gasket-style attachment system that locks security window film to window frames.

2.2 DECORATIVE FILM

- A. Opaque Film (FLM-4): Blackout film material with pressure sensitive adhesive for use in blocking out light over glazing application.
1. Products: Subject to compliance to the requirements, provide “3635-22b, Blockout Film” window film as manufactured by 3M.
 - a. Thicknesses: 0.005 inch, with adhesive.
 - b. Color:
 - 1) Face Side: Black.
 - 2) Adhesive Side: White.
 - c. Finish: Matte.
 - d. Application Method: Dry.
 - 1) Apply on exterior side of exterior glazing unless otherwise indicated.
 - e. Adhesive Type: Pressure sensitive.
 - 1) Adhesive Color: Clear.
- B. Oneway Mirror Film (FLM-5): Subject to compliance to the requirements, provide “Symphony DS 15” dual-reflective window film as manufactured by SunTek Window Films; A Division of Commonwealth Laminating & Coating.

1. Thickness: 1.5 mil.
- C. Translucent Overlay Film (FLM-6): Translucent overlay film material with pressure sensitive adhesive.
 1. Products: Subject to compliance to the requirements, provide "1172, ElectroCut Film" window film as manufactured by 3M.
 - a. Thicknesses: 3 mils.
 - b. Color: Red.
 - c. Finish: Transparent.
 - d. Application Method: Dry.
 - 1) Apply on interior side of exterior glazing unless otherwise indicated.
 - e. Adhesive Type: Pressure sensitive.
 - 1) Adhesive Color: Clear.
- D. Transparent Solar Film (FLM-7): Translucent infra-red reflective polyester film with pressure sensitive adhesive.
 1. Products: Subject to compliance to the requirements, provide "Model #V-Kool 70, Solitaire Series" window film as manufactured by V-Kool International Pte Ltd.
 - a. Thicknesses: 1.5 mils.
 - b. Finish: Transparent.
 - c. Application Method: Wet.
 - 1) Apply on interior side of exterior glazing.
 2. Performance Requirements:
 - a. Visible Light Transmittance: 70%
 - b. UV Light Rejected: 99%
 - c. Visible Light Reflected: 8%
- E. Transparent Solar Film (FLM-8): Translucent infra-red reflective polyester film with pressure sensitive adhesive.
 1. Products: Subject to compliance to the requirements, provide "Model #V-Kool 40, Solitaire Series" window film as manufactured by V-Kool International Pte Ltd.
 - a. Thicknesses: 1.5 mils.
 - b. Finish: Transparent.
 - c. Application Method: Wet.
 - 1) Apply on interior side of exterior glazing.
 2. Performance Requirements:

- a. Visible Light Transmittance: 42.8%
- b. UV Light Rejected: 99%
- c. Visible Light Reflected: 10.3%

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine glass surfaces with Installer present to ensure that glass surfaces are free from defects and imperfections, which can affect installation and final appearance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean surfaces thoroughly prior to installation.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.

3.3 INSTALLATION

- A. Install in accordance with manufacturer's instructions.
- B. Cut film edges neatly and square at a uniform distance of 1/8 inch to 1/16 inch of window sealant. Use new blade tips after 3 to 4 cuts.
- C. Spray slip solution of type as recommended by glazing surface film manufacturer on glass substrates and adhesive to facilitate proper positioning of film.
- D. Apply film to glass and lightly spray film with slip solution.
- E. Squeegee from top to bottom of window. Spray slip solution to film and squeegee a second time.
- F. Bump film edge with lint-free towel wrapped around edge of a 5-way tool.
- G. Upon completion of film application, allow 30 days for moisture from film installation to dry thoroughly, and to allow film to dry flat with no moisture dimples when viewed under normal viewing conditions.

3.4 CLEANING AND PROTECTION

- A. Remove left over material and debris from Work area. Use necessary means to protect film before, during, and after installation.
- B. Touch-up, repair or replace damaged products before Substantial Completion.

- C. After application of film, wash film using common window cleaning solutions, including ammonia solutions, 30 days after application. Do not use abrasive type cleaning agents and bristle brushes to avoid scratching film. Use synthetic sponges or soft cloths.

END OF SECTION 08 87 00

SECTION 09 22 16 - NON-STRUCTURAL METAL FRAMING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Non-load-bearing steel framing systems for interior gypsum board assemblies.
2. Suspension systems for interior gypsum ceilings, soffits, and grid systems.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Material Information.
 - d. LEED Materials and Resources Calculator.

1.3 INFORMATIONAL SUBMITTALS

A. Evaluation Reports: For firestop tracks, from ICC-ES.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Structural Performance:

1. Typical Walls: All standard wallboard areas shall be constructed for deflection not to exceed 1/240 of the wall height when subjected to a positive and negative pressure of 5 psf.
2. Walls with Ceramic Tile Finish: All standard wallboard areas to receive ceramic tile finishes shall be constructed for deflection not to exceed 1/360 of the wall height when subjected to a positive and negative pressure of 5 psf.
3. Ceilings, bulkheads, soffits, ceiling transitions, ledges, and coves shall be constructed for a deflection not to exceed 1/360 of the distance between supports.

- B. Fire-Test-Response Characteristics: For fire-resistance-rated assemblies that incorporate non-load-bearing steel framing, provide materials and construction identical to those tested in assembly indicated, according to ASTM E 119 by an independent testing agency.
- C. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated, according to ASTM E 90 and classified according to ASTM E 413 by an independent testing agency.

2.2 FRAMING SYSTEMS

- A. Framing Members, General: Comply with ASTM C 754 for conditions indicated.
 - 1. Steel Sheet Components: Comply with ASTM C 645 requirements for metal unless otherwise indicated.
 - 2. Protective Coating: ASTM A 653/A 653M, G40, hot-dip galvanized unless otherwise indicated. No equivalent coatings (EQ) allowed.
- B. Studs and Runners: ASTM C 645.
 - 1. Steel Studs and Runners:
 - a. Minimum Base-Metal Thickness: As required to comply with deflection criteria.
 - 1) Typical: As required to comply with deflection criteria but not less than 0.0179 inch (25 gauge.)
 - 2) Partitions Supporting Wall Mounted Casework: 0.0538 inch (16 gauge) minimum base metal thickness.
 - b. Depth: As indicated on Drawings.
- C. Silent Stud Framing System: ASTM C 645, ASTM E 119 and ASTM E 90.
 - 1. Product: Subject to compliance with requirements, provide “Sound Guard” silent steel framing system as manufactured by Marino\WARE. Substitutions will not be accepted.
 - a. Minimum STC Rating: 51.
 - 2. Minimum Base-Metal Thickness: 0.0451 inch.
 - 3. Depth: As indicated on drawings.
- D. Slip-Type Head Joints:
 - 1. Deflection Track: Steel sheet top runner manufactured to prevent cracking of finishes applied to interior partition framing resulting from deflection of structure above; in thickness not less than indicated for studs and in width to accommodate depth of studs.
- E. Flat Strap and Backing Plate: Steel sheet for blocking and bracing in length and width indicated.
 - 1. Minimum Base-Metal Thickness: 0.0312 inch.

- F. Cold-Rolled Channel Bridging: Steel, 0.053-inch minimum base-metal thickness, with minimum 1/2-inch- wide flanges.
 - 1. Depth: 1-1/2 inches.
 - 2. Clip Angle: Not less than 1-1/2 by 1-1/2 inches, 0.068-inch- thick, galvanized steel.
- G. Hat-Shaped, Rigid Furring Channels: ASTM C 645.
 - 1. Minimum Base-Metal Thickness: 0.0179 inch.
 - 2. Depth: 7/8 inch, unless otherwise indicated.
- H. Resilient Furring Channels: 1/2-inch- deep, steel sheet members designed to reduce sound transmission.
 - 1. Configuration: Asymmetrical or hat shaped.
- I. Cold-Rolled Furring Channels: 0.053-inch uncoated-steel thickness, with minimum 1/2-inch- wide flanges.
 - 1. Depth: As indicated on Drawings.
 - 2. Furring Brackets: Adjustable, corrugated-edge type of steel sheet with minimum uncoated-steel thickness of 0.033 inch.
- J. Tie Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.062-inch- diameter wire, or double strand of 0.048-inch- diameter wire.
- K. Z-Shaped Furring: With slotted or nonslotted web, face flange of 1-1/4 inches, wall attachment flange of 7/8 inch, minimum uncoated-metal thickness of 0.018 inch, and depth required to fit insulation thickness indicated.

2.3 SUSPENSION SYSTEMS

- A. Tie Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.062-inch- diameter wire, or double strand of 0.048-inch- diameter wire.
- B. Hanger Attachments to Overhead Decks: Suitable for application indicated, fabricated from corrosion resistant materials, with eyepins, clips, or other devices for attaching hangers and capable of sustaining, without failure, a load equal to 5 times that imposed by the complete ceiling systems.
- C. Hangers: As follows:
 - 1. Wire Hangers: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.16 inch in diameter.
- D. Carrying Channels: Cold-rolled, commercial-steel sheet with a base-metal thickness of 0.053 inch and minimum 1/2-inch- wide flanges, with manufacturer's standard corrosion-resistant coating.
 - 1. Depth: 1-1/2 inches, unless otherwise indicated.

- E. Furring Channels (Furring Members): Commercial-steel sheet with manufacturer's standard corrosion-resistant coating.
 - 1. Cold-Rolled Channels: 0.053-inch uncoated-steel thickness, with minimum 1/2-inch-wide flanges, 3/4 inch deep.
 - 2. Steel Studs and Runners: ASTM C 645.
 - a. Minimum Base-Metal Thickness: 0.0312 inch thickness.
 - b. Depth: As indicated on Drawings.
 - 3. Hat-Shaped, Rigid Furring Channels: ASTM C 645, 7/8 inch deep.
 - a. Minimum Base-Metal Thickness: 0.0312 inch thickness.
 - 4. Resilient Furring Channels: 1/2-inch- deep members designed to reduce sound transmission.
 - a. Configuration: Asymmetrical or hat shaped.

2.4 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards.
 - 1. Fasteners for Metal Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and substrates, with Installer present, and including welded hollow-metal frames, cast-in anchors, and structural framing, for compliance with requirements and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Suspended Assemblies: Coordinate installation of suspension systems with installation of overhead structure to ensure that inserts and other provisions for anchorages to building structure have been installed to receive hangers at spacing required to support the Work and that hangers will develop their full strength.
 - 1. Furnish concrete inserts and other devices indicated to other trades for installation in advance of time needed for coordination and construction.

3.3 INSTALLATION, GENERAL

- A. Installation Standard: ASTM C 754.

1. Gypsum Board Assemblies: Also comply with requirements in ASTM C 840 that apply to framing installation.
- B. Install supplementary framing, blocking, backing plates, and bracing at terminations in gypsum board assemblies to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.
 1. Comply with details indicated and with gypsum board manufacturer's written recommendations or, if none available, comply with United States Gypsum's "Gypsum Construction Handbook."
- C. Install bracing at terminations in assemblies.
- D. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.
- E. Isolate steel framing from building structure to prevent transfer of loading imposed by structural movement.
 1. Where building structure abuts ceiling perimeter or penetrates ceiling.
 2. Where partition framing and wall furring abuts structure, except at floor. Install slip-type joints at head of assemblies that avoid axial loading of assembly while laterally supporting the assembly.

3.4 INSTALLING FRAMED ASSEMBLIES

- A. Extend partition framing full height to structural supports or substrates above suspended ceilings, except where partitions are indicated to terminate at suspended ceilings and at partial height partitions. Continue framing over frames for doors and openings and frame around ducts penetrating partitions above ceiling to provide support for gypsum board.
 1. Cut studs 1/2 inch short of full height to provide perimeter relief. Do not fasten studs to top track to allow independent movement of studs and track.
 2. For fire-resistance-rated and STC-rated partitions that extend to the underside of floor/roof slabs and decks or other continuous solid-structure surfaces to obtain ratings, install framing around structural and other members extending below floor/roof slabs and decks, as needed to support gypsum board closures and to make partitions continuous from floor to underside of solid structure.
 3. Terminate partition framing at suspended ceilings as indicated.
 4. Terminate partial height partition framing as indicated.
- B. Install framing system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
 1. Single-Layer Application: 16 inches o.c. unless otherwise indicated.
 2. Multilayer Application: 16 inches o.c. unless otherwise indicated.
- C. Install studs so flanges within framing system point in same direction.

- D. Install tracks (runners) at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts penetrating partitions above ceiling.
1. Slip-Type Head Joints: Where framing extends to overhead structural supports, install to produce joints at tops of framing systems that prevent axial loading of finished assemblies.
 2. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install runner track section (for cripple studs) at head and secure to jamb studs.
 - a. Install two studs at each jamb unless otherwise indicated.
 - b. Install cripple studs at head adjacent to each jamb stud, with a minimum 1/2-inch clearance from jamb stud to allow for installation of control joint in finished assembly.
 - c. Extend jamb studs through suspended ceilings and attach to underside of overhead structure.
 3. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.
 4. Fire-Resistance-Rated Partitions: Install framing to comply with fire-resistance-rated assembly indicated and support closures and to make partitions continuous from floor to underside of solid structure.
 - a. Firestop Track: Where indicated, install to maintain continuity of fire-resistance-rated assembly indicated.
 5. Sound-Rated Partitions: Install framing to comply with sound-rated assembly indicated.
 6. Curved Partitions:
 - a. Bend track to uniform curve and locate straight lengths so they are tangent to arcs.
 - b. Begin and end each arc with a stud, and space intermediate studs equally along arcs. On straight lengths of no fewer than two studs at ends of arcs, place studs 6 inches o.c.
- E. Z-Furring Members:
1. Erect insulation, specified in Division 07 Section "Thermal Insulation," vertically and hold in place with Z-furring members spaced 24 inches o.c.
 2. Except at exterior corners, securely attach narrow flanges of furring members to wall with concrete stub nails, screws designed for masonry attachment, or powder-driven fasteners spaced 24 inches o.c.
 3. At exterior corners, attach wide flange of furring members to wall with short flange extending beyond corner; on adjacent wall surface, screw-attach short flange of furring channel to web of attached channel. At interior corners, space second member no more than 12 inches from corner and cut insulation to fit.
- F. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch from the plane formed by faces of adjacent framing.

3.5 INSTALLING SUSPENSION SYSTEMS

- A. Install suspension system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
 - 1. Hangers: 48 inches o.c.
 - 2. Carrying Channels (Main Runners): 48 inches o.c.
 - 3. Furring Channels (Furring Members): 16 inches o.c.
- B. Isolate suspension systems from building structure where they abut or are penetrated by building structure to prevent transfer of loading imposed by structural movement.
- C. Suspend hangers from building structure as follows:
 - 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structural or suspension system.
 - a. Splay hangers only where required to miss obstructions and offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
 - 2. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with locations of hangers required to support standard suspension system members, install supplemental suspension members and hangers in the form of trapezes or equivalent devices.
 - a. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced installation standards.
 - 3. Wire Hangers: Secure by looping and wire tying, either directly to structures or to inserts, eye screws, or other devices and fasteners that are secure and appropriate for substrate, and in a manner that will not cause hangers to deteriorate or otherwise fail.
 - 4. Flat Hangers: Secure to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices and fasteners that are secure and appropriate for structure and hanger, and in a manner that will not cause hangers to deteriorate or otherwise fail.
 - 5. Do not attach hangers to steel roof deck.
 - 6. Do not attach hangers to permanent metal forms. Furnish cast-in-place hanger inserts that extend through forms.
 - 7. Do not attach hangers to rolled-in hanger tabs of composite steel floor deck.
 - 8. Do not connect or suspend steel framing from ducts, pipes, or conduit.
- D. Fire-Resistance-Rated Assemblies: Wire tie furring channels to supports.
- A. Seismic Bracing: Sway-brace suspension systems with hangers used for support.
- B. Installation Tolerances: Install suspension systems that are level to within 1/8 inch in 12 feet measured lengthwise on each member that will receive finishes and transversely between parallel members that will receive finishes.

Gensler

057.7202.950

Bank of America / BAC Performance / Bulletin 03-2020 / 03-16-20

January 22, 2021
Issue for Construction

Bank of America
BAC Centerville GU
Centerville, UT

END OF SECTION 09 22 16

SECTION 09 24 00 - CEMENT PLASTERING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Exterior portland cement plasterwork (stucco) on metal lath.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Low Emitting Materials Information.
 - d. Regional Material Information.
 - e. LEED Materials and Resources Calculator.

C. Shop Drawings: Show locations and installation of control and expansion joints including plans, elevations, sections, details of components, and attachments to other work.

D. Samples for Verification: For each type of factory-prepared finish coat indicated; 12 by 12 inches, and prepared on rigid backing.

1.3 QUALITY ASSURANCE

A. Mockups: Before plastering, install mockups of at least 100 sq. ft. in surface area to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Install mockups for each type of finish indicated.
2. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

B. Preinstallation Conference: Conduct conference at Project site.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Store materials inside under cover and keep them dry and protected against damage from weather, direct sunlight, surface contamination, corrosion, construction traffic, and other causes.

1.5 PROJECT CONDITIONS

- A. Comply with ASTM C 926 requirements.
- B. Interior Plasterwork: Maintain room temperatures at greater than 40 deg F for at least 48 hours before plaster application, and continuously during and after application.
 - 1. Avoid conditions that result in plaster drying out during curing period. Distribute heat evenly; prevent concentrated or uneven heat on plaster.
 - 2. Ventilate building spaces as required to remove water in excess of that required for hydrating plaster in a manner that prevents drafts of air from contacting surfaces during plaster application and until plaster is dry.
- C. Exterior Plasterwork:
 - 1. Apply and cure plaster to prevent plaster drying out during curing period. Use procedures required by climatic conditions, including moist curing, providing coverings, and providing barriers to deflect sunlight and wind.
 - 2. Apply plaster when ambient temperature is greater than 40 deg F.
 - 3. Protect plaster coats from freezing for not less than 48 hours after set of plaster coat has occurred.
- D. Factory-Prepared Finishes: Comply with manufacturer's written recommendations for environmental conditions for applying finishes.

PART 2 - PRODUCTS

2.1 MANUFACTURES

- A. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1. BASF Wall Systems; "Sentry Stucco Wall System."
 - 2. Dryvit; "Commercial Cement Plaster 2."
 - 3. Parex, Inc., a brand of ParexLaHabra, Inc.; "Parex Armourwall 300 Stucco Assembly."
 - 4. Sto Industries; "StoPowerwall NExT Stucco."

2.2 METAL LATH

- A. Expanded-Metal Lath: ASTM C 847 with ASTM A 653/A 653M, G60, hot-dip galvanized zinc coating.
 - 1. Diamond-Mesh Lath: Self-furring, 3.4 lb/sq. yd.

2.3 ACCESSORIES

- A. General: Comply with ASTM C 1063 and coordinate depth of trim and accessories with thicknesses and number of plaster coats required.
- B. Metal Accessories:
 - 1. Foundation Weep Screed: Fabricated from hot-dip galvanized-steel sheet, ASTM A 653/A 653M, G60 zinc coating.
 - 2. Cornerite: Fabricated from metal lath with ASTM A 653/A 653M, G60, hot-dip galvanized zinc coating.
 - 3. External-Corner Reinforcement: Fabricated from metal lath with ASTM A 653/A 653M, G60, hot-dip galvanized zinc coating.
 - 4. Cornerbeads: Fabricated from zinc.
 - a. Small nose cornerbead with expanded flanges; use unless otherwise indicated.
 - b. Small nose cornerbead with perforated flanges; use on curved corners.
 - c. Small nose cornerbead with expanded flanges reinforced by perforated stiffening rib; use on columns and for finishing masonry corners.
 - 5. Casing Beads: Fabricated from zinc; square-edged style; with expanded flanges.
 - 6. Control Joints: Fabricated from zinc; one-piece-type, folded pair of unperforated screeds in M-shaped configuration; with perforated flanges and removable protective tape on plaster face of control joint.
 - 7. Expansion Joints: Fabricated from zinc; folded pair of unperforated screeds in M-shaped configuration; with expanded flanges.
 - 8. Two-Piece Expansion Joints: Fabricated from zinc; formed to produce slip-joint and square-edged reveal that is adjustable from 1/4 to 5/8 inch wide; with perforated flanges.
 - 9. Reveal Joints: Fabricated from extruded aluminum with factory primed finish.
 - a. Wide Channel Screed (SA-1):
 - 1) Size: 3/4-inch Depth by 2 1/2-inch Width.
 - 2) Products: Subject to compliance with requirements, provide products by one of the following:
 - a) Fry Reglet Corp.; "PCS-75-250."
 - b) Gordon Incorporated; "RP-3425."
 - c) Stockton Products; "PCS-75-250."
 - b. Narrow Channel Screed (SA-2):
 - 1) Size: 3/4-inch Depth by 1/2-inch Width.
 - 2) Products: Subject to compliance with requirements, provide products by one of the following:
 - a) Fry Reglet Corp.; "PCS-75-50."
 - b) Gordon Incorporated; "RP-3412."
 - c) Stockton Products; "PCS-75-50."

10. Modified Channel Screed (SA-3): Fabricated from extruded aluminum with factory primed finish.
 - a. Size: 3/4-inch Depth by 2 1/2-inch Width.
 - b. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Fry Reglet Corp.; "Factory modified PCS-75-250 to make FPM-75-250."
 - 2) Gordon Incorporated; "Factory custom RP-3425 to make "F" profile reveal trim by removing 7/8-inch mounting flange.
 - 3) Stockton Products; "Factory modified PCS-75-250 to make FPM-75-250."
11. Soffit Vent Channel Screed (SA-4): Fabricated from extruded aluminum with factory primed finish.
 - a. Size: 5/8-inch Depth by 4-inch Width.
 - b. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Fry Reglet Corp.; "DCS-625-V-400."
 - 2) Gordon Incorporated; "RD-5840V."
 - 3) Stockton Products; "DCS-625-V-400."
12. "J" Molding (SA-5): Fabricate J-shaped configuration from extruded aluminum with factory primed finish, used to receive exterior plaster finish at termination.
 - a. Size: 3/4-inch Depth.
 - b. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Fry Reglet Corp.; "JDM-75."
 - 2) Gordon Incorporated; "JP-34."
 - 3) Stockton Products; "JPM-75."

2.4 MISCELLANEOUS MATERIALS

- A. Water for Mixing: Potable and free of substances capable of affecting plaster set or of damaging plaster, lath, or accessories.
- B. Asphalt-Saturated Felt: ASTM D 226, Type I (No. 15), nonperforated.
- C. Steel Drill Screws: For metal-to-metal fastening, ASTM C 1002 or ASTM C 954, as required by thickness of metal being fastened; with pan head that is suitable for application; in lengths required to achieve penetration through joined materials of no fewer than three exposed threads.
- D. Fasteners for Attaching Metal Lath to Substrates: Complying with ASTM C 1063.
- E. Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, not less than 0.0475-inch diameter, unless otherwise indicated.

- F. Primer: Manufacturers standard 100% acrylic-based primer.
- G. Acoustical Sealant: As specified in Division 07 Section "Joint Sealants."
 - 1. Sealants shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

2.5 PLASTER MATERIALS

- A. Portland Cement: ASTM C 150, Type I or Type II.
- B. Lime: ASTM C 206, Type S; or ASTM C 207, Type S.
- C. Sand Aggregate: ASTM C 897.
 - 1. Color for Job-Mixed Finish Coats: White.
- D. Acrylic-Based Finish Coatings: Factory-mixed acrylic-emulsion coating systems, formulated with colorfast mineral pigments and fine aggregates; for use over portland cement plaster base coats. Include manufacturer's recommended primers and sealing topcoats for acrylic-based finishes.
 - 1. Colors and Finishes: Refer to "Finish Schedule" located on Drawings for basis-of-design color and finish selections.

2.6 PLASTER MIXES

- A. General: Comply with ASTM C 926 for applications indicated.
- B. Factory Blended Cementitious Base-Coat Mixes for Use over Metal Lath: ASTM C 926, factory prepared base-coat mix consisting of portland cement, lime, fibers contents and manufacturers proprietary materials for use as scratch and brown coatings for three-coat plasterwork. Comply with manufacturer's written instructions.
- C. Factory-Prepared Finish-Coat Mixes: For acrylic-based finish coatings, comply with manufacturer's written instructions.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and substrates, with Installer present, and including welded hollow-metal frames, cast-in anchors, and structural framing, for compliance with requirements and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Protect adjacent work from soiling, spattering, moisture deterioration, and other harmful effects caused by plastering.
- B. Prepare solid substrates for plaster that are smooth or that do not have the suction capability required to bond with plaster according to ASTM C 926.

3.3 INSTALLATION, GENERAL

- A. Clean plaster bases and substrates for direct application of plaster, removing loose material and substances that may impair the Work.
- B. Install temporary grounds and screeds to ensure accurate rodding of plaster to true surfaces; coordinate with scratch-coat work.
- C. Refer to Division 06 Sections "Rough Carpentry" for installing permanent wood grounds.
- D. Refer to Division 07 Sections "Sheet Metal Flashing and Trim" for installing flashing.
- E. Surface Conditioning: Immediately before plastering, dampen concrete and concrete unit masonry substrates, except where a bonding agent has been applied, to produce optimum suction for plastering.

3.4 INSTALLING METAL LATH

- A. Expanded-Metal Lath: Install according to ASTM C 1063.

3.5 INSTALLING ACCESSORIES

- A. Install according to ASTM C 1063 and at locations indicated on Drawings.
 - 1. Attach accessories securely to plaster bases to hold accessories in place and alignment during plastering. Securely fasten with hardened galvanized screws. Space fastenings not more than 7 inches apart and staggered.
- B. Reinforcement for External Corners:
 - 1. Install lath-type, external-corner reinforcement at exterior locations.
- C. Casing Beads: Install at terminations of plaster work. Miter or cope accessories at corners. Set beads level, plumb and true to line.
- D. Control Joints: Install control joints at locations indicated on Drawings.
- E. Weep Screed: Install weep screed at locations indicated on Drawings and as follows:
 - 1. Install weep screed at or below foundation plate line on all exterior walls unless otherwise indicated.
 - 2. Install weep screed a minimum of 4 inches above the earth or 2 inches above paved areas

- F. Horizontal Reveals: Make horizontal reveals at parapet walls and other locations where indicated, with a positive slope away from building sheathing.

3.6 PLASTER APPLICATION

A. General: Comply with ASTM C 926.

1. Mechanically mix cementitious materials for plasters to comply with applicable referenced application standard and with recommendations of plaster manufacturer.
 - a. Do not use materials that are frozen, caked, lumpy, dirty, or contaminated by foreign materials.
 - b. Do not use excessive water in mixing and applying plaster materials.
2. Do not deviate more than plus or minus 1/8 inch in 10 feet from a true plane in finished plaster surfaces, as measured by a 10-foot straightedge placed on surface.
3. Grout hollow-metal frames, bases, and similar work occurring in plastered areas, with base-coat plaster material, and before lathing where necessary. Except where full grouting is indicated or required for fire-resistance rating, grout at least 6 inches at each jamb anchor.
4. Sequence plaster application with installation and protection of other work so that neither will be damaged by installation of other.
5. Finish plaster flush with metal frames and other built-in metal items or accessories that act as a plaster ground unless otherwise indicated. Where casing bead does not terminate plaster at metal frame, cut base coat free from metal frame before plaster sets and groove finish coat at junctures with metal.
6. Provide plaster surfaces that are ready to receive field-applied finishes indicated.
7. Corners: Make internal corners and angles square; finish external corners flush with cornerbeads on interior work, square and true with plaster faces on exterior work.

B. Walls; Base-Coat Mixes for Use over Metal Lath: Scratch and brown coats for three-coat plasterwork; 3/4-inch thickness.

1. Portland cement mixes.

C. Ceilings; Base-Coat Mixes for Use over Metal Lath: Scratch and brown coats for three-coat plasterwork; 1/2 inch thick.

1. Portland cement mixes.

D. Acrylic-Based Finish Coatings: Apply coating system, including primers, finish coats, and sealing topcoats, according to manufacturer's written instructions.

1. Remove surface contaminants such as dust and dirt without damaging the brown coat substrate. Apply only to brown coat surfaces that are sound, clean, dry, and free from any residue which may affect the ability of the primer to bond to the brown coat surface. Apply finish coat primer with a roller, brush or a hopper sprayer gun in a continuous coat of thickness as recommended by the finish coat manufacturer. Allow to dry completely before applying finish coat.

- E. Concealed Exterior Plasterwork: Where plaster application will be used as a base for adhered finishes, omit finish coat.

3.7 PLASTER REPAIRS

- A. Repair or replace work to eliminate cracks, dents, blisters, buckles, crazing and check cracking, dry outs, efflorescence, sweat outs, and similar defects and where bond to substrate has failed.
 - 1. Cut, patch, replace, repair, and point up plaster as necessary to accommodate other work.
 - 2. Point-up finish plaster surfaces around items that are built into or penetrate plaster surfaces.
 - 3. Repair or replace work as necessary to comply with required visual effects.

3.8 PROTECTION

- A. Remove temporary protection and enclosure of other work. Promptly remove plaster from door frames, windows, and other surfaces not indicated to be plastered. Repair floors, walls, and other surfaces stained, marred, or otherwise damaged during plastering.

END OF SECTION 09 24 00

SECTION 09 29 00 - GYPSUM BOARD

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior gypsum board.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.
 - d. Low-Emitting Materials Information
 - e. Laboratory Testing or GreenGuard Gold Certificates.

C. Samples: For the following products:

1. Trim Accessories: Full-size Sample in 12-inch- long length for each trim accessory indicated.

1.3 QUALITY ASSURANCE

A. Mockups: Before beginning gypsum board installation, install mockups of at least 100 sq. ft. in surface area to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Install mockups for the following:
 - a. Each level of gypsum board finish indicated for use in exposed locations.
2. Apply or install final decoration indicated, including painting on exposed surfaces for review of mockups.
3. Simulate finished lighting conditions for review of mockups.
4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.4 DELIVERY, STORAGE AND HANDLING

- A. Store materials inside under cover and keep them dry and protected against weather, condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

1.5 FIELD CONDITIONS

- A. Environmental Limitations: Comply with ASTM C 840 requirements or gypsum board manufacturer's written recommendations, whichever are more stringent.
- B. Do not install paper-faced gypsum panels until installation areas are enclosed and conditioned.
- C. Do not install panels that are wet, those that are moisture damaged, and those that are mold damaged.
 - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
 - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Resistance-Rated Assemblies: For fire-resistance-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 119 by an independent testing agency.
- B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 90 and classified according to ASTM E 413 by an independent testing agency.
- C. Sustainability: All gypsum board assemblies installed in the building interior must meet the testing and product requirements of the California Department of Health Services Standard Practice for the Testing of Volatile Organic Emissions from the Various Sources Using Small-Scale Environmental Chambers, including 2004 addenda.

2.2 GYPSUM BOARD, GENERAL

- A. Size: Provide maximum lengths and widths available that will minimize joints in each area and that correspond with support system indicated.

2.3 INTERIOR GYPSUM BOARD

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. American Gypsum.

2. CertainTeed Corporation.
3. Georgia-Pacific Gypsum LLC.
4. National Gypsum Company.
5. USG Corporation.

B. Gypsum Wallboard: ASTM C 1396/C 1396M.

1. Thickness: 5/8 inch.
2. Long Edges: Tapered.

C. Gypsum Board, Type X: ASTM C 1396/C 1396M.

1. Thickness: 5/8 inch.
2. Long Edges: Tapered.

D. Flexible Gypsum Board: ASTM C 1396/C 1396M. Manufactured to bend to fit radii and to be more flexible than standard regular-type gypsum board of same thickness.

1. Thickness: 1/4 inch.
2. Long Edges: Tapered.

E. Gypsum Ceiling Board: ASTM C 1396/C 1396M.

1. Thickness: 1/2 inch.
2. Long Edges: Tapered.

F. Moisture- and Mold-Resistant Gypsum Board: ASTM C 1396/C 1396M. With moisture- and mold-resistant core and paper surfaces.

1. Core: 5/8 inch, Type X.
2. Long Edges: Tapered.
3. Mold Resistance: ASTM D 3273, score of 10 as rated according to ASTM D 3274.

2.4 TRIM ACCESSORIES

A. Interior Trim: ASTM C 1047.

1. Material: Galvanized or aluminum-coated steel sheet or rolled zinc.
 2. Shapes:
 - a. Cornerbead.
 - b. Bullnose bead.
 - c. L-Bead: L-shaped; exposed long flange receives joint compound.
 - d. U-Bead: J-shaped; exposed short flange does not receive joint compound.
 - e. Expansion (control) joint.
 - f. Curved-Edge Cornerbead: With notched or flexible flanges.
 - g. F-Reveal Molding: F-shaped; exposed flange receives joint compound.
- 1) Basis-of-Design Product: Subject to compliance to the requirements, provide "Model #DRMF-50-125" non-vented, F-shaped, reveal molding as

manufactured by Fry Reglet Corporation or proposed substitution complying with Division 01 Section "Substitution Procedures."

a) Size: 1/2-inch Depth by 1/8-inch Width.

B. Aluminum Trim: Extruded accessories of profiles and dimensions indicated.

1. Aluminum: Alloy and temper with not less than the strength and durability properties of ASTM B 221, Alloy 6063-T5.
2. Finish: Corrosion-resistant primer compatible with joint compound and finish materials specified.

2.5 JOINT TREATMENT MATERIALS

A. General: Comply with ASTM C 475/C 475M.

B. Joint Tape:

1. Interior Gypsum Board: Paper.

C. Joint Compound for Interior Gypsum Board: For each coat use formulation that is compatible with other compounds applied on previous or for successive coats.

1. Prefilling: At open joints and damaged surface areas, use setting-type taping compound.
2. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use setting-type taping compound.
3. Fill Coat: For second coat, use setting-type, sandable topping compound.
4. Finish Coat: For third coat, use drying-type, all-purpose compound.
5. Skim Coat: For final coat of Level 5 finish, use drying-type, all-purpose compound.

2.6 AUXILIARY MATERIALS

A. General: Provide auxiliary materials that comply with referenced installation standards and manufacturer's written recommendations.

B. Steel Drill Screws: ASTM C 1002, unless otherwise indicated.

1. Use screws complying with ASTM C 954 for fastening panels to steel members from 0.033 to 0.112 inch thick.

C. Sound Attenuation Blankets: ASTM C 665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.

1. Fire-Resistance-Rated Assemblies: Comply with mineral-fiber requirements of assembly.

D. Acoustical Joint Sealant: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834. Product effectively reduces airborne sound transmission through

perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.

1. Products: Subject to compliance with requirements, provide one of the following products or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Accumetric LLC; BOSS 824 Acoustical Sound Sealant.
 - b. Pecora Corporation; AIS-919.
 - c. USG Corporation; SHEETROCK Acoustical Sealant.
2. Acoustical joint sealant shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

E. Thermal Insulation: As specified in Division 07 Section "Thermal Insulation."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and substrates including welded hollow-metal frames and framing, with Installer present, for compliance with requirements and other conditions affecting performance.
- B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLYING AND FINISHING PANELS, GENERAL

- A. Comply with ASTM C 840.
- B. Install ceiling panels across framing to minimize the number of abutting end joints and to avoid abutting end joints in central area of each ceiling. Stagger abutting end joints of adjacent panels not less than one framing member.
- C. Install panels with face side out. Butt panels together for a light contact at edges and ends with not more than 1/16 inch of open space between panels. Do not force into place.
- D. Locate edge and end joints over supports, except in ceiling applications where intermediate supports or gypsum board back-blocking is provided behind end joints. Do not place tapered edges against cut edges or ends. Stagger vertical joints on opposite sides of partitions. Do not make joints other than control joints at corners of framed openings.
- E. Form control and expansion joints with space between edges of adjoining gypsum panels.
- F. Cover both faces of support framing with gypsum panels in concealed spaces (above ceilings, etc.), except in chases braced internally.

1. Unless concealed application is indicated or required for sound, fire, air, or smoke ratings, coverage may be accomplished with scraps of not less than 8 sq. ft. in area.
 2. Fit gypsum panels around ducts, pipes, and conduits.
 3. Where partitions intersect structural members projecting below underside of floor/roof slabs and decks, cut gypsum panels to fit profile formed by structural members; allow 1/4- to 3/8-inch- wide joints to install sealant.
- G. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments, except floors. Provide 1/4- to 1/2-inch- wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.
- H. Attachment to Steel Framing: Attach panels so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.
- I. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical sealant. Install acoustical sealant at both faces of partitions at perimeters and through penetrations. Comply with ASTM C 919 and with manufacturer's written recommendations for locating edge trim and closing off sound-flanking paths around or through assemblies, including sealing partitions above acoustical ceilings.
- J. Install sound attenuation blankets before installing gypsum panels unless blankets are readily installed after panels have been installed on one side.

3.3 APPLYING INTERIOR GYPSUM BOARD

- A. Install interior gypsum board in the following locations:
1. Wallboard Type: Vertical surfaces unless otherwise indicated.
 2. Type X: Where required for fire-resistance-rated assembly.
 3. Flexible Type: Apply in double layer at curved assemblies.
 4. Ceiling Type: Ceiling surfaces.
 5. Moisture- and Mold-Resistant Type: As indicated on Drawings.
- B. Single-Layer Application:
1. On ceilings, apply gypsum panels before wall/partition board application to greatest extent possible and at right angles to framing unless otherwise indicated.
 2. On partitions/walls, apply gypsum panels vertically (parallel to framing) unless otherwise indicated or required by fire-resistance-rated assembly, and minimize end joints.
 - a. Stagger abutting end joints not less than one framing member in alternate courses of panels.
 - b. At stairwells and other high walls, install panels horizontally unless otherwise indicated or required by fire-resistance-rated assembly.
 3. On Z-furring members, apply gypsum panels vertically (parallel to framing) with no end joints. Locate edge joints over furring members.
 4. Fastening Methods: Apply gypsum panels to supports with steel drill screws.

C. Multilayer Application:

1. On ceilings, apply gypsum board indicated for base layers before applying base layers on walls/partitions; apply face layers in same sequence. Apply base layers at right angles to framing members and offset face-layer joints one framing member, 16 inches minimum, from parallel base-layer joints, unless otherwise indicated or required by fire-resistance-rated assembly.
2. On partitions/walls, apply gypsum board indicated for base layers and face layers vertically (parallel to framing) with joints of base layers located over stud or furring member and face-layer joints offset at least one stud or furring member with base-layer joints, unless otherwise indicated or required by fire-resistance-rated assembly. Stagger joints on opposite sides of partitions.
3. On Z-furring members, apply base layer vertically (parallel to framing) and face layer either vertically (parallel to framing) or horizontally (perpendicular to framing) with vertical joints offset at least one furring member. Locate edge joints of base layer over furring members.
4. Fastening Methods: Fasten base layers and face layers separately to supports with screws.

D. Curved Surfaces:

1. Install panels horizontally (perpendicular to supports) and unbroken, to extent possible, across curved surface plus 12-inch- long straight sections at ends of curves and tangent to them.
2. For double-layer construction, fasten base layer to studs with screws 16 inches o.c. Center gypsum board face layer over joints in base layer, and fasten to studs with screws spaced 12 inches o.c.

3.4 INSTALLING TRIM ACCESSORIES

- A. General:** For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.
- B. Control Joints:** Install control joints at locations indicated on Drawings.
- C. Interior Trim:** Install in the following locations:
1. Cornerbead: Use at outside corners.
 2. Bullnose Bead: Use where indicated.
 3. L-Bead: Use where indicated.
 4. U-Bead: Use at exposed panel edges.
 5. Curved-Edge Cornerbead: Use at curved openings.
 6. F-Reveal Molding: Use where indicated.
- D. Aluminum Trim:** Install in locations indicated on Drawings.

3.5 FINISHING GYPSUM BOARD

- A. General: Treat gypsum board joints, interior angles, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare gypsum board surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.
- B. Prefill open joints and damaged surface areas.
- C. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.
- D. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C 840 and GA-214:
 - 1. Level 1: Ceiling plenum areas, concealed areas, and where indicated.
 - 2. Level 2: Panels that are substrate for tile and where indicated on Drawings.
 - 3. Level 4: At panel surfaces that will be exposed to view unless otherwise indicated.
 - a. Primer and its application to surfaces are specified in Division 09 Section "Interior Painting."
 - 4. Level 5: At surfaces receiving gloss and semigloss enamels and other surfaces subject to severe lighting and where else indicated on Drawings.
 - a. Primer and its application to surfaces are specified in Division 09 Section "Interior Painting."

3.6 PROTECTION

- A. Protect adjacent surfaces from drywall compound and promptly remove from floors and other non-drywall surfaces. Repair surfaces stained, marred, or otherwise damaged during drywall application.
- B. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.
- C. Remove and replace panels that are wet, moisture damaged, and mold damaged.
 - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
 - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

END OF SECTION 09 29 00

SECTION 09 30 13 - CERAMIC TILING**PART 1 - GENERAL****1.1 SUMMARY****A. Section Includes:**

1. Porcelain tile.
2. Tile backing panels.
3. Crack isolation membrane.
4. Metal edge strips.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 DEFINITIONS

- A. General: Definitions in the ANSI A108 series of tile installation standards and in ANSI A137.1 apply to Work of this Section unless otherwise specified.
- B. ANSI A108 Series: ANSI A108.01, ANSI A108.02, ANSI A108.1A, ANSI A108.1B, ANSI A108.1C, ANSI A108.4, ANSI A108.5, ANSI A108.6, ANSI A108.8, ANSI A108.9, ANSI A108.10, ANSI A108.11, ANSI A108.12, ANSI A108.13, ANSI A108.14, ANSI A108.15, ANSI A108.16, and ANSI A108.17, which are contained in its "Specifications for Installation of Ceramic Tile."
- C. Face Size: Actual tile size, excluding spacer lugs.

1.3 PERFORMANCE REQUIREMENTS

- A. General: Provide floor tiles complying with one of the following standard and performance requirements.
- B. Dynamic Coefficient of Friction (DCOF): For tile installed on walkway surfaces, provide products with the following value as determined by testing identical products by the DCOF AcuTest Method per ANSI 137.1, 2012 Edition.
 1. Walkway Surfaces: Minimum 0.42.

1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1. Review requirements in ANSI A108.01 for substrates and for preparation by other trades.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. LEED Documentation Submittals:
 1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Low Emitting Materials Information.
 - d. FloorScore certification.
- C. Shop Drawings: Show locations of each type of tile and tile pattern. Show widths, details, and locations of expansion, contraction, control, and isolation joints in tile substrates and finished tile surfaces.
- D. Samples for Verification:
 1. Full-size units of each type and composition of tile and for each color and finish required.
 2. Assembled samples mounted on a rigid panel, with grouted joints, for each type and composition of tile and for each color and finish required. Make samples at least 12 inches square, but not fewer than four tiles. Use grout of type and in color or colors approved for completed Work.
 3. Full-size units of each type of trim and accessory.
 4. Metal edge strips in 6-inch lengths.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Certificates: For each type of product.

1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match and are from same production runs as products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 1. Tile and Trim Units: Furnish quantity of full-size units equal to 3 percent of amount installed for each type, composition, color, pattern, and size indicated.
 2. Grout: Furnish quantity of grout equal to 3 percent of amount installed for each type, composition, and color indicated.

1.8 QUALITY ASSURANCE

- A. Installer Qualifications: Engage an installer, with a minimum of 5 years of successful commercial tile installations similar in material, design, and scope to that indicated.
- B. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
 - 1. Build mockups at locations and size as directed by the Architect.
 - 2. Build mockup of each type of floor tile installation.
 - 3. Build mockup of each type of wall tile installation.
 - 4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver and store packaged materials in original containers with seals unbroken and labels intact until time of use. Comply with requirements in ANSI A137.1 for labeling tile packages.
- B. Store tile and cementitious materials on elevated platforms, under cover, and in a dry location.
- C. Store liquid materials in unopened containers and protected from freezing.

1.10 FIELD CONDITIONS

- A. Environmental Limitations: Do not install tile until construction in spaces is complete and ambient temperature and humidity conditions are maintained at the levels indicated in referenced standards and manufacturer's written instructions.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Source Limitations for Tile: Obtain tile of each type from single source or producer.
 - 1. Obtain tile of each type and color or finish from same production run and of consistent quality in appearance and physical properties for each contiguous area.
- B. Source Limitations for Setting and Grouting Materials: Obtain ingredients of a uniform quality for each mortar, adhesive, and grout component from single manufacturer and each aggregate from single source or producer.
 - 1. Obtain setting and grouting materials, except for unmodified Portland cement and aggregate, from single manufacturer.
 - 2. Obtain crack isolation membrane, from manufacturer of setting and grouting materials.

- C. Source Limitations for Other Products: Obtain each of the following products specified in this Section from a single manufacturer:

1. Cementitious backer units.
2. Metal edge strips.

2.2 PRODUCTS, GENERAL

- A. ANSI Ceramic Tile Standard: Provide tile that complies with ANSI A137.1 for types, compositions, and other characteristics indicated.
1. Provide tile complying with Standard grade requirements unless otherwise indicated.
- B. ANSI Standards for Tile Installation Materials: Provide materials complying with ANSI A108.02, ANSI standards referenced in other Part 2 articles, ANSI standards referenced by TCNA installation methods specified in tile installation schedules, and other requirements specified.
- C. Factory Blending: For tile exhibiting color variations within ranges, blend tile in factory and package so tile units taken from one package show same range in colors as those taken from other packages and match approved Samples.

2.3 TILE PRODUCTS

- A. Field Tile Type (CT-5): Unglazed porcelain tile.
1. Product: Subject to compliance with requirements, provide “Nest Porcelain Stone” field tile as manufactured by Crossville, Inc.
 - a. Tile Color: #AV353 - Blissful Oak.
 2. Nominal Size: 6 by 36 inches.
 3. Thickness: 0.413 inch (10.5mm.)
 4. Face: Plain with square or cushion edges.
 5. Grout Color: Refer to “Finish Schedule” located on Drawings for color selection.
- A. Tile Type (CT-12): Glazed ceramic tile.
1. Product: Subject to compliance with requirements, provide “Color Wheel Collection - Classic” tile as manufactured by Daltile.
 - a. Tile Color: Matte Desert X714.
 2. Nominal Size: 3 by 6 inches.
 3. Thickness: 5/16 inch.
 4. Face: Plain with square or cushion edges.
 5. Grout Color: Refer to “Finish Schedule” located on Drawings for color selection.

6. Trim Units: Coordinated with sizes and coursing of adjoining flat tile where applicable and matching characteristics of adjoining flat tile. Provide shapes as follows, selected from manufacturer's standard shapes:
 - a. Bullnose Trims for Thin-Set Mortar Installations (CT-12b): Surface bullnose, same size as adjoining flat tile.
 - 1) Product: Subject to compliance with requirements, provide "Color Wheel Collection - Classic, #S-4369M" wall bullnose tile as manufactured by Daltile.
 - a) Face Size: 3 inches by 6 inches.
 - b) Color: Match wall tile.
 - b. Base for Thin-Set Mortar Installations (CT-12c): Cove base.
 - 1) Product: Subject to compliance with requirements, provide "Color Wheel Collection - Classic, #A-3361" flat top cove base tile as manufactured by Daltile.
 - a) Face Size: 3 inches by 6 inches.
 - b) Color: Match wall tile.

2.4 TILE BACKING PANELS

- A. Cementitious Backer Units: ANSI A118.9 or ASTM C1325, Type A, in maximum lengths available to minimize end-to-end butt joints.
 1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. National Gypsum Company; "PermaBase Cement Board"
 - b. USG Corporation; "Durock Brand Cement Board with EdgeGuard."
 2. Thickness: 1/2 inch.

2.5 CRACK ISOLATION MEMBRANE

- A. General: Manufacturer's standard product that complies with ANSI A118.12 for standard performance and is recommended by the manufacturer for the application indicated. Include reinforcement and accessories recommended by manufacturer.
- B. Fluid-Applied Membrane: Liquid-latex rubber or elastomeric polymer.
 1. Basis-of-Design Products: Subject to compliance with requirements, provide "Mapelastic CI" crack-isolation membrane as manufactured by MAPEI Corporation or comparable product offered by one of the following:

- a. Custom Building Products; “RedGard Waterproofing and Crack Prevention Membrane.”
- b. LATICRETE SUPERCAP, LLC.; “Hydro Ban.”

2.6 SETTING MATERIALS

A. Improved Modified Dry-Set Mortar (Thinset): ANSI A118.15HT.

- 1. Basis-of-Design Products: Subject to compliance with requirements, provide “Ultraflex LFT” mortar as manufactured by MAPEI Corporation or comparable product offered by one of the following:
 - a. Custom Building Products; “ProLite Premium Large Format Tile Mortar.”
 - b. LATICRETE SUPERCAP, LLC.; “4-XLT.”
- 2. Provide prepackaged, dry-mortar mix containing dry, redispersible, vinyl acetate or acrylic additive to which only water must be added at Project site.
- 3. For wall applications, provide mortar that complies with requirements for nonsagging mortar in addition to the other requirements in ANSI A118.15.

2.7 GROUT MATERIALS

A. High-Performance Tile Grout: ANSI A118.7.

- 1. Basis-of-Design Products: Subject to compliance with requirements, provide “Ultracolor Plus FA” mortar of color as indicated on Drawings and as manufactured by MAPEI Corporation or comparable product offered by one of the following:
 - a. Custom Building Products; “Prism Color Consistent Grout.”
 - b. LATICRETE SUPERCAP, LLC.; “Permacolor Select.”
- 2. Polymer Type: Ethylene vinyl acetate or acrylic additive, in dry, redispersible form, prepackaged with other dry ingredients.

2.8 MISCELLANEOUS MATERIALS

- A. Trowelable Underlayments and Patching Compounds: Latex-modified, portland cement-based formulation provided or approved by manufacturer of tile-setting materials for installations indicated.
- B. Metal Edge and Transition Strips: Provide transition and reducer metal edge stripping in single lengths wherever possible, keeping the number of joints or splices to a minimum and of height required to protect exposed edges of tile. Provide in quantities and locations as job required based upon the recommended good practice of the industry; include in every location where tile terminates and other flooring continues.

1. Products: Subject to compliance with requirements, provide the following metal edge and transition strip products as manufactured by Genotek; Tele: (800)741-8936:
 - a. Ceramic Tile to VCT (TS-4): 5/8-inch thick "Genotek; Model: #681-Adjustable Short Arm; Color: #64-Satin Black" anodized aluminum finish, transition strip.
 - b. Ceramic Tile to Walkoff Mat (TS-3): 5/8-inch thick "Genotek; Model: #320-Edge Divider-Large; Color: #64-Satin Black" anodized aluminum finish edge divider.
 - c. Carpet to Ceramic Tile (TS-1): 5/8-inch thick "Genotek; Model: #630-Tile Transition; Color: #64-Satin Black" anodized aluminum finish transition strip. Tile Cleaner: A neutral cleaner capable of removing soil and residue without harming tile and grout surfaces, specifically approved for materials and installations indicated by tile and grout manufacturers.

C. Joint Sealants:

1. Typical Surfaces: "Mildew-Resistant Silicone Sealant", as specified in Section 07 92 00 "Joint Sealants."

D. Tile Cleaner: A neutral cleaner capable of removing soil and residue without harming tile and grout surfaces, specifically approved for materials and installations indicated by tile and grout manufacturers.

E. Grout Sealer: Manufacturer's standard product for sealing grout joints and that does not change color or appearance of grout.

2.9 MIXING MORTARS AND GROUT

- A. Mix mortars and grouts to comply with referenced standards and mortar and grout manufacturers' written instructions.
- B. Add materials, water, and additives in accurate proportions.
- C. Obtain and use type of mixing equipment, mixer speeds, mixing containers, mixing time, and other procedures to produce mortars and grouts of uniform quality with optimum performance characteristics for installations indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions where tile will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

1. Verify that substrates for setting tile are firm; dry; clean; free of coatings that are incompatible with tile-setting materials, including curing compounds and other substances that contain soap, wax, oil, or silicone; and comply with flatness tolerances required by ANSI A108.01 for installations indicated.
 2. Verify that concrete substrates for tile floors installed with thinset mortar comply with surface finish requirements in ANSI A108.01 for installations indicated.
 - a. Verify that surfaces that received a steel trowel finish have been mechanically scarified.
 - b. Verify that protrusions, bumps, and ridges have been removed by sanding or grinding.
 3. Verify that installation of grounds, anchors, recessed frames, electrical and mechanical units of work, and similar items located in or behind tile has been completed.
 4. Verify that joints and cracks in tile substrates are coordinated with tile joint locations; if not coordinated, adjust joint locations in consultation with Architect.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Fill cracks, holes, and depressions in concrete substrates for tile floors installed with thinset mortar with trowelable leveling and patching compound specifically recommended by tile-setting material manufacturer.
- B. Blending: For tile exhibiting color variations, verify that tile has been factory blended and packaged so tile units taken from one package show same range of colors as those taken from other packages and match approved Samples. If not factory blended, either return to manufacturer or blend tiles at Project site before installing.

3.3 INSTALLATION OF CERAMIC TILE

- A. Comply with TCNA's "Handbook for Ceramic, Glass, and Stone Tile Installation" for TCNA installation methods specified in tile installation schedules. Comply with parts of the ANSI A108 series "Specifications for Installation of Ceramic Tile" that are referenced in TCNA installation methods, specified in tile installation schedules, and apply to types of setting and grouting materials used.
 1. For the following installations, follow procedures in the ANSI A108 series of tile installation standards for providing 95 percent mortar coverage:
 - a. Tile floors in wet areas.
 - b. Tile floors consisting of tiles 8 by 8 inches or larger.
- B. Extend tile work into recesses and under or behind equipment and fixtures to form complete covering without interruptions unless otherwise indicated. Terminate work neatly at obstructions, edges, and corners without disrupting pattern or joint alignments.

- C. Accurately form intersections and returns. Perform cutting and drilling of tile without marring visible surfaces. Carefully grind cut edges of tile abutting trim, finish, or built-in items for straight aligned joints. Fit tile closely to electrical outlets, piping, fixtures, and other penetrations so plates, collars, or covers overlap tile.
- D. Provide manufacturer's standard trim shapes where necessary to eliminate exposed tile edges.
- E. Jointing Pattern: Lay tile in grid pattern unless otherwise indicated. Lay out tile work and center tile fields in both directions in each space or on each wall area. Lay out tile work to minimize the use of pieces that are less than half of a tile. Provide uniform joint widths unless otherwise indicated.
 - 1. Where adjoining tiles on floor, base, walls, or trim are specified or indicated to be same size, align joints.
 - 2. Where tiles are specified or indicated to be whole integer multiples of adjoining tiles on floor, base, walls, or trim, align joints unless otherwise indicated.
- F. Joint Widths: Unless otherwise indicated, install tile with the following joint widths:
 - 1. Porcelain Tile:
 - a. Wall Tile, Base Tile and Trims (CT-12, CT-12b & CT-12c): 1/8 inch.
 - b. Floor Tile (CT-8): 1/8 inch.
 - c. Plank Floor Tile:
 - 1) (CT-5): 1/8 inch.
- G. Expansion Joints: Provide expansion joints and other sealant-filled joints, including control, contraction, and isolation joints, where indicated. Form joints during installation of setting materials, mortar beds, and tile. Do not saw-cut joints after installing tiles.
 - 1. Where joints occur in concrete substrates, locate joints in tile surfaces directly above them.
- H. Metal Edge Strips: Install at locations indicated.
- I. Floor Sealer: Apply floor sealer to grout joints according to floor-sealer manufacturer's written instructions. As soon as floor sealer has penetrated grout joints, remove excess sealer and sealer from tile faces by wiping with soft cloth.

3.4 INSTALLATION OF TILE BACKING PANEL

- A. Install panels and treat joints according to ANSI A108.11 and manufacturer's written instructions for type of application indicated.

3.5 INSTALLATION OF CRACK ISOLATION MEMBRANE

- A. Install crack isolation membrane to comply with ANSI A108.17 and manufacturer's written instructions to produce membrane of uniform thickness that is bonded securely to substrate.
- B. Allow crack isolation membrane to cure before installing tile or setting materials over it.

3.6 ADJUSTING AND CLEANING

- A. Remove and replace tile that is damaged or that does not match adjoining tile. Provide new matching units, installed as specified and in a manner to eliminate evidence of replacement.
- B. Cleaning: On completion of placement and grouting, clean all ceramic tile surfaces so they are free of foreign matter.
 - 1. Remove grout residue from tile as soon as possible.
 - 2. Clean grout smears and haze from tile according to tile and grout manufacturer's written instructions but no sooner than 10 days after installation. Use only cleaners recommended by tile and grout manufacturers and only after determining that cleaners are safe to use by testing on samples of tile and other surfaces to be cleaned. Protect metal surfaces and plumbing fixtures from effects of cleaning. Flush surfaces with clean water before and after cleaning.

3.7 PROTECTION

- A. Protect installed tile work with kraft paper or other heavy covering during construction period to prevent staining, damage, and wear. If recommended by tile manufacturer, apply coat of neutral protective cleaner to completed tile walls and floors.
- B. Prohibit foot and wheel traffic from tiled floors for at least seven days after grouting is completed.
- C. Before final inspection, remove protective coverings and rinse neutral protective cleaner from tile surfaces.

3.8 INTERIOR CERAMIC TILE INSTALLATION SCHEDULE

- A. Interior Floor Installations, Concrete Subfloor:
 - 1. Ceramic Tile Installation: TCNA F125-Full; thinset mortar on crack isolation membrane.
 - a. Ceramic Tile Type: CT-5
 - b. Thinset Mortar: Improved modified dry-setmortar.
 - c. Grout: High-performance sanded grout.
- B. Interior Wall Installations, Wood or Metal Studs or Furring:
 - 1. Ceramic Tile Installation: TCNA W244C; thinset mortar on cementitious backer units.

- a. Ceramic Tile Type: CT-12, CT-12b & CT-12c.
- b. Thinset Mortar: Improved modified dry-set mortar.
- c. Grout: High-performance sanded grout.

END OF SECTION 09 30 13

SECTION 09 51 10 - ACOUSTICAL CEILINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Acoustical panels and exposed suspension systems for ceilings.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.
 - d. Low Emitting Materials Information.
 - e. Laboratory Testing or GreenGuard Certificates.

- C. Samples for Verification: For each component indicated and for each exposed finish required, prepared on Samples of size indicated below.

1. Acoustical Panel: Set of 6-inch- square Samples of each type, color, pattern, and texture.
2. Exposed Suspension-System Members, Moldings, and Trim: Set of 6-inch- long Samples of each type, finish, and color.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Suspended ceiling components.
2. Structural members to which suspension systems will be attached.
3. Size and location of initial access modules for acoustical panels.
4. Items penetrating finished ceiling including the following:

- a. Lighting fixtures.
- b. Air outlets and inlets.
- c. Speakers.
- d. Access panels.

5. Perimeter moldings.

B. Qualification Data: For testing agency.

C. Evaluation Reports: For each acoustical panel ceiling suspension system and anchor and fastener type, from ICC-ES.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For finishes to include in maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

- 1. Acoustical Ceiling Panels: Full-size panels equal to 2 percent of quantity installed.
- 2. Suspension-System Components: Quantity of each exposed component equal to 2 percent of quantity installed.

1.7 QUALITY ASSURANCE

A. Testing Agency Qualifications: Qualified according to NVLAP for testing indicated.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Deliver acoustical panels, suspension-system components, and accessories to Project site in original, unopened packages and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.
- B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.
- C. Handle acoustical panels carefully to avoid chipping edges or damaging units in any way.

1.9 FIELD CONDITIONS

- A. Environmental Limitations: Do not install acoustical panel ceilings until spaces are enclosed and weatherproof, wet work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Seismic Performance (For Projects in Seismic Zones): Provide acoustical panel ceilings designed and installed to withstand the effects of earthquake motions according to the following:
 - 1. CISCA's Guidelines for Systems Requiring Seismic Restraint: Comply with CISCA's "Guidelines for Seismic Restraint of Direct-Hung Suspended Ceiling Assemblies-- Seismic Zones 3 & 4."
- B. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: Comply with ASTM E 1264 for Class A materials.
 - 2. Smoke-Developed Index: 50 or less.
- C. Environmental Characteristics: Comply with testing and product requirements of the California Department of Health Services Standard Practice for the Testing of Volatile Organic Emissions from the Various Sources Using Small-Scale Environmental Chambers, including 2004 addend

2.2 ACOUSTICAL PANELS, GENERAL

- A. Source Limitations:
 - 1. Acoustical Ceiling Panel: Obtain each type from single source from single manufacturer.
 - 2. Suspension System: Obtain each type from single source from single manufacturer.
- B. Glass-Fiber-Based Panels: Made with binder containing no urea formaldehyde.
- C. Acoustical Panel Standard: Provide manufacturer's standard panels of configuration indicated that comply with ASTM E 1264 classifications as designated by types, patterns, acoustical ratings, and light reflectances unless otherwise indicated.
 - 1. Mounting Method for Measuring NRC: Type E-400; plenum mounting in which face of test specimen is 15-3/4 inches away from test surface according to ASTM E 795.
- D. Acoustical Panel Colors and Patterns: Match appearance characteristics indicated for each product type.
 - 1. Where appearance characteristics of acoustical panels are indicated by referencing pattern designations in ASTM E 1264 and not manufacturers' proprietary product designations, provide products selected by Architect from each manufacturer's full range that comply with requirements indicated for type, pattern, color, light reflectance, acoustical performance, edge detail, and size.

2.3 ACOUSTICAL PANELS

- A. Acoustical Ceiling Tile (ACT-4): ASTM E 1264, Type IV, (mineral base with membrane-faced overlay), Form 2 (water felted,) and Pattern E (lightly textured). Binder shall not contain urea formaldehyde.
1. Product: Subject to compliance with requirements, provide “Model #2824 - Calla” acoustical ceiling panel as manufactured by Armstrong World Industries, Inc.
 - a. Size: 24” x 24” x 1”.
 2. Color: White.
 3. Light Reflectance (LR): Not less than 0.85.
 4. Ceiling Attenuation Class (CAC): Not less than 35.
 5. Articulation Class (AC): Not less than 170.
 6. Edge/Joint Detail: Square Tegal.
 7. Broad Spectrum Antimicrobial Fungicide and Bactericide Treatment: Provide acoustical panels treated with manufacturer's standard antimicrobial formulation that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested according to ASTM D 3273 and evaluated according to ASTM D 3274 or ASTM G 21.
- B. Acoustical Ceiling Tile (ACT-5): ASTM E 1264, Type IV, (mineral base with membrane-faced overlay), Form 2 (water felted,) and Pattern E (lightly textured). Binder shall not contain urea formaldehyde.
1. Product: Subject to compliance with requirements, provide “Model #1914 - Ultima” acoustical ceiling panel as manufactured by Armstrong World Industries, Inc.
 - a. Size: 24” x 48” x 3/4”.
 2. Color: White.
 3. Light Reflectance (LR): Not less than 0.88.
 4. Noise Reduction Coefficient (NRC): Not less than 0.75.
 5. Ceiling Attenuation Class (CAC): Not less than 35.
 6. Edge/Joint Detail: Beveled Tegal.
 7. Broad Spectrum Antimicrobial Fungicide and Bactericide Treatment: Provide acoustical panels treated with manufacturer's standard antimicrobial formulation that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested according to ASTM D 3273 and evaluated according to ASTM D 3274 or ASTM G 21.

2.4 METAL SUSPENSION SYSTEMS, GENERAL

- A. Metal Suspension-System Standard: Provide manufacturer's standard direct-hung metal suspension systems of types, structural classifications, and finishes indicated that comply with applicable requirements in ASTM C 635/C 635M.
- B. Hanger Attachments to Overhead Structural Decks: Suitable for application indicated, fabricated from corrosion resistant materials, with eyepins, clips, or other devices for attaching

hangers and capable of sustaining, without failure, a load equal to 5 times the design load indicated in ASTM C 635/C 635M, Table 1, Direct Hung. Corrosion protection of hanger attachments to be as follows:

1. Hanger Attachments and Fasteners for Interior Suspended Ceilings: Carbon steel zinc plated to comply with ASTM B 633, Class Fe/Zn 5 for Class SC 1 service condition (mild).
- C. Hangers: As follows, except provide only galvanized round steel threaded or flat strap type hangers sized as required to comply with the maximum deflection conditions specified under Article 'Performance Requirements.'
1. Wire Hangers, Braces, and Ties: Provide wires complying with the following requirements:
 - a. Zinc-Coated, Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
 - b. Size: Select wire diameter so its stress at three times hanger design load (ASTM C 635/C 635M, Table 1, "Direct Hung") will be less than yield stress of wire, but provide not less than 0.106-inch- diameter wire.
- D. Angle Hangers: Angles with legs not less than 7/8 inch wide; formed with 0.04-inch- thick, galvanized-steel sheet complying with ASTM A 653/A 653M, G90 coating designation; with bolted connections and 5/16-inch- diameter bolts.
- E. Carrying Channels: ASTM C754, cold rolled steel channels, 1-1/2", 475 lbs. Per 1000 linear ft. Size carrying channels as required to comply with the maximum deflection conditions specified under Article 'Performance Requirements' for the maximum soffit areas to be supported.
- F. Seismic Stabilizer Bars: Manufacturer's standard perimeter stabilizers designed to accommodate seismic forces.
- G. Seismic Struts (For Projects in Seismic Zones Only): Manufacturer's standard compression struts designed to accommodate seismic forces.
- H. Clips: Provide support clips, clamps, fasteners, splines, and other attachment devices as required to align components and to connect components and transfer imposed loads of suspension system.
1. Provide partition attachment clips, for reveal edge panels, and fasteners for areas where partition ceiling runners are secured to the ceiling suspension system.
 2. Provide attachment clips for runner to angle molding to avoid use of pop rivets.
 3. Provide grid converter accessories as required to change main tee direction 90 degrees from adjacent main tee.
 4. Provide light fixture clips.
 5. Hold-Down Clips: Where indicated, provide manufacturer's standard hold-down clips spaced 24 inches o.c. on all cross tees.
 - a. Location: Provide hold down clips at drive thru soffit areas, and in interior ceiling entryways to reduce flutter.

6. Seismic Clips (For Projects in Seismic Zones Only): Manufacturer's standard seismic clips designed and spaced to secure acoustical panels in-place.

2.5 METAL SUSPENSION SYSTEM

- A. Wide-Face, Capped, Double-Web, Steel Suspension System (ACT-5): Main and cross runners roll formed from cold-rolled steel sheet; prepainted, electrolytically zinc coated, or hot-dip galvanized according to ASTM A 653/A 653M, not less than galvanized coating designation indicated below; with prefinished 15/16-inch- wide metal caps on flanges.
 1. Product: Subject to compliance with requirements, provide "Prelude XL" suspension system as manufactured by Armstrong World Industries, Inc.
 2. Structural Classification: Intermediate-duty system.
 3. End Condition of Cross Runners: Butt-edge type.
 4. Face Design: Flat, flush.
 5. Cap Material: Cold-rolled steel or aluminum.
 6. Cap Finish: Painted white.
- B. Narrow-Face, Capped, Double-Web, Steel Suspension System (ACT-4): Main and cross runners roll formed from cold-rolled steel sheet; prepainted, electrolytically zinc coated, or hot-dip galvanized, G30 coating designation; with prefinished 9/16-inch- wide metal caps on flanges.
 1. Product: Subject to compliance with requirements, provide "9/16 Suprafine XL" suspension system as manufactured by Armstrong World Industries, Inc.
 2. Structural Classification: Intermediate-duty system.
 3. End Condition of Cross Runners: Override (stepped) type.
 4. Face Design: Flat, flush.
 5. Cap Material: Cold-rolled steel or aluminum.
 6. Cap Finish: Painted white.

2.6 METAL EDGE MOLDINGS AND TRIM

- A. Extruded-Aluminum Edge Moldings and Trim: Where indicated, provide manufacturer's extruded-aluminum edge moldings and trim of profile indicated or referenced by manufacturer's designations, including splice plates, corner pieces, and attachment and other clips, complying with seismic design requirements and the following:
 1. Aluminum Alloy: Alloy and temper recommended by aluminum producer and finisher for type of use and finish indicated, and with not less than the strength and durability properties of aluminum extrusions complying with ASTM B 221 for Alloy and Temper 6063-T5.
 2. Baked-Enamel or Powder-Coat Finish: Minimum dry film thickness of 1.5 mils. Comply with ASTM C 635/C 635M and coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.
 3. Types and Profiles: Provide the following molding and trim types, unless otherwise indicated:

- a. Shadow Molding: Provide metal shadow line reveal at edges of ceiling fields where they meet vertical walls and columns. Provide outside and inside corner molding accessories to accommodate corner transitions.
 - 1) Product: Subject to compliance with requirements, provide Model # 7877 as manufactured by Armstrong World Industries, Inc.
 - 2) Reveal Dimension: As indicated on Drawings.
 - b. F Moldings: Provide F moldings at ceiling breaks, soffits, bulkheads, and changes in elevation other than vertical walls and columns to the extent indicated.
 - c. Transition Trims: Provide vertical panel transition trims at transitions between gypsum broad ceilings and acoustical ceilings assemblies.
 - 1) Basis-of-Design Product: Subject to compliance with requirements, provide "Model # AXTR8STR, Axiom Transitions" trims as manufactured by Armstrong World Industries, Inc. or proposed substitution complying with Division 01 Section "Substitution Procedures:"
- B. Flexible Shadow Molding: Provide flexible shadow molding for use at radius wall surfaces matching adjacent trims in size, profile and finish.
- 1. Basis-of-Design Product: Subject to compliance with the requirements, provide "Ultra-Flex Shadow Mold" flexible acoustical ceiling trim as manufactured by the Kenbeck Company and distributed by USG Interiors, Inc. or proposed substitution complying with Division 01 Section "Substitution Procedures:"
 - a. Face Width: 9/16 inch.
 - b. Reveal: 3/8 by 3/8 inches.

2.7 ACOUSTICAL SEALANT

- A. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to the following:
- 1. Acoustical Sealant for Exposed and Concealed Joints:
 - a. Pecora Corporation; AC-20 FTR Acoustical and Insulation Sealant.
 - b. USG Corporation; SHEETROCK Acoustical Sealant.
 - 2. Acoustical Sealant for Concealed Joints:
 - a. Henkel Corporation; OSI Pro-Series SC-175 Acoustical Sound Sealant.
 - b. Pecora Corporation; AIS-919.
 - c. Tremco, Inc.; Tremco Acoustical Sealant.
- B. Acoustical Sealant: Manufacturer's standard sealant complying with ASTM C 834 and effective in reducing airborne sound transmission through perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.
- 1. Exposed and Concealed Joints: Nonsag, paintable, nonstaining latex sealant.

2. Concealed Joints: Nondrying, nonhardening, nonskinning, nonstaining, gunnable, synthetic-rubber sealant.
3. Acoustical sealant shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.
- B. Examine acoustical panels before installation. Reject acoustical panels that are wet, moisture damaged, or mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders, and comply with layout shown on reflected ceiling plans.

3.3 INSTALLATION

- A. General: Install acoustical panel ceilings to comply with ASTM C 636/C 636M and seismic design requirements indicated, according to manufacturer's written instructions and CISCA's "Ceiling Systems Handbook."
- B. Suspend ceiling hangers from building's structural members and as follows:
 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
 2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
 3. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension-system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices.
 4. Hangers:
 - a. Secure wire hangers to ceiling-suspension members and to supports above with a minimum of three tight turns. Connect hangers directly either to structures or to inserts, eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.

- b. Secure flat, angle, channel, and rod hangers to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices that are secure and appropriate for both the structure to which hangers are attached and the type of hanger involved. Install hangers in a manner that will not cause them to deteriorate or fail due to age, corrosion, or elevated temperatures.
 - 5. Do not support ceilings directly from permanent metal forms or floor deck. Fasten hangers to cast-in-place hanger inserts, postinstalled mechanical or adhesive anchors, or power-actuated fasteners that extend through forms into concrete.
 - 6. When steel framing does not permit installation of hanger wires at spacing required, install carrying channels or other supplemental support for attachment of hanger wires.
 - 7. Do not attach hangers to steel deck tabs.
 - 8. Do not attach hangers to steel roof deck. Attach hangers to structural members.
 - 9. Space hangers not more than 48 inches o.c. along each member supported directly from hangers unless otherwise indicated; provide hangers not more than 8 inches from ends of each member.
 - 10. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards and publications.
- C. Secure bracing wires to ceiling suspension members and to supports with a minimum of four tight turns. Suspend bracing from building's structural members as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs. Fasten bracing wires into concrete with cast-in-place or postinstalled anchors.
- D. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
- 1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
 - 2. Screw attach moldings to substrate at intervals not more than 16 inches o.c. and not more than 3 inches from ends, leveling with ceiling suspension system to a tolerance of 1/8 inch in 12 feet. Miter corners accurately and connect securely.
 - 3. Do not use exposed fasteners, including pop rivets, on moldings and trim.
- E. Install suspension-system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- F. Install acoustical panels with undamaged edges and fit accurately into suspension-system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide a neat, precise fit.
- 1. Arrange directionally patterned acoustical panels as follows:
 - a. As indicated on reflected ceiling plans.
 - 2. For square-edged panels, install panels with edges fully hidden from view by flanges of suspension-system runners and moldings.
 - 3. For reveal-edged panels on suspension-system runners, install panels with bottom of reveal in firm contact with top surface of runner flanges.

4. Paint cut edges of panel remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.
5. Install clips in areas indicated, in areas required by authorities having jurisdiction and in spaces as recommended by panel manufacturer's written instructions unless otherwise indicated.

3.4 FIELD QUALITY CONTROL

- A. Special Inspections: Engage a qualified special inspector to perform the following special inspections:
 1. Compliance of seismic design.
- B. Testing Agency: Engage a qualified testing agency to perform tests and inspections and prepare test reports.
- C. Perform the following tests and inspections of completed installations of acoustical panel ceiling hangers and anchors and fasteners in successive stages. Do not proceed with installations of acoustical panel ceiling hangers for the next area until test results for previously completed installations show compliance with requirements.
 1. Extent of Each Test Area: When installation of ceiling suspension systems on each floor has reached 20 percent completion but no panels have been installed.
 - a. Within each test area, testing agency will select one of every 10 power-actuated fasteners and postinstalled anchors used to attach hangers to concrete and will test them for 200 lbf of tension; it will also select one of every two postinstalled anchors used to attach bracing wires to concrete and will test them for 440 lbf of tension.
 - b. When testing discovers fasteners and anchors that do not comply with requirements, testing agency will test those anchors not previously tested until 20 pass consecutively and then will resume initial testing frequency.
- D. Acoustical panel ceiling hangers and anchors and fasteners will be considered defective if they do not pass tests and inspections.
- E. Prepare test and inspection reports.

3.5 CLEANING

- A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension-system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 09 51 13

SECTION 09 64 00 - WOOD FLOORING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Factory-finished wood flooring.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. FSC Certified Wood Information.
 - c. FSC Chain of Custody Certificates.
 - d. Recycled Content Information.
 - e. Regional Materials Information.
 - f. Low Emitting Materials Information.
 - g. LEED Materials and Resources Calculator.

C. Shop Drawings: For each type of floor assembly and accessory. Include plans, sections, and attachment details. Include expansion provisions and trim details.

D. Samples: For each exposed product and for each color and texture specified, approximately 12 inches long and of same thickness and material indicated for the Work and showing the full range of normal color and texture variations expected.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Product Certificates: For each type of product.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Wood Flooring: Equal to 1 percent of amount installed for each type, color, and finish of wood flooring indicated.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Engage an Installer with five years experience in the installation of materials specified, and who has completed wood flooring installation similar in material, and extent to that indicated for this Project with a record of successful in-service performance.
- B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.
 1. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver wood flooring materials in unopened cartons or bundles.
- B. Protect wood flooring from exposure to moisture. Do not deliver wood flooring until after concrete, masonry, plaster, ceramic tile, and similar wet-work is complete and dry.
- C. Store wood flooring materials in a dry, warm, ventilated, weathertight location.

1.7 FIELD CONDITIONS

- A. Conditioning period begins not less than seven days before wood flooring installation, is continuous through installation, and continues not less than seven days after wood flooring installation.
 1. Environmental Conditioning: Maintain ambient temperature between 65 and 75 deg F and relative humidity planned for building occupants in spaces to receive wood flooring during the conditioning period.
 2. Wood Flooring Conditioning: Move wood flooring into spaces where it will be installed, no later than the beginning of the conditioning period.
 - a. Do not install flooring until it adjusts to relative humidity of, and is at same temperature as, space where it is to be installed.
 - b. Open sealed packages to allow wood flooring to acclimatize immediately on moving flooring into spaces in which it will be installed.
- B. After conditioning period, maintain relative humidity and ambient temperature planned for building occupants.
- C. Install factory-finished wood flooring after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 FACTORY-FINISHED WOOD FLOORING

- A. Caramelized, Bamboo Flooring: FSC certified, bamboo flooring fabricated from bamboo strand composite in a pressure treated adhesive base to form a high density homogenous bamboo plank. Bamboo flooring shall be fabricated with no added urea-formaldehyde.

1. Product: Subject to compliance with the requirements, provide "FL-V5872PA-FSC" wood flooring as manufactured by Plyboo; A Division of Smith & Fong Company.

- a. Caramelized Color: Amber.

2. Species: Moso (Phyllostachys Pubescens.)
 3. Thickness: 5/8 inch.
 4. Face Width: 3-5/8 inches.
 5. Lengths: 72 inches.
 6. Edge Style: Square edge with tongue and grove on four sides.
 7. Finish: UV urethane.
 8. Performance Properties:

- a. Critical Radiant Flux: ASTM E648:

- 1) Flat Grain prefinished: Class 1
 - 2) Edge Grain prefinished: Class 1

- b. Dimensional Stability: 50% to 20% RH; ASTM D1037

- 1) Linear Expansion:

- a) Flat Grain: Parallel -0.04%, Perpendicular -0.13%
 - b) Edge Grain: Parallel -0.02%, Perpendicular -0.07%

- 2) Thickness Swell:

- a) Flat Grain: -0.17%
 - b) Edge Grain: -0.34%

- 3) Hardness (Janka Ball Test)

- a) Flat Grain Amber: 1,400 lbf (avg)
 - b) Edge Grain Amber: 1,300 lbf (avg)

- c. Compressive Strength: ASTM D3501

- 1) Compressive Strength / Max Load

- a) Flat Grain: 7,249 lbs / 13,522 lbs.
 - b) Edge Grain: 6,160 lbs / 12,201 lbf (avg)

- d. Adhesion by Tape Test: ASTM D3359
 - 1) Flat Grain: Class 4B
 - 2) Edge Grain: Class 4B
- e. Taber Abrasion: ASTM D4060
 - 1) Avg. Wear-through / Wear Rate
 - a) Flat Grain Amber: 22,500 cycles / 5,500 cycles per 0.001 inch
 - b) Edge Grain Amber: 20,000 cycles / 6,897 cycles per 0.001 inch
- f. Moisture Content: ASTM D4442
 - 1) Flat and Edge Grain: 6% – 9% (average range)
- g. Organic Emissions [CA Section 01350; Indoor Air Quality]: ASTM D5116-06
 - 1) Office scenario / Classroom scenario:
 - a) Flat and Edge Grain: Pass / Pass

2.2 ACCESSORY MATERIALS

- A. Wood Flooring Adhesive: Mastic recommended by flooring and adhesive manufacturers for application indicated.
- B. Trowelable Leveling and Patching Compound: Latex-modified, hydraulic-cement-based formulation approved by wood flooring manufacturer.
- C. Metal Reducer Strip: Tapered, and in thickness required to match height of flooring.
 - 1. Products: Subject to compliance with the requirements, provide “Model #234 - Carpet Transition” as manufactured by Genotek; Tele: (800)741-8936.
 - a. Finish: #63 - Satin Silver.
 - 2. Style and Location:
 - a. Edge Transition Strip: At carpet and wood flooring transitions
- D. Cork Expansion Strip: Composition cork strip.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for maximum moisture content, installation tolerances, and other conditions affecting performance of wood flooring.

- B. Proceed with installation only after unsatisfactory conditions have been corrected.
- C. Concrete Slabs: Verify that concrete substrates are dry and moisture-vapor emissions are within acceptable levels according to manufacturer's written instructions.
 - 1. Moisture Testing: Perform tests so that each test area does not exceed 1000 sq. ft., and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.
 - a. Anhydrous Calcium Chloride Test: ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
 - b. Perform additional moisture tests recommended by manufacturer. Proceed with installation only after substrates pass testing.

3.2 PREPARATION

- A. Concrete Slabs:
 - 1. Grind high spots and fill low spots to produce a maximum 1/8-inch deviation in any direction when checked with a 10-foot straight edge.
 - 2. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, and depressions in substrates.
 - 3. Remove coatings, including curing compounds, and other substances on substrates that are incompatible with installation adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by manufacturer. Do not use solvents.
- B. Broom or vacuum clean substrates to be covered immediately before product installation. After cleaning, examine substrates for moisture, alkaline salts, carbonation, or dust. Proceed with installation only after unsatisfactory conditions have been corrected.

3.3 INSTALLATION

- A. Comply with flooring manufacturer's written installation instructions, but not less than applicable recommendations in NWFA's "Installation Guidelines."
- B. Provide expansion space at walls and other obstructions and terminations of flooring of not less than 3/4 inch.

3.4 PROTECTION

- A. Protect installed wood flooring during remainder of construction period with covering of heavy kraft paper or other suitable material. Do not use plastic sheet or film that might cause condensation.
 - 1. Do not move heavy and sharp objects directly over kraft-paper-covered wood flooring. Protect flooring with plywood or hardboard panels to prevent damage from storing or moving objects over flooring.

Gensler

057.7202.950

Bank of America / BAC Proprietary / Bulletin 02 / 09-14-15

January 22, 2021
Issue for Construction

Bank of America
BAC Centerville GU
Centerville, UT

END OF SECTION 09 64 00

SECTION 09 65 13 - RESILIENT BASE AND ACCESSORIES**PART 1 - GENERAL****1.1 SUMMARY****A. Section Includes:**

1. Resilient base.
2. Resilient molding accessories.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS**A. Product Data:** For each type of product.**B. LEED Documentation Submittals:**

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Low Emitting Materials Information.

C. Samples: For each exposed product and for each color and texture specified, not less than 12 inches long.**D. Product Schedule:** For resilient base and accessory products. Use same designations indicated on Drawings.**1.3 MAINTENANCE MATERIAL SUBMITTALS****A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.**

1. Furnish not less than 10 linear feet for every 500 linear feet or fraction thereof, of each type, color, pattern, and size of resilient product installed.

1.4 DELIVERY, STORAGE, AND HANDLING**A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F.**

1.5 FIELD CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive resilient products during the following time periods:
 - 1. 48 hours before installation.
 - 2. During installation.
 - 3. 48 hours after installation.
- B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 95 deg F.
- C. Install resilient products after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. FloorScore Compliance: Resilient base shall comply with requirements of FloorScore certification.

2.2 RUBBER WALL BASE

- A. Rubber Wall Base (B-11): ASTM F 1861, Type TP (rubber, thermoplastic).
 - 1. Product: Subject to compliance with requirements, provide "Mandalay Series, MW-XX_H" wall base as manufactured by Tarkett.
 - a. Colors: #82 – Black Pearl.
 - 2. Group: I (solid, homogeneous).
 - 3. Style and Location:
 - a. Style C, Millwork Profiled: Where indicated on Drawings or if not indicated, as directed by Architect.
 - 4. Thickness: 0.375 inch.
 - 5. Height: 4-1/2 inch.
 - 6. Lengths: Manufacturer's standard length.
 - 7. Outside Corners: Job formed.
 - 8. Inside Corners: Job formed.
- B. Rubber Wall Base (B-12): ASTM F 1861, Type TS (rubber, vulcanized thermoset), Group I (solid, homogeneous).
 - 1. Product: Subject to compliance with requirements, provide "Baseworks Thermoset Rubber Wall Base" as manufactured by Tarkett.

- a. Color: #TA6 – Bedrock.”
2. Style and Location:
 - a. Cove base (with top-set toe) at locations where indicated on Drawings.
 - b. Straight base at locations where indicated on Drawings.
3. Minimum Thickness: 0.125 inch.
4. Height: 4 inches.
5. Lengths: Coils in manufacturer's standard length.
6. Outside Corners: Job formed.
7. Inside Corners: Job formed.
8. Surface: Smooth.

2.3 MOLDING ACCESSORY

- A. Transition Moldings (TS-2): For 1/4-inch transitions to 1/8-inch.
 1. Product: Subject to compliance to the requirements, provide “CTA-20-H” transition as manufactured by Tarkett.
 - a. Color: #20 - Charcoal.
 2. Style and Location:
 - a. Transition Molding: At CPT to VCT transitions.
- B. Transition Moldings (TS-6): For 1/4-inch transitions to 0.080-inch.
 1. Product: Subject to compliance to the requirements, provide “Slim Line Transitions; SLT-XX-C” as manufactured by Tarkett.
 - a. Color: #82 - Black Pearl.
 2. Style and Location:
 - a. Adaptor Transition Molding: At VCT to LVT transitions.
- C. Transition Moldings (TS-7): For 3/8-inch transitions to 1/4-inch.
 1. Product: Subject to compliance to the requirements, provide “Metaledge Series; ME003” transitions as manufactured by Tarkett.
 - a. Color: #82 - Black Pearl.
 2. Style and Location:
 - a. Adaptor Transition Molding: At CPT to LVT transitions.
- D. Reducer Moldings (TS-8): For 1/8-inch reducer.

1. Product: Subject to compliance to the requirements, provide “SSR-XX-B” reducer as manufactured by Tarkett.
 - a. Color: #20 - Charcoal.
2. Style and Location:
 - a. Reduce Molding: At CPT over Tile transitions.

2.4 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland cement based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.
 1. Adhesives shall have a VOC content of 50 g/L or less.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
 1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
 1. Installation of resilient products indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.
- B. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- C. Do not install resilient products until they are the same temperature as the space where they are to be installed.
 1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.

- D. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

3.3 RESILIENT BASE INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient base.
- B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.
- C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.
- D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
- E. Do not stretch resilient base during installation.
- F. On masonry surfaces or other similar irregular substrates, fill voids along top edge of resilient base with manufacturer's recommended adhesive filler material.
- G. Job-Formed Corners:
 - 1. Outside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches in length.
 - a. Form without producing discoloration (whitening) at bends.
 - 2. Inside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches in length.
 - a. Miter corners to minimize open joints.

3.4 RESILIENT ACCESSORY INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient accessories.
- B. Resilient Molding Accessories: Butt to adjacent materials and tightly adhere to substrates throughout length of each piece. Install reducer strips at edges of floor covering that would otherwise be exposed.

3.5 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.
- B. Perform the following operations immediately after completing resilient-product installation:
 - 1. Remove adhesive and other blemishes from exposed surfaces.
- C. Protect resilient products from marks, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.

- D. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION 09 65 13

SECTION 09 65 19 - RESILIENT TILE FLOORING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Vinyl composition floor tile.
2. Solid Vinyl Floor Planks

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. Regional Material Information.
 - d. LEED Materials and Resources Calculator.

C. Samples: Full-size units of each color, texture, and pattern of floor tile required.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance Data: For each type of floor tile to include in maintenance manuals.

1.5 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Floor Tile: Furnish one box for every 50 boxes or fraction thereof, of each type, color, and pattern of floor tile installed.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are competent in techniques required by manufacturer for floor tile installation and seaming method indicated.
 1. Engage an installer who employs workers for this Project who are trained or certified by floor tile manufacturer for installation techniques required.
- B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.
 1. Build mockups at locations and size as directed by the Architect.
 2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Store floor tile and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F. Store floor tiles on flat surfaces.

1.8 FIELD CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive floor tile during the following periods:
 1. 48 hours before installation.
 2. During installation.
 3. 48 hours after installation.
- B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 95 deg F.
- C. Close spaces to traffic during floor tile installation.
- D. Close spaces to traffic for 48 hours after floor tile installation.
- E. Install floor tile after other finishing operations, including painting, have been completed.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: For resilient floor tile, as determined by testing identical products according to ASTM E 648 or NFPA 253 by a qualified testing agency.
 - 1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.
- B. FloorScore Compliance: Resilient tile flooring shall comply with requirements of FloorScore certification.

2.2 VINYL COMPOSITION FLOOR TILE

- A. Vinyl Composition Tile (VCT-2): ASTM F 1066, Class 2, through pattern.
 - 1. Product: Subject to compliance with requirements, provide "Tarkett VCT, Color: 1374 - Charcoal" as manufactured by Tarkett North America.
 - 2. Wearing Surface: Smooth.
 - 3. Thickness: 0.125 inch.
 - 4. Size: 12 by 12 inches.

2.3 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by floor tile manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by floor tile and adhesive manufacturers to suit floor tile and substrate conditions indicated.
 - 1. Adhesives shall have a VOC content of 50 g/L or less.
- C. Floor Polish: Provide protective, liquid floor-polish products recommended by floor tile manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
 - 1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of floor tile.

- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Prepare substrates according to floor tile manufacturer's written instructions to ensure adhesion of resilient products.
- B. Concrete Substrates: Prepare according to ASTM F 710.
 - 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
 - 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by floor tile manufacturer. Do not use solvents.
 - 3. Alkalinity and Adhesion Testing: Perform tests recommended by floor tile manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 10 pH.
 - 4. Moisture Testing: Perform tests so that each test area does not exceed 1000 sq. ft. (304.8 sq. m), and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.
 - a. Anhydrous Calcium Chloride Test: ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. (1.36 kg of water/92.9 sq. m) in 24 hours.
 - b. Relative Humidity Test: Using in-situ probes, ASTM F 2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level measurement.
- C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- D. Do not install floor tiles until materials are the same temperature as space where they are to be installed.
 - 1. At least 48 hours in advance of installation, move resilient floor tile and installation materials into spaces where they will be installed.
- E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient floor tile.

3.3 FLOOR TILE INSTALLATION

- A. Comply with manufacturer's written instructions for installing floor tile.
- B. Lay out floor tiles from center marks established with principal walls, discounting minor offsets, so tiles at opposite edges of room are of equal width. Adjust as necessary to avoid using cut widths that equal less than one-half tile at perimeter.
 - 1. Lay tiles in pattern indicated on drawings.

- C. Match floor tiles for color and pattern by selecting tiles from cartons in the same sequence as manufactured and packaged, if so numbered. Discard broken, cracked, chipped, or deformed tiles.
 - 1. Lay tiles with grain direction alternating in adjacent tiles (basket-weave pattern), unless otherwise indicated.
- D. Scribe, cut, and fit floor tiles to butt neatly and tightly to vertical surfaces and permanent fixtures including built-in furniture, cabinets, pipes, outlets, and door frames.
- E. Extend floor tiles into toe spaces, door reveals, closets, and similar openings. Extend floor tiles to center of door openings.
- F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on floor tiles as marked on substrates. Use chalk or other nonpermanent marking device.
- G. Adhere floor tiles to substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.

3.4 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting floor tile.
- B. Perform the following operations immediately after completing floor tile installation:
 - 1. Remove adhesive and other blemishes from surfaces.
 - 2. Sweep and vacuum surfaces thoroughly.
 - 3. Damp-mop surfaces to remove marks and soil.
- C. Protect floor tile from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.
- D. Floor Polish: Remove soil, adhesive, and blemishes from floor tile surfaces before applying liquid floor polish.
 - 1. Apply two coat(s).
- E. Cover floor tile until Substantial Completion.

END OF SECTION 09 65 19

SECTION 09 68 16 - SHEET CARPETING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Tufted carpet.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review methods and procedures related to carpet installation including, but not limited to, the following:
 - a. Review delivery, storage, and handling procedures.
 - b. Review ambient conditions and ventilation procedures.
 - c. Review subfloor preparation procedures.

1.3 ACTION SUBMITTALS

A. Product Data: For the following, including installation recommendations for each type of substrate:

1. Carpet: For each type indicated. Include manufacturer's written data on physical characteristics, durability, and fade resistance.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. CRI's "Green Label Plus" program.
 - c. Low Emitting Materials Information.
 - d. Regional Materials Information.
 - e. Recycled Content Information.
 - f. LEED Materials and Resources Calculator.

C. Shop Drawings: Show the following:

1. Columns, doorways, enclosing walls or partitions, built-in cabinets, and locations where cutouts are required in carpet.

2. Carpet type, color, and dye lot.
3. Locations where dye lot changes occur.
4. Seam locations, types, and methods.
5. Type of subfloor.
6. Type of installation.
7. Pattern type, repeat size, location, direction, and starting point.
8. Pile direction.
9. Type, color, and location of insets and borders.
10. Type, color, and location of edge, transition, and other accessory strips.
11. Transition details to other flooring materials.

D. Samples: For each of the following products and for each color and texture required. Label each Sample with manufacturer's name, material description, color, pattern, and designation indicated on Drawings and in schedules.

1. Carpet: 12-inch- square Sample.
2. Exposed Edge, Transition, and Other Accessory Stripping: 12-inch- long Samples.
3. Carpet Seam: 6-inch Sample.
4. Mitered Carpet Border Seam: 12-inch- square Sample. Show carpet pattern alignment.

E. Product Schedule: For carpet. Use same designations indicated on Drawings.

F. Sustainability: Provide the Statement of the Achievement Level the carpet has attained to meet desired LEED certification credits indicated in Division 01 Section "LEED Sustainable Design Requirements," based on specific Sustainable Attribute Performance for all product stages according to ANSI/NSF 140.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer.
- B. Product Test Reports: For carpet, for tests performed by a qualified testing agency.
- C. Sample Warranties: For special warranties.

1.5 CLOSEOUT SUBMITTALS

A. Maintenance Data: For carpet to include in maintenance manuals. Include the following:

1. Methods for maintaining carpet, including cleaning and stain-removal products and procedures and manufacturer's recommended maintenance schedule.
2. Precautions for cleaning materials and methods that could be detrimental to carpet.

1.6 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Carpet: Full-width rolls equal to 5 percent of amount installed for each type indicated, but not less than 10 sq. yd.

1.7 QUALITY ASSURANCE

- A. **Installer Qualifications:** An experienced Installer who is certified by the International Certified Floorcovering Installers Association at the Master II certification level.
- B. **Fire-Test-Response Ratings:** Where indicated, provide carpet identical to those of assemblies tested for fire response per NFPA 253 by a qualified testing agency.
- C. **Mockups:** Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for fabrication and installation.
 - 1. Build mockups at locations and in sizes shown on Drawings.
 - 2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Comply with CRI 104.

1.9 FIELD CONDITIONS

- A. Comply with CRI 104 for temperature, humidity, and ventilation limitations.
- B. **Environmental Limitations:** Do not deliver or install carpet until spaces are enclosed and weathertight, wet work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at occupancy levels during the remainder of the construction period.
- C. Do not install carpet over concrete slabs until slabs have cured, are sufficiently dry to bond with adhesive, and have pH range recommended by carpet manufacturer.
- D. Where demountable partitions or other items are indicated for installation on top of carpet, install carpet before installing these items.

1.10 WARRANTY

- A. **Special Warranty for Carpet:** Manufacturer agrees to repair or replace components of carpet installation that fail in materials or workmanship within specified warranty period.
 - 1. Warranty does not include deterioration or failure of carpet due to unusual traffic, failure of substrate, vandalism, or abuse.
 - 2. Failures include, but are not limited to, more than 10 percent loss of face fiber, edge raveling, snags, runs, loss of tuft bind strength, excess static discharge, and delamination.
 - 3. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SHEET CARPETING (CPT-5)

- A. Products: Subject to compliance with requirements, provide “Power2 Carpet with Powerbond cushion RS” as manufactured by Tarkett; Contact Information: Frank Wiseman; Tel: (704) 728-9552 / email: frank.wiseman@tarkett.com.
 - 1. Roll Width: 72 inches.
 - 2. Color: Refer to “Finish Schedule” located on Drawings.

2.2 INSTALLATION ACCESSORIES

- A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided or recommended by carpet manufacturer.
- B. Adhesives: Water-resistant, mildew-resistant, nonstaining type to suit products and subfloor conditions indicated, that complies with flammability requirements for installed carpet and is recommended or provided by carpet manufacturer.
 - 1. Use adhesives with VOC content not more than 50 g/L when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- C. Seam Adhesive: Hot-melt adhesive tape or similar product recommended by carpet manufacturer for sealing and taping seams and butting cut edges at backing to form secure seams and to prevent pile loss at seams.
- D. Edge/Transition Strips: Provide profile and width shown, of height required to protect exposed edge of carpet, and of maximum lengths to minimize running joints.
 - 1. Vinyl Transition Moldings: Refer to Division 09 Section “Resilient Base and Accessories” for product selection and finish.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet performance. Examine carpet for type, color, pattern, and potential defects.
- B. Concrete Subfloors: Verify that concrete slabs comply with ASTM F 710 and the following:
 - 1. Slab substrates are dry and free of curing compounds, sealers, hardeners, and other materials that may interfere with adhesive bond. Determine adhesion and dryness characteristics by performing bond and moisture tests recommended by carpet manufacturer.

2. Subfloor finishes comply with requirements specified in Division 03 Section "Cast-in-Place Concrete" for slabs receiving carpet.
3. Subfloors are free of cracks, ridges, depressions, scale, and foreign deposits.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. General: Comply with CRI 104, Section 7.3, "Site Conditions; Floor Preparation," and with carpet manufacturer's written installation instructions for preparing substrates.
- B. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, depressions, and protrusions in substrates. Fill or level cracks, holes and depressions 1/8 inch wide or wider, and protrusions more than 1/32 inch, unless more stringent requirements are required by manufacturer's written instructions.
- C. Remove coatings, including curing compounds, and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, without using solvents. Use mechanical methods recommended in writing by carpet manufacturer.
- D. Broom and vacuum clean substrates to be covered immediately before installing carpet.

3.3 INSTALLATION

- A. Comply with CRI 104 and carpet manufacturer's written installation instructions for the following:
 1. Preapplied Adhesive Installation: Comply with CRI 104, Section 11.4, "Pre-Applied Adhesive Systems (Peel and Stick)."
- B. Comply with carpet manufacturer's written recommendations and Shop Drawings for seam locations and direction of carpet; maintain uniformity of carpet direction and lay of pile. At doorways, center seams under the door in closed position.
- C. Do not bridge building expansion joints with carpet.
- D. Cut and fit carpet to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended by carpet manufacturer.
- E. Extend carpet into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.
- F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on finish flooring as marked on subfloor. Use nonpermanent, nonstaining marking device.
- G. Install pattern parallel to walls and borders to comply with CRI 104, Section 15, "Patterned Carpet Installations" and with carpet manufacturer's written recommendations.

3.4 CLEANING AND PROTECTING

- A. Perform the following operations immediately after installing carpet:
 - 1. Remove excess adhesive, seam sealer, and other surface blemishes using cleaner recommended by carpet manufacturer.
 - 2. Remove yarns that protrude from carpet surface.
 - 3. Vacuum carpet using commercial machine with face-beater element.
- B. Protect installed carpet to comply with CRI 104, Section 16, "Protecting Indoor Installations."
- C. Protect carpet against damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by carpet manufacturer and carpet cushion and adhesive manufacturers.

END OF SECTION 09 68 16

SECTION 09 72 00 - WALL COVERINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Wall covering and accessories.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include data on physical characteristics, durability, fade resistance, and fire-test-response characteristics.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:

- a. LEED Criteria Worksheet.
- b. Low Emitting Materials Information.
- c. LEED Materials and Resources Calculator.

C. Shop Drawings: Show location and extent of each wall-covering type. Indicate pattern placement seams and termination points.

D. Samples: For each type of wall covering and for each color, pattern, texture, and finish specified, full width by 36 inches long in size.

1. Wall-Covering Sample: From same production run to be used for the Work.

- a. Show complete pattern repeat.
- b. Mark top and face of fabric.

1.4 INFORMATIONAL SUBMITTALS

- A. Product Test Reports: For each wall covering, for tests performed by a qualified testing agency.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer acceptable to product manufacturer who has completed successfully installations of wall covering similar in material, design, and extent to that indicated for Project.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For wall coverings to include in maintenance manuals.

1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same production run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Wall-Covering Materials: For each type, color, texture, and finish, full width by length to equal to 5 percent of amount installed.

1.8 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install wall coverings until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, work above ceilings is complete, and HVAC system is operating and maintaining ambient temperature and humidity conditions at levels intended for occupants after Project completion during the remainder of the construction period.
- B. Lighting: Do not install wall covering until lighting that matches conditions intended for occupants after Project completion is provided on the surfaces to receive wall covering.
- C. Ventilation: Provide continuous ventilation during installation and for not less than the time recommended by wall-covering manufacturer for full drying or curing.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: As determined by testing identical wall coverings applied with identical adhesives to substrates in accordance with test method indicated below by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Surface-Burning Characteristics: Comply with ASTM E84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - a. Flame-Spread Index: 25 or less.
 - b. Smoke-Developed Index: 450 or less.
2. Fire-Growth Contribution: No flashover and heat and smoke release when tested in accordance with NFPA 265.

2.2 WALL COVERING PRODUCTS

- A. General: Provide rolls of each type of wall covering from the same run number or dye lot.
- B. Vinyl Wall Covering (WC-16):
 1. Product: Subject to compliance with the requirements, provide “6687 – Chord / Color: #804 - Shadow” wallcovering as manufactured by Designtex.
 - a. Contact Information: Kevin Murphy / Tel: (917) 575-1854
 2. Description: Provide mildew-resistant products in rolls from same production run and complying with the following:
 - a. FS CCC-W-408D and CFFA-W-101-D for Type II, Medium-Duty products.
 3. Width: 54 inches.
 4. Backing: Osnaburg fabric.
 - a. Fiber Content: Cotton and Polyester.
- C. Textile Wall Covering (WC-17):
 1. Product: Subject to compliance with the requirements, provide “6427W – Meteor / Color: #752” wallcovering as manufactured by Carnegie Fabrics, LLC.
 - a. Contact Information: Lorry Collier / Tel: (727) 946-2612
 2. Description: Provide mildew-resistant, wall coverings in rolls from same production run and that comply with ASTM F 793.
 3. Test Responses:
 - a. Colorfastness to Wet and Dry Crocking: Passes AATCC 8, Grade 3, minimum.
 - b. Colorfastness to Light: Passes AATCC 16, Test Option 1 or 3, Grade 4, minimum, at 40 hours.
 4. Width: 52 inches, unless otherwise indicated.
 5. Applied Backing Material: Provide wall covering manufacturer’s proprietary paperbacked backing material that prevents stains and moisture from passing through the wall covering to wall substrate.

D. Felt Wall Covering (WC-18):

1. Product: Subject to compliance with the requirements, provide "9mm thick felt / Color: #06 - Charcoal" wallcovering as manufactured by Turf.

- a. Contact Information: Mary Keller Costa / Tel: (704) 280-6299 / email: mkcosta@cmgreps.com

E. Adhesive: Mildew-resistant, nonstaining adhesive, for use with specific wall covering and substrate application indicated and as recommended in writing by wall-covering manufacturer.

F. Primer/Sealer: Mildew resistant, complying with written recommendations by primer/sealer and wall-covering manufacturers for intended substrate.

1. Product: Subject to compliance with the requirements, provide "Fresh Start High-Hiding All Purpose Primer - #046" as manufactured by Benjamin Moore & Co.

G. Metal Primer: Interior ferrous metal primer complying with requirements in Section 09 91 23 "Interior Painting" and recommended in writing by primer and wall-covering manufacturers for intended substrate.

H. Seam Tape: As recommended in writing by wall-covering manufacturer.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation surfaces being true in plane and vertical and horizontal alignment, maximum moisture content, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Comply with manufacturer's written instructions for surface preparation.
- B. Clean substrates of substances that could impair bond of wall covering, including dirt, oil, grease, mold, and mildew.
- C. Prepare substrates to achieve a smooth, dry, clean, structurally sound surface free of flaking, unsound coatings, cracks, and defects.
 1. Moisture Content: Maximum of 5 percent on new plaster, concrete, and concrete masonry units when tested with an electronic moisture meter.
 2. Metals: If not factory primed, clean and apply metal primer as recommended in writing by metal-primer manufacturer and wall-covering manufacturer.

3. Gypsum Board: Apply primer/sealer as recommended in writing by primer/sealer manufacturer and wall-covering manufacturer.
4. Painted Surfaces:
 - a. Check for pigment bleeding. Apply primer/sealer to areas susceptible to pigment bleeding as recommended in writing by primer/sealer manufacturer.
 - b. Sand gloss, semigloss, and eggshell finishes with fine sandpaper.
- D. Remove hardware and hardware accessories, electrical plates and covers, light fixture trims, and similar items.
- E. Acclimatize wall-covering materials by removing them from packaging in the installation areas not less than 24 hours before installation.

3.3 INSTALLATION OF WALL COVERING

- A. Comply with wall-covering manufacturers' written installation instructions applicable to products and applications indicated.
- B. Cut wall-covering strips in roll number sequence. Change the roll numbers at partition breaks and corners.
- C. Install strips in same order as cut from roll.
 1. For solid-color, even-texture, or random-match wall coverings, reverse every other strip.
- D. Install wall covering without lifted or curling edges and without visible shrinkage.
- E. Trim edges and seams for color uniformity, pattern match, and tight closure. Butt seams without overlaps or gaps between strips.
- F. Fully bond wall covering to substrate. Remove air bubbles, wrinkles, blisters, and other defects.

3.4 CLEANING

- A. Remove excess adhesive at seams, perimeter edges, and adjacent surfaces.
- B. Use cleaning methods recommended in writing by wall-covering manufacturer.
- C. Replace strips that cannot be cleaned.
- D. Reinstall hardware and hardware accessories, electrical plates and covers, light fixture trims, and similar items.

END OF SECTION 09 72 00

SECTION 09 91 13 - EXTERIOR PAINTING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Surface preparation and the application of paint systems on exterior substrates.
2. Surface preparation, priming, and finish coats specified in this Section are in addition to shop priming and surface treatment specified in other Sections.

B. Paint exposed surfaces, except where these Specifications indicate that the surface or material is not to be painted. If an item or a surface is not specifically mentioned, paint the item or surface the same as similar adjacent materials or surfaces. If a color of finish is not indicated, Architect will select from standard colors and finishes available.

C. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 DEFINITIONS

A. Gloss ranges used in this Section include the following:

1. Satin or Low Luster: 20 to 35 units at 60 degrees and not less than 35 units at 85 degrees.
2. Semigloss: 35 to 70 units at 60 degrees.

B. Exterior Surfaces: Exterior surfaces to be painted are defined as those surfaces which are indicated in areas exposed to conditions which are not controlled by building heating and cooling systems.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product. Include preparation requirements and application instructions.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. LEED Materials and Resources Calculator.

C. Samples for Verification: For each type of paint system and each color and gloss of topcoat.

1. Submit Samples on rigid backing, 8 inches square.

2. Step coats on Samples to show each coat required for system.
3. Label each coat of each Sample.
4. Label each Sample for location and application area.

D. Product List: For each product indicated, include the following:

1. Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in schedules.
2. VOC content.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Paint: 5 percent, but not less than 1 gal. of each material and color applied.

1.5 QUALITY ASSURANCE

A. Applicator Qualifications: Engage an experienced applicator who has completed painting system applications similar in material, design, and extent to those indicated for this Project, whose work has resulted in applications with a record of successful in-service performance.

B. Mockups: Apply mockups of each paint system indicated and each color and finish selected to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Architect will select one surface to represent surfaces and conditions for application of each paint system specified in Part 3.
 - a. Vertical and Horizontal Surfaces: Provide samples of at least 100 sq. ft.
 - b. Other Items: Architect will designate items or areas required.
2. Final approval of color selections will be based on mockups.
 - a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Architect at no added cost to Owner.
3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials to Project site in manufacturer's original, unopened packages and containers bearing manufacturer's name and label and other identifying information.

- B. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.

- 1. Maintain containers in clean condition, free of foreign materials and residue.
 - 2. Remove rags and waste from storage areas daily.

1.7 FIELD CONDITIONS

- A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F.
- B. Do not apply paints in snow, rain, fog, or mist; when relative humidity exceeds 85 percent; at temperatures less than 5 deg F above the dew point; or to damp or wet surfaces.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Products: Subject to compliance with requirements, provide products specified in this section by Benjamin Moore & Co. (Benjamin Moore). Substitutions will not be accepted.
 - 1. Manufacturers' shortened names shown within parentheses shall be used in identifying available products in Part 2 of this section.

2.2 PAINT, GENERAL

- A. Material Compatibility: Provide primers, and finish-coat materials that are compatible with one another and with the substrates indicated under conditions of service and application, as demonstrated by manufacturer based on testing and field experience.
 - 1. For each coat in a paint system, provide products recommended in writing by manufacturers of topcoat for use in paint system and on substrate indicated.
- B. Material Quality: Provide manufacturer's best-quality paint material of the various coating types specified that are factory formulated and recommended by manufacturer for application indicated. Paint-material containers not displaying manufacturer's product identification will not be acceptable.
 - 1. Proprietary Names: Use of manufacturer's proprietary product names to designate colors or materials is not intended to imply that products named are required to be used to the exclusion of equivalent products of other manufacturers. Furnish manufacturer's material data and certificates of performance for proposed substitutions.
- C. VOC Content: Products shall comply with VOC limits of authorities having jurisdiction and VOC limits indicated in Division 01 Section "LEED Sustainable Design Requirements."
- D. Colors: Provide custom colors of the finished paint systems to match the Architect's samples.

2.3 EXTERIOR PRIMERS

- A. Exterior Gypsum Soffit Board Primer: Factory-formulated alkyd- or alkali-resistant acrylic-latex primer for exterior application.
- B. Exterior Ferrous-Metal Primer: Factory-formulated rust-inhibitive metal primer for exterior application.
- C. Exterior Galvanized Metal Primer: Factory-formulated galvanized metal primer for exterior application.
- D. Exterior Aluminum Primer: Factory-formulated acrylic-based metal primer for exterior application.
- E. Exterior Primer for Existing Painted Metal Surfaces: Factory-formulated acrylic-based metal primer for exterior application over existing painted metal surfaces including metal roof and wall panels.
 - 1. Benjamin Moore; Super Spec HP Acrylic Metal Primer - No. P04: Applied at a dry film thickness of not less than 1.7 mils.

2.4 EXTERIOR FINISH COATS

- A. Exterior Satin Acrylic Paint: Factory-formulated low-sheen acrylic-latex paint exterior application.
 - 1. Benjamin Moore: Refer to "Finish Schedule" located on drawings for indicated locations where the following products are used.
 - a. Super Spec 100% Acrylic Latex Low Lustre House Paint - No. N185: Applied at a dry film thickness of not less than 1.3 mils.
 - b. Ultra Spec EXT 100% Acrylic Exterior Satin Finish Paint - No. N448: Applied at a dry film thickness of not less than 1.5 mils.
- B. Exterior Low-Luster Acrylic Paint for Existing Painted Metal Surfaces: Factory-formulated low-sheen acrylic paint for exterior application over existing painted metal surfaces including metal roof and wall panels.
 - 1. Benjamin Moore; Super Spec HP D.T.M. Acrylic Low Lustre - No. P25: Applied at a dry film thickness of not less than 2.0 mils.
- C. Exterior Semigloss Acrylic Enamel: Factory-formulated semigloss acrylic-latex enamel for exterior application.
 - 1. Benjamin Moore; Ultra Spec EXT 100% Acrylic Gloss Paint - No. N449: Applied at a dry film thickness of not less than 1.5 mils.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
 - 1. Comply with the Painting and Decorating Contractors of America for procedures specified in PDCA P4 - Responsibility for Inspection and Acceptance of Surfaces Prior to Painting and Decorating.”
- B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
 - 1. Concrete: 12 percent.
 - 2. Masonry (Clay and CMU): 12 percent.
 - 3. Wood: 15 percent.
 - 4. Portland Cement Plaster: 12 percent.
 - 5. Gypsum Board: 12 percent.
- C. Portland Cement Plaster Substrates: Verify that plaster is fully cured.
- D. Exterior Gypsum Board Substrates: Verify that finishing compound is sanded smooth.
- E. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.
- F. Proceed with coating application only after unsatisfactory conditions have been corrected.
 - 1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. General: Remove hardware and hardware accessories, covers, plates, machined surfaces, lighting fixtures, and similar items already installed that are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.
 - 1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection.
- B. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
 - 1. Schedule cleaning and painting so dust and other contaminants from the cleaning process will not fall on wet, newly painted surfaces.
 - 2. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.

- C. Concrete Substrates: Remove release agents, curing compounds, efflorescence, and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces to be painted exceeds that permitted in manufacturer's written instructions.
- D. Masonry Substrates: Remove efflorescence and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces or mortar joints exceeds that permitted in manufacturer's written instructions.
- E. Steel Substrates: Remove rust, loose mill scale, and shop primer if any. Clean using methods recommended in writing by paint manufacturer but not less than the following:
 - 1. SSPC-SP 3, "Power Tool Cleaning."
- F. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and abraded areas of shop paint, and paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.
- G. Galvanized-Metal Substrates: Remove grease and oil residue from galvanized sheet metal by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied paints.
- H. Aluminum Substrates: Remove loose surface oxidation.
- I. Wood Substrates:
 - 1. Scrape and clean knots. Before applying primer, apply coat of knot sealer recommended in writing by topcoat manufacturer for exterior use in paint system indicated.
 - 2. Sand surfaces that will be exposed to view, and dust off.
 - 3. Prime edges, ends, faces, undersides, and backsides of wood.
 - 4. After priming, fill holes and imperfections in the finish surfaces with putty or plastic wood filler. Sand smooth when dried.
- J. Plastic Trim Fabrication Substrates: Remove dust, dirt, and other foreign material that might impair bond of paints to substrates.
- K. Material Preparation: Mix and prepare paint materials according to manufacturer's written instructions.
 - 1. Maintain containers used in mixing and applying paint in a clean condition, free of foreign materials and residue.
 - 2. Stir material before application to produce a mixture of uniform density. Stir as required during application. Do not stir surface film into material. If necessary, remove surface film and strain material before using.
 - 3. Use only thinners approved by paint manufacturer and only within recommended limits.

3.3 APPLICATION

- A. Application, General:

1. Application Procedures: Apply paints and coatings by brush, roller, spray, or other applicators according to manufacturer's written instructions.
 - a. Brushes: Use brushes best suited for type of material applied. Use brush of appropriate size for surface or item being painted.
 - b. Rollers: Use rollers of carpet, velvet-back, or high-pile sheep's wool as recommended by manufacturer for material and texture required.
 - c. Spray Equipment: Use airless spray equipment with orifice size as recommended by manufacturer for material and texture required.
 2. Scheduling Painting: Apply first coat to surfaces that have been cleaned, pretreated, or otherwise prepared for painting as soon as practicable after preparation and before subsequent surface deterioration.
 - a. The number of coats and film thickness required are the same regardless of application method. Do not apply succeeding coats until previous coat has cured as recommended by manufacturer. If sanding is required to produce a smooth, even surface according to manufacturer's written instructions, sand between applications.
 - b. Allow sufficient time between successive coats to permit proper drying. Do not recoat surfaces until paint has dried to where it feels firm, and does not deform or feel sticky under moderate thumb pressure, and until application of another coat of paint does not cause undercoat to lift or lose adhesion.
 3. Minimum Coating Thickness: Apply paint materials no thinner than manufacturer's recommended spreading rate to achieve dry film thickness indicated. Provide total dry film thickness of the entire system as recommended by manufacturer.
 4. Completed Work: Match approved samples for color, texture, and coverage. Remove, refinish, or repaint work not complying with requirements.
- B. Apply paint according to manufacturer's written instructions. Use applicators and techniques best suited for substrate and type of material being applied.
1. The term "exposed surfaces" includes areas visible when permanent or built-in fixtures, and similar components are in place. Extend coatings in these areas, as required, to maintain system integrity and provide desired protection.
 2. Provide finish coats that are compatible with primers used.
 3. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
 4. Paint exterior doors on tops, bottoms, and side edges and entire exposed surface of exterior door frames.
 5. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
 6. Do not paint over dirt, rust, scale, grease, moisture, scuffed surfaces, or conditions detrimental to formation of a durable paint film.
 7. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.
 8. Paint colors, surface treatments, and finishes are indicated in the paint schedules.
 9. Sand lightly between each succeeding enamel or varnish coat.

- C. Prime Coats: Before applying finish coats, apply a prime coat, as recommended by manufacturer, to material that is required to be painted or finished and that has not been prime coated by others. Recoat primed and sealed surfaces where evidence of suction spots or unsealed areas in first coat appears, to ensure a finish coat with no burn-through or other defects due to insufficient sealing.
- D. Tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of same material are to be applied. Tint undercoats to match color of topcoat, but provide sufficient difference in shade of undercoats to distinguish each separate coat.
- E. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.
 - 1. Ensure that edges, corners, crevices, welds, and exposed fasteners receive a dry film thickness equivalent to that of flat surfaces.
- F. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.
 - 1. Pigmented (Opaque) Finishes: Completely cover surfaces as necessary to provide a smooth, opaque surface of uniform finish, color, appearance, and coverage.
 - a. Cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness, or other surface imperfections will not be acceptable.
 - 2. Stipple Enamel Finish: Roll and redistribute paint to an even and fine texture.
 - a. Leave no evidence of rolling, such as laps, irregularity in texture, skid marks, or other surface imperfections.
- G. Painting Fire Suppression, Plumbing, HVAC, Electrical, Communication, and Electronic Safety and Security Work:
 - 1. Paint the following work where exposed to view:
 - a. Equipment, including panelboards.
 - b. Uninsulated metal piping.
 - c. Uninsulated plastic piping.
 - d. Pipe hangers and supports.
 - e. Metal conduit.
 - f. Plastic conduit.
 - g. Tanks that do not have factory-applied final finishes.

3.4 FIELD QUALITY CONTROL

- A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test paint for dry film thickness.
 - 1. Contractor shall touch up and restore painted surfaces damaged by testing.

2. If test results show that dry film thickness of applied paint does not comply with paint manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with paint manufacturer's written recommendations.

3.5 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
- B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- D. Provide "Wet Paint" signs to protect newly painted finishes. After completing painting operations, remove temporary protective wrappings provided by others to protect their work.
 1. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces. Comply with procedures specified in PDCA P1.

3.6 EXTERIOR PAINTING SCHEDULE

- A. Ferrous Metal: Provide the following finish systems over exterior ferrous metal. Primer is not required on shop-primed items.
 1. Semi-Gloss Acrylic-Enamel Finish: Two finish coats over a rust-inhibitive primer.
 - a. Primer: Exterior ferrous-metal primer.
 - b. Finish Coats: Exterior semi-gloss acrylic enamel.
- B. Zinc-Coated Metal: Provide the following finish systems over all exterior zinc-coated metal surfaces that are not part of the exterior façade system.
 1. Semigloss Acrylic-Enamel Finish: Two finish coats over a galvanized metal primer.
 - a. Primer: Exterior galvanized metal primer.
 - b. Finish Coats: Exterior semigloss acrylic enamel.
- C. Aluminum: Provide the following finish systems over exterior aluminum surfaces:
 1. Semi-Gloss Acrylic-Enamel Finish: Two finish coats over a primer.
 - a. Primer: Exterior aluminum primer.
 - b. Finish Coats: Exterior semi-gloss acrylic enamel.
- D. Existing Exterior Painted Metal Surfaces: Provide the following finish systems over existing exterior painted metal surfaces including metal roof and wall panels.

1. Low-Luster Acrylic Enamel Finish for Existing Painted Metal Surfaces: Two finish coats over an exterior acrylic primer.
 - a. Primer: Exterior primer for existing painted metal surfaces.
 - b. Finish Coats: Exterior low-luster acrylic enamel for existing painted metal surfaces.

END OF SECTION 09 91 13

SECTION 09 91 23 - INTERIOR PAINTING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Surface preparation and field painting of exposed interior items and surfaces.
2. Surface preparation, priming, and finish coats specified in this Section are in addition to shop priming and surface treatment specified in other Sections.

B. Paint exposed surfaces, except where these Specifications indicate that the surface or material is not to be painted. If an item or a surface is not specifically mentioned, paint the item or surface the same as similar adjacent materials or surfaces. If a color of finish is not indicated, Architect will select from standard colors and finishes available.

C. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 DEFINITIONS

A. Gloss ranges used in this Section include the following:

1. Flat, or Matte: Not more than 5 units at 60 degrees and 10 units at 85 degrees.
2. Eggshell: 10 to 25 units at 60 degrees and 10 to 35 units at 85 degrees.
3. Semigloss: 35 to 70 units at 60 degrees.

B. Interior Surfaces: Interior surfaces to be painted are defined as those surfaces which are indicated in areas exposed to conditions which are controlled by building heating and cooling systems.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product. Include preparation requirements and application instructions.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. LEED Materials and Resources Calculator.

C. Samples for Verification: For each type of paint system and in each color and gloss of topcoat.

1. Submit Samples on rigid backing, 8 inches square.
2. Step coats on Samples to show each coat required for system.
3. Label each coat of each Sample.
4. Label each Sample for location and application area.

D. Product List: For each product indicated, include the following:

1. Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in schedules.
2. VOC content.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Paint: 5 percent, but not less than 1 gal. of each material and color applied.

1.5 QUALITY ASSURANCE

A. Applicator Qualifications: Engage an experienced applicator who has completed painting system applications similar in material, design, and extent to those indicated for this Project, whose work has resulted in applications with a record of successful in-service performance.

B. Mockups: Apply mockups of each paint system indicated and each color and finish selected to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Architect will select one surface to represent surfaces and conditions for application of each paint system specified in Part 3.
 - a. Vertical and Horizontal Surfaces: Provide samples of at least 100 sq. ft.
 - b. Other Items: Architect will designate items or areas required.
2. Final approval of color selections will be based on mockups.
 - a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Architect at no added cost to Owner.
3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials to Project site in manufacturer's original, unopened packages and containers bearing manufacturer's name and label and other identifying information.

- B. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.
 - 1. Maintain containers in clean condition, free of foreign materials and residue.
 - 2. Remove rags and waste from storage areas daily.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Products: Subject to compliance with requirements, provide products specified in this section by Benjamin Moore & Co. (Benjamin Moore). Substitutions will not be accepted.
 - 1. Manufacturers' shortened names shown within parentheses shall be used in identifying available products in Part 2 of this section.

2.2 PAINT MATERIALS, GENERAL

- A. Material Compatibility: Provide primers, and finish-coat materials that are compatible with one another and with the substrates indicated under conditions of service and application, as demonstrated by manufacturer based on testing and field experience.
 - 1. For each coat in a paint system, provide products recommended in writing by manufacturers of topcoat for use in paint system and on substrate indicated.
- B. Material Quality: Provide manufacturer's best-quality paint material of the various coating types specified that are factory formulated and recommended by manufacturer for application indicated. Paint-material containers not displaying manufacturer's product identification will not be acceptable.
 - 1. Proprietary Names: Use of manufacturer's proprietary product names to designate colors or materials is not intended to imply that products named are required to be used to the exclusion of equivalent products of other manufacturers. Furnish manufacturer's material data and certificates of performance for proposed substitutions.
- C. VOC Content: Products shall comply with VOC limits of authorities having jurisdiction and VOC limits indicated in Division 01 Section "LEED Sustainable Design Requirements."
- D. Colors: Provide custom colors of the finished paint systems to match the Architect's samples.

2.3 INTERIOR PRIMERS

- A. Interior Gypsum Board Primer: Factory-formulated latex-based primer for interior application.
- B. Interior Ferrous-Metal Primer: Factory-formulated quick-drying rust-inhibitive alkyd-based metal primer.
- C. Interior Zinc-Coated Metal Primer: Factory-formulated galvanized metal primer.

- D. Interior Metal Primer for Metal Ladders: Factory-formulated quick-drying rust-inhibitive acrylic-based metal primer.

- 1. Benjamin Moore; Ultra Spec HP Acrylic Metal Primer No. HP-04: Applied at a dry film thickness of not less than 1.7 mils.

2.4 INTERIOR FINISH COATS

- A. Interior Flat Latex-Emulsion Size: Factory-formulated flat latex-based interior paint.

- 1. Benjamin Moore; Ultra-Spec 500 Interior Flat Finish No. N536: Applied at a dry film thickness of not less than 1.8 mils.

- B. Interior Eggshell Acrylic Enamel: Factory-formulated eggshell acrylic-latex interior enamel.

- 1. Benjamin Moore; Ultra-Spec 500 Interior Eggshell Finish No. N538: Applied at a dry film thickness of not less than 1.8 mils.

- C. Interior Semigloss Acrylic Enamel: Factory-formulated semigloss acrylic-latex enamel for interior application.

- 1. Benjamin Moore; Ultra-Spec 500 Interior Semi-Gloss Finish No. N539: Applied at a dry film thickness of not less than 1.8 mils.

- D. Interior Low Sheen Latex Enamel for Metal Ladders: Factory-formulated low sheen acrylic-latex enamel for interior application.

- 1. Benjamin Moore; Latex Floor & Patio Low Sheen Enamel No. N122.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

- 1. Comply with the Painting and Decorating Contractors of America for procedures specified in PDCA P4 - Responsibility for Inspection and Acceptance of Surfaces Prior to Painting and Decorating.”

- B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:

- 1. Concrete: 12 percent.
 - 2. Masonry (Clay and CMU): 12 percent.
 - 3. Wood: 15 percent.
 - 4. Gypsum Board: 12 percent.

- C. Gypsum Board Substrates: Verify that finishing compound is sanded smooth.

- D. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.
- E. Proceed with coating application only after unsatisfactory conditions have been corrected.
 - 1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Remove hardware and hardware accessories, covers, plates, machined surfaces, lighting fixtures, and similar items already installed that are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.
 - 1. After completing painting operations in each space or area, reinstall items removed using workers skilled in the trades involved.
- B. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
 - 1. Schedule cleaning and painting so dust and other contaminants from the cleaning process will not fall on wet, newly painted surfaces.
 - 2. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.
- C. Concrete Substrates: Remove release agents, curing compounds, efflorescence, and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces to be painted exceeds that permitted in manufacturer's written instructions.
- D. Masonry Substrates: Remove efflorescence and chalk. Do not paint surfaces if moisture content or alkalinity of surfaces or mortar joints exceed that permitted in manufacturer's written instructions.
- E. Ferrous Metals Substrates: Clean ungalvanized ferrous-metal surfaces that have not been shop coated; remove oil, grease, dirt, and other foreign substances in accordance with SSPC SP 1 "Solvent Cleaning". After solvent cleaning prepare any bare metal surfaces by removing all stratified rust (rust scale), all loose mill scale, all loose or non-adherent rust and detrimental welding deposits by methods specified in SSPC SP-3 "Power Tool Cleaning".
 - 1. Touch up bare areas, heads of bolts, welded surfaces which are unpainted, and shop-applied prime coats that have been damaged. Wire-brush, clean with solvents recommended by paint manufacturer, and touch up with same primer as the shop coat.
 - 2. Surfaces requiring touch up painting shall be cleaned and primed as soon as practicable after erection and before excessive rusting or other damage occurs to such surfaces from weather or other exposure.
- F. Steel Substrates: Remove rust, loose mill scale, and shop primer, if any. Clean using methods recommended in writing by paint manufacturer but not less than the following:
 - 1. SSPC-SP 3, "Power Tool Cleaning."

- G. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and abraded areas of shop paint, and paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.
- H. Galvanized-Metal Substrates: Remove grease and oil residue from galvanized sheet metal fabricated from coil stock by mechanical methods to produce clean, lightly etched surfaces that promote adhesion of subsequently applied paints.
- I. Wood Substrates:
 - 1. Scrape and clean knots, and apply coat of knot sealer before applying primer.
 - 2. Sand surfaces that will be exposed to view, and dust off.
 - 3. Prime edges, ends, faces, undersides, and backsides of wood.
 - 4. After priming, fill holes and imperfections in the finish surfaces with putty or plastic wood filler. Sand smooth when dried.
- J. Gypsum Wallboard: Repair all surfaces in gypsum wallboard with wallboard joint finishing compound or spackling compound, filled out flush and sanded smooth. Clean all surfaces and taped joints of dust, dirt and other contaminants and be sure they are thoroughly dry before applying paint.
- K. Material Preparation: Mix and prepare paint materials according to manufacturer's written instructions.
 - 1. Maintain containers used in mixing and applying paint in a clean condition, free of foreign materials and residue.
 - 2. Stir material before application to produce a mixture of uniform density. Stir as required during application. Do not stir surface film into material. If necessary, remove surface film and strain material before using.
 - 3. Use only thinners approved by paint manufacturer and only within recommended limits.

3.3 APPLICATION

- A. Application, General:
 - 1. Application Procedures: Apply paints and coatings by brush, roller, spray, or other applicators according to manufacturer's written instructions.
 - a. Brushes: Use brushes best suited for type of material applied. Use brush of appropriate size for surface or item being painted.
 - b. Rollers: Use rollers of carpet, velvet-back, or high-pile sheep's wool as recommended by manufacturer for material and texture required.
 - c. Spray Equipment: Use airless spray equipment with orifice size as recommended by manufacturer for material and texture required.
 - 2. Scheduling Painting: Apply first coat to surfaces that have been cleaned, pretreated, or otherwise prepared for painting as soon as practicable after preparation and before subsequent surface deterioration.

- a. The number of coats and film thickness required are the same regardless of application method. Do not apply succeeding coats until previous coat has cured as recommended by manufacturer. If sanding is required to produce a smooth, even surface according to manufacturer's written instructions, sand between applications.
 - b. Allow sufficient time between successive coats to permit proper drying. Do not recoat surfaces until paint has dried to where it feels firm, and does not deform or feel sticky under moderate thumb pressure, and until application of another coat of paint does not cause undercoat to lift or lose adhesion.
 3. Minimum Coating Thickness: Apply paint materials no thinner than manufacturer's recommended spreading rate to achieve dry film thickness indicated. Provide total dry film thickness of the entire system as recommended by manufacturer.
 4. Completed Work: Match approved samples for color, texture, and coverage. Remove, refinish, or repaint work not complying with requirements.
- B. Apply paint according to manufacturer's written instructions. Use applicators and techniques best suited for substrate and type of material being applied.
1. The term "exposed surfaces" includes areas visible when permanent or built-in fixtures, grilles, convector covers, and similar components are in place. Extend coatings in these areas, as required, to maintain system integrity and provide desired protection.
 2. Provide finish coats that are compatible with primers used.
 3. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
 4. Paint back sides of access panels and removable or hinged covers to match exposed surfaces.
 5. Access panels, electrical panels, air diffusing outlets, supply and exhaust grilles, louvers, exposed conduit, primed hardware items, primed outlet covers, primed wall and ceiling plates and other items in painted areas shall be painted to match the areas in which they occur unless otherwise directed by the Architect.
 6. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
 7. Do not paint over dirt, rust, scale, grease, moisture, scuffed surfaces, or conditions detrimental to formation of a durable paint film.
 8. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.
 9. Paint colors, surface treatments, and finishes are indicated in the paint schedules.
 10. Sand lightly between each succeeding enamel or varnish coat.
- C. Prime Coats: Before applying finish coats, apply a prime coat, as recommended by manufacturer, to material that is required to be painted or finished and that has not been prime coated by others. Recoat primed and sealed surfaces where evidence of suction spots or unsealed areas in first coat appears, to ensure a finish coat with no burn-through or other defects due to insufficient sealing.
- D. Tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of same material are to be applied. Tint undercoats to match color of topcoat, but provide sufficient difference in shade of undercoats to distinguish each separate coat.

- E. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.
 - 1. Ensure that edges, corners, crevices, welds, and exposed fasteners receive a dry film thickness equivalent to that of flat surfaces.
- F. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.
 - 1. Pigmented (Opaque) Finishes: Completely cover surfaces as necessary to provide a smooth, opaque surface of uniform finish, color, appearance, and coverage.
 - a. Cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness, or other surface imperfections will not be acceptable.
 - 2. Stipple Enamel Finish: Roll and redistribute paint to an even and fine texture.
 - a. Leave no evidence of rolling, such as laps, irregularity in texture, skid marks, or other surface imperfections.
- G. Painting Fire Suppression, Plumbing, HVAC, Electrical, Communication, and Electronic Safety and Security Work:
 - 1. Paint the following work where exposed in equipment rooms:
 - a. Equipment, including panelboards and switch gear.
 - b. Uninsulated metal piping.
 - c. Uninsulated plastic piping.
 - d. Pipe hangers and supports.
 - e. Metal conduit.
 - f. Plastic conduit.
 - g. Tanks that do not have factory-applied final finishes.
 - h. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.
 - 2. Paint the following work where exposed in occupied spaces:
 - a. Equipment, including panelboards.
 - b. Uninsulated metal piping.
 - c. Uninsulated plastic piping.
 - d. Pipe hangers and supports.
 - e. Metal conduit.
 - f. Plastic conduit.
 - g. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.
 - h. Other items as directed by Architect.
 - 3. Paint portions of internal surfaces of metal ducts, without liner, behind air inlets and outlets that are visible from occupied spaces.

- a. Color: Flat, black paint.

3.4 FIELD QUALITY CONTROL

- A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test paint for dry film thickness.
 1. Contractor shall touch up and restore painted surfaces damaged by testing.
 2. If test results show that dry film thickness of applied paint does not comply with paint manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with paint manufacturer's written recommendations.

3.5 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
- B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- D. Provide "Wet Paint" signs to protect newly painted finishes. After completing painting operations, remove temporary protective wrappings provided by others to protect their work.
 1. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces. Comply with procedures specified in PDCA P1.

3.6 INTERIOR PAINT SCHEDULE

- A. Gypsum Board: Provide the following finish systems over interior gypsum board surfaces:
 1. Low-Luster Acrylic-Enamel Finish (Typical System): Two finish coats over a primer.
 - a. Primer: Interior gypsum board primer.
 - b. Finish Coats: Interior low-luster acrylic enamel.
 2. Semigloss Acrylic-Enamel Finish (Provide only where scheduled): Two finish coats over a primer.
 - a. Primer: Interior gypsum board primer.
 - b. Finish Coats: Interior semigloss acrylic enamel.
- B. Primed Wood Doors: Provide the following paint finish system over primed wood door surfaces:

1. Semigloss Acrylic-Enamel Finish: Two finish coats.
 - a. Finish Coats: Interior semigloss acrylic enamel.
- C. Ferrous Metal: Provide the following finish systems over ferrous metal:
 1. Semigloss Acrylic-Enamel Finish: Two finish coats over a primer.
 - a. Primer: Interior ferrous-metal primer.
 - b. Finish Coats: Interior semigloss acrylic enamel.
- D. Zinc-Coated Metal: Provide the following finish systems over interior zinc-coated metal surfaces:
 1. Semigloss Acrylic-Enamel Finish: Two finish coats over a primer.
 - a. Primer: Interior zinc-coated metal primer.
 - b. Finish Coats: Interior semigloss acrylic enamel.
- E. All-Service Jacket over Insulation: Provide the following finish system on cotton or canvas insulation covering:
 1. Flat Acrylic Finish: Two finish coats. Add fungicidal agent to render fabric mildew proof.
 2. Finish Coats: Interior flat latex-emulsion size.
- F. Interior Metal Ladders: Provide the following finish systems over ferrous metal:
 1. Low Sheen Latex-Enamel Finish: Two finish coats over a primer.
 - a. Primer: Interior metal primer for metal ladder.
 - b. Finish Coats: Interior low sheen latex enamel for metal ladder.

3.7 COLOR SCHEDULE

- A. Reference to a particular manufacturer's number or color name is used only as a convenience for the Architect in order to establish the Project color requirements. These references are not intended to describe the required generic paint systems. For generic paint systems requirements, refer to the "Finish Schedule" located on Drawings for interior painting as applicable to the respective conditions of use.
- B. The selection of paint colors are indicated on the drawings by manufacturer and color type.
 1. Furnish the same lots, batches, etc. within the same contiguous areas of the building (i.e. corridors on the same floors, common rooms which adjoin each other, etc.).

END OF SECTION 09 91 23

SECTION 09 96 20 - GRAFFITI-RESISTANT COATING SYSTEM

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Surface preparation and field application of anti-graffiti coating systems.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 DEFINITIONS

A. Gloss ranges used in this Section include the following:

1. Matte refers to finish with a gloss range below 15 when measured at an 85-degree meter.

B. Non-Sacrificial Coatings: Impervious, chemical resistant paints that allows solvent blends to dissolve defacement paints, inks, and dyes, while leaving the non-sacrificial paint or coating unaffected by the cleaning or removal process.

1.3 PERFORMANCE REQUIREMENTS

A. General Performance: Coating system shall meet performance requirements indicated without failure due to defective manufacture, fabrication, or installation.

1. Anti-Graffiti Coating Systems: Comply with performance requirements specified, as determined by testing on manufacturer's standard substrate assemblies representing those indicated for this Project.

B. Anti-Graffiti Coating Systems: Comply with the following:

1. Non-Sacrificial Coating System: Coatings shall not require re-application regardless of number of graffiti taggings during the warranty period.
2. Coating system shall show no signs of deterioration, ghosting, staining, shadowing or change of appearance after graffiti removal during the warranty period.
 - a. Upon graffiti removal, no evidence of graffiti shall remain.
3. Capability of removing 100 percent of all types of paint and graffiti materials from treated surfaces without damaging the coating or the substrate.
4. Capable of withstanding a minimum of 120 cleaning cycles over the same area without measurable coating deterioration.
5. Shall not increase dirt pick-up of substrate.
6. Shall comply with the following test results:

a.	MEK:	No effect after 5 days.
b.	Carboxylic Acid:	No effect after 5 days.
c.	75% Phosphoric Acid:	No effect after 5 days.
d.	37% HCL:	3 hours blister.
e.	50% Sulfuric Acid:	No effect after 5 days.
f.	20% NIT :	68 hours blister.

C. Material Compatibility:

1. Provide materials for use within each coating system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
2. For each coating system, provide products recommended in writing by manufacturers of coating system for use on substrate indicated.

- D. VOC Content: Products shall comply with VOC limits of authorities having jurisdiction and VOC limits indicated in Division 01 Section "Sustainable Design Requirements," which ever more stringent.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include preparation requirements and application instructions.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. LEED Materials and Resources Calculator.

- C. Samples: For each type of coating system applied onto each type of finish substrate indicated to receive coating system; 12 by 12 inches in size, with specified coating applied to half of each Sample.

D. Product List: For each product indicated, include the following:

1. Cross-reference to coating system and locations of application areas. Use same designations indicated on Drawings and in schedules.
2. VOC content.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Applicator.

- B. Product Certificates: For each type of coating system, from manufacturer.

- C. Field quality-control reports.

1.6 QUALITY ASSURANCE

- A. Applicator Qualifications: A firm experienced in applying coating system similar in material, design, and extent to that indicated for this Project, whose work has resulted in applications with a record of successful in-service performance, and that employs workers trained and approved by manufacturer.
- B. Mockups: Apply coating system to each type of substrate required.
 - 1. Locate each test application as directed by Architect.
 - 2. Size: 10 sq. ft.
 - 3. Final approval by Architect of coating system application will be from test applications.
- C. Preinstallation Conference: Conduct conference at Project site.

1.7 PROJECT CONDITIONS

- A. Limitations: Proceed with application only when the following existing and forecasted weather and substrate conditions permit coating system to be applied according to manufacturers' written instructions and warranty requirements:
 - 1. Concrete surfaces and mortar have cured for not less than 28 days.
 - 2. Building has been closed in for not less than 30 days before treating wall assemblies.
 - 3. Ambient temperature is above 40 deg F and below 100 deg F and will remain so for 24 hours.
 - 4. Substrate is not frozen and substrate-surface temperature is above 40 deg F and below 100 deg F.
 - 5. Rain or snow is not predicted within 24 hours.
 - 6. Not less than seven days have passed since surfaces were last wet.
 - 7. Windy conditions do not exist that might cause coating to be blown onto vegetation or surfaces not intended to be treated.

1.8 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace materials that fail to preserve the original aesthetics of the finish substrate material being protected and comply with specified "Performance Requirements" Article within specified warranty period.
 - 1. Failure includes, changes of finish substrate appearance after graffiti removal but not limited to the following:
 - a. Deterioration of coating system including yellowing.
 - b. Ghosting.
 - c. Staining.
 - d. Shadowing.
 - 2. Warranty Period: 10 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 ANTI-GRAFFITI COATINGS

- A. Proprietary-Anti-Gaffti Coating System: Clear, penetrating, non-sacrificial anti-graffiti coating system that can withstand repeated graffiti removals using system cleaning solution product without need of reapplying anti-graffiti coating system.
1. Testing Standard: Comply with the following:
 - a. ASTM B 117 and ASTM D 714 (salt spray minimum acceptable of 8000 hours).
 - b. ASTM D 530 (hardness).
 - c. ASTM D 412 (tensile strength and elongation).
 - d. ASTM D 522 (pass 3/8 inch mandral).
 - e. ASTM 968 (abrasion test).
 - f. ASTM E 96 (vapor transmission).
 - g. Water clear, non-yellowing, free of waxes and urethanes.
 - h. Shall allow moisture vapor transmission.
 2. Products: Subject to compliance with requirements, provide "Graffiti Solution System" consisting of the following products as manufactured by GSS Coatings, LLC; Tel: (801) 255-9505.
 - a. Undercoating: Water-based high performance under coating sealer.
 - 1) Undercoating applied onto stucco, concrete, and masonry surfaces.
 - a) Product: "#GSS307 - Clear VU High Solids Base Coating."
 - 2) Undercoating applied onto metal, marble, slate and tile surfaces
 - a) Product: "#GSS308 - Sure Bond."
 - b. Top Coatings: Non-sacrificial, anti-graffiti top coating with clear, matte finish.
 - 1) Product: "#GSS100 - Clear Matte."
 - c. Graffiti Cleaning Solution: Non-flammable, biodegradable, with a pH 7 - 8.5 and recyclable, allowing graffiti removal without the use of blasting equipment, hot water, or high pressure wash equipment.
 - 1) Product: "#GSS400 - Erasol."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Applicator present, for compliance with requirements and conditions affecting performance of the Work.

1. Verify that surfaces are clean and dry according to coating system manufacturer's requirements. Check moisture content in three representative locations by method recommended by manufacturer.
 2. Verify that there is no efflorescence or other removable residues that would be trapped beneath the application of coating system.
 3. Verify that required repairs are complete, cured, and dry before applying coating system.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Cleaning: Before application of coating system, clean substrate of substances that could impair penetration or performance of product according to coating system manufacturer's written instructions.
- B. Protect adjoining work, including mortar and sealant bond surfaces, from spillage or blow-over of coating system. Cover adjoining and nearby surfaces of aluminum and glass if there is the possibility of coating system being deposited on surfaces. Cover live vegetation.
- C. Coordination with Mortar Joints: Do not apply coating system until pointing mortar for joints adjacent to surfaces receiving coating system treatment has been installed and cured.
- D. Coordination with Sealant Joints: Do not apply coating system until sealants for joints adjacent to surfaces receiving coating system treatment have been installed and cured.
1. Coating system work may precede sealant application only if sealant adhesion and compatibility have been tested and verified using substrate, coating system, and sealant materials identical to those required.

3.3 APPLICATION

- A. Apply a heavy-saturation coating of coating system, on surfaces indicated for treatment, using 15 psi- pressure spray with a fan-type spray nozzle to the point of saturation. Apply coating in dual passes of uniform, overlapping strokes. Remove excess material; do not allow material to puddle beyond saturation. Comply with manufacturer's written instructions for application procedure unless otherwise indicated.

3.4 CLEANING

- A. Immediately clean coating system from adjoining surfaces and surfaces soiled or damaged by coating application as work progresses. Correct damage to work of other trades caused by coating application, as approved by Architect.
1. Comply with manufacturer's written cleaning instructions.

END OF SECTION 09 96 20

SECTION 10 11 00 - VISUAL DISPLAY SURFACES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

1.2 SUMMARY

A. Section Includes:

1. (OFCD) Owner furnished Contractor installed visual display units.

1.3 ACTION SUBMITTALS

- ##### A. Product Schedule: For visual display surfaces. Use same designations indicated on Drawings.

1.4 QUALITY ASSURANCE

- ##### A. Surface-Burning Characteristics: As determined by testing identical products according to ASTM E 84 by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1.5 DELIVERY, STORAGE, AND HANDLING

- ##### A. Deliver factory-built visual display surfaces, including factory-applied trim where indicated, completely assembled in one piece without joints, where possible. If dimensions exceed maximum manufactured panel size, provide two or more pieces of equal length as acceptable to Architect. When overall dimensions require delivery in separate units, prefit components at the factory, disassemble for delivery, and make final joints at the site.
- ##### B. Store visual display surfaces vertically with packing materials between each unit.

1.6 PROJECT CONDITIONS

- ##### A. Environmental Limitations: Do not deliver or install visual display surfaces until spaces are enclosed and weathertight, wet work in spaces is complete and dry, work above ceilings is complete, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

PART 2 - PRODUCTS

2.1 VISUAL DISPLAY SURFACES

- ##### A. General: Owner will furnish visual display surfaces as required for site-assembly. Refer to Division 01 Section "Summary" for "Owner Furnished Products" and addition requirements.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances, surface conditions of wall, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Comply with manufacturer's written instructions for surface preparation.
- B. Clean substrates of substances that could impair the performance of and affect the smooth, finished surfaces of visual display boards, including dirt, mold, and mildew.

3.3 INSTALLATION, GENERAL

- A. General: Install visual display surfaces in locations and at mounting heights indicated on Drawings, or if not indicated, as directed by Architect. Keep perimeter lines straight, level, and plumb. Provide grounds, clips, backing materials, adhesives, brackets, anchors, trim, and accessories necessary for complete installation.
 - 1. Attach to wall surface with concealed brackets screwed to wall.

3.4 CLEANING AND PROTECTION

- A. Clean visual display surfaces according to manufacturer's written instructions. Attach one cleaning label to visual display surface in each room.
- B. Touch up factory-applied finishes to restore damaged or soiled areas.
- C. Cover and protect visual display surfaces after installation and cleaning.

END OF SECTION 10 11 00

SECTION 10 14 23 - PANEL SIGNAGE

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Room-identification signs.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 DEFINITIONS

- A. Accessible: In accordance with the accessibility standard.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.
 - d. Low Emitting Materials Information.
 - e. LEED Materials and Resources Calculator.

C. Shop Drawings: For panel signs.

1. Include fabrication and installation details and attachments to other work.
2. Show sign mounting heights, locations of supplementary supports to be provided by others, and accessories.
3. Show message list, typestyles, graphic elements, including raised characters and Braille, and layout for each sign at least half size.

D. Samples for Verification: For each type of sign assembly showing all components and with the required finish(es), in manufacturer's standard size unless otherwise indicated and as follows:

1. Room-Identification Signs: Full-size Sample.
2. Exposed Accessories: Full-size Sample of each accessory type.

E. Sign Schedule: Use same designations specified or indicated on Drawings or in a sign schedule.

- F. Delegated-Design Submittal: For signs indicated in "Performance Requirements" Article.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For signs to include in maintenance manuals.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

1.7 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of signs that fail in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Deterioration of finishes beyond normal weathering.
 - b. Deterioration of embedded graphic image.
 - c. Separation or delamination of sheet materials and components.
 - 2. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Accessibility Standard: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1.

2.2 RESTROOM SIGNS

- A. Room-Identification Sign: Sign with smooth, uniform surfaces; with message and characters having uniform faces, sharp corners, and precisely formed lines and profiles; and as follows:
 - 1. Products: Provide "RRE-130_150PairedSet_White_on_Black" women and men restroom signage with raised text, internal pictogram, and Grade 2 Braille" as manufactured by Compliance Signs.com; Tele: (800) 578-1245.
 - 2. Solid-Sheet Sign: Manufacture's standard cast acrylic sheets as follows:
 - a. Acrylic Substrate Sheet (Background): Matte acrylic sheet with a minimum 1/16 inch thickness.

- b. Acrylic Graphics and Tactile Sheet (Raised Characters): Raised characters routed from tactile layer that is chemically welded to substrate sheet to produce raised graphics, tactile and braille of a minimum 1/36 inch thickness.
 - 1) Text and Typeface: Accessible raised characters and Braille. Finish raised characters to contrast with background color, and finish Braille to match background color.
- 3. Sign-Panel Perimeter: Finish edges smooth.
 - a. Edge Condition: Square cut.
 - b. Corner Condition in Elevation: Rounded to radius indicated.
- 4. Mounting: Surface mounted to wall with two-face tape.

2.3 INTERIOR EXIT SIGNS

- A. Room-Identification Sign: Sign with smooth, uniform surfaces; with message and characters having uniform faces, sharp corners, and precisely formed lines and profiles; and as follows:
 - 1. Products: Provide “RRE-655_White_on_Charcoal Gray” 6-inch by 4-inch exit signage and “RSME-19471_White_on_Charcoal Gray” 8-inch by 2-inch exit signage with raised text, and Grade 2 Braille” as manufactured by Compliance Signs.com; Tele: (800) 578-1245.
 - a. Color:
 - 1) Raised Characters: White.
 - 2) Background: Charcoal Gray.
 - 2. Mounting: Surface mounted to wall with two-face tape.
 - 3. Text and Typeface: Accessible raised characters and Braille. Finish raised characters to contrast with background color, and finish Braille to match raised characters color.

2.4 ACCESSORIES

- A. Two-Face Tape: Manufacturer's standard high-bond, foam-core tape, 0.045 inch thick, with adhesive on both sides.
- B. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D 1187.

2.5 FABRICATION

- A. Shop- and Subsurface-Applied Vinyl: Align vinyl film in final position and apply to surface. Firmly press film from the middle outward to obtain good bond without blisters or fishmouths.

2.6 GENERAL FINISH REQUIREMENTS

- A. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of signage work.
- B. Verify that sign-support surfaces are within tolerances to accommodate signs without gaps or irregularities between backs of signs and support surfaces unless otherwise indicated.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. General: Install signs using mounting methods indicated and according to manufacturer's written instructions.
 - 1. Install signs level, plumb, true to line, and at locations and heights indicated, with sign surfaces free of distortion and other defects in appearance.
 - 2. Install signs so they do not protrude or obstruct according to the accessibility standard.
 - 3. Before installation, verify that sign surfaces are clean and free of materials or debris that would impair installation.
- B. Room-Identification Signs and Other Accessible Signage: Install in locations on walls according to accessibility standard.
- C. Mounting Methods:
 - 1. Two-Face Tape: Clean bond-breaking materials from substrate surface and remove loose debris. Apply tape strips symmetrically to back of sign and of suitable quantity to support weight of sign without slippage. Keep strips away from edges to prevent visibility at sign edges. Place sign in position, and push to engage tape adhesive.

3.3 ADJUSTING AND CLEANING

- A. Remove and replace damaged or deformed signs and signs that do not comply with specified requirements. Replace signs with damaged or deteriorated finishes or components that cannot be successfully repaired by finish touchup or similar minor repair procedures.
- B. Remove temporary protective coverings and strippable films as signs are installed.

- C. On completion of installation, clean exposed surfaces of signs according to manufacturer's written instructions, and touch up minor nicks and abrasions in finish. Maintain signs in a clean condition during construction and protect from damage until acceptance by Owner.

END OF SECTION 10 14 23

SECTION 10 28 00 - TOILET ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Public-use washroom accessories.
2. Warm-air dryers.
3. Childcare accessories.
4. Underlavatory guards.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated. Include the following:

1. Construction details and dimensions.
2. Anchoring and mounting requirements, including requirements for cutouts in other work and substrate preparation.
3. Material and finish descriptions.
4. Features that will be included for Project.
5. Manufacturer's warranty.
6. Include electrical characteristics.

B. Samples: Full size, for each accessory item to verify design, operation, and finish requirements.

1. Approved full-size Samples will be returned and may be used in the Work.

C. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.

1. Identify locations using room designations indicated.

1.3 INFORMATIONAL SUBMITTALS

A. Warranty: Sample of special warranty.

1.4 CLOSEOUT SUBMITTALS

A. Maintenance Data: For toilet and bath accessories to include in maintenance manuals.

1.5 QUALITY ASSURANCE

A. Source Limitations: For products listed together in the same Part 2 articles, obtain products from single source from single manufacturer.

B. Regulatory Requirements: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA) and

Architectural Barriers Act (ABA) Accessibility Guidelines for Buildings and Facilities" and ICC/ANSI A117.1 for grab bar requirements.

1.6 COORDINATION

- A. Coordinate accessory locations with other work to prevent interference with clearances required for access by people with disabilities, and for proper installation, adjustment, operation, cleaning, and servicing of accessories.
- B. Deliver inserts and anchoring devices set into concrete or masonry as required to prevent delaying the Work.

1.7 WARRANTY

- A. Special Mirror Warranty: Manufacturer's standard form in which manufacturer agrees to replace mirrors that develop visible silver spoilage defects and that fail in materials or workmanship within specified warranty period.

- 1. Warranty Period: 15 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Stainless Steel: ASTM A 666, Type 304, 0.031-inch minimum nominal thickness unless otherwise indicated.
- B. Galvanized-Steel Mounting Devices: ASTM A 153/A 153M, hot-dip galvanized after fabrication.
- C. Fasteners: Screws, bolts, and other devices of same material as accessory unit and tamper-and-theft resistant where exposed, and of galvanized steel where concealed.
- D. Chrome Plating: ASTM B 456, Service Condition Number SC 2 (moderate service).
- E. Mirrors: ASTM C 1503, Mirror Glazing Quality, clear-glass mirrors, nominal 6.0 mm thick.

2.2 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.3 PUBLIC-USE WASHROOM ACCESSORIES

- A. Combination Towel (Folded) Dispenser/Waste Receptacle - (Toilet Accessory Type #1):
 - 1. Products: Subject to compliance with requirements, provide products by one of the following:

- a. Bobrick Washroom Equipment, Inc.; “B-38034”
 - b. American Specialties, Inc.; “6467”
 2. Description: Combination unit for dispensing C-fold or multifold towels, with removable waste receptacle.
 3. Mounting: Recessed.
 - a. Designed for nominal 4-inch wall depth.
 4. Minimum Towel-Dispenser Capacity: 600 C-fold or 800 multifold paper towels.
 5. Minimum Waste-Receptacle Capacity: 3.7 gal.
 6. Material and Finish: Stainless steel, No. 4 finish (satin).
 7. Liner: Reusable, vinyl waste-receptacle liner.
 8. Lockset: Tumbler type for towel-dispenser compartment and waste receptacle.
- B. Paper Towel (Folded) Dispenser - (Toilet Accessory Type #02):
 1. Recessed Paper Towel Dispenser (Option #1):
 - a. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Bobrick Washroom Equipment, Inc.; “B-35903”
 - 2) American Specialties, Inc.; “6457”
 - b. Mounting: Recessed.
 - c. Minimum Capacity: 300 C-fold or 400 multifold towels.
 - d. Material and Finish: Stainless steel, No. 4 finish (satin).
 2. Surface Mounted Paper Towel Dispenser (Option #2):
 - a. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Bobrick Washroom Equipment, Inc.; “B-359039”
 - b. Mounting: Surface mounted.
 - c. Minimum Capacity: 300 C-fold or 400 multifold towels.
 - d. Material and Finish: Stainless steel, No. 4 finish (satin).
- C. Grab Bar:
 1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. Bobrick Washroom Equipment, Inc.; “B-6806.99”
 - b. Bradley Corporation; “812-2”
 - c. American Specialties, Inc.; “3800 Series”
 2. Mounting: Flanges with concealed fasteners.

3. Material: Stainless steel, 0.05 inch thick.
 - a. Finish: Smooth, No. 4 finish (satin) on ends and slip-resistant texture in grip area.
4. Outside Diameter: 1-1/2 inches.
5. Configuration and Length:
 - a. Toilet Accessory Type #3: Straight, 42-inches long.
 - b. Toilet Accessory Type #4: Straight, 36-inches long.
 - c. Toilet Accessory Type #5: Straight, 18-inches long.
- D. Utility Hook - (Toilet Accessory Type #6):
 1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. Bobrick Washroom Equipment, Inc.; "B-6707"
 - b. Bradley Corporation; "9114"
 - c. American Specialties, Inc.; "7340S"
 2. Description: Single-prong unit.
 3. Material and Finish: Stainless steel, No. 4 finish (satin).
- E. Farmless Backlit Mirror Unit - (Toilet Accessory Type #07):
 1. Products: Subject to compliance with requirements, provide "Mirror-Lux LED Wheelchair Mirror; #MLWC4024" as manufactured by AAMSCO Lighting, Inc.
 - a. Voltage: 120 -277.
 - b. Light Source: LED.
 2. Annealed Monolithic Glass Mirrors: ASTM C 1503; Mirror Select Quality, clear.
 3. Glass Size: 24-inch width by 40-inch height.
- F. Automatic Liquid-Soap Dispenser - (Toilet Accessory Type #8):
 1. Automatic Liquid-Soap Dispenser (Option #1):
 - a. Products: Subject to compliance with requirements, provide "Enmotion Gen2" automated touchless soap & sanitizer dispenser as manufactured by Georgia-Pacific.
 - b. Description: Automatic dispenser with infrared sensor to detect presence of hands; battery powered; designed for dispensing antibacterial soap in liquid or lotion form.
 - c. Mounting: Vertically oriented, surface mounted.
 - d. Capacity: 1,200 ml.
 - e. Refill Indicator: LED indicator.
 - f. Low Battery Indicator: LED indicator.
 2. Automatic Liquid-Soap Dispenser (Option #2):

- a. Products: Subject to compliance with requirements, provide “ESD-2000-CP / Catalog #3346089” deck-mounted foam soap dispenser as manufactured by Sloan.
- b. Description: Description: Automatic dispenser with infrared sensor to detect presence of hands; battery powered; designed for dispensing antibacterial soap in lather form.
- c. Mounting: Deck mounted.
- d. Capacity: 1,500 ml.
- e. Refill Indicator: LED indicator.
- f. Low Battery Indicator: LED indicator.

G. Sanitary-Napkin Disposal Unit - (Toilet Accessory Type #9):

1. Surface-Mounted, Sanitary-Napkin Disposal Unit (Option #1):

- a. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Bobrick Washroom Equipment, Inc.; “B-254”
 - 2) American Specialties, Inc.; “6471-9”
- b. Mounting: Surface mounted.
- c. Door or Cover: Self-closing, disposal-opening cover and hinged face panel with tumbler lockset.
- d. Receptacle: Removable.
- e. Material and Finish: Stainless steel, No. 4 finish (satin).

2. Toilet Partition-Mounted, Sanitary-Napkin Disposal Unit (Option #2):

- a. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Bobrick Washroom Equipment, Inc.; “B-354”
 - 2) American Specialties, Inc.; “0472-1”
- b. Mounting: Partition mounted, dual access.
- c. Door or Cover: Self-closing, disposal-opening cover and hinged face panel with tumbler lockset.
- d. Receptacle: Removable.
- e. Material and Finish: Stainless steel, No. 4 finish (satin).

H. Toilet Tissue (Roll) Dispenser - (Toilet Accessory Type #10):

1. Surface-Mounted, Toilet Tissue (Roll) Dispenser (Option #1):

- a. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Bobrick Washroom Equipment, Inc.; “B-2888”
 - 2) American Specialties, Inc.; “0030”

- b. Description: Double-roll dispenser.
 - c. Mounting: Surface mounted.
 - d. Operation: Noncontrol delivery with theft-resistant spindle.
 - e. Capacity: Designed for 4-1/2- or 5 1/4-inch- diameter tissue rolls.
 - f. Material and Finish: Stainless steel, No. 4 finish (satin).
- 2. Surface-Mounted, Double-Roll Toilet Tissue Dispenser (Option #2):
 - a. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Bobrick Washroom Equipment, Inc.; "B-265"
 - 2) American Specialties, Inc.; "0715"
 - b. Description: Double-roll dispenser.
 - c. Mounting: Surface mounted.
 - d. Operation: Spindleless with tension-spring controlled delivery.
 - e. Capacity: Designed for 4-1/2-inch- diameter tissue rolls.
 - f. Material and Finish: Stainless steel, No. 4 finish (satin).
- I. Recessed-Mounted, Sanitary-Napkin Disposal and Toilet Tissue Dispenser - (Toilet Accessory Type #11):
 - 1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. Bobrick Washroom Equipment, Inc.; "B-3094"
 - b. American Specialties, Inc.; "04823"
 - 2. Description: Combination unit with double-roll toilet tissue dispenser and the following:
 - a. Removable sanitary-napkin waste receptacle with self-closing, disposal-opening cover.
 - 3. Mounting: Recessed mounted.
 - 4. Toilet Tissue Dispenser Capacity: 4-1/2- or 5-1/4-inch- diameter tissue rolls.
 - 5. Toilet Tissue Dispenser Operation: Noncontrol delivery with theft-resistant spindles.
 - 6. Material and Finish: Stainless steel, No. 4 finish (satin).
 - 7. Lockset: Tumbler type.
- J. Waste Receptacle - (Toilet Accessory Type #14):
 - 1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. Bobrick Washroom Equipment, Inc.; "B-35633"
 - b. Bradley Corporation; "3257"
 - c. American Specialties, Inc.; "6459"
 - 2. Mounting: Self-closing disposal-opening cover, recessed.

3. Minimum Capacity: 2.8-gal.
4. Material and Finish: Stainless steel, No. 4 finish (satin).
5. Liner: Reusable vinyl liner.
6. Lockset: Tumbler type for waste receptacle.

K. Seat-Cover Dispenser - (Toilet Accessory Type #17):

1. Surface Mounted, Seat-Cover Dispenser (Option #1):
 - a. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Bobrick Washroom Equipment, Inc.; "B-4221"
 - 2) American Specialties, Inc.; "6477-9"
 - b. Mounting: Surface mounted.
 - c. Minimum Capacity: 250 seat covers.
 - d. Exposed Material and Finish: Stainless steel, No. 4 finish (satin).
 - e. Lockset: Tumbler type.
2. Recessed, Seat-Cover Dispenser (Option #2):
 - a. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1) Bobrick Washroom Equipment, Inc.; "B-301"
 - 2) American Specialties, Inc.; "0477"
 - b. Mounting: Surface mounted.
 - c. Minimum Capacity: 250 seat covers.
 - d. Exposed Material and Finish: Stainless steel, No. 4 finish (satin).
 - e. Lockset: Tumbler Type.

L. Mirror Unit - (Toilet Accessory Type #19):

1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. Bobrick Washroom Equipment, Inc.; "B-165-2436"
 - b. Bradley Corporation; "781-2436"
 - c. American Specialties, Inc.; "0620-24x36"
2. Annealed Monolithic Glass Mirrors: ASTM C 1503; Mirror Select Quality, clear.
 - a. Nominal Thickness: 6.0 mm.
3. Frame: Stainless-steel channel.
 - a. Corners: Mitered and mechanically interlocked.

4. Hangers: Produce rigid, tamper- and theft-resistant installation, using method indicated below.
 - a. One-piece, galvanized-steel, wall-hanger device with spring-action locking mechanism to hold mirror unit in position with no exposed screws or bolts.
5. Size: 24-inch width by 36-inch height.

2.4 WARM-AIR DRYERS (Toilet Accessory Type #13)

- A. Source Limitations: Obtain warm-air dryers from single source from single manufacturer.
- B. High-Speed Warm-Air Dryer (Option #1):
 1. Products: Subject to compliance with requirements, provide “Xlerator - #XL-SB” as manufactured by Excel Dryer Inc.
 - a. Recess Mounting Kit: “Excel Dryer Inc.; Xlerator Hand Dryer - ADA Compliant Recess Kit.”
 - 1) Finish: No. 4 finish (satin), stainless steel.
 2. Description: High-speed, warm-air hand dryer for rapid hand drying.
 3. Mounting: Surface mounted.
 4. Operation: Electronic-sensor activated with operation time of 10 to 15 seconds.
 5. Cover Material and Finish: No. 4 finish (satin), stainless steel.
 6. Electrical Requirements: 110/120 VAC, 12 Amp, 1500 Watts.
- C. High-Speed Warm-Air Dryer (Option #2):
 1. Products: Subject to compliance with requirements, provide “Airblade V Series – HU02 (Nickel)” as manufactured by Dyson.
 2. Description: High-speed, warm-air hand dryer for rapid hand drying.
 3. Mounting: Surface mounted.
 4. Operation: Electronic-sensor activated with operation time of 10 to 15 seconds.
 5. Cover Material and Finish: Polycarbonate; sprayed antibacterial nickel paint coating.
 6. Electrical Requirements: 110/120 VAC, 12 Amp, 1500 Watts.

2.5 CHILDCARE ACCESSORIES (Toilet Accessory Type #16)

- A. Source Limitations: Obtain childcare accessories from single source from single manufacturer.
- B. Surface Mounted, Horizontal Orientated, Diaper-Changing Station (Option #1):
 1. Product: Subject to compliance with the requirements, provide one of the following:
 - a. Koala Kare Products, A Division of Bobrick; “KB208, Color: #01 – Grey.”

2. Description: Horizontal unit that opens by folding down from stored position and with child-protection strap.
 - a. Engineered to support minimum of 250-lb static load when opened.
3. Mounting: Surface mounted, with unit projecting not more than 4 inches from wall when closed.
4. Operation: By pneumatic shock-absorbing mechanism.
5. Material and Finish: HDPE in manufacturer's standard color.
6. Liner Dispenser: Built in.

C. Surface Mounted, Vertical Orientated, Diaper-Changing Station (Option #2):

1. Product: Subject to compliance with the requirements, provide one of the following:
 - a. Koala Kare Products, A Division of Bobrick; "KB101, Color: #01 – Grey."
2. Description: Vertical unit that opens by folding down from stored position and with child-protection strap.
 - a. Engineered to support minimum of 250-lb static load when opened.
3. Mounting: Surface mounted, with unit projecting not more than 4 inches from wall when closed.
4. Operation: By pneumatic shock-absorbing mechanism.
5. Material and Finish: HDPE in manufacturer's standard color.
6. Liner Dispenser: Built in.

2.6 UNDERLAVATORY GUARDS

A. Underlavatory Guard - (Toilet Accessory Type #12):

1. Products: Subject to compliance with requirements, provide products by one of the following:
 - a. Truebro by IPS Corporation; "Lav-Guard 2, EZ Series"
 - b. Plumberex Specialty Products Inc.; "Pro-Extreme"
2. Description: Insulating pipe covering for supply and drain piping assemblies that prevent direct contact with and burns from piping; allow service access without removing coverings.
3. Material and Finish: Antimicrobial, molded plastic, white.

2.7 FABRICATION

- A. General: Fabricate units with tight seams and joints, and exposed edges rolled. Hang doors and access panels with full-length, continuous hinges. Equip units for concealed anchorage and with corrosion-resistant backing plates.

- B. Keys: Provide universal keys for internal access to accessories for servicing and resupplying. Provide minimum of six keys to Owner's representative.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.
- B. Grab Bars: Install to withstand a downward load of at least 250 lbf, when tested according to ASTM F 446.
 - 1. Grab bars shall be installed at heights and locations as indicated on Drawings, complying with local building code and governing agency having jurisdiction.

3.2 ADJUSTING AND CLEANING

- A. Adjust accessories for unencumbered, smooth operation. Replace damaged or defective items.
- B. Remove temporary labels and protective coatings.
- C. Clean and polish exposed surfaces according to manufacturer's written recommendations.

END OF SECTION 10 28 00

SECTION 10 44 00 - FIRE PROTECTION SPECIALTIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Portable, hand-carried fire extinguishers.
2. Fire protection cabinets.
3. Mounting brackets for fire extinguishers

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include rating and classification, construction details, material descriptions, dimensions of individual components and profiles, and finishes for fire protection specialties.
1. Fire Protection Cabinets: Include roughing-in dimensions, details showing mounting methods, relationships of box and trim to surrounding construction, door hardware, cabinet type, trim style, and panel style.
- B. Shop Drawings: For fire protection cabinets. Include plans, elevations, sections, details, and attachments to other work.
- C. Samples for Initial Selection: For each type of fire protection specialties indicated.
- D. Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below:
1. Size: 6 by 6 inches square.
- E. Product Schedule: For fire protection specialties. Coordinate final fire protection cabinet schedule with fire extinguisher schedule to ensure proper fit and function. Use same designations indicated on Drawings.

1.3 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For fire protection specialties to include in maintenance manuals.

1.4 QUALITY ASSURANCE

- A. NFPA Compliance: Fabricate and label fire extinguishers to comply with NFPA 10, "Portable Fire Extinguishers."
- B. Fire Extinguishers: Listed and labeled for type, rating, and classification by an independent testing agency acceptable to authorities having jurisdiction.
1. Provide fire extinguishers approved, listed, and labeled by FMG.

- C. Fire-Rated, Fire Protection Cabinets: Listed and labeled to comply with requirements in ASTM E 814 for fire-resistance rating of walls where they are installed.
- D. Preinstallation Conference: Conduct conference at Project site.
 - 1. Review methods and procedures related to fire protection specialties including, but not limited to, the following:
 - a. Schedules and coordination requirements.

1.5 COORDINATION

- A. Coordinate size of fire protection cabinets to ensure that type and capacity of fire extinguishers indicated are accommodated.
- B. Coordinate sizes and locations of fire protection cabinets with wall depths.

1.6 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace fire extinguishers that fail in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Failure of hydrostatic test according to NFPA 10.
 - b. Faulty operation of valves or release levers.
 - 2. Warranty Period: Six years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B.
- B. Tempered Float Glass: ASTM C 1048, Kind FT, Condition A, Type I, Quality q3, 3 mm thick, Class 1 (clear).

2.2 PORTABLE, HAND-CARRIED FIRE EXTINGUISHERS

- A. Fire Extinguishers: Type, size, and capacity for each fire protection cabinet indicated.
 - 1. Valves: Manufacturer's standard.
 - 2. Handles and Levers: Manufacturer's standard.
 - 3. Instruction Labels: Include pictorial marking system complying with NFPA 10, Appendix B and bar coding for documenting fire extinguisher location, inspections, maintenance, and recharging.

- B. Multipurpose Dry-Chemical Type in Steel Container Insert drawing designation: UL-rated 2-A:10-B:C, 5-lb nominal capacity, with monoammonium phosphate-based dry chemical in enameled-steel container.

2.3 FIRE PROTECTION CABINET

- A. Cabinet Type: Suitable for fire extinguisher.
- B. Cabinet Construction: Nonrated.
- C. Cabinet Material: Steel sheet.
- D. Recessed Cabinet: Cabinet box recessed in walls of sufficient depth to suit style of trim indicated.
 - 1. Trimless with Hidden Flange: Flange of same metal and finish as box overlaps surrounding wall finish and is concealed from view by an overlapping door.
- E. Door Material: Steel sheet.
- F. Door Style: Vertical duo panel with frame.
- G. Door Glazing: Tempered float glass (clear).
- H. Door Hardware: Manufacturer's standard door-operating hardware of proper type for cabinet type, trim style, and door material and style indicated.
 - 1. Provide projecting door pull and friction latch.
 - 2. Provide concealed hinge permitting door to open 180 degrees.
- I. Accessories:
 - 1. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as indicated.
 - a. Identify fire extinguisher in fire protection cabinet with the words "FIRE EXTINGUISHER."
 - 1) Location: Applied to cabinet door.
 - 2) Application Process: Die cut, pressure-sensitive vinyl letters.
 - 3) Lettering Color: Black.
 - 4) Orientation: Vertical.
- J. Finishes:
 - 1. Manufacturer's standard baked-enamel paint for the following:
 - a. Exterior of cabinet door except for those surfaces indicated to receive another finish.
 - 1) Color: White.

b. Interior of cabinet and door.

1) Color: Match exterior cabinet finish.

2.4 MOUNTING BRACKETS

- A. Mounting Brackets: Manufacturer's standard steel, designed to secure fire extinguisher to wall or structure, of sizes required for types and capacities of fire extinguishers indicated, with plated or black baked-enamel finish.
- B. Identification: Lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as indicated by Architect.
 - 1. Identify bracket-mounted fire extinguishers with the words "FIRE EXTINGUISHER" in red letter decals applied to mounting surface.
 - a. Orientation: Horizontal.

2.5 FABRICATION

- A. Fire Protection Cabinets: Provide manufacturer's standard box (tub) with trim, frame, door, and hardware to suit cabinet type, trim style, and door style indicated.
 - 1. Weld joints and grind smooth.
 - 2. Provide factory-drilled mounting holes.
 - 3. Prepare doors and frames to receive locks.
- B. Cabinet Doors: Fabricate doors according to manufacturer's standards, from materials indicated and coordinated with cabinet types and trim styles selected.
 - 1. Fabricate door frames with tubular stiles and rails and hollow-metal design, minimum 1/2 inch thick.
 - 2. Miter and weld perimeter door frames.
- C. Cabinet Trim: Fabricate cabinet trim in one piece with corners mitered, welded, and ground smooth.

2.6 GENERAL FINISH REQUIREMENTS

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Protect mechanical finishes on exposed surfaces of fire protection cabinets from damage by applying a strippable, temporary protective covering before shipping.
- C. Finish fire protection cabinets after assembly.
- D. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.7 STEEL FINISHES

- A. Baked-Enamel or Powder-Coat Finish: Immediately after cleaning and pretreating, apply manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat. Comply with coating manufacturer's written instructions for applying and baking to achieve a minimum dry film thickness of 2 mils.

- 1. Color and Gloss: Match Architect's sample.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine fire extinguishers for proper charging and tagging.
 - 1. Remove and replace damaged, defective, or undercharged fire extinguishers.
- B. Examine walls and partitions for suitable framing depth and blocking where recessed cabinets will be installed.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Prepare recesses for recessed fire protection cabinets as required by type and size of cabinet and trim style.

3.3 INSTALLATION

- A. General: Install fire protection specialties in locations and at mounting heights indicated or, if not indicated, at heights indicated below:
 - 1. Fire Protection Cabinets and Mounting Brackets: 54 inches above finished floor to top of cabinet.
- B. Fire Protection Cabinets: Fasten cabinets to structure, square and plumb.
 - 1. Unless otherwise indicated, provide recessed fire protection cabinets. If wall thickness is not adequate for recessed cabinets, provide semirecessed fire protection cabinets.
- C. Mounting Brackets: Fasten mounting brackets to surfaces, square and plumb, at locations indicated.

3.4 ADJUSTING AND CLEANING

- A. Remove temporary protective coverings and strippable films, if any, as fire protection cabinets are installed unless otherwise indicated in manufacturer's written installation instructions.
- B. Adjust fire protection cabinet doors to operate easily without binding. Verify that integral locking devices operate properly.

- C. On completion of fire protection cabinet installation, clean interior and exterior surfaces as recommended by manufacturer.
- D. Touch up marred finishes, or replace fire protection cabinets that cannot be restored to factory-finished appearance. Use only materials and procedures recommended or furnished by fire protection cabinet and mounting bracket manufacturers.
- E. Replace fire protection cabinets that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION 10 44 00

SECTION 10 75 16 - GROUND-SET FLAGPOLES**PART 1 - GENERAL****1.1 SUMMARY**

- A. Section includes ground-set flagpoles made from aluminum.
- B. (OFCl) Owner furnished Contractor installed flags.
 - 1. US Flag.
 - 2. Bank of America Flag.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, operating characteristics, fittings, accessories, and finishes for flagpoles.
- B. Shop Drawings: For flagpoles.
 - 1. Include plans, elevations, and attachment details. Show general arrangement, jointing, fittings, accessories, grounding, anchoring, and support.
 - 2. Include section, and details of foundation system.
- C. Samples for Verification: For each type of exposed finish, in manufacturer's standard sizes.
- D. Delegated-Design Submittal: For flagpoles.

1.3 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For flagpoles to include in operation and maintenance manuals.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Spiral wrap flagpoles with heavy paper and enclose in a hard fiber tube or other protective container.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Source Limitations: Obtain flagpoles as complete units, including fittings, accessories, bases, and anchorage devices, from single source from single manufacturer.

2.2 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 01 40 00 "Quality Requirements," to design flagpole assemblies.
- B. Seismic Performance: Flagpole assemblies shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
- C. Structural Performance: Flagpole assemblies, including anchorages and supports, shall withstand design loads indicated within limits and under conditions indicated.
 - 1. Design flagpole assemblies, including anchorages and supports, capable of withstanding the maximum effects of wind loads, determined according to NAAMM FP 1001, "Guide Specifications for Design of Metal Flagpoles" using wind loads as determined by Section 6 of ASCE 7, and the authorities having jurisdiction for the geographic location of the building.
 - 2. Base flagpole design on polyester flags of maximum standard size suitable for use with flagpole or flag size indicated, whichever is more stringent.

2.3 ALUMINUM FLAGPOLES

- A. Aluminum Flagpoles: Cone-tapered flagpoles fabricated from seamless extruded tubing complying with ASTM B241/B241M, Alloy 6063, with a minimum wall thickness of 3/16 inch.
 - 1. Product: Subject to compliance with requirements, provide model "PT-306C" cone tapered aluminum flagpoles as manufactured by Pole-Tech Company Inc.
- B. Exposed Height: 30 feet.
- C. Construct flagpoles in one piece if possible. If more than one piece is necessary, comply with the following:
 - 1. Fabricate shop and field joints without using fasteners, screw collars, or lead calking.
 - 2. Provide flush hairline joints using self-aligning, snug-fitting, internal sleeves.
- D. Metal Foundation Tube: Manufacturer's standard corrugated-steel foundation tube, 0.060-inch wall thickness with 3/16-inch steel bottom plate and support plate; 3/4-inch- diameter, steel ground spike; and steel centering wedges welded together. Galvanize foundation tube after assembly. Furnish loose hardwood wedges at top of foundation tube for plumbing pole.

1. Flashing Collar: Same material and finish as flagpole.

2.4 FITTINGS

- A. Finial and Down-Lighting: Manufacturer's standard flush-seam tapered profile finial with integral down lighting fixture and halyard system. Finish shall match flagpole.
 1. Product: Subject to compliance with requirements, provide model "SKU #208349 - Integral Flagpole Beacon – 6.5 inches-IH-12V" as manufactured by Flagpole Warehouse.com; A division of Global Flags Unlimited, LLC.
 2. Provide manufacture's standard transformer or 120 volt power supply with down light fixture.
- B. Internal Halyard, Winch System: Manually operated winch with control stop device and removable handle, stainless-steel cable halyard, and concealed revolving truck assembly with plastic-coated counterweight and sling. Furnish flush access door secured with cylinder lock. Finish truck assembly to match flagpole.
 1. Halyard Flag Snaps: Stainless-steel swivel snap hooks with neoprene or vinyl covers. Furnish two per halyard.

2.5 MISCELLANEOUS MATERIALS

- A. Sand: ASTM C33/C33M, fine aggregate.
- B. Elastomeric Joint Sealant: Multicomponent nonsag urethane joint sealant complying with requirements in Section 07 92 00 "Joint Sealants."
- C. Bituminous Paint: Cold-applied asphalt emulsion complying with ASTM D1187/D1187M.

2.6 ALUMINUM FINISHES

- A. Clear Anodic Finish: AAMA 611, AA-M12C22A41.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Prepare uncoated metal flagpoles that are set in foundation tubes by painting below-grade portions with a heavy coat of bituminous paint.
- B. Foundation Excavation: Excavate to neat clean lines in undisturbed soil. Remove loose soil and foreign matter from excavation and moisten earth before placing concrete. Place and compact drainage material at excavation bottom.

- C. Provide forms where required due to unstable soil conditions and for perimeter of flagpole base at grade. Secure and brace forms to prevent displacement during concreting.
- D. Foundation Tube: Place foundation tube, center, and brace to prevent displacement during concreting. Place concrete. Plumb and level foundation tube and allow concrete to cure.
- E. Place concrete, as specified in Section 03 30 00 "Cast-in-Place Concrete." Compact concrete in place by using vibrators. Moist-cure exposed concrete for no fewer than seven days or use nonstaining curing compound.
- F. Trowel exposed concrete surfaces to a smooth, dense finish, free of trowel marks, and uniform in texture and appearance. Provide positive slope for water runoff to perimeter of concrete base.

3.2 FLAGPOLE INSTALLATION

- A. General: Install flagpoles where indicated and according to Shop Drawings and manufacturer's written instructions.
- B. Foundation Tube: Place flagpole in tube, seated on bottom plate between steel centering wedges, and install hardwood wedges to secure flagpole in place. Place and compact sand in foundation tube and remove hardwood wedges. Seal top of foundation tube with a 2-inch layer of elastomeric joint sealant and cover with flashing collar.

3.3 FLAG INSTALLATION

- A. General: Install owner furnished flags to comply with flagpole manufacturer's recommendation and with NAAMM's "Metal Flagpole Manual" for recommendations on displaying the flag.
 - 1. When the flag of the United States is displayed from a staff projecting horizontally or at an angle from the window sill, balcony, or front of a building, the union of the flag should be placed at the peak of the staff unless the flag is at half-staff.
- B. When the flag of the United States is displayed from the same flagpole with another flag, the flag of the United States must always be at the top.

END OF SECTION 10 75 16

SECTION 11 31 10 - PANTRY APPLIANCES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Filtered Water Dispenser.
2. Microwave.
3. Refrigerator / Freezer.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product indicated. Include rated capacities, operating characteristics, dimensions, furnished accessories, and finishes for each appliance.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.

C. Product Schedule: For appliances. Use same designations indicated on Drawings.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For qualified Installer.

B. Product Certificates: For each type of appliance, from manufacturer.

C. Field quality-control reports.

D. Warranties: Sample of special warranties.

1.4 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For each residential appliance to include in operation and maintenance manuals.

1.5 QUALITY ASSURANCE

- A. **Installer Qualifications:** An employer of workers trained and approved by manufacturer for installation and maintenance of units required for this Project.
- B. **Source Limitations:** Obtain each type of residential appliance from single manufacturer.
- C. **Regulatory Requirements:** Comply with the following:
 - 1. **NFPA:** Provide electrical appliances listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- D. **Accessibility:** Where residential appliances are indicated to comply with accessibility requirements, comply with the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines and ICC/ANSI A117.1.
- E. **Preinstallation Conference:** Conduct conference at Project site.
 - 1. Coordinate with plumbing and electrical trades to ensure that required plumbing, shutoff valves, and electrical outlets of type and size comply with filtered water dispenser manufacturer's recommendations.
 - a. Provide plumbing and electrical at locations where recommended with filtered water dispenser manufacturer.

1.6 WARRANTY

- A. **Special Warranties:** Manufacturer agrees to repair or replace residential appliances or components that fail in materials or workmanship within specified warranty period.
 - 1. **Warranty Period:** Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 FILTERED WATER DISPENSER

- A. **Countertop Unit (Item Code #65):**
 - 1. **Products:** Subject to compliance with requirements, provide "TS400" countertop filtered water dispenser as manufactured by ION.
 - 2. **Dimensions:**
 - a. Height: 16.2-inches.
 - b. Width: 13.6-inches.
 - c. Depth: 20.6-inches.
 - 3. **Plumbing and Electrical:** Refer to Division 22 "Plumbing and Division 26 "Electrical" for plumbing and electrical requirements.

2.2 MICROWAVE OVENS

A. Microwave Oven (Item Code #15):

1. Product: Subject to compliance with the requirements, provide "Model #JES2051SNSS" microwave as manufactured by General Electric Company.
2. Mounting: Countertop.
3. Type: Conventional.
4. Dimensions:
 - a. Width: 24-1/8 inches.
 - b. Depth: 19-1/4 inches.
 - c. Height: 13-5/8 inches.
5. Weight: 50 lbs.
6. Capacity: 2.0 cu. ft.
7. Oven Door: Door with observation window and pushbutton latch release.
8. Microwave Power Rating: Manufacturer's standard.
9. Electric Power Supply: 120 V, 60 Hz, 1 phase, 15 A.
10. Controls: Digital panel controls and timer display.
11. Other Features: Turntable.
12. Material: Stainless steel.

2.3 REFRIGERATOR/FREEZERS

A. Refrigerator/Freezer (Item Code #16): Two-door refrigerator/freezer with freezer on top and complying with AHAM HRF-1.

1. Product: Subject to compliance with the requirements, provide "Model # GIE18GSNRSS" microwave as manufactured by General Electric Company.
2. Type: Freestanding.
3. Dimensions:
 - a. Width: 28 inches.
 - b. Depth: 32-5/8 inches.
 - c. Height: 67-3/8 inches.
4. Storage Capacity:
 - a. Refrigeration Compartment Volume: 13.49 cu. ft.
 - b. Freezer Volume: 4.04 cu. ft.
 - c. Shelf Area: Two adjustable glass shelves.
5. General Features:
 - a. Door Configuration: Overlay.
 - b. Dual refrigeration systems.

- c. Separate temperature controls for each compartment.
- 6. Refrigerator Features:
 - a. Interior light in refrigeration compartment.
 - b. Compartment Storage: vegetable crisper and meat compartment.
 - c. Door Storage: Modular compartments and Gallon-milk-container storage.
 - d. Temperature-controlled meat/deli bin.
- 7. Freezer Features: One freezer compartment(s) with door.
 - a. Automatic defrost.
 - b. Automatic icemaker and storage bin.
 - c. One adjustable wire shelf.
- 8. ENERGY STAR: Provide appliances that qualify for the EPA/DOE ENERGY STAR product-labeling program.
- 9. Front Panel(s): Stainless steel.
- 10. Appliance Color/Finish: Stainless steel.

2.4 GENERAL FINISH REQUIREMENTS

- A. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances, power connections, and other conditions affecting installation and performance of pantry appliances.
- B. Examine roughing-in for piping systems to verify actual locations of piping connections before appliance installation.
- C. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

- A. General: Comply with manufacturer's written instructions.

- B. Built-in Equipment: Securely anchor units to supporting cabinets or countertops with concealed fasteners. Verify that clearances are adequate for proper functioning and that rough openings are completely concealed.
- C. Utilities: Comply with plumbing and electrical requirements.
- D. Freestanding Equipment: Place units in final locations after finishes have been completed in each area. Verify that clearances are adequate to properly operate equipment.

3.3 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Tests and Inspections:
 - 1. Perform visual, mechanical, and electrical inspection and testing for each appliance according to manufacturers' written recommendations. Certify compliance with each manufacturer's appliance-performance parameters.
 - 2. Leak Test: After installation, test for leaks. Repair leaks and retest until no leaks exist.
 - 3. Operational Test: After installation, start units to confirm proper operation.
 - 4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and components.
- C. An appliance will be considered defective if it does not pass tests and inspections.
- D. Prepare test and inspection reports.

3.4 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain residential appliances.

END OF SECTION 11 31 10

SECTION 12 24 13 - ROLLER WINDOW SHADES**PART 1 - GENERAL****1.1 SUMMARY****A. Section Includes:**

1. Manually operated roller shades with single rollers.

1.2 ACTION SUBMITTALS**A. Product Data:** For each type of product.

1. Include styles, material descriptions, construction details, dimensions of individual components and profiles, features, finishes, and operating instructions for roller shades.

B. Shop Drawings: Show fabrication and installation details for roller shades, including shadeband materials, their orientation to rollers, and their seam and batten locations.**C. Samples:** For each exposed product and for each color and texture specified, 10 inches long.**D. Roller-Shade Schedule:** Use same designations indicated on Drawings.**1.3 INFORMATIONAL SUBMITTALS****A. Qualification Data:** For Installer.**B. Product Certificates:** For each type of shadeband material, signed by product manufacturer.**C. Product Test Reports:** For each type of shadeband material, for tests performed by a qualified testing agency.**1.4 CLOSEOUT SUBMITTALS****A. Maintenance Data:** For roller shades to include in maintenance manuals.**1.5 MAINTENANCE MATERIAL SUBMITTALS****A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.**

1. Roller Shades: Full-size units equal to 5 percent of quantity installed for each size, color, and shadeband material indicated, but no fewer than two units.

1.6 QUALITY ASSURANCE**A. Installer Qualifications:** Fabricator of products.

- B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.
 - 1. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 - 2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver roller shades in factory packages, marked with manufacturer, product name, and location of installation using same designations indicated on Drawings.

1.8 FIELD CONDITIONS

- A. Environmental Limitations: Do not install roller shades until construction and finish work in spaces, including painting, is complete and dry and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.
- B. Field Measurements: Where roller shades are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Allow clearances for operating hardware of operable glazed units through entire operating range. Notify Architect of installation conditions that vary from Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Products: Subject to compliance with requirements, provide products by one of the following:
 - 1. Manually Operated Roller Shades: Mecho Shade, Inc.; "Mecho/5 Wide Bracket."
 - a. Shadeband Material: Provide the following window shade product as manufactured by Mecho Shade, Inc.:
 - 1) Window Shade (SH-1): EcoVeil Screen; #0950 Series:
 - a) Openness Factor: 1 percent.
 - b) Color: #0969 – Silver Birch.
 - b. Roll Fascia Color: Match shadeband material color.
- B. Source Limitations: Obtain roller shades from single source from single manufacturer.

2.2 MANUALLY OPERATED SHADES WITH SINGLE ROLLERS

- A. Chain-and-Clutch Operating Mechanisms: With continuous-loop bead chain and clutch that stops shade movement when bead chain is released; permanently adjusted and lubricated.
 - 1. Bead Chains: Stainless steel.
 - a. Loop Length: Full length of roller shade.
 - b. Limit Stops: Provide upper and lower ball stops.
 - c. Chain-Retainer Type: Clip, jamb mount, unless otherwise indicated.
- B. Rollers: Corrosion-resistant steel or extruded-aluminum tubes of diameters and wall thicknesses required to accommodate operating mechanisms and weights and widths of shadebands indicated without deflection. Provide with permanently lubricated drive-end assemblies and idle-end assemblies designed to facilitate removal of shadebands for service.
 - 1. Roller Drive-End Location: Right side of inside face of shade, unless otherwise indicated.
 - 2. Direction of Shadeband Roll: Regular, from back of roller.
 - 3. Shadeband-to-Roller Attachment: Removable spline fitting integral channel in tube.
- C. Mounting Hardware: Brackets or endcaps, corrosion resistant and compatible with roller assembly, operating mechanism, installation accessories, and mounting location and conditions indicated.
- D. Shadebands:
 - 1. Shadeband Material: Light-filtering fabric.
 - 2. Shadeband Bottom (Hem) Bar: Steel or extruded aluminum.
 - a. Type: Enclosed in sealed pocket of shadeband material.
- E. Installation Accessories:
 - 1. Front Fascia: Aluminum extrusion that conceals front and underside of roller and operating mechanism and attaches to roller endcaps without exposed fasteners.
 - a. Shape: L-shaped.
 - b. Height: Manufacturer's standard height required to conceal roller and shadeband when shade is fully open, but not less than 4 inches.
 - 2. Exposed Headbox: Rectangular, extruded-aluminum enclosure including front fascia, top and back covers, endcaps, and removable bottom closure.
 - a. Height: Manufacturer's standard height required to enclose roller and shadeband when shade is fully open, but not less than 4 inches.

2.3 SHADEBAND MATERIALS

- A. Shadeband Material Flame-Resistance Rating: Comply with NFPA 701. Testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
- B. Light-Filtering Fabric: Woven fabric, stain and fade resistant.
 - 1. Source: Roller-shade manufacturer.
 - 2. Type: 100 percent polyester.
 - 3. Roll Width: 63 inches and 118 inches wide.
 - 4. Orientation on Shadeband: Up the bolt, unless otherwise indicated.
 - 5. Openness Factor: As scheduled.

2.4 ROLLER-SHADE FABRICATION

- A. Product Safety Standard: Fabricate roller shades to comply with WCMA A 100.1, including requirements for flexible, chain-loop devices; lead content of components; and warning labels.
- B. Unit Sizes: Fabricate units in sizes to fill window and other openings as follows, measured at 74 deg F:
 - 1. Between (Inside) Jamb Installation: Width equal to jamb-to-jamb dimension of opening in which shade is installed less 1/4 inch per side or 1/2-inch total, plus or minus 1/8 inch. Length equal to head-to-sill or -floor dimension of opening in which shade is installed less 1/4 inch, plus or minus 1/8 inch.
- C. Shadeband Fabrication: Fabricate shadebands without battens or seams to extent possible except as follows:
 - 1. Vertical Shades: Where width-to-length ratio of shadeband is equal to or greater than 1:4, provide battens and seams at uniform spacings along shadeband length to ensure shadeband tracking and alignment through its full range of movement without distortion of the material.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, operational clearances, locations of connections to building electrical system, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 ROLLER-SHADE INSTALLATION

- A. Install roller shades level, plumb, and aligned with adjacent units according to manufacturer's written instructions.

- B. Roller Shade Locations: As indicated on Drawings.

3.3 ADJUSTING

- A. Adjust and balance roller shades to operate smoothly, easily, safely, and free from binding or malfunction throughout entire operational range.

3.4 CLEANING AND PROTECTION

- A. Clean roller-shade surfaces after installation, according to manufacturer's written instructions.
- B. Provide final protection and maintain conditions, in a manner acceptable to manufacturer and Installer, that ensure that roller shades are without damage or deterioration at time of Substantial Completion.
- C. Replace damaged roller shades that cannot be repaired, in a manner approved by Architect, before time of Substantial Completion.

END OF SECTION 12 24 13

SECTION 12 36 61 - SIMULATED STONE COUNTERTOPS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Solid-surface-material countertops.
2. Quartz agglomerate countertops.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For countertop materials and sinks.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Low Emitting Materials Information.
 - c. Recycled Content Information.
 - d. Regional Materials Information.
 - e. LEED Materials and Resources Calculator.

C. Shop Drawings: For countertops. Show materials, finishes, edge and backsplash profiles, methods of joining, and cutouts for plumbing fixtures.

D. Samples for Initial Selection: For each type of material exposed to view.

E. Samples for Verification: For the following products:

1. Countertop material, 6 inches square.
2. One full-size solid-surface-material countertop, with front edge, 8 by 10 inches, of construction and in configuration specified.
3. One full-size and minimum 6 inches in length, solid-surface-material custom cash try, of construction and in configuration specified.

1.3 PROJECT CONDITIONS

A. Field Measurements: Verify dimensions of countertops by field measurements after base cabinets are installed but before countertop fabrication is complete.

1.4 COORDINATION

- A. Coordinate locations of utilities that will penetrate countertops or backsplashes.

PART 2 - PRODUCTS

2.1 SOLID-SURFACE-MATERIAL COUNTERTOPS

- A. Configuration: Provide countertops with the following front style:
 - 1. Front: Straight, slightly eased at top, unless otherwise indicated.
- B. Countertops: 1/2-inch- thick, solid surface material with front edge built up with same material.
- C. Fabrication: Fabricate tops in one piece with shop-applied edges unless otherwise indicated. Comply with solid-surface-material manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.
 - 1. Install integral sink bowls in countertops in the shop.

2.2 QUARTZ AGGLOMERATE COUNTERTOPS

- A. Configuration: Provide countertops with the following front style:
 - 1. Front: Straight, slightly eased at top, unless otherwise indicated.
- B. Countertops: 3/4-inch- thick, quartz agglomerate with front edge built up with same material.
- C. Fabrication: Fabricate tops in one piece with shop-applied edges unless otherwise indicated. Comply with quartz agglomerate manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.

2.3 MATERIALS

- A. Adhesives: Adhesives shall not contain urea formaldehyde.
- B. Solid Surface Material: Homogeneous solid sheets of filled plastic resin complying with ANSI SS1.
 - 1. Type: Provide Standard Type unless Special Purpose Type is indicated.
 - 2. Integral Sink Bowls: Comply with ISSFA-2 and ANSI Z124.3, Type 5 or Type 6, without a precoated finish.
 - 3. Colors and Patterns: As scheduled.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install countertops level to a tolerance of 1/8 inch in 8 feet.
- B. Fasten countertops by screwing through corner blocks of base units into underside of countertop. Pre-drill holes for screws as recommended by manufacturer. Align adjacent surfaces and, using adhesive in color to match countertop, form seams to comply with manufacturer's written instructions. Carefully dress joints smooth, remove surface scratches, and clean entire surface.
 - 1. Install to comply with manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.

END OF SECTION 12 36 61

SECTION 12 48 13 - ENTRANCE FLOOR MATS AND FRAMES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Interior, Recessed, roll-up rail mats.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 COORDINATION

- A. Coordinate size and location of recesses in concrete to receive floor mats and frames.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for floor mats and frames.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.
 - d. LEED Materials and Resources Calculator.

C. Shop Drawings:

1. Items penetrating floor mats and frames, including door control devices.
2. Divisions between mat sections.
3. Recessed edge filler moldings.

D. Samples: For the following products, in manufacturer's standard sizes:

1. Floor Mat: Assembled sections of floor mat.

1.4 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For floor mats and frames to include in maintenance manuals.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Resilient-Tile Entrance Mats: Full-size tile units equal to 2 percent of amount installed, but no fewer than 10 units.

PART 2 - PRODUCTS

2.1 ENTRANCE FLOOR MATS AND FRAMES, GENERAL

- A. Structural Performance: Provide roll-up rail mats and frames capable of withstanding the following loads and stresses within limits and under conditions indicated:
 - 1. Wheel load of 300 lb per wheel.
- B. Regulatory Requirements: Comply with applicable provisions in A117.1.

2.2 INTERIOR ROLL-UP RAIL MATS (WM-1)

- A. Product: Subject to compliance with requirements, provide “Perfec Mat; Tread #538” surface mounted entrance mats with four-sided vinyl edge fillers as manufactured by Reese Enterprises, Inc.
- B. Roll-up, Aluminum-Rail Hinged Mats: Extruded-aluminum tread rails 2 inches Insert dimension wide by 3/8-inch-thick, sitting on continuous vinyl cushions.
 - 1. Tread Inserts: Polypropylene brush.
 - a. Color: Refer to “Finish Schedule” located on Drawings for color selection.
 - 2. Rail Color: Clear.
 - 3. Hinges: Plastic.
 - 4. Mat Size: As indicated on Drawings.
- C. Accessories:
 - 1. Vinyl Edge Filler Molding: Provide entrance floor mat manufacturers standard perimeter vinyl edge filler for entrance mat application. Trim vinyl edge filler in accordance to manufactures written instructions.
 - a. Profile: Square.
 - b. Width: 2 inches.
 - c. Height: 1/2 inch, unless otherwise indicated.
 - d. Color: Refer to “Finish Schedule” located on Drawings for color selection.

- D. Floor Mats: Shop fabricate units to greatest extent possible in sizes indicated. Unless otherwise indicated, provide single unit for each mat installation; do not exceed manufacturer's recommended maximum sizes for units that are removed for maintenance and cleaning. Where joints in mats are necessary, space symmetrically and away from normal traffic lanes. Miter corner joints in framing elements with hairline joints or provide prefabricated corner units without joints.
- E. Recessed Vinyl Edge Filler Molding: As indicated, for permanent recessed installation.
 - 1. Fabricate edge filler molding in single lengths.

2.3 ALUMINUM FINISHES

- A. Clear Anodic Finish: AAMA 611, AA-M12C22A41, Class I, 0.018 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and floor conditions for compliance with requirements for location, sizes, and other conditions affecting installation of floor mats and frames.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install recessed mats and edge filler molding at height recommended by manufacturer for most effective cleaning action; coordinate tops of mat surfaces with bottoms of doors that swing across mats to provide clearance between door and mat.
 - 1. Frame: Refer to Division 09 Section "Tiling" for installation of metal edge strips at perimeter of entrance floor mats.
 - 2. Install grout and fill around frames and, if required to set mat tops at proper elevations, in recesses under mats. Finish grout and fill smooth and level.

3.3 PROTECTION

- A. After completing frame installation and concrete work, provide temporary filler of plywood or fiberboard in recesses and cover frames with plywood protective flooring. Maintain protection until construction traffic has ended and Project is near Substantial Completion.

END OF SECTION 12 48 13

SECTION 12 90 00 - BUILDING ACCESSORIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Bicycle racks.
2. Coat Hooks.
3. Fireman's Lockbox.
4. Exterior trash receptacles.
5. Interior trash receptacles.
6. Precast concrete equipment pad.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
 - b. Recycled Content Information.
 - c. Regional Materials Information.
 - d. LEED Materials and Resources Calculator.

C. Samples for Verification: For each type of exposed finish, not less than 6-inch- long linear components and 4-inch- square sheet components.

D. Product Schedule: For building accessories. Use same designations indicated on Drawings.

1.3 CLOSEOUT SUBMITTALS

A. Maintenance Data: For building accessories to include in maintenance manuals.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Trash/Ash Receptacle Inner Containers: Five full-size units for each size indicated, but no fewer than two units.

PART 2 - PRODUCTS

2.1 BICYCLE RACKS

A. Bicycle Rack Construction:

1. Frame: Galvanized steel.
 - a. Pipe OD: Not less than 2 inches.
2. Style: Double-side parking.
 - a. Overall Height: 35-inch to 39-inch.
 - b. Overall Depth: 22-inch to 25-inch.
 - c. Capacity: Designed to accommodate no fewer than two bicycles.
3. Security: Designed to lock wheel and frame.
4. Installation Method: Cast in concrete, unless otherwise indicated.

B. Steel Finish: Galvanized.

2.2 COAT HOOK

A. Description: Double-prong unit.

B. Material and Finish: Polished chrome-plated zinc alloy (zamac).

2.3 FIREMAN'S LOCKBOX

A. Description: Recessed mounted 1/4-inch plate steel housing with 1/2-inch thick steel door with interior gasket seal and stainless steel door hinge. Box, lock and tamper switches shall be UL Listed.

1. Weight: Not more than 9 lbs.
2. Minimum Size: 7-inch height by 7-inch width
3. Finish: Powder-coat finish.
 - a. Color: Black.
4. Lock: Double-action rotating tumblers and hardened steel pins accessed by a biased cut key.
 - a. Provide lock with 1/8-inch thick stainless steel dust cover with tamper seal mounting capability.

B. Accessories:

1. Recessed Mounting Kit: Provide recessed mounting kit consisting of shell hosing and mounting hardware for installation in cast-in-place concrete or masonry wall assemblies.

2.4 EXTERIOR TRASH RECEPTACLES

- A. Freestanding; Trash Receptacles (Equipment #02): Subject to compliance with requirements, provide “Corner Stone Series, Model No. FGC2035T, Finish: Pebble” open top waste receptacle as manufactured by United Receptacles.

1. Trash Receptacle:

- a. Receptacle Shape and Form: Round cylinder with top; with opening for depositing from top.
- b. Lids and Tops: 8-inch diameter opening for depositing trash.
- c. Receptacle Height: 36-inch.
- d. Diameter: 20-inch diameter.
- e. Weight: 40 lbs.
- f. Inner Container: Rigid plastic container with lift-out handles; designed to be removable and reusable.
- g. Capacity: Not less than 23 gal.
- h. Service Access: Removable lid or top; inner container lift out for emptying.

2. Accessories: Provide manufacturers standard anchoring kits.

- B. Freestanding; Trash Receptacles (Alternate): Subject to compliance with requirements, provide “Corner Stone Series, Model No. FGC2044, Finish: Pebble” side disposal waste receptacle as manufactured by United Receptacles.

1. Trash Receptacle:

- a. Receptacle Shape and Form: Round cylinder with side disposal openings.
 - 1) 8-inch wide by 6-1/2-inch-high disposal openings.
- b. Receptacle Height: 46-inch.
- c. Diameter: 20-inch diameter.
- d. Weight: 47 lbs.
- e. Inner Container: Rigid plastic container with lift-out handles; designed to be removable and reusable.
- f. Capacity: Not less than 23 gal.
- g. Service Access: Removable lid or top; inner container lift out for emptying.

2. Accessories: Provide manufacturers standard anchoring kits.

2.5 INTERIOR TRASH RECEPTACLES

- A. Freestanding; Square Trash Receptacles (Equipment #90): Subject to compliance with requirements, provide “Designer Line - Silhouettes, Model No. SC14EPL Open Top” waste receptacle as distributed by Rubbermaid.

1. Steel Facing Surrounds: Perforated cold rolled steel.
2. Trash and Ash Receptacles:

- a. Receptacle Shape and Form: Square with 8-inch diameter opening on top of lid or top for depositing trash.
 - b. Lids and Tops: Galvanized steel secured by stainless steel hinge to allow top to open 90 degrees.
 - c. Receptacle Height: 30-inch.
 - d. Receptacle Size: 14-3/4-inch by 14-3/4-inch.
 - e. Inner Container: Rigid plastic container with lift-out handles; designed to be removable and reusable.
 - f. Capacity: Not less than 8-1/2 gal.
 - g. Service Access: Removable lid or top; inner container lift out for emptying.
 3. Steel Finish: Galvanized and color coated.
 - a. Color: Desert Pearl Metallic.
- B. Freestanding; Half Round Trash Receptacles (Equipment #91): Subject to compliance with requirements, provide "Designer Line - Silhouettes, Model No. SH12E Open Top Half Round" waste receptacle as distributed by Rubbermaid.
 1. Steel Facing Surrounds: Perforated cold rolled steel.
 2. Trash and Ash Receptacles:
 - a. Receptacle Shape and Form: Half round with 7-inch diameter opening on top of lid or top for depositing trash.
 - b. Lids and Tops: Galvanized steel secured by stainless steel hinge to allow top to open 90 degrees.
 - c. Receptacle Height: 32-inch.
 - d. Receptacle Size: 18-inch by 9-inch.
 - e. Inner Container: Rigid plastic container with lift-out handles; designed to be removable and reusable.
 - f. Capacity: Not less than 12 gal.
 - g. Service Access: Removable lid or top; inner container lift out for emptying.
 3. Steel Finish: Galvanized and color coated.
 - a. Color: Textured Black.
- C. Freestanding; Round Trash Receptacles (90-ALT): Subject to compliance with requirements, provide "AL18-SVN" two piece design waste receptacle as distributed by Belson Outdoors, LLC.
 1. Receptacle Height: 30.5-inch.
 2. Diameter: 15-inch diameter.
 3. Capacity: 32 gal.
 4. Finish: Aluminum, Satin Clear.
 5. Inner Trash Receptacle Liner: Rigid plastic container with lift-out handles; designed to be removable and reusable.

2.6 PRECAST CONCRETE EQUIPMENT PAD

- A. Precast Concrete Equipment Pad: Provide steel reinforced, precast equipment pads of sizes indicated on drawings that is capable of withstanding commercial equipment loads of type specified on drawings.
 - 1. Edges: Rounded.
 - 2. Color: Concrete gray.

2.7 MATERIALS

- A. Steel and Iron: Free of surface blemishes and complying with the following:
 - 1. Plates, Shapes, and Bars: ASTM A 36/A 36M.
 - 2. Steel Pipe: Standard-weight steel pipe complying with ASTM A 53/A 53M, or electric-resistance-welded pipe complying with ASTM A 135/A 135M.
 - 3. Tubing: Cold-formed steel tubing complying with ASTM A 500/A 500M.
 - 4. Mechanical Tubing: Cold-rolled, electric-resistance-welded carbon or alloy steel tubing complying with ASTM A 513, or steel tubing fabricated from steel complying with ASTM A 1011/A 1011M and complying with dimensional tolerances in ASTM A 500/A 500M; zinc coated internally and externally.
 - 5. Sheet: Commercial steel sheet complying with ASTM A 1011/A 1011M.
 - 6. Malleable-Iron Castings: ASTM A 47/A 47M, grade as recommended by fabricator for type of use intended.
 - 7. Gray-Iron Castings: ASTM A 48/A 48M, Class 200.
- B. Plastic: Color impregnated, color and UV-light stabilized, and mold resistant.
 - 1. Polyethylene: Fabricated from virgin plastic HDPE resin.
- C. Anchors, Fasteners, Fittings, and Hardware: Manufacturer's standard, corrosion-resistant-coated or noncorrodible materials; commercial quality, tamperproof, vandal and theft resistant.
 - 1. Antitheft Hold-Down Brackets: For securing building accessories to substrate; two per unit, unless otherwise indicated.
- D. Nonshrink, Nonmetallic Grout: Premixed, factory-packaged, nonstaining, noncorrosive, nongaseous grout complying with ASTM C 1107/C 1107M; recommended in writing by manufacturer, for exterior applications.
- E. Erosion-Resistant Anchoring Cement: Factory-packaged, nonshrink, nonstaining, hydraulic-controlled expansion cement formulation for mixing with potable water at Project site to create pourable anchoring, patching, and grouting compound; resistant to erosion from water exposure without needing protection by a sealer or waterproof coating; recommended in writing by manufacturer, for exterior applications.
- F. Galvanizing: Where indicated for steel and iron components, provide the following protective zinc coating applied to components after fabrication:

1. Hot-Dip Galvanizing: According to ASTM A 123/A 123M, ASTM A 153/A 153M, or ASTM A 924/A 924M.

2.8 FABRICATION

- A. Metal Components: Form to required shapes and sizes with true, consistent curves, lines, and angles. Separate metals from dissimilar materials to prevent electrolytic action.
- B. Welded Connections: Weld connections continuously. Weld solid members with full-length, full-penetration welds and hollow members with full-circumference welds. At exposed connections, finish surfaces smooth and blended so no roughness or unevenness shows after finishing and welded surface matches contours of adjoining surfaces.
- C. Pipes and Tubes: Form simple and compound curves by bending members in jigs to produce uniform curvature for each repetitive configuration required; maintain cylindrical cross section of member throughout entire bend without buckling, twisting, cracking, or otherwise deforming exposed surfaces of handrail and railing components.
- D. Exposed Surfaces: Polished, sanded, or otherwise finished; all surfaces smooth, free of burrs, barbs, splinters, and sharpness; all edges and ends rolled, rounded, or capped.
- E. Factory Assembly: Assemble components in the factory to greatest extent possible to minimize field assembly. Clearly mark units for assembly in the field.

2.9 GENERAL FINISH REQUIREMENTS

- A. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

2.10 STEEL AND GALVANIZED-STEEL FINISHES

- A. Baked-Enamel, Powder-Coat Finish: Manufacturer's standard, baked, polyester, powder-coat finish complying with finish manufacturer's written instructions for surface preparation, including pretreatment, application, baking, and minimum dry film thickness.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and conditions, with Installer present, for compliance with requirements for correct and level finished grade, mounting surfaces, installation tolerances, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

- A. Comply with manufacturer's written installation instructions unless more stringent requirements are indicated. Complete field assembly of building accessories where required.
- B. Install building accessories level, plumb, true, and securely anchored at locations indicated on Drawings.
- C. Coat Hooks:
 - 1. Multiple Coat Hooks: Install coat hooks spaced at 5-inches on centers, securely mount coat hooks on to a 6-inch width by 18-inch length by 1/2-inch thick plywood painted to match wall.
 - 2. Single Coat Hooks: Securely mount coat hooks on to a 6-inch width by 6-inch length by 1/2-inch thick plywood painted to match wall, unless otherwise indicated.
 - 3. Refer to Division 06 Section "Rough Carpentry" for additional plywood requirements.

END OF SECTION 12 90 00

SECTION 31 31 16 - TERMITE CONTROL

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes the following for termite control:

1. Soil treatment.

1.2 SUBMITTALS

- A. Product Data: Treatments and application instructions, including EPA-Registered Label.
- B. Product Certificates: Signed by manufacturers of termite control products certifying that treatments furnished comply with requirements.
- C. Soil Treatment Application Report: After application of termiticide is completed, submit report for Owner's record information, including the following as applicable:
1. Date and time of application.
 2. Moisture content of soil before application.
 3. Brand name and manufacturer of termiticide.
 4. Quantity of undiluted termiticide used.
 5. Dilutions, methods, volumes, and rates of application used.
 6. Areas of application.
 7. Water source for application.

1.3 QUALITY ASSURANCE

- A. Applicator Qualifications: A pest control operator who is licensed according to regulations of authorities having jurisdiction to apply termite control treatment in jurisdiction where Project is located.
- B. Regulatory Requirements: Formulate and apply termiticides, and label with a Federal registration number, to comply with EPA regulations and authorities having jurisdiction.

1.4 PROJECT CONDITIONS

- A. Environmental Limitations: To ensure penetration, do not treat soil that is water saturated or frozen. Do not treat soil while precipitation is occurring. Comply with EPA-Registered Label requirements and requirements of authorities having jurisdiction.

1.5 COORDINATION

- A. Coordinate soil treatment application with excavating, filling, and grading and concreting operations. Treat soil under footings, grade beams, and ground-supported slabs, before construction.

1.6 WARRANTY

- A. Special Warranty: Written warranty, signed by applicator and Contractor certifying that termite control work, consisting of applied soil termiticide treatment, will prevent infestation of subterranean termites. If subterranean termite activity or damage is discovered during warranty period, re-treat soil and repair or replace damage caused by termite infestation.
- B. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SOIL TREATMENT

- A. Termiticide: Provide an EPA-registered termiticide complying with requirements of authorities having jurisdiction, in a soluble or emulsible, concentrated formulation that dilutes with water or foaming agent, and formulated to prevent termite infestation. Use only soil treatment solutions that are not harmful to plants. Provide quantity required for application at the label volume and rate for the maximum termiticide concentration allowed for each specific use, according to the product's EPA-Registered Label.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Applicator present, for compliance with requirements for moisture content of the soil, interfaces with earthwork, slab and foundation work, landscaping, and other conditions affecting performance of termite control. Proceed with application only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. General: Comply with the most stringent requirements of authorities having jurisdiction and with manufacturer's written instructions for preparing substrate. Remove all extraneous sources of wood cellulose and other edible materials such as wood debris, tree stumps and roots, stakes, formwork, and construction waste wood from soil and around foundations.
- B. Soil Treatment Preparation: Remove foreign matter and impermeable soil materials that could decrease treatment effectiveness on areas to be treated. Loosen, rake, and level soil to be treated, except previously compacted areas under slabs and footings. Termiticides may be applied before placing compacted fill under slabs if recommended by termiticide manufacturer.

3.3 APPLICATION, GENERAL

- A. General: Comply with the most stringent requirements of authorities having jurisdiction and with manufacturer's EPA-Registered Label for products.

3.4 APPLYING SOIL TREATMENT

- A. Application: Mix soil treatment termiticide solution to a uniform consistency. Provide quantity required for application at the label volume and rate for the maximum specified concentration of termiticide, according to manufacturer's EPA-Registered Label, to the following so that a continuous horizontal and vertical termiticidal barrier or treated zone is established around and under building construction. Distribute the treatment evenly.
 - 1. Slabs-on-Grade: Under ground-supported slab construction, including footings, building slabs, and attached slabs as an overall treatment. Treat soil materials before concrete footings and slabs are placed.
 - 2. Foundations: Adjacent soil including soil along entire inside perimeter of foundation walls, along both sides of interior partition walls, around plumbing pipes and electric conduit penetrating slab, and around interior column footers, and along entire outside perimeter, from grade to bottom of footing. Avoid soil washout around footings.
 - 3. Masonry: Treat voids.
 - 4. Penetrations: At expansion joints, control joints, and areas where slabs will be penetrated.
- B. Avoid disturbance of treated soil after application. Keep off treated areas until completely dry.
- C. Protect termiticide solution, dispersed in treated soils and fills, from being diluted until ground-supported slabs are installed. Use waterproof barrier according to EPA-Registered Label instructions.
- D. Post warning signs in areas of application.
- E. Reapply soil treatment solution to areas disturbed by subsequent excavation, grading, landscaping, or other construction activities following application.

END OF SECTION 31 31 16

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Wheel stops.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:

- a. LEED Criteria Worksheet.
- b. Recycled Content Information.

C. Samples for Verification: For wheel stops, 6 inches long, showing color and cross section; with fasteners.

PART 2 - PRODUCTS

2.1 PARKING BUMPERS

A. Resilient Wheel Stops: Compression molded, 100 percent recycled rubber and polyurethane prepolymer; UV stabilized and resistant to oils, moisture and extreme temperature variations. Provide chamfered corners and a minimum of four factory-formed or -drilled vertical holes through wheel stop for anchoring to substrate.

1. Size: 4 inches high by 6 inches wide by 72 inches long.
2. Color: Black with yellow reflective markings.
 - a. Markings: Provide molded-in, reflective markings, permanently inset in exposed surface.
3. Mounting Hardware: Galvanized-steel lag screw, shield, and washers; 1/2-inch diameter, 8-inch minimum length.
4. Adhesive: As recommended by wheel-stop manufacturer for adhesion to pavement.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that pavement is in suitable condition to begin installation according to manufacturer's written instructions.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. General: Install wheel stops according to manufacturer's written instructions unless otherwise indicated.
- B. Install wheel stops in bed of adhesive before anchoring.
- C. Securely anchor wheel stops to pavement with hardware in each preformed vertical hole in wheel stop as recommended in writing by manufacturer. Recess head of hardware beneath top of wheel stop.

END OF SECTION 32 17 13

SECTION 32 17 23 - PAVEMENT MARKINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Painted markings applied to asphalt and concrete pavement.
2. Stain markings applied to concrete pavement.

B. Related Sections:

1. Section 01 81 13 "Sustainable Design Requirements" for additional LEED requirements.

1.2 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review methods and procedures related to marking pavement including, but not limited to, the following:
 - a. Pavement aging period before application of pavement markings.
 - b. Review requirements for protecting pavement markings, including restriction of traffic during installation period.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include technical data and tested physical and performance properties.

B. LEED Documentation Submittals:

1. Comply with submittal requirements of Division 01 Section "LEED Sustainable Design Requirements" including, but not limited to:
 - a. LEED Criteria Worksheet.
2. Low Emitting Materials Information.

C. Shop Drawings: For pavement markings.

1. Indicate pavement markings, colors, lane separations, defined parking spaces, and dimensions to adjacent work.
2. Indicate, with international symbol of accessibility, spaces allocated for people with disabilities.

- D. Samples: For each exposed product and for each color and texture specified; on rigid backing, 8 inches square.

1.4 FIELD CONDITIONS

- A. Environmental Limitations: Proceed with pavement marking only on clean, dry surfaces and at a minimum ambient or surface temperature of 55 deg F for water-based materials, and not exceeding 95 deg F.

PART 2 - PRODUCTS

2.1 PAVEMENT-MARKING PAINT

- A. Pavement-Marking Paint: Latex, waterborne emulsion, lead and chromate free, ready mixed, complying with FS TT-P-1952, Type II, with drying time of less than 45 minutes.

- 1. Colors: White and Yellow.

- B. Glass Beads: AASHTO M 247, Type 1 made of 100 percent recycled glass.

- 1. Roundness: Minimum 75 percent true spheres by weight.

- C. VOC Content: Pavement markings used on building interior shall have a VOC content of 150 g/L or less.

2.2 PAVEMENT-MARKING STAIN

- A. Penetrating Stain: Water-based, acrylic latex, penetrating stain with colorfast pigments.

- 1. Basis-of-Design Product: Subject to compliance with the requirements, provide “#111.08 - Concrete Stain Solid Color Water Based” penetrating stain as manufactured by H&C Concrete; Tel: (800) 867-8246.

- a. Color: Yellow.

2.3 ADMIXTURES

- A. Slip Resistant Admixture: Provide micronized polymer slip resistant admixture certified by manufacturer to be compatible with solvent paint coatings and have minimal effects on coating viscosity. Do not use admixture containing silica.

- 1. Basis-of-Design Product: Subject to compliance with the requirements, provide “#111.32 – Shark Grip Slip Resistant Additive” as manufactured by H&C Concrete; Tel: (800) 867-8246.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that pavement is dry and in suitable condition to begin pavement marking according to manufacturer's written instructions.
- B. Proceed with pavement marking only after unsatisfactory conditions have been corrected.

3.2 PAVEMENT MARKING

- A. Do not apply pavement-marking paint until layout, colors, and placement have been verified with Architect.
- B. Allow paving to age for a minimum of 90 days before starting pavement marking.
- C. Sweep and clean surface to eliminate loose material and dust.
- D. Apply paint with mechanical equipment to produce pavement markings, of dimensions indicated, with uniform, straight edges. Apply at manufacturer's recommended rates to provide a minimum wet film thickness of 15 mils.
 - 1. Apply graphic symbols and lettering with paint-resistant, die-cut stencils, firmly secured to pavement. Mask an extended area beyond edges of each stencil to prevent paint application beyond the stencil. Apply paint so that it cannot run beneath the stencil.
 - 2. Broadcast glass beads uniformly into wet markings at a rate of 6 lb/gal.
 - 3. Slip-Resistive Mixture: Mix slip-resistive admixture into paint at rate complying with admixture manufacturer's written instructions.
 - a. Apply slip-resistive paint mixture by method recommended by admixture manufacturer.

3.3 PROTECTING AND CLEANING

- A. Protect pavement markings from damage and wear during remainder of construction period.
- B. Clean spillage and soiling from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

END OF SECTION 32 17 23